



6/12/2020 1:05 PM

AASHTOWare Project™ Version 4.2.2 Revision 034

Schedule of Pay Items

Report v1

Letting Call: 200619 232**Letting Date:** June 19, 2020**Contract ID:** 13082-209954**Description:** Hot mix asphalt overlay, full depth deck and pier patching, concrete surface coating and pavement markings on 8 bridges, Calhoun and Kalamazoo Counties.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
209954A	N/A	N/A	M 13082

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0010	Mobilization, Max \$48,000.00	1500001	1.000	LSUM
0020	Rem and Disposal of Asbestos Materials	2040002	20,000.000	Dir
0030	Asbestos Survey (B01 of 39102)	2040003	1.000	LSUM
0040	Asbestos Survey (S01-3 of 13082)	2040003	1.000	LSUM
0050	Asbestos Survey (S01-4 of 13082)	2040003	1.000	LSUM
0060	Asbestos Survey (S02-3 of 13082)	2040003	1.000	LSUM
0070	Asbestos Survey (S02-4 of 13082)	2040003	1.000	LSUM
0080	Asbestos Survey (S03-3 of 13082)	2040003	1.000	LSUM
0090	Asbestos Survey (S03-4 of 13082)	2040003	1.000	LSUM
0100	Asbestos Survey (S04 of 13082)	2040003	1.000	LSUM
0110	Pavt Mrkg, Waterborne, 4 inch, White	8110231	190.000	Ft
0120	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	2,892.000	Ft
0130	Pavt Mrkg, Waterborne, 6 inch, White	8110233	1,450.000	Ft
0140	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	190.000	Ft
0150	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	2,892.000	Ft
0160	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	1,450.000	Ft
0170	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0190	Lighted Arrow, Type C, Furn	8120140	8.000	Ea
0200	Lighted Arrow, Type C, Oper	8120141	8.000	Ea
0210	Ltg for Night Work	8120160	1.000	LSUM
0220	Minor Traf Devices	8120170	1.000	LSUM
0230	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,400.000	Ft
0240	Plastic Drum, Fluorescent, Furn	8120252	200.000	Ea
0250	Plastic Drum, Fluorescent, Oper	8120253	200.000	Ea
0260	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	24.000	Ft

0270	PTS System, Temp, Furn	8120270	1.000	Ea
0280	PTS System, Temp, Oper	8120271	1.000	Ea
0290	Sign Cover	8120310	10.000	Ea
0300	Sign, Portable, Changeable Message, Furn	8120330	4.000	Ea
0310	Sign, Portable, Changeable Message, Oper	8120331	4.000	Ea
0320	Sign, Type A, Temp, Prismatic, Furn	8120340	1,567.000	Sft
0330	Sign, Type A, Temp, Prismatic, Oper	8120341	12.000	Sft
0340	Sign, Type B, Temp, Prismatic, Oper	8120351	1,555.000	Sft
0350	Traf Regulator Control	8120370	1.000	LSUM
0351	_ Traf Speed Sensor, Portable, Temp	8127050	4.000	Ea
0352	_ Control System, Dynamic Work Zone Traf Monitoring System	8127051	1.000	LSUM

Section: 2

0360	HMA Surface, Rem	5010005	697.000	Syd
0370	Pavt for Butt Joints, Rem	5010008	43.000	Syd
0380	HMA Approach	5010061	98.000	Ton
0390	_ Conc, Deck Surface Repr	7067021	90.000	Cyd
0400	Substructure Horizontal Surface Sealer (S04 of 13082)	7100030	87.000	Syd
0410	Hand Chipping, Deep	7120004	796.000	Syd
0420	Hand Chipping, Other Than Deck	7120007	154.000	Cft
0430	Patch, Full Depth	7120010	16.000	Cyd
0440	Patch, Forming	7120017	862.000	Sft
0450	Patching Conc, C-L	7120112	5.000	Cyd
0460	_ Hand Chipping, Full Depth	7127020	336.000	Cft



Schedule of Pay Items

Report v1

Letting Call: 200619 801

Letting Date: June 19, 2020

Contract ID: 11016-130008

Description: Design Build Project: 7.2 mi of hot mix asphalt reconstruction on I-94 with three lanes in each direction; an auxiliary lane will be added on eastbound I-94 between I-94BL and I-196; acceleration/deceleration lengths will be improved on two ramps of the I-196 interchange, I-94BL will be reconstructed from a four lane divided to three lane roadway with a roundabout at the I-94BL and Crystal Avenue intersection; construction of 2 new bridges, 1 bridge replacement, 1 bridge rehabilitation and 2 bridge removals; and the new US-31 freeway from north of Napier Avenue to I-94/I-94BL in the cities of Benton Harbor, Coloma and Watervliet, Berrien County. This project includes a 5 year materials and workmanship pavement warranty, one 2 year warranty on concrete surface coating and one 2 year warranty on bridge coating.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
130008A	20A0461	N/A	N/A 11016
205792A	1900759	N/A	N/A 11112

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0010	_ Design-Build for JN 130008	1027051	1.000	LSUM
0020	_ Design-Build for JN 205792	1027051	1.000	LSUM
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	300.000	Cyd
0035	_ Fallopiia Plant Material Treatment and Disposal	2057021	6,700.000	Cyd
0045	_ Peat Excavation/Swamp Backfill, Modified	2057021	5,000.000	Cyd
0047	_ Phragmites Plant Material Treatment and Disposal	2057021	23,000.000	Cyd
0050	_ Subgrade Undercutting, Type II, Modified	2057021	1,000.000	Cyd
0060	HMA Quality Initiative	5010007	470,800.000	Dlr
0062	HMA Quality Initiative	5010007	528,000.000	Dlr
0065	Longitudinal Joint Density Quality Initiative	5010018	880,000.000	Dlr
0075	_ Ride Incentive	5017060	125,000.000	Dlr
0080	_ Transporting Salv MDOT Materials, Modified	8107051	1.000	LSUM
0090	_ Power Company Estimated Cost to Design-Builder	8207060	1,650.000	Dlr