



8/4/2021 1:46 PM

AASHTOWare Project™ Version 4.5 Revision 027

Schedule of Pay Items

Report v1

Letting Call: 210917 201**Letting Date:** September 17
2021**Contract ID:** 33044-210093

Description: Design-Build Project: 2.00 mi of reconstruction on I-496, ramp extensions, drainage improvements to include rehabilitation and capital preventive maintenance on 17 bridges from Lansing Road to the Grand River in the city of Lansing, Ingham County. This project contains a 2 year bridge painting warranty and a 2 year warranty on concrete surface coating. Alternate 1 (section 2) is an HMA alternate and contains two 5 year materials and workmanship pavement warranties. Alternate 2 (section 3) is a concrete alternate and contains a 5 year materials and workmanship pavement warranty. This is an OJT VIP Pilot Project. Please see Special Provision for Preparation and Consideration of Bids on On-the-Job-Training Voluntary Incentive Program Projects. Only shortlisted contractors are eligible to bid on this project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
210093A	21A0741	N/A	RBMP, IM 33044

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0010	_ Design-Build for JN 210093	1027051	1.000	LSUM
0020	Dispute Review Board, Hearing	1040010	15,000.000	Dlr
0030	Dispute Review Board, Progress Meeting	1040050	66,500.000	Dlr
0040	Backfill, Swamp	2050001	3,000.000	Cyd
0050	Non Haz Contaminated Material Handling and Disposal, LM	2050031	300.000	Cyd
0060	_ Subgrade Undercutting, Modified	2057021	7,000.000	Cyd
0070	Trench Undercut and Backfill	4021260	1,000.000	Cyd
0080	HMA Quality Initiative	5010007	26,000.000	Dlr
0090	Pavt Joint and Crack Repr, Det 7	5010020	7,200.000	Ft
0100	Pavt Joint and Crack Repr, Det 8	5010021	4,800.000	Ft
0110	Hand Patching	5010025	1,200.000	Ton
0120	_ Ride Incentive	5017060	32,000.000	Dlr
0130	False Decking	7060060	25,150.000	Sft
0140	Reinforcement, Steel, Epoxy Coated	7060092	20,340.000	Lb
0150	Hand Chipping, Shallow	7120003	30.000	Syd
0160	Hand Chipping, Deep	7120004	20.000	Syd
0170	Hand Chipping, Other Than Deck	7120007	1,030.000	Cft
0180	Patch, Full Depth	7120010	40.000	Cyd
0190	Patch, Forming	7120017	430.000	Sft
0200	Flushing Cracks, Water	7120098	130.000	Ft
0210	Structural Crack, Repr	7120099	130.000	Ft
0220	Patching Conc, C-L	7120112	60.000	Cyd

0230	Embedded Galvanic Anode	7120120	900.000	Ea
0240	_ Deck Scaling	7127010	280.000	Sft
0250	_ Hand Chipping, Full Depth	7127020	900.000	Cft
0260	Beam Plate, Seal Perimeter	7130010	570.000	Ft
0270	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	13,230.000	Lb

Section: 2

0280	_ Design-Build for JN 210093 (HMA Pavement Section)	1027051	1.000	LSUM
0290	HMA Quality Initiative	5010007	128,000.000	Dlr

Section: 3

0300	_ Design-Build for JN 210093 (Concrete Pavement Section)	1027051	1.000	LSUM
0310	Conc Quality Initiative	6020401	36,000.000	Dlr

Section: 4

0320	_ Calendar Days of Contract Time for Substantial Completion	1027051	1.000	LSUM
------	---	---------	-------	------
