



6/27/2025 10:07 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 001**Letting Date:** August 1, 2025**Contract ID:** 17011-208427

Description: 14.43 mi of hot mix asphalt reconstruction, concrete curb and gutter, storm sewer, drainage improvements, sidewalks, streetlighting, traffic signal upgrades, aggregate shoulders, corrugations, guardrail and pavement markings on M-123 from south of Curley Lewis Highway to North Whitefish Road, Chippewa County. This project includes two 5 year and one 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
208427A	25A0753	N/A	ST 17011
213407A	N/A	N/A	M 17011

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$638,700.00	1100001	1.000	LSUM
0010	Tree, Rem, 6 inch to 18 inch	2020004	4.000	Ea
0015	Dr Structure, Rem	2030011	11.000	Ea
0020	Sewer, Rem, Less than 24 inch	2030015	1,879.000	Ft
0025	Curb and Gutter, Rem	2040020	202.000	Ft
0030	Guardrail, Rem	2040035	1,576.000	Ft
0035	Pavt, Rem	2040050	115.000	Syd
0040	Embankment, CIP	2050010	285.000	Cyd
0045	Excavation, Earth	2050016	10,737.000	Cyd
0050	Non Haz Contaminated Material Handling and Disposal, LM	2050031	85.000	Cyd
0055	Erosion Control, Check Dam, Stone	2080012	96.000	Ft
0060	Erosion Control, Gravel Access Approach	2080016	3.000	Ea
0065	Erosion Control, Inlet Protection, Fabric Drop	2080020	29.000	Ea
0070	Erosion Control, Inlet Protection, Sediment Trap	2080024	38.000	Ea
0075	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0080	Erosion Control, Sediment Trap	2080034	1.000	Ea
0085	Erosion Control, Silt Fence	2080036	2,836.000	Ft
0090	Subbase, CIP	3010002	5,822.000	Cyd
0095	Aggregate Base	3020001	640.000	Ton
0100	Aggregate Base, 6 inch	3020016	11,844.000	Syd
0105	HMA Base Crushing and Shaping	3050002	338.000	Syd
0110	Material, Surplus and Unsuitable, Rem, LM	3050010	128.000	Cyd
0115	Driveway Maintenance, Commercial	3062000	18.000	Ea
0120	Driveway Maintenance, Residential	3062001	16.000	Ea

0125	Intersection Maintenance	3062002	3.000	Ea
0130	Approach, CI I	3070001	806.000	Ton
0135	Approach, CI I, 6 inch	3070008	333.000	Syd
0140	Approach, CI II	3070021	850.000	Ton
0145	Shld, CI II	3070121	4,156.000	Ton
0150	Trenching	3070200	25.000	Sta
0155	Culv End Sect, 24 inch	4010024	1.000	Ea
0160	Sewer, CI A, 12 inch, Tr Det B	4020033	1,827.000	Ft
0165	Sewer, CI A, 15 inch, Tr Det B	4020034	348.000	Ft
0170	Sewer, CI A, 18 inch, Tr Det B	4020035	317.000	Ft
0175	Sewer, CI A, 24 inch, Tr Det B	4020036	680.000	Ft
0180	Sewer Tap, 15 inch	4021205	1.000	Ea
0185	Sewer Bulkhead, 15 inch	4021231	1.000	Ea
0190	Video Taping Sewer and Culv Pipe	4021275	3,139.000	Ft
0195	Dr Structure Cover, Type B	4030010	6.000	Ea
0200	Dr Structure Cover, Type D	4030025	2.000	Ea
0205	Dr Structure Cover, Type G	4030040	9.000	Ea
0210	Dr Structure Cover, Type J	4030045	6.000	Ea
0215	Dr Structure Cover, Type K	4030050	21.000	Ea
0220	Dr Structure Cover, Type R	4030070	1.000	Ea
0225	Dr Structure, 48 inch dia	4030210	45.000	Ea
0230	Dr Structure, 60 inch dia	4030220	1.000	Ea
0235	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	19.000	Ft
0240	Dr Structure, Add Depth of 60 inch dia, 8 foot to 15 foot	4030260	7.000	Ft
0245	Underdrain, Subbase, 6 inch	4040063	3,487.000	Ft
0250	Underdrain Outlet, 6 inch	4040093	222.000	Ft
0255	Video Inspection of Underdrain	4040200	3,487.000	Ft
0260	Bump Grinding	5010004	100.000	Syd
0265	HMA Surface, Rem	5010005	22,515.000	Syd
0270	HMA Quality Initiative	5010007	55,752.000	Dlr
0275	Longit Joint Density Quality Initiative	5010018	108,400.000	Dlr
0280	Hand Patching	5010025	20.000	Ton
0285	HMA Approach	5010061	1,159.000	Ton
0290	Micro Texture Pavt Milling	5010101	228,160.000	Syd
0295	HMA, 4EL	5012024	3,108.000	Ton
0300	HMA, 5EL	5012036	23,589.000	Ton
0305	HMA, Temp Pavt (4EL)	5012102	40.000	Ton
0310	_ Conc Pavt, Decorative, Nonreinf, 4 inch	6027011	784.000	Syd
0315	_ Conc Pavt, Decorative, Nonreinf, 6 inch	6027011	173.000	Syd
0320	_ Conc Slab, Reinf, 9 inch	6027011	5.000	Syd
0325	Driveway, Nonreinf Conc, 6 inch	8010005	321.000	Syd
0330	Curb, Conc, Det E2	8020002	100.000	Ft
0335	Curb and Gutter, Conc, Det B2	8020016	576.000	Ft

0340	Curb and Gutter, Conc, Det F4	8020038	2,990.000	Ft
0345	Detectable Warning Surface	8030010	45.000	Ft
0350	Curb Ramp Opening, Conc	8030030	101.000	Ft
0355	Sidewalk, Conc, 4 inch	8030044	4,960.000	Sft
0360	Sidewalk, Conc, 6 inch	8030046	4,933.000	Sft
0365	Curb Ramp, Conc, 4 inch	8032001	1,049.000	Sft
0370	Shared use Path, Aggregate	8060010	237.000	Ton
0375	Shared use Path, HMA	8060040	233.000	Ton
0380	Guardrail Approach Terminal, Type 2M	8070044	13.000	Ea
0385	Guardrail Departing Terminal, Type B	8070050	4.000	Ea
0390	Guardrail Post, Culv	8070070	1.000	Ea
0395	Guardrail Reflector	8070080	182.000	Ea
0400	Guardrail Height, Adj	8070100	50.000	Ft
0405	Guardrail, Reconst, Type B	8070105	50.000	Ft
0410	Guardrail, Temp, Type MGS-8, 72 inch Post	8072004	147.000	Ft
0415	Guardrail, Long Span, Det MGS-1	8072121	3.000	Ea
0420	Guardrail, Curved, Type B-CRT	8072154	100.000	Ft
0425	Guardrail, Type B, 72 inch Post	8072171	589.000	Ft
0430	Guardrail, Type B, 96 inch Post	8072172	25.000	Ft
0435	Guardrail, Type MGS-8, 108 inch Post	8072180	1,965.000	Ft
0440	_ Guardrail, Post, Slab, Adhesive Anchored	8077050	1.000	Ea
0445	Delineator Reflector, Green	8100133	17.000	Ea
0450	Fdn, Wood Support, Rem	8100280	6.000	Ea
0455	Installing MDOT Supplied Sign, Type III	8100302	4.000	Ea
0460	Post, Rigid, Delineator	8100361	17.000	Ea
0465	Post, Steel, 3 pound	8100371	374.000	Ft
0470	Post, Wood, 6 inch by 8 inch	8100382	102.000	Ft
0475	Sign, Type II, Rem	8100397	3.000	Ea
0480	Sign, Type IIA	8100398	18.000	Sft
0485	Sign, Type III, Rem	8100403	25.000	Ea
0490	Sign, Type IIIA	8100404	54.000	Sft
0495	Sign, Type IIIB	8100405	82.000	Sft
0500	Reflective Panel for Permanent Sign Support, 6 foot	8100616	8.000	Ea
0505	Ground Mtd Sign Support, Rem	8102010	16.000	Ea
0510	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	200.000	Ft
0515	Pavt Mrkg, Polyurea, Bike, Small Sym	8110105	7.000	Ea
0520	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	130.000	Ft
0525	Pavt Mrkg, Waterborne, 6 inch, White	8110233	153,377.000	Ft
0530	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	43,240.000	Ft
0535	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	153,377.000	Ft
0540	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	43,240.000	Ft
0545	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0550	Pavt Mrkg, Polyurea, School	8110414	2.000	Ea
0555	Pavt Mrkg, Polyurea, Stop	8110415	72.000	Ea
0560	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	2.000	Ea

0565	Recessing Pavt Mrkg, Longit	8110450	9,790.000	Ft
0570	Recessing Pavt Mrkg, Transv	8110451	272.000	Sft
0575	Protective Ovly, Snowmobile Trail Crossing	8110550	455.000	Syd
0580	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0585	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0590	Connected Arrow Board, Type C, Furn	8120155	7.000	Ea
0595	Connected Arrow Board, Type C, Oper	8120156	7.000	Ea
0600	Minor Traf Devices	8120170	1.000	LSUM
0605	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	5,000.000	Ft
0610	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	100.000	Ft
0615	Plastic Drum, Fluorescent, Furn	8120252	1,275.000	Ea
0620	Plastic Drum, Fluorescent, Oper	8120253	1,275.000	Ea
0625	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	72.000	Ft
0630	PTS, Temp, Furn	8120272	3.000	Ea
0635	PTS, Temp, Oper	8120273	3.000	Ea
0640	Sign Cover	8120310	12.000	Ea
0645	Sign, Type B, Temp, Prismatic, Furn	8120350	1,539.000	Sft
0650	Sign, Type B, Temp, Prismatic, Oper	8120351	1,539.000	Sft
0655	Traf Regulator Control	8120370	1.000	LSUM
0660	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	8,455.000	Ft
0665	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	13,423.000	Ft
0670	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	4,110.000	Ft
0675	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	11,838.000	Ft
0680	Pavt Mrkg, Wet Reflective, Type NR, Tape, 6 inch, White, Temp	8122008	3,000.000	Ft
0685	Pavt Mrkg, Wet Reflective, Type NR, Tape, 6 inch, Yellow, Temp	8122010	350.000	Ft
0690	Rumble Strip, Temp, Portable, Furn	8122188	36.000	Ea
0695	Rumble Strip, Temp, Portable, Oper	8122189	36.000	Ea
0700	Slope Restoration, Non-Freeway, Type A	8162001	323.000	Syd
0705	Slope Restoration, Non-Freeway, Type B	8162002	2,718.000	Syd
0710	Slope Restoration, Non-Freeway, Type C	8162003	830.000	Syd
0715	Conduit, DB, 1, 1 1/2 inch	8182048	40.000	Ft
0720	Conduit, DB, 3, 3 inch	8182056	40.000	Ft
0725	Conduit, Schedule 80, 3 inch	8182148	3,200.000	Ft
0730	DB Cable, in Conduit, 600V, 1/C#6	8182187	9,250.000	Ft
0735	DB Cable, in Conduit, 600V, 1/C#8	8182188	10,790.000	Ft
0740	DB Cable, in Conduit, 600V, 1/C#10	8182189	8,700.000	Ft
0745	Cable, Equipment Grounding Wire, 1/C#6	8182291	3,200.000	Ft
0750	Cable, Equipment Grounding Wire, 1/C#8	8182292	6,150.000	Ft
0755	Cable, Equipment Grounding Wire, 1/C#10	8182293	1,100.000	Ft

0760	Hh, Round	8182310	24.000	Ea
0765	Metered Serv	8182338	2.000	Ea
0770	Wood Pole, Rem	8182363	1.000	Ea
0775	Serv Disconnect	8182366	1.000	Ea
0780	Serv Disconnect, Rem	8182367	1.000	Ea
0785	Light Std Arm, Install	8190275	44.000	Ea
0790	Light Std Fdn	8190279	22.000	Ea
0795	Light Std Shaft, 30 foot or less	8190285	22.000	Ea
0800	_ Elec Service Panel	8197050	1.000	Ea
0805	_ Ltg Control Panel	8197050	1.000	Ea
0810	_ Luminaire, (Municipal)	8197050	44.000	Ea
0815	_ Outdoor Outlet	8197050	22.000	Ea
0820	_ Wire Grip Rodent Barrier	8197050	22.000	Ea
0825	Case Sign (LED), Four Way, 24 inch by 30 inch	8200023	1.000	Ea
0830	Controller and Cabinet, Rem	8200030	1.000	Ea
0835	Fdn, Rem	8200065	1.000	Ea
0840	Flsh Beacon, Controller and Cabinet, Solid State	8200070	1.000	Ea
0845	Span Wire	8200140	1.000	Ea
0850	Span Wire, Rem	8200141	1.000	Ea
0855	Steel Pole, Rem	8200145	1.000	Ea
0860	TS, Span Wire Mtd, Rem	8200182	2.000	Ea
0865	Case Sign, Non-Illuminated, Rem	8200432	1.000	Ea
0870	Strain Pole, Steel, 6 bolt, Size 1A	8200463	2.000	Ea
0875	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	24.000	Ft
0880	Casing, 42 inch	8200485	17.000	Ft
0885	TS, Three Way Span Wire Mtd, One Sect (LED), Long Life	8202281	2.000	Ea
0890	Monument Box	8210001	2.000	Ea
0895	Monument Box, Adj	8210005	29.000	Ea
0900	Monument Preservation	8210010	62.000	Ea
0905	Protect Corners	8210020	2.000	Ea
0910	Centerline Corrugations, Milled, HMA	8220013	69,298.000	Ft
0915	Contractor Staking	8240001	1.000	LSUM
0920	Staking Plan Errors and Extras, Max \$180/hour	8240002	67.000	Hr

Schedule of Pay Items

Report v1

Letting Call: 250801 002

Letting Date: August 1, 2025

Contract ID: 82000-220412

Description: 14.85 mi of hot mix asphalt cold milling and resurfacing, concrete curb, gutter, sidewalk and ramps and pavement markings at 18 locations from 14th Street to I-75 Chrysler Service Drive in the city of Detroit, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220412A	25A0727	N/A	STU 82000
220415A	25A0734	N/A	STU 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, Detroit Connecting Railroad	1027060	6,500.000	Dlr
0010	Mobilization, Max \$1,547,600.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	320.000	Ft
0020	Pavt, Rem	2040050	3,177.000	Syd
0025	Sidewalk, Rem	2040055	23,014.000	Syd
0030	Track, Rem	2040065	50.000	Ft
0035	_ Curb, Rem, Modified	2047001	13,676.000	Ft
0040	_ Integral Curb and Sidewalk, 2 Feet, Rem, Modified	2047001	2,012.000	Ft
0045	Granular Material, CI II	2050023	75.000	Cyd
0050	Non Haz Contaminated Material Handling and Disposal, LM	2050031	100.000	Cyd
0055	Subgrade Undercutting, Type II	2050041	50.000	Cyd
0060	_ Excavation, Earth, Modified	2057021	149.000	Cyd
0065	Aggregate Base, 4 inch	3020010	50.000	Syd
0070	_ Dr Structure Lead, Cleaning, Modified	4037001	6,670.000	Ft
0075	_ Dr Structure Cleaning, Modified	4037050	642.000	Ea
0080	_ Dr Structure Cover, Adj, Case 1, Modified	4037050	1,503.000	Ea
0085	_ Dr Structure Cover, Adj, Case 2, Modified	4037050	40.000	Ea
0090	_ Dr Structure Cover, Type CB, Modified	4037050	642.000	Ea
0095	_ Dr Structure Cover, Type PLD HH, Modified	4037050	72.000	Ea
0100	_ Dr Structure Cover, Type PLD MH, Modified	4037050	37.000	Ea
0105	_ Dr Structure Cover, Type Sewer MH, Modified	4037050	209.000	Ea
0110	_ Dr Structure Cover, Type Water MH Modified	4037050	293.000	Ea
0115	_ Dr Structure Cover, Type Water Valve Box , Modified	4037050	86.000	Ea
0120	_ Reconstructing Dr Structure, Case 1, Modified	4037050	105.000	Ea
0125	_ Reconstructing Dr Structure, Case 2, Modified	4037050	10.000	Ea

0130	Pavt, Cleaning	5010001	1.000	LSUM
0135	HMA Surface, Rem	5010005	50.000	Syd
0140	Hand Patching	5010025	10.000	Ton
0145	HMA, 4EML	5012025	36,515.000	Ton
0150	HMA, 5EML	5012037	27,389.000	Ton
0155	_ Cold Milling HMA Surface, Approach, Modified	5017011	28,184.000	Syd
0160	_ Cold Milling HMA Surface, Modified	5017011	310,049.000	Syd
0165	_ Conditioning Existing Pavement, Modified	5017031	40.000	Ton
0170	_ HMA Approach, Driveway, Modified	5017031	246.000	Ton
0175	_ HMA Approach, Modified	5017031	5,981.000	Ton
0180	Cement	6030005	10.000	Ton
0185	_ Pavt Repr, Nonreinf Conc, 10 inch, Modified	6037011	2,601.000	Syd
0190	_ Pavt Repr, Rem, Modified	6037011	2,601.000	Syd
0195	Driveway, Nonreinf Conc, 8 inch	8010007	1,058.000	Syd
0200	Curb and Gutter, Conc, Det F3	8020037	320.000	Ft
0205	_ Curb, Conc, Detail CD, Modified	8027001	6,744.000	Ft
0210	_ Detectable Warning Surface Tile, Modified	8027001	4,166.000	Ft
0215	Curb Ramp Opening, Conc	8030030	6,932.000	Ft
0220	_ Grinding Sidewalk, Modified	8037001	934.000	Ft
0225	_ Integral Curb and Sidewalk, 2 Feet, Modified	8037001	2,012.000	Ft
0230	_ Sidewalk Ramp, ADA, Modified	8037010	48,057.000	Sft
0235	_ Sidewalk, Conc with Tree Roots, 4 inch, Modified	8037010	11,084.000	Sft
0240	_ Sidewalk, Conc with Tree Roots, 6 inch, Modified	8037010	200.000	Sft
0245	_ Sidewalk, Conc, 4 inch, Modified	8037010	138,897.000	Sft
0250	_ Sidewalk, Conc, 6 inch, Modified	8037010	8,840.000	Sft
0255	Pavt Mrkg, Polyurea, 4 inch, White	8110091	8,221.000	Ft
0260	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	15,695.000	Ft
0265	Pavt Mrkg, Polyurea, Bike, Small Sym	8110105	56.000	Ea
0270	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, White	8110108	10,898.000	Ft
0275	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	1,750.000	Ft
0280	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	4,593.000	Ft
0285	Pavt Mrkg, Polyurea, 18 inch, Stop Bar	8110113	4,420.000	Ft
0290	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	102.000	Ft
0295	Pavt Mrkg, Polyurea, Sharrow Sym	8110115	6.000	Ea
0300	Pavt Mrkg, Sprayable Thermopl, 4 inch, White	8110153	60,979.000	Ft
0305	Pavt Mrkg, Sprayable Thermopl, 4 inch, Yellow	8110154	40,992.000	Ft
0310	Pavt Mrkg, Sprayable Thermopl, 6 inch, White	8110155	17,733.000	Ft
0315	Rem Spec Mrkg	8110343	1,000.000	Sft
0320	Pavt Mrkg, Polyurea, Bus	8110400	15.000	Ea
0325	Pavt Mrkg, Polyurea, Rt and Lt Turn Arrow Sym	8110404	1.000	Ea
0330	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	17.000	Ea
0335	Pavt Mrkg, Polyurea, Only	8110410	31.000	Ea
0340	Pavt Mrkg, Polyurea, Railroad Sym	8110411	2.000	Ea
0345	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	9.000	Ea
0350	Pavt Mrkg, Polyurea, Stop	8110415	15.000	Ea

0355	Pavt Mrkg, Polyurea, Thru and Lt Turn Arrow Sym	8110416	2.000	Ea
0360	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	6.000	Ea
0365	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	7.000	Ea
0370	Recessing Pavt Mrkg, Transv	8110451	19,770.000	Sft
0375	Scarification, for Polyurea Spec Mrkg	8112159	1,000.000	Sft
0380	Pavt Mrkg, Polyurea, Bike Thru Arrow Sym	8112170	56.000	Ea
0385	_ Pavt Mrkg, Polymer Cement, Base Field, Green	8117010	500.000	Sft
0390	_ Pavt Mrkg, Polymer Cement, Bike Directional Arrow, White	8117050	5.000	Ea
0395	_ Pavt Mrkg, Polymer Cement, Bike Sym, Small, White	8117050	5.000	Ea
0400	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	60.000	Ea
0405	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	60.000	Ea
0410	Pedestrian Type II Barricade, Temp	8120026	30.000	Ea
0415	Lighted Arrow, Type C, Furn	8120140	12.000	Ea
0420	Lighted Arrow, Type C, Oper	8120141	12.000	Ea
0425	Minor Traf Devices	8120170	1.000	LSUM
0430	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	2,000.000	Ft
0435	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	200.000	Ft
0440	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	8,384.000	Ft
0445	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	5,180.000	Ft
0450	Plastic Drum, Fluorescent, Furn	8120252	1,200.000	Ea
0455	Plastic Drum, Fluorescent, Oper	8120253	1,200.000	Ea
0460	Sign, Type B, Temp, Prismatic, Furn	8120350	3,000.000	Sft
0465	Sign, Type B, Temp, Prismatic, Oper	8120351	3,000.000	Sft
0470	Traf Regulator Control	8120370	1.000	LSUM
0475	Sodding	8160055	50.000	Syd
0480	Water, Sodding/Seeding	8160090	100.000	Unit
0485	_ Seeding, Mixture THM, Modified	8167011	1,718.000	Syd
0490	_ Topsoil Surface, Furn, LM, Modified	8167021	315.000	Cyd
0495	Monument Box	8210001	5.000	Ea
0500	Monument Preservation	8210010	5.000	Ea
0505	_ Underground Sprinklers, Identify, Protect and Restore, Modified	8237050	30.000	Ea
0510	_ Water Shutoff, Adj, Case 1, Modified	8237050	126.000	Ea
0515	_ Door Hanger Notifications, Modified	8237051	1.000	LSUM

Schedule of Pay Items

Report v1

Letting Call: 250801 003

Letting Date: August 1, 2025

Contract ID: 38000-219895

Description: 6.89 mi of tree removal, flashing LED stop sign, sign upgrades, guardrail improvements, and pavement markings along Jackson Road from Vicary Road to Kimmel Road and Ackerson Lake Road at Hart Road, Jackson County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219895A	25A0728	N/A	HRRR 38000
220179A	25A0729	N/A	HSIP 38000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$42,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	49.000	Ea
0015	Tree, Rem, 37 inch or Larger	2020003	20.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	23.000	Ea
0025	Stump, Rem, 19 inch to 36 inch	2020006	1.000	Ea
0030	Guardrail, Rem	2040035	1,198.000	Ft
0035	Embankment, CIP	2050010	250.000	Cyd
0040	Guardrail Approach Terminal, Type 2M	8070044	6.000	Ea
0045	Guardrail Reflector	8070080	56.000	Ea
0050	Guardrail, Type MGS-8, 108 inch Post	8072180	1,200.000	Ft
0055	Delineator Reflector, Green	8100133	6.000	Ea
0060	Post, Rigid, Delineator	8100361	6.000	Ea
0065	Post, Steel, 3 pound	8100371	1,416.000	Ft
0070	Sign, Type III, Erect, Salv	8100402	9.000	Ea
0075	Sign, Type III, Rem	8100403	66.000	Ea
0080	Sign, Type IIIA	8100404	179.000	Sft
0085	Sign, Type IIIB	8100405	264.000	Sft
0090	Sign, Type V, Rem	8100421	2.000	Ea
0095	Sign, Type VB	8100425	24.000	Sft
0100	Reflective Panel for Permanent Sign Support, 6 foot	8100616	84.000	Ea
0105	Sign, Type III, Rem, Salv	8102003	9.000	Ea
0110	Ground Mtd Sign Support, Rem	8102010	47.000	Ea
0115	_ Flashing LED Border Sign, Solar	8107050	1.000	Ea
0120	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	102.000	Ft
0125	Rem Spec Mrkg	8110343	80.000	Sft
0130	Recessing Pavt Mrkg, Longit	8110450	142,578.000	Ft

0135	Recessing Pavt Mrkg, Transv	8110451	204.000	Sft
0140	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 4 inch, White	8112000	71,692.000	Ft
0145	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 4 inch, Yellow	8112003	70,886.000	Ft
0150	Pavt Mrkg, Wet Reflective Waterborne, 4 inch, White	8112144	71,692.000	Ft
0155	Pavt Mrkg, Wet Reflective Waterborne, 4 inch, Yellow	8112147	70,886.000	Ft
0160	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	220.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	220.000	Ea
0170	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0175	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0180	Minor Traf Devices	8120170	1.000	LSUM
0185	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0190	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0195	Sign, Type B, Temp, Prismatic, Furn	8120350	457.000	Sft
0200	Sign, Type B, Temp, Prismatic, Oper	8120351	457.000	Sft
0205	Traf Regulator Control	8120370	1.000	LSUM
0210	Slope Restoration, Non-Freeway, Type A	8162001	1,150.000	Syd



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 004**Letting Date:** August 1, 2025**Contract ID:** 82000-221319**Description:** 0.70 mi of concrete sidewalk and streetscape improvements along various routes in the city of Wyandotte, Wayne County. This is a Local Agency project.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221319A	25A0720	N/A	TAU 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$143,000.00	1100001	1.000	LSUM
0010	Curb, Rem	2040021	2,110.000	Ft
0015	Sidewalk, Rem	2040055	4,617.000	Syd
0020	Erosion Control, Inlet Protection, Fabric Drop	2080020	30.000	Ea
0025	Dr Structure Cover, Adj, Case 1	4030005	10.000	Ea
0030	Curb, Conc, Det E2	8020002	241.000	Ft
0035	_ Curb, Conc, Monolithic	8027001	1,182.000	Ft
0040	_ Curb, Repr	8027001	1,987.000	Ft
0045	Detectable Warning Surface	8030010	305.000	Ft
0050	Curb Ramp Opening, Conc	8030030	687.000	Ft
0055	Sidewalk, Conc, 4 inch	8030044	9,637.000	Sft
0060	Sidewalk, Conc, 6 inch	8030046	80.000	Sft
0065	Sidewalk, Conc, 8 inch	8030048	2,319.000	Sft
0070	Sidewalk, Clay Brick Pavers, Rem	8030051	33,613.000	Sft
0075	Curb Ramp, Conc, 6 inch	8032002	8,704.000	Sft
0080	_ Sidewalk, Conc, 4 inch, Spec	8037010	54,102.000	Sft
0085	Pedestrian Type II Barricade, Temp	8120026	100.000	Ea
0090	Minor Traf Devices	8120170	1.000	LSUM
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	24.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	24.000	Sft
0105	TS Face, Bag	8200458	12.000	Ea
0110	TS Face, Bag, Rem	8200459	12.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 005**Letting Date:** August 1, 2025**Contract ID:** 25000-220171**Description:** Installation of solar beacons, intersection signing and pavement markings on Belsay Road at Carpenter Road, Genesee County. This is a Local Agency project.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220171A	25A0723	N/A	HSIP 25000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$3,000.00	1100001	1.000	LSUM
0010	Post, Steel, 3 pound	8100371	112.000	Ft
0015	Post, Wood, 6 inch by 8 inch	8100382	60.000	Ft
0020	Sign, Type III, Rem	8100403	14.000	Ea
0025	Sign, Type IIIA	8100404	36.000	Sft
0030	Sign, Type IIIB	8100405	54.000	Sft
0035	Reflective Panel for Permanent Sign Support, 6 foot	8100616	16.000	Ea
0040	Ground Mtd Sign Support, Rem	8102010	16.000	Ea
0045	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,000.000	Ft
0050	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	1,000.000	Ft
0055	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	20.000	Ea
0060	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	20.000	Ea
0065	Minor Traf Devices	8120170	1.000	LSUM
0070	Sign, Type B, Temp, Prismatic, Furn	8120350	100.000	Sft
0075	Sign, Type B, Temp, Prismatic, Oper	8120351	100.000	Sft
0080	Flsh Beacon, Solar Power	8200071	4.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 006**Letting Date:** August 1, 2025**Contract ID:** 58000-222053**Description:** Installation of a dynamic radar speed sign, LED border stop signs and tree removals on various routes at multiple locations, Monroe County. This is a Local Agency project.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222053A	25A0712	N/A	HSIP 58000
222054A	25A0713	N/A	HSIP 58000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$37,000.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.100	Acre
0015	Tree, Rem, 37 inch or Larger	2020003	4.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	4.000	Ea
0025	Post, Steel, 3 pound	8100371	2,693.000	Ft
0030	Sign, Type III, Erect, Salv	8100402	14.000	Ea
0035	Sign, Type III, Rem	8100403	84.000	Ea
0040	Sign, Type IIIB	8100405	688.000	Sft
0045	Reflective Panel for Permanent Sign Support, 6 foot	8100616	118.000	Ea
0050	Sign, Type III, Rem, Salv	8102003	14.000	Ea
0055	Ground Mtd Sign Support, Rem	8102010	52.000	Ea
0060	_ Advisory Speed Radar Assembly	8107050	18.000	Ea
0065	_ Speed Radar Assembly	8107050	20.000	Ea
0070	_ Stop Flasher Assembly	8107050	10.000	Ea
0075	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0080	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	4.000	Ea
0085	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	20.000	Ea
0090	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	20.000	Ea
0095	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0100	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0105	Minor Traf Devices	8120170	1.000	LSUM
0110	Sign, Type B, Temp, Prismatic, Furn	8120350	500.000	Sft
0115	Sign, Type B, Temp, Prismatic, Oper	8120351	500.000	Sft
0120	Traf Regulator Control	8120370	1.000	LSUM

Schedule of Pay Items

Report v1

Letting Call: 250801 007

Letting Date: August 1, 2025

Contract ID: 41000-220162

Description: 0.53 mi of roundabout construction, sidewalk ramps, lighting, signing and pavement markings at the intersection of Pine Island Drive at 10 Mile Road, Kent County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220162A	25A0736	N/A	HSIP 41000
223345A	25A0737	N/A	STPF 41000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$181,300.00	1100001	1.000	LSUM
0010	Stump, Rem, 6 inch to 18 inch	2020008	1.000	Ea
0015	Culv, Rem, Less than 24 inch	2030001	10.000	Ea
0020	Dr Structure, Rem	2030011	3.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	687.000	Ft
0030	Curb and Gutter, Rem	2040020	207.000	Ft
0035	Fence, Rem	2040025	183.000	Ft
0040	Masonry and Conc Structure, Rem	2040045	7.000	Cyd
0045	Pavt, Rem	2040050	445.000	Syd
0050	_ Exploratory Trenching	2047001	30.000	Ft
0055	Embankment, CIP	2050010	680.000	Cyd
0060	Excavation, Earth	2050016	8,760.000	Cyd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	20.000	Cyd
0070	Erosion Control, Inlet Protection, Fabric Drop	2080020	15.000	Ea
0075	Erosion Control, Silt Fence	2080036	2,800.000	Ft
0080	_ Project Cleanup, Modified	2097051	1.000	LSUM
0085	Subbase, CIP	3010002	5,467.000	Cyd
0090	_ Aggregate Base, 6 inch, Modified	3027011	12,732.000	Syd
0095	_ Aggregate Surface Cse, 6 inch, Modified	3067011	231.000	Syd
0100	Approach, CI II, 6 inch	3070028	91.000	Syd
0105	Shld, CI I, 6 inch	3070108	508.000	Syd
0110	Culv End Sect, 12 inch	4010012	4.000	Ea
0115	Culv End Sect, 18 inch	4010018	1.000	Ea
0120	Culv, CI F, 12 inch	4010607	205.000	Ft
0125	Culv, CI F, 18 inch	4010609	26.000	Ft
0130	Sewer, CI A, 12 inch, Tr Det B	4020033	1,270.000	Ft

0135	Sewer, CI A, 18 inch, Tr Det B	4020035	468.000	Ft
0140	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0145	Dr Structure Cover, Type C	4030015	6.000	Ea
0150	Dr Structure Cover, Type J	4030045	9.000	Ea
0155	Dr Structure, 48 inch dia	4030210	15.000	Ea
0160	Underdrain Outlet, 6 inch	4040093	149.000	Ft
0165	Underdrain, Outlet Ending, 6 inch	4040113	6.000	Ea
0170	_ Underdrain, Subbase, 6 inch, Modified	4047001	2,980.000	Ft
0175	HMA Surface, Rem	5010005	11,044.000	Syd
0180	Hand Patching	5010025	2.000	Ton
0185	HMA Approach	5010061	67.000	Ton
0190	HMA, 4EML	5012025	2,270.000	Ton
0195	HMA, 5EML	5012037	758.000	Ton
0200	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	894.000	Syd
0205	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	367.000	Syd
0210	Joint, Contraction, Cp	6020200	210.000	Ft
0215	Joint, Expansion, E3	6020208	60.000	Ft
0220	Driveway, Nonreinf Conc, 7 inch	8010006	85.000	Syd
0225	Curb, Conc, Det E1	8020001	173.000	Ft
0230	Curb, Conc, Det E2	8020002	110.000	Ft
0235	Curb and Gutter, Conc, Det B2	8020016	1,928.000	Ft
0240	Divider, Conc, Type I	8022000	387.000	Sft
0245	_ Curb and Gutter, Conc, Det B2, Modified	8027001	1,356.000	Ft
0250	_ Curb and Gutter, Conc, Det D2, Modified	8027001	268.000	Ft
0255	Curb Ramp Opening, Conc	8030030	200.000	Ft
0260	Curb Ramp, Conc, 6 inch	8032002	1,190.000	Sft
0265	Curb Slp, HMA	8050010	1,118.000	Ft
0270	Post, Mailbox	8070095	12.000	Ea
0275	Delineator Reflector, Yellow	8100132	4.000	Ea
0280	Post Hole Through Conc for Steel Post	8100340	12.000	Ea
0285	Post, Steel, 3 pound	8100371	864.000	Ft
0290	Sign, Type IIA	8100398	48.000	Sft
0295	Sign, Type IIB	8100399	32.000	Sft
0300	Sign, Type III, Rem	8100403	48.000	Ea
0305	Sign, Type IIIA	8100404	23.000	Sft
0310	Sign, Type IIIB	8100405	248.000	Sft
0315	Sign, Type V, Rem	8100421	1.000	Ea
0320	Post, Flexible, Delineator, Surface Mtd, 48 inch	8100552	4.000	Ea
0325	Reflective Panel for Permanent Sign Support, 3 foot	8100613	24.000	Ea
0330	Reflective Panel for Permanent Sign Support, 6 foot	8100616	4.000	Ea
0335	Ground Mtd Sign Support, Rem	8102010	40.000	Ea
0340	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	391.000	Ft
0345	Pavt Mrkg, Polyurea, 12 inch, White	8110111	80.000	Ft
0350	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	5,154.000	Ft
0355	Pavt Mrkg, Waterborne, 6 inch, White	8110233	4,551.000	Ft

0360	Recessing Pavt Mrkg, Longit	8110450	9,705.000	Ft
0365	Recessing Pavt Mrkg, Transv	8110451	471.000	Sft
0370	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0375	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0380	Minor Traf Devices	8120170	1.000	LSUM
0385	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0390	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0395	Sign, Type B, Temp, Prismatic, Furn	8120350	768.000	Sft
0400	Sign, Type B, Temp, Prismatic, Oper	8120351	768.000	Sft
0405	Traf Regulator Control	8120370	1.000	LSUM
0410	Riprap, Plain	8130010	63.000	Syd
0415	_ HMA Spillway	8147011	25.000	Syd
0420	Slope Restoration, Non-Freeway, Type A	8162001	1,680.000	Syd
0425	Slope Restoration, Non-Freeway, Type D	8162004	170.000	Syd
0430	Slope Restoration, Non-Freeway, Type F	8162006	2,380.000	Syd
0435	Slope Restoration, Non-Freeway, Type G	8162007	280.000	Syd
0440	Power Company (Estimated Cost to Contractor)	8180001	1,000.000	Dlr
0445	Conduit, Schedule 80, 2 inch	8182146	360.000	Ft
0450	DB Cable, in Conduit, 600V, 1/C#8	8182188	1,140.000	Ft
0455	Cable, Equipment Grounding Wire, 1/C#8	8182292	380.000	Ft
0460	Hh, Heavy Duty Cover	8182308	4.000	Ea
0465	Wood Pole, Rem	8182363	2.000	Ea
0470	Serv Disconnect, Rem	8182367	1.000	Ea
0475	Light Std Arm, 15 foot	8190269	4.000	Ea
0480	Light Std Fdn	8190279	4.000	Ea
0485	Light Std Shaft, 30 foot or less	8190285	4.000	Ea
0490	Luminaire	8190330	4.000	Ea
0495	_ Ltg Control Panel	8197050	1.000	Ea
0500	Controller and Cabinet, Rem	8200030	1.000	Ea
0505	Span Wire, Rem	8200141	1.000	Ea
0510	TS, Span Wire Mtd, Rem	8200182	2.000	Ea
0515	Junction Box, Rem	8200457	1.000	Ea
0520	Monument Preservation	8210010	2.000	Ea
0525	Water Shutoff, Adj, Case 1	8230421	1.000	Ea
0530	Gate Box, Adj, Case 1	8230431	3.000	Ea
0535	Gate Box, Adj, Case 2	8230432	2.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 008**Letting Date:** August 1, 2025**Contract ID:** 25000-214364

Description: 1.09 mi of hot mix asphalt reconstruction, aggregate base, concrete curb and gutter, signing and pavement markings on Green Road from Gale Road to Ridge Road in the village of Goodrich, Genesee County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214364A	25A0730	N/A	STUL 25000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$110,000.00	1100001	1.000	LSUM
0010	Embankment, CIP	2050010	2,000.000	Cyd
0015	Excavation, Earth	2050016	1,200.000	Cyd
0020	_ Subgrade Undercutting, Type IV, Modified	2057021	1,500.000	Cyd
0025	Erosion Control, Silt Fence	2080036	10,000.000	Ft
0030	_ Aggregate Base, Modified	3027031	6,075.000	Ton
0035	_ Maintenance Gravel, Modified	3067031	300.000	Ton
0040	_ Approach, CI II, Modified	3077031	252.000	Ton
0045	_ Shld, CI II, Modified	3077031	1,750.000	Ton
0050	HMA Surface, Rem	5010005	1,698.000	Syd
0055	HMA, 3EL	5012012	2,580.000	Ton
0060	HMA, 5EL	5012036	1,710.000	Ton
0065	_ HMA Residential Approach, Spec	5017011	907.000	Syd
0070	Driveway, Nonreinf Conc, 6 inch	8010005	124.000	Syd
0075	Curb and Gutter, Conc, Det B2	8020016	431.000	Ft
0080	Spillway, Conc	8020075	15.000	Ft
0085	Post, Mailbox	8070095	41.000	Ea
0090	Post, Steel, 3 pound	8100371	546.000	Ft
0095	Sign, Type III, Rem	8100403	12.000	Ea
0100	Sign, Type IIIA	8100404	46.000	Sft
0105	Sign, Type IIIB	8100405	140.000	Sft
0110	Sign, Type V, Rem	8100421	1.000	Ea
0115	Sign, Type VB	8100425	8.000	Sft
0120	Reflective Panel for Permanent Sign Support, 6 foot	8100616	8.000	Ea
0125	Ground Mtd Sign Support, Rem	8102010	12.000	Ea
0130	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	60.000	Ft
0135	Pavt Mrkg, Waterborne, 4 inch, White	8110231	11,478.000	Ft

0140	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	5,851.000	Ft
0145	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	11,478.000	Ft
0150	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	5,851.000	Ft
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	4.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0170	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0175	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0180	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0185	Minor Traf Devices	8120170	1.000	LSUM
0190	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	900.000	Ft
0195	Sign, Type B, Temp, Prismatic, Furn	8120350	435.000	Sft
0200	Sign, Type B, Temp, Prismatic, Oper	8120351	435.000	Sft
0205	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	120.000	Sft
0210	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	120.000	Sft
0215	Traf Regulator Control	8120370	1.000	LSUM
0220	Slope Restoration, Non-Freeway, Type E	8162005	5,000.000	Syd
0225	Monument Box	8210001	2.000	Ea
0230	Monument Preservation	8210010	2.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 009**Letting Date:** August 1, 2025**Contract ID:** 24000-218895**Description:** 2.46 mi of hot mix asphalt crush, shape and resurface, aggregate shoulder, guardrail and pavement markings on Brutus Road from US-31 to Brill Road, Emmett County. This is a Local Agency project.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218895A	25A0721	N/A	EAR 24000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$120,000.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	750.000	Ft
0015	Pavt, Rem	2040050	20.000	Syd
0020	Embankment, LM	2050011	1,700.000	Cyd
0025	Aggregate Base	3020001	6,900.000	Ton
0030	HMA Base Crushing and Shaping	3050002	42,855.000	Syd
0035	Approach, CI I	3070001	160.000	Ton
0040	Approach, CI II	3070021	200.000	Ton
0045	Shld, CI II	3070121	974.000	Ton
0050	Trenching	3070200	258.000	Sta
0055	HMA Surface, Rem	5010005	200.000	Syd
0060	HMA Approach	5010061	113.000	Ton
0065	HMA, 4EL	5012024	6,692.000	Ton
0070	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0075	Guardrail Departing Terminal, Type MGS	8070052	2.000	Ea
0080	Guardrail Reflector	8070080	26.000	Ea
0085	Post, Mailbox	8070095	13.000	Ea
0090	Guardrail, Curved, Type MGS-8, 108 inch Post	8072146	50.000	Ft
0095	Guardrail, Type MGS-8, 108 inch Post	8072180	625.000	Ft
0100	Pavt Mrkg, Waterborne, 4 inch, White	8110231	26,200.000	Ft
0105	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	12,000.000	Ft
0110	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	300.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	300.000	Ea
0120	Lighted Arrow, Type C, Furn	8120140	3.000	Ea
0125	Lighted Arrow, Type C, Oper	8120141	3.000	Ea
0130	Minor Traf Devices	8120170	1.000	LSUM
0135	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,100.000	Ft

0140	Sign, Type B, Temp, Prismatic, Furn	8120350	669.000	Sft
0145	Sign, Type B, Temp, Prismatic, Oper	8120351	669.000	Sft
0150	Traf Regulator Control	8120370	1.000	LSUM
0155	Slope Restoration, Non-Freeway, Type A	8162001	3,000.000	Syd
0160	Monument Box	8210001	5.000	Ea
0165	Monument Preservation	8210010	5.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 010**Letting Date:** August 1, 2025**Contract ID:** 80000-218644

Description: 0.23 mi of hot mix asphalt reconstruction, concrete sidewalk and ramps, sewer work and pavement markings on Huron Street from Kalamazoo Street to Broadway Street in the city of South Haven, Van Buren County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218644A	25A0725	N/A	STUL 80000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$45,000.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	8.000	Ea
0015	Sewer, Rem, Less than 24 inch	2030015	189.000	Ft
0020	Sidewalk, Rem	2040055	553.000	Syd
0025	_ Pavt Rem, Modified	2047011	5,647.000	Syd
0030	Subgrade Undercutting, Type II	2050041	223.000	Cyd
0035	Flowable Fill, Non-Structural	2050148	3.000	Cyd
0040	_ Machine Grading, Modified	2057002	11.000	Sta
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	8.000	Ea
0050	Subbase, CIP	3010002	1,825.000	Cyd
0055	Aggregate Base, 6 inch	3020016	549.000	Syd
0060	Aggregate Base, 8 inch	3020020	5,103.000	Syd
0065	Maintenance Gravel, LM	3060021	294.000	Cyd
0070	Sewer, Cl B, 12 inch, Tr Det B	4020183	455.000	Ft
0075	Sewer, Cl B, 15 inch, Tr Det B	4020184	123.000	Ft
0080	Sewer Tap, 15 inch	4021205	1.000	Ea
0085	Video Taping Sewer and Culv Pipe	4021275	728.000	Ft
0090	_ Cured-In-Place Lining, 12 inch	4027001	35.000	Ft
0095	_ Cured-In-Place Lining, 15 inch	4027001	115.000	Ft
0100	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0105	Dr Structure Cover, Type D	4030025	5.000	Ea
0110	Dr Structure Cover, Type K	4030050	7.000	Ea
0115	Dr Structure, 24 inch dia	4030200	7.000	Ea
0120	Dr Structure, 48 inch dia	4030210	6.000	Ea
0125	_ Dr Struture Cover Frame, Type B, Modified	4037050	3.000	Ea
0130	_ Dr Struture Cover Frame, Type Q, Modified	4037050	3.000	Ea
0135	_ Utility Structure Cover, Logo	4037050	8.000	Ea

0140	Underdrain, Subbase, 6 inch	4040063	2,189.000	Ft
0145	Hand Patching	5010025	29.000	Ton
0150	HMA, 4EML	5012025	748.000	Ton
0155	HMA, 5EML	5012037	450.000	Ton
0160	Conc Pavt, Nonreinf, 7 inch	6020102	70.000	Syd
0165	Conc Pavt, Nonreinf, 9 inch	6020106	35.000	Syd
0170	Driveway, Nonreinf Conc, 6 inch	8010005	289.000	Syd
0175	Curb and Gutter, Conc, Det F4	8020038	1,962.000	Ft
0180	Driveway Opening, Conc, Det M	8020050	155.000	Ft
0185	_ Curb, Conc., Stand Up, Det E-4, Modified	8027001	229.000	Ft
0190	Sidewalk, Conc, 4 inch	8030044	3,528.000	Sft
0195	Sidewalk, Conc, 6 inch	8030046	2,270.000	Sft
0200	_ Detectable Warning Surface, Cast Iron	8037001	20.000	Ft
0205	_ Sidewalk Ramp, Conc, Colored, Exposed Aggregate 6 inch	8037010	251.000	Sft
0210	_ Sidewalk, Conc, Colored, Exposed Aggregate 6 inch	8037010	440.000	Sft
0215	Post Hole Through Conc for Steel Post	8100340	15.000	Ea
0220	Post, Steel, 3 pound	8100371	42.000	Ft
0225	Sign, Type III, Erect, Salv	8100402	19.000	Ea
0230	Sign, Type III, Rem	8100403	1.000	Ea
0235	Sign, Type IIIA	8100404	6.000	Sft
0240	_ Post, Rem	8107050	38.000	Ea
0245	_ Post, Square Tube, Powder Coat	8107050	20.000	Ea
0250	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	168.000	Ft
0255	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	77.000	Ft
0260	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	2,004.000	Ft
0265	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	829.000	Ft
0270	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0275	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0280	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0285	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	105.000	Ea
0290	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	105.000	Ea
0295	Minor Traf Devices	8120170	1.000	LSUM
0300	Sign, Type B, Temp, Prismatic, Furn	8120350	384.000	Sft
0305	Sign, Type B, Temp, Prismatic, Oper	8120351	384.000	Sft
0310	Traf Regulator Control	8120370	1.000	LSUM
0315	_ Conduit, Irrigation, 2 inch	8157001	232.000	Ft
0320	_ Planting Soil Mix	8157021	30.000	Cyd
0325	_ Surface Restoration	8167011	892.000	Syd
0330	Hh, Adj	8182328	6.000	Ea
0335	_ Water Main, DI, 6 inch, Tr Det G, Modified	8237001	30.000	Ft
0340	_ Fire Hydrant, Modified	8237050	2.000	Ea
0345	_ Gate Box, Adj, Case 2, Modified	8237050	6.000	Ea

0350	_ Hydrant, Rem, Modified	8237050	1.000	Ea
0355	_ Live Tap, 6 inch by 12 inch, Modified	8237050	2.000	Ea
0360	_ Monitoring Well, Adj	8237050	1.000	Ea
0365	Sanitary Structure, Tap, 6 inch	8252110	1.000	Ea
0370	Sanitary Sewer, Serv Lead, PVC, 6 inch	8252122	85.000	Ft
0375	Sanitary Structure Cover, Adj, Case 1	8252145	4.000	Ea
0380	_ Sanitary Sewer, Serv Lead, Inside Drop	8257050	1.000	Ea



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 011**Letting Date:** August 1, 2025**Contract ID:** 38101-224574**Description:** Superstructure replacement due to high load hit with 27 inch steel rolled beams and pavement markings on I-94 under Airport Road in the city of Jackson, Jackson County.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
224574A	25A0755	N/A	MER 38101

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$139,300.00	1100001	1.000	LSUM
0010	Bridge Sign Connection, Conc, Type A1	8100031	1.000	Ea
0015	Bridge Sign Connection, Type A, Rem	8100080	1.000	Ea
0020	Sign, Type II, Rem	8100397	1.000	Ea
0025	Sign, Type IIB	8100399	16.000	Sft
0030	Pavt Mrkg, Waterborne, 6 inch, White	8110233	600.000	Ft
0035	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	600.000	Ft
0040	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	600.000	Ft
0045	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	17.000	Ea
0050	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	17.000	Ea
0055	Conc Barrier Ending, Temp, Det 2, Furn	8120041	2.000	Ea
0060	Conc Barrier Ending, Temp, Det 2, Oper	8120042	2.000	Ea
0065	Conc Barrier, Temp, Furn	8120081	400.000	Ft
0070	Conc Barrier, Temp, Oper	8120082	400.000	Ft
0075	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0080	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0085	Ltg for Night Work	8120160	1.000	LSUM
0090	Minor Traf Devices	8120170	1.000	LSUM
0095	Mobile Attenuator	8120180	2.000	Ea
0100	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	600.000	Ft
0105	Plastic Drum, Fluorescent, Furn	8120252	156.000	Ea
0110	Plastic Drum, Fluorescent, Oper	8120253	156.000	Ea
0115	Sign Cover	8120310	2.000	Ea
0120	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	15.000	Ea
0125	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	15.000	Ea
0130	Sign, Type A, Temp, Prismatic, Furn	8120340	497.000	Sft

0135	Sign, Type A, Temp, Prismatic, Oper	8120341	497.000	Sft
0140	Sign, Type B, Temp, Prismatic, Furn	8120350	2,046.000	Sft
0145	Sign, Type B, Temp, Prismatic, Oper	8120351	2,046.000	Sft
0150	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	600.000	Ft
0155	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	2,052.000	Ft
0160	_ Sec Closure System, Temp	8127050	30.000	Ea
0165	_ Traf Speed Sensor, Portable, Temp	8127050	6.000	Ea
0170	_ Control System, Dynamic Work Zone Traf Monitoring System	8127051	1.000	LSUM

Section: 2

0175	Bridge Ltg, Furn and Rem (S05 of 38101)	7060001	1.000	LSUM
0180	Bridge Ltg, Oper and Maintain	7060002	82.000	Cyd
0185	Conc, Low Temperature Protection	7060020	91.000	Cyd
0190	Expansion Joint Device	7060050	104.000	Ft
0195	Expansion Joint Device, Cover Plate	7060051	16.000	Ft
0200	False Decking	7060060	3,010.000	Sft
0205	Reinforcement, Steel, Epoxy Coated	7060092	15,200.000	Lb
0210	Superstructure Conc, Form, Finish, and Cure, Night Casting (S05 of 38101)	7060112	1.000	LSUM
0215	Superstructure Conc, Night Casting, High Performance	7060117	82.000	Cyd
0220	Sealing Localized Cracks (S05 of 38101)	7060220	1.000	LSUM
0225	Shear Developers (S05 of 38101)	7070040	1.000	LSUM
0230	Structural Steel, Rolled Shape, Erect	7070070	42,490.000	Lb
0235	_ Structural Steel, Rolled Shape, Furn and Fab, Modified	7077030	42,490.000	Lb
0240	_ Bearing, Elastomeric, 1 3/4 Inch, Erect	7077050	9.000	Ea
0245	_ Bearing, Elastomeric, 1 5/8 Inch, Erect	7077050	9.000	Ea
0250	_ Bridge Barrier Railing, Spec, High Performance	7117001	56.000	Ft
0255	Structures, Rehabilitation, Rem Portions (S05 of 38101)	7120070	1.000	LSUM
0260	Deck Joint, Rem	7120071	104.000	Ft
0265	_ Embedded Galvanic Anode, High Performing	7127050	58.000	Ea
0270	Field Repr of Damaged Coating (S05 of 38101)	7160001	1.000	LSUM
0275	Sealing Localized Conc Barrier Cracks (S05 of 38101)	8040000	1.000	LSUM
0280	Fence, Structure	8080110	770.000	Sft



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 012**Letting Date:** August 1, 2025**Contract ID:** 09042-211561

Description: Bridge rehabilitation including concrete deck patching and repairs, paint top flanges and beam ends and mechanical work on M-25 over Saginaw River in the city of Bay City, Bay County. A mandatory pre-bid meeting will be held at 1:00 p.m. on Thursday, July 16, 2025, in Suite 309 of the Davidson Building located at 916 Washington Avenue, Bay City, Michigan. All prospective bidders must attend in order to be considered eligible to bid.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211561A	25A0748	N/A	BFP 09042

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$144,100.00	1100001	1.000	LSUM
0010	Project Cleanup	2090001	1.000	LSUM
0015	Pavt, Cleaning	5010001	1.000	LSUM
0020	Pavt Mrkg, Waterborne, 6 inch, White	8110233	100.000	Ft
0025	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0030	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0035	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	88.000	Ea
0040	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	88.000	Ea
0045	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0050	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0055	Ltg for Night Work	8120160	1.000	LSUM
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Mobile Attenuator	8120180	2.000	Ea
0070	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0075	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0080	Sign Cover	8120310	15.000	Ea
0085	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0090	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	592.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	592.000	Sft

Section: 2

0105	_ Maintaining Navigation (B01 of 09042)	1077051	1.000	LSUM
0110	Structure Demolition Plan, Complex (B01 of 09042)	2040064	1.000	LSUM

0115	False Decking	7060060	198.000	Sft
0120	Reinforcement, Steel, Epoxy Coated	7060092	1,121.000	Lb
0125	Sealing Localized Cracks (B01 of 09042)	7060220	1.000	LSUM
0130	Shear Developers (B01 of 09042)	7070040	1.000	LSUM
0135	Complex Steel Erection (B01 of 09042)	7072000	1.000	LSUM
0140	Hand Chipping, Other Than Deck	7120007	29.000	Cft
0145	Patch, Forming	7120017	87.000	Sft
0150	Structures, Rehabilitation, Rem Portions with Shear Developer Rem (B01 of 09042)	7120065	1.000	LSUM
0155	Deck Joint, Rem	7120071	27.000	Ft
0160	Top Flanges and Beam Ends, Clean and Coat	7120100	5.000	Syd
0165	_ Rapid-Setting Polymer Conc	7127020	20.000	Cft
0170	_ Rapid-Setting Polymer Conc, Spec	7127020	19.000	Cft
0175	_ Rapid-Setting Polymer Conc for Joints	7127021	4.000	Cyd
0180	Beam Plate, Seal Perimeter	7130010	210.000	Ft
0185	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	2,781.000	Lb
0190	_ Hinged Walk, Rem, Salv, and Erect	7137050	1.000	Ea
0195	_ Work Zone Protection Plates	7137051	1.000	LSUM
0200	Steel Structure, Cleaning, Partial, Type 4 (B01 of 09042)	7150047	1.000	LSUM
0205	Steel Structure, Coating, Partial, Type 4 (B01 of 09042)	7150048	1.000	LSUM
0210	_ Clean and Coat Hinged Walk	7157050	1.000	Ea
0215	Field Repr of Damaged Coating (B01 of 09042)	7160001	1.000	LSUM
0220	_ Bronze Castings, Delivery	8007051	1.000	LSUM
0225	_ Mechanical Work (B01 of 09042)	8007051	1.000	LSUM



7/3/2025 7:45 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 013**Letting Date:** August 1, 2025**Contract ID:** 34043-209377**Description:** 17.31 mi of installation of traffic surveillance cameras, vehicle detection system, dynamic message signs and related communications infrastructure on I-96 at multiple locations, Ionia County.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
209377A	25A0762	N/A	NHFP 34043

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$172,600.00	1100001	1.000	LSUM
0010	Excavation, Earth	2050016	50.000	Cyd
0015	Non Haz Contaminated Material Handling and Disposal, LM	2050031	25.000	Cyd
0020	_ Embankment, CIP, Spec	2057021	70.000	Cyd
0025	Erosion Control, Aggregate Cover	2080010	25.000	Syd
0030	Erosion Control, Check Dam, Stone	2080012	20.000	Ft
0035	Erosion Control, Gravel Access Approach	2080016	7.000	Ea
0040	Erosion Control, Maintenance, Sediment Rem	2080026	10.000	Cyd
0045	Erosion Control, Sediment Trap	2080034	4.000	Ea
0050	Erosion Control, Silt Fence	2080036	350.000	Ft
0055	Project Cleanup	2090001	1.000	LSUM
0060	Aggregate Surface Cse, 6 inch	3060010	60.000	Syd
0065	Geotextile, Separator, Non-Woven	3082000	130.000	Syd
0070	Culv End Sect, 24 inch	4010024	1.000	Ea
0075	Culv, CI E, 24 inch	4010542	55.000	Ft
0080	Culv, Slp End Sect, 1 on 6, 24 inch, Longit	4010955	1.000	Ea
0085	Video Taping Sewer and Culv Pipe	4021275	55.000	Ft
0090	Temp Casing-Left in Place	7180121	48.000	Ft
0095	Dynamic Message Sign, Fdn	7180200	48.000	Ft
0100	_ Antenna Support, Install on Dynamic Message Sign	8007050	2.000	Ea
0105	_ Cellular Modem, 4G	8007050	5.000	Ea
0110	_ Dynamic Message Sign, Full Color, 20mm, 96 by 400	8007050	2.000	Ea
0115	_ Power Distribution Unit	8007050	5.000	Ea
0120	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
0125	Sidewalk, Conc, 6 inch	8030046	48.000	Sft
0130	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea

0135	Guardrail Departing Terminal, Type MGS	8070052	2.000	Ea
0140	Guardrail Approach Terminal, Type 3M	8070060	1.000	Ea
0145	Guardrail Reflector	8070080	18.000	Ea
0150	Guardrail, Type MGS-8, 72 inch Post	8072179	601.000	Ft
0155	Guardrail, Type MGS-8D, 72 inch Post	8072181	75.000	Ft
0160	Delineator Reflector, Green	8100133	4.000	Ea
0165	Post, Rigid, Delineator	8100361	4.000	Ea
0170	Connected Arrow Board, Type C, Furn	8120155	5.000	Ea
0175	Connected Arrow Board, Type C, Oper	8120156	5.000	Ea
0180	Minor Traf Devices	8120170	1.000	LSUM
0185	Mobile Attenuator	8120180	1.000	Ea
0190	Plastic Drum, Fluorescent, Furn	8120252	176.000	Ea
0195	Plastic Drum, Fluorescent, Oper	8120253	176.000	Ea
0200	Sign Cover	8120310	5.000	Ea
0205	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	1.000	Ea
0210	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	1.000	Ea
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	1,656.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	1,656.000	Sft
0225	_ Slope Restoration, Freeway, Type B, Modified	8167011	250.000	Syd
0230	Power Company (Estimated Cost to Contractor)	8180001	1,000.000	Dlr
0235	Conduit, Directional Bore, 1, 3 inch	8182035	1,045.000	Ft
0240	Conduit, DB, 1, 1 1/2 inch	8182048	260.000	Ft
0245	Conduit, DB, 1, 3 inch	8182050	3,455.000	Ft
0250	Conduit, DB, 2, 3 inch	8182053	110.000	Ft
0255	Conduit, DB, 4, 3 inch	8182059	35.000	Ft
0260	DB Cable, 600V, 1/C#1	8182169	3,885.000	Ft
0265	DB Cable, 600V, 1/C#4	8182173	1,845.000	Ft
0270	DB Cable, 600V, 1/C#6	8182174	7,585.000	Ft
0275	Cable, Equipment Grounding Wire, 1/C#1	8182287	1,295.000	Ft
0280	Cable, Equipment Grounding Wire, 1/C#4	8182290	15.000	Ft
0285	Cable, Equipment Grounding Wire, 1/C#6	8182291	3,130.000	Ft
0290	Hh, Round, 3 foot dia	8182319	2.000	Ea
0295	_ Hh, Round, Elec	8187050	19.000	Ea
0300	Contractor Staking	8240001	1.000	LSUM
0305	Staking Plan Errors and Extras, Max \$180/hour	8240002	18.000	Hr
0310	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0315	Lightning Protection, Pole	8260021	3.000	Ea
0320	Lightning Protection, Structure, Large Dynamic Message Sign	8260022	2.000	Ea
0325	Dynamic Message Sign, Support Structure	8260025	2.000	Ea
0330	Microwave Vehicle Detection System	8260040	3.000	Ea
0335	Fiber Optic, Marker, Above Ground	8260069	21.000	Ea
0340	Managed Field Ethernet Switch, Layer 2	8260080	5.000	Ea
0345	Power Serv, Underground, 30AMP, 120/240V	8260100	1.000	Ea

0350	Power Serv, Underground, 60AMP, 120/240V	8260101	2.000	Ea
0355	Power Serv, Overhead, 30AMP, 120/240V	8260104	2.000	Ea
0360	Safety Switch, Fusible	8260109	4.000	Ea
0365	Elec Rack	8260110	4.000	Ea
0370	ITS Cabinet, Ground Mtd	8260130	2.000	Ea
0375	ITS Cabinet, Pole Mtd	8260134	3.000	Ea
0380	Uninterruptible Power Supply, ITS Cabinet	8260140	2.000	Ea
0385	Flowable Fill, Spun Pole Fdn	8260149	9.000	Cyd
0390	Spun Conc Pole, Type A	8260152	3.000	Ea
0395	Drilled Shaft and Conc Skirt, Cased	8260155	3.000	Ea
0400	Surveillance System, Remote Site, Type A	8260157	5.000	Ea
0405	System Integration and Testing	8260160	1.000	LSUM
0410	Camera Lowering Device	8260161	3.000	Ea
0415	Drilled Shaft, Add Depth, Aggregate	8260247	9.000	Ft

Schedule of Pay Items

Report v1

Letting Call: 250801 014

Letting Date: August 1, 2025

Contract ID: 03023-216576

Description: 3.55 mi of hot mix asphalt cold milling and resurfacing, detail 7 and 8 joint repairs, concrete curb, gutter, sidewalk and ramps and pavement markings on M-89 from Kalamazoo River Bridge east to US-131 in the city of Otsego, Allegan County. This project includes a 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216576A	25A0752	N/A	NH 03023

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$213,900.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	403.000	Ft
0015	Sidewalk, Rem	2040055	215.000	Syd
0020	Excavation, Earth	2050016	76.000	Cyd
0025	Non Haz Contaminated Material Handling and Disposal, LM	2050031	25.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	18.000	Ea
0035	Subbase, CIP	3010002	39.000	Cyd
0040	Aggregate Base, 3 inch	3020008	151.000	Syd
0045	Shld, CI II	3070121	19.000	Ton
0050	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0055	_ Accessible Dr Structure Cover	4037050	1.000	Ea
0060	Cold Milling HMA Surface	5010002	119,269.000	Syd
0065	Bump Grinding	5010004	250.000	Syd
0070	HMA Quality Initiative	5010007	21,602.000	Dlr
0075	Longit Joint Density Quality Initiative	5010018	39,477.000	Dlr
0080	Pavt Joint and Crack Repr, Det 7	5010020	1,908.000	Ft
0085	Pavt Joint and Crack Repr, Det 8	5010021	1,908.000	Ft
0090	Hand Patching	5010025	606.000	Ton
0095	HMA Approach	5010061	766.000	Ton
0100	HMA Approach, High Stress	5010520	643.000	Ton
0105	HMA, 5EMH	5012038	4,672.000	Ton
0110	HMA, 5EMH, High Stress	5012086	4,114.000	Ton
0115	Curb and Gutter, Conc, Det F4	8020038	403.000	Ft
0120	Detectable Warning Surface	8030010	185.000	Ft
0125	Curb Ramp Opening, Conc	8030030	212.000	Ft
0130	Sidewalk, Conc, 4 inch	8030044	405.000	Sft

0135	Curb Ramp, Conc, 6 inch	8032002	1,393.000	Sft
0140	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, White	8110039	1,000.000	Ft
0145	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	19.000	Ea
0150	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	12.000	Ea
0155	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	1.000	Ea
0160	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,820.000	Ft
0165	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	920.000	Ft
0170	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	4.000	Ea
0175	Pavt Mrkg, Waterborne, 6 inch, White	8110233	13,600.000	Ft
0180	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	50,700.000	Ft
0185	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	13,600.000	Ft
0190	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	50,700.000	Ft
0195	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	320.000	Ft
0200	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	486.000	Ft
0205	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0210	Recessing Pavt Mrkg, Transv	8110451	2,750.000	Sft
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	40.000	Ea
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	40.000	Ea
0225	Pedestrian Type II Barricade, Temp	8120026	28.000	Ea
0230	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	600.000	Ea
0235	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	600.000	Ea
0240	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0245	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0250	Minor Traf Devices	8120170	1.000	LSUM
0255	Sign Cover	8120310	30.000	Ea
0260	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0265	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0270	Sign, Type B, Temp, Prismatic, Furn	8120350	1,975.000	Sft
0275	Sign, Type B, Temp, Prismatic, Oper	8120351	1,975.000	Sft
0280	Traf Regulator Control	8120370	1.000	LSUM
0285	Pavt Mrkg, Wet Reflective, Type NR, Tape, 6 inch, White, Temp	8122008	3,400.000	Ft
0290	Pavt Mrkg, Wet Reflective, Type NR, Tape, 6 inch, Yellow, Temp	8122010	11,000.000	Ft
0295	Rumble Strip, Temp, Portable, Furn	8122188	6.000	Ea
0300	Rumble Strip, Temp, Portable, Oper	8122189	6.000	Ea
0305	Pedestrian Path, Temp	8122250	232.000	Ft
0310	Pedestrian Ramp, Temp	8122251	6.000	Ea
0315	Slope Restoration, Non-Freeway, Type A	8162001	113.000	Syd
0320	Traf Loop	8200170	9.000	Ea
0325	TS Face, Bag	8200458	8.000	Ea

0330	TS Face, Bag, Rem	8200459	8.000	Ea
0335	Monument Box	8210001	1.000	Ea
0340	Monument Box, Adj	8210005	1.000	Ea
0345	Monument Preservation	8210010	4.000	Ea
0350	Protect Corners	8210020	2.000	Ea
0355	Contractor Staking	8240001	1.000	LSUM
0360	Staking Plan Errors and Extras, Max \$180/hour	8240002	24.000	Hr



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 015**Letting Date:** August 1, 2025**Contract ID:** 81104-221917**Description:** 19.66 mi of installation of enhanced delineation on I-94 and on I-96 at multiple locations in the city of Ann Arbor, Livingston and Washtenaw Counties.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221917A	25A0786	N/A	HSIP 81104

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$30,300.00	1100001	1.000	LSUM
0010	Delineator, Rem	8100349	50.000	Ea
0015	Post, Flexible, Delineator, Ground Mtd	8100555	630.000	Ea
0020	_ Enhanced Delineation, Bidirectional, Conc Barrier, Side Mtd	8107001	600.000	Ft
0025	_ Enhanced Delineation, Bidirectional, Guardrail, Channel Mtd	8107001	950.000	Ft
0030	_ Enhanced Delineation, Unidirectional, Conc Barrier, Side Mtd	8107001	47,610.000	Ft
0035	_ Enhanced Delineation, Unidirectional, Guardrail, Channel Mtd	8107001	13,715.000	Ft
0040	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0045	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0050	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0055	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Mobile Attenuator	8120180	1.000	Ea
0070	Plastic Drum, Fluorescent, Furn	8120252	112.000	Ea
0075	Plastic Drum, Fluorescent, Oper	8120253	112.000	Ea
0080	Sign Cover	8120310	8.000	Ea
0085	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0090	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0095	Sign, Type A, Temp, Prismatic, Furn	8120340	42.000	Sft
0100	Sign, Type A, Temp, Prismatic, Oper	8120341	42.000	Sft
0105	Sign, Type B, Temp, Prismatic, Furn	8120350	360.000	Sft
0110	Sign, Type B, Temp, Prismatic, Oper	8120351	360.000	Sft
0115	Traf Regulator Control	8120370	1.000	LSUM
0120	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0125	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 016**Letting Date:** August 1, 2025**Contract ID:** 82144-211986**Description:** Traffic signal modernization at 2 signals on I-275/I-96SB off ramp at 6 Mile Road and M-102 (Vernier Road) at Beaconsfield Road in the cities of Livonia and Harper Woods, Wayne County.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
211986A	25A0793	N/A	STG 82144

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$69,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	393.000	Ft
0015	Pavt, Rem	2040050	171.000	Syd
0020	Sidewalk, Rem	2040055	103.000	Syd
0025	Exploratory Investigation, Vertical	2040080	40.000	Ft
0030	Embankment, CIP	2050010	3.000	Cyd
0035	Excavation, Earth	2050016	25.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0045	Erosion Control, Maintenance, Sediment Rem	2080026	2.000	Cyd
0050	Erosion Control, Silt Fence	2080036	100.000	Ft
0055	Aggregate Base, 4 inch	3020010	394.000	Syd
0060	Dr Structure Cover, Adj, Case 1, Modified	4030004	5.000	Ea
0065	Dr Structure Cover, Adj, Case 1	4030005	6.000	Ea
0070	HMA Surface, Rem	5010005	118.000	Syd
0075	Conc Pavt, Misc, Nonreinf, 12 inch	6020062	95.000	Syd
0080	Lane Tie, Epoxy Anchored	6030030	121.000	Ea
0085	Curb and Gutter, Conc, Det F5	8020039	333.000	Ft
0090	Detectable Warning Surface	8030010	56.000	Ft
0095	Curb Ramp Opening, Conc	8030030	70.000	Ft
0100	Sidewalk, Conc, 4 inch	8030044	419.000	Sft
0105	Curb Ramp, Conc, 6 inch	8032002	605.000	Sft
0110	Fdn, Wood Support, Rem	8100280	2.000	Ea
0115	Perforated Steel Square Tube Breakaway System	8100330	3.000	Ea
0120	Post Hole Through Conc for Steel Post	8100340	3.000	Ea
0125	Post, Steel, 3 pound	8100371	32.000	Ft
0130	Sign, Type II, Rem	8100397	1.000	Ea
0135	Sign, Type IIA	8100398	9.000	Sft
0140	Sign, Type III, Rem	8100403	5.000	Ea

0145	Sign, Type IIIA	8100404	10.000	Sft
0150	Sign, Type IIIB	8100405	8.000	Sft
0155	Reflective Panel for Permanent Sign Support, 6 foot	8100616	2.000	Ea
0160	Ground Mtd Sign Support, Rem	8102010	3.000	Ea
0165	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	1.000	Ea
0170	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	1.000	Ea
0175	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	234.000	Ft
0180	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	286.000	Ft
0185	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	235.000	Ft
0190	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	234.000	Ft
0195	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	286.000	Ft
0200	Rem Curing Compound, for Spec Mrkg	8110321	31.000	Sft
0205	Rem Spec Mrkg	8110343	667.000	Sft
0210	Recessing Pavt Mrkg, Longit	8110450	286.000	Ft
0215	Recessing Pavt Mrkg, Transv	8110451	858.000	Sft
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0225	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0230	Pedestrian Type II Barricade, Temp	8120026	7.000	Ea
0235	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0240	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0245	Minor Traf Devices	8120170	1.000	LSUM
0250	Plastic Drum, Fluorescent, Furn	8120252	125.000	Ea
0255	Plastic Drum, Fluorescent, Oper	8120253	125.000	Ea
0260	Sign Cover	8120310	5.000	Ea
0265	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	1.000	Ea
0270	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	1.000	Ea
0275	Sign, Type B, Temp, Prismatic, Furn	8120350	1,075.000	Sft
0280	Sign, Type B, Temp, Prismatic, Oper	8120351	1,075.000	Sft
0285	Traf Regulator Control	8120370	1.000	LSUM
0290	Pedestrian Path, Temp	8122250	60.000	Ft
0295	Pedestrian Ramp, Temp	8122251	8.000	Ea
0300	_ Turf Establishment, Performance	8167011	137.000	Syd
0305	Conduit, Rem	8182000	150.000	Ft
0310	Conduit, DB, 1, 1 1/2 inch	8182048	260.000	Ft
0315	Conduit, DB, 3, 3 inch	8182056	100.000	Ft
0320	Conduit, DB, 4, 3 inch	8182059	18.000	Ft
0325	Conduit, DB, 1, 1 inch	8182060	20.000	Ft
0330	Cable, Sec, 600V, 1, 3/C#6	8182238	700.000	Ft
0335	Hh, Polymer Conc	8182309	4.000	Ea
0340	Hh, Round	8182310	7.000	Ea
0345	Hh, Round, 3 foot dia	8182319	2.000	Ea
0350	Hh, Rem	8182330	6.000	Ea

0355	Wood Pole, Rem	8182363	3.000	Ea
0360	Serv Disconnect	8182366	2.000	Ea
0365	Case Sign, Rem	8200020	4.000	Ea
0370	Case Sign (LED), Two Way, 24 inch by 30 inch	8200022	1.000	Ea
0375	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	4.000	Ea
0380	Controller and Cabinet, Rem	8200030	2.000	Ea
0385	Controller Fdn, Base Mtd	8200045	2.000	Ea
0390	Global Positioning System Module	8200050	2.000	Ea
0395	Global Positioning System Module, Rem	8200053	1.000	Ea
0400	Pedestal, Alum	8200100	4.000	Ea
0405	Pedestal, Fdn	8200105	4.000	Ea
0410	Pedestal Fdn, Rem	8200106	1.000	Ea
0415	Pedestal, Rem	8200110	1.000	Ea
0420	Push Button Station and Sign	8200128	2.000	Ea
0425	Span Wire	8200140	7.000	Ea
0430	Span Wire, Rem	8200141	3.000	Ea
0435	Span Wire Tether	8200142	7.000	Ea
0440	TS, Pedestal Mtd, Rem	8200179	1.000	Ea
0445	TS, Span Wire Mtd, Rem	8200182	6.000	Ea
0450	Cabinet, NEMA Type	8200186	2.000	Ea
0455	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0460	Warning Sign, Rem	8200261	1.000	Ea
0465	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	4.000	Ea
0470	Bracket, Truss, with 18 foot Arm	8200378	3.000	Ea
0475	Video Traf Detection System	8200380	2.000	Ea
0480	Video Traf Detection Camera	8200381	3.000	Ea
0485	Junction Box, Span Wire	8200456	7.000	Ea
0490	Junction Box, Rem	8200457	3.000	Ea
0495	TS Face, Bag	8200458	4.000	Ea
0500	TS Face, Bag, Rem	8200459	4.000	Ea
0505	Strain Pole, Steel, 6 bolt, Size 2	8200466	9.000	Ea
0510	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	160.000	Ft
0515	Casing, 48 inch	8200486	128.000	Ft
0520	TS, One Way Bracket Arm Mtd (LED), Long Life	8202200	1.000	Ea
0525	TS, One Way Span Wire Mtd, One Sect (LED), Long Life	8202275	2.000	Ea
0530	TS, One Way Span Wire Mtd (LED), Long Life	8202287	14.000	Ea
0535	_ Backplate, TS, Flexible	8207050	15.000	Ea
0540	_ Controller, NEMA, ATC Type	8207050	2.000	Ea
0545	Contractor Staking	8240001	1.000	LSUM
0550	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0555	Lightning Protection, Pole	8260021	2.000	Ea



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 017**Letting Date:** August 1, 2025**Contract ID:** 32091-217675

Description: 6.02 mi of hot mix asphalt cold milling and resurfacing, joint repairs, detail 7 and 8 pavement repairs, shoulder work, and pavement markings on M-25 from the south Huron County line to Helena Road, Huron County. This project includes a 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217675A	N/A	N/A	M 32091

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$246,700.00	1100001	1.000	LSUM
0010	Excavation, Earth	2050016	110.000	Cyd
0015	_ Shld, CI II, Modified	3077031	720.000	Ton
0020	HMA Surface, Rem	5010005	1,271.000	Syd
0025	HMA Quality Initiative	5010007	68,229.000	Dlr
0030	Longit Joint Density Quality Initiative	5010018	94,569.000	Dlr
0035	Hand Patching	5010025	1,480.000	Ton
0040	HMA Approach	5010061	620.000	Ton
0045	Micro Texture Pavt Milling	5010101	143,964.000	Syd
0050	HMA, 5EL	5012036	12,791.000	Ton
0055	_ Pavt Joint and Crack Repr, Det 7, Spec	5017001	25,600.000	Ft
0060	_ Pavt Joint and Crack Repr, Det 8, Spec	5017001	2,000.000	Ft
0065	_ Conc Parking Rail	8027050	13.000	Ea
0070	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	2.000	Ea
0075	Pavt Mrkg, Waterborne, 6 inch, White	8110233	62,240.000	Ft
0080	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	33,900.000	Ft
0085	Pavt Mrkg, Waterborne, 12 inch, White	8110237	240.000	Ft
0090	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	62,240.000	Ft
0095	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	33,900.000	Ft
0100	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	625.000	Ft
0105	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0110	Recessing Pavt Mrkg, Longit	8110450	64,862.000	Ft
0115	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0125	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	320.000	Ea
0130	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	320.000	Ea

0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0145	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0150	Sign, Type B, Temp, Prismatic, Furn	8120350	575.000	Sft
0155	Sign, Type B, Temp, Prismatic, Oper	8120351	575.000	Sft
0160	Traf Regulator Control	8120370	1.000	LSUM
0165	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	5,200.000	Ft
0170	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	5,200.000	Ft
0175	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0180	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0185	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0190	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	47,187.000	Ft
0195	_ Sinusoidal Corrugations, Milled, HMA Centerline	8227001	28,048.000	Ft

Schedule of Pay Items

Report v1

Letting Call: 250801 018

Letting Date: August 1, 2025

Contract ID: 82142-219767

Description: 0.66 mi of hot mix asphalt cold milling and one course HMA resurfacing, pavement repairs, ADA ramp upgrades, drainage structure cleaning, drainage structure adjustments, maintenance of traffic, and pavement markings on M-102 from Edgewood Place westerly to Ralston Street (at M-1) in the city of Detroit, Wayne County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219767A	25A0791	N/A	NH 82142

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$151,300.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	1,120.000	Ft
0015	Pavt, Rem	2040050	270.000	Syd
0020	Sidewalk, Rem	2040055	774.000	Syd
0025	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	116.000	Ea
0035	Project Cleanup	2090001	1.000	LSUM
0040	Aggregate Base	3020001	290.000	Ton
0045	Aggregate Base, Conditioning	3020050	720.000	Syd
0050	Dr Structure Cover, Adj, Case 1, Modified	4030004	26.000	Ea
0055	Dr Structure Cover, Adj, Case 1	4030005	6.000	Ea
0060	Dr Structure, Cleaning	4030290	20.000	Ea
0065	Pavt, Cleaning	5010001	1.000	LSUM
0070	Cold Milling HMA Surface	5010002	47,012.000	Syd
0075	Bump Grinding	5010004	528.000	Syd
0080	HMA Surface, Rem	5010005	270.000	Syd
0085	HMA Quality Initiative	5010007	9,108.000	Dlr
0090	Pavt Joint and Crack Repr, Det 7	5010020	4,900.000	Ft
0095	Hand Patching	5010025	480.000	Ton
0100	HMA Approach, High Stress	5010520	301.000	Ton
0105	HMA, 5EMH, High Stress	5012086	3,773.000	Ton
0110	Joint, Contraction, Crg	6030020	150.000	Ft
0115	Lane Tie, Epoxy Anchored	6030030	510.000	Ea
0120	Pavt Repr, Nonreinf Conc, 11 1/2 inch	6030051	96.000	Syd
0125	Pavt Repr, Rem	6030080	96.000	Syd
0130	Saw Cut, Intermediate	6030090	80.000	Ft

0135	_ Resealing Longit Joints with Polyurethane	6037001	2,050.000	Ft
0140	_ Resealing Trans Joints with Polyurethane	6037001	1,400.000	Ft
0145	_ Curb and Gutter, Conc, Det F5, Modified	8027001	230.000	Ft
0150	_ Curb and Gutter, Conc, Det F6, Modified	8027001	542.000	Ft
0155	Detectable Warning Surface	8030010	190.000	Ft
0160	Curb Ramp Opening, Conc	8030030	375.000	Ft
0165	Curb Ramp, Conc, 6 inch	8032002	7,154.000	Sft
0170	_ Existing Sidewalk, Clean and Edge	8037010	4,000.000	Sft
0175	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0180	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	4.000	Ea
0185	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	551.000	Ft
0190	Pavt Mrkg, Polyurea, 6 inch, White	8110094	180.000	Ft
0195	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	227.000	Ft
0200	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0205	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea
0210	Pavt Mrkg, Polyurea, Only	8110410	4.000	Ea
0215	Pavt Mrkg, Polyurea, Thru and Lt Turn Arrow Sym	8110416	2.000	Ea
0220	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	2.000	Ea
0225	Recessing Pavt Mrkg, Longit	8110450	13,450.000	Ft
0230	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	7,690.000	Ft
0235	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	2,160.000	Ft
0240	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	3,600.000	Ft
0245	Scarification, for Polyurea Spec Mrkg	8112159	1,100.000	Sft
0250	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	70.000	Ea
0255	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	70.000	Ea
0260	Pedestrian Type II Barricade, Temp	8120026	9.000	Ea
0265	Pedestrian Type II Channelizer, Temp	8120027	132.000	Ft
0270	Connected Arrow Board, Type C, Furn	8120155	9.000	Ea
0275	Connected Arrow Board, Type C, Oper	8120156	9.000	Ea
0280	Ltg for Night Work	8120160	1.000	LSUM
0285	Minor Traf Devices	8120170	1.000	LSUM
0290	Mobile Attenuator	8120180	2.000	Ea
0295	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	1,000.000	Ft
0300	Plastic Drum, Fluorescent, Furn	8120252	775.000	Ea
0305	Plastic Drum, Fluorescent, Oper	8120253	775.000	Ea
0310	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	88.000	Ft
0315	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	44.000	Ft
0320	Sign Cover	8120310	40.000	Ea
0325	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0330	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0335	Sign, Type A, Temp, Prismatic, Furn	8120340	261.000	Sft

0340	Sign, Type A, Temp, Prismatic, Oper	8120341	261.000	Sft
0345	Sign, Type B, Temp, Prismatic, Furn	8120350	2,050.000	Sft
0350	Sign, Type B, Temp, Prismatic, Oper	8120351	2,050.000	Sft
0355	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	250.000	Sft
0360	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	250.000	Sft
0365	Traf Regulator Control	8120370	1.000	LSUM
0370	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	6,800.000	Ft
0375	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	3,800.000	Ft
0380	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	3,000.000	Ft
0385	Pedestrian Path, Temp	8122250	180.000	Ft
0390	Pedestrian Ramp, Temp	8122251	9.000	Ea
0395	Slope Restoration, Non-Freeway, Type B	8162002	730.000	Syd
0400	_ Shredded Bark Mulch, Rem, Salv and Reinstall	8167010	1,000.000	Sft
0405	Hh, Adj	8182328	6.000	Ea
0410	TS Face, Bag	8200458	20.000	Ea
0415	TS Face, Bag, Rem	8200459	20.000	Ea
0420	Monument Box	8210001	4.000	Ea
0425	Monument Box, Adj	8210005	4.000	Ea
0430	Monument Preservation	8210010	5.000	Ea
0435	Protect Corners	8210020	20.000	Ea
0440	Gate Box, Adj, Case 1	8230431	4.000	Ea
0445	Contractor Staking	8240001	1.000	LSUM
0450	Staking Plan Errors and Extras, Max \$180/hour	8240002	18.000	Hr



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 019**Letting Date:** August 1, 2025**Contract ID:** 82051-220638**Description:** Traffic Signal Modernization and ADA ramp upgrades on US-24 (Telegraph Road) at Vreeland Road in the city of Flat Rock, Wayne County.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220638A	N/A	N/A	M 82051

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$43,600.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	175.000	Ft
0015	Curb, Rem	2040021	5.000	Ft
0020	Pavt, Rem	2040050	33.000	Syd
0025	Sidewalk, Rem	2040055	150.000	Syd
0030	Exploratory Investigation, Vertical	2040080	60.000	Ft
0035	Embankment, CIP	2050010	25.000	Cyd
0040	Excavation, Earth	2050016	35.000	Cyd
0045	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0055	Erosion Control, Silt Fence	2080036	500.000	Ft
0060	Subbase, CIP	3010002	16.000	Cyd
0065	Aggregate Base, 4 inch	3020010	128.000	Syd
0070	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0075	HMA Surface, Rem	5010005	27.000	Syd
0080	HMA Quality Initiative	5010007	350.000	Dlr
0085	Hand Patching	5010025	15.000	Ton
0090	Conc Pavt, Misc, Nonreinf, 9 inch	6020056	34.000	Syd
0095	_ Vibration Monitoring, Utility	8007051	1.000	LSUM
0100	Curb and Gutter, Conc, Det F4	8020038	146.000	Ft
0105	Detectable Warning Surface	8030010	44.000	Ft
0110	Curb Ramp Opening, Conc	8030030	48.000	Ft
0115	Curb Ramp, Conc, 6 inch	8032002	1,242.000	Sft
0120	Post, Steel, 3 pound	8100371	14.000	Ft
0125	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0130	Sign, Type III, Rem, Salv	8102003	1.000	Ea
0135	Ground Mtd Sign Support, Rem	8102010	1.000	Ea

0140	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	563.000	Ft
0145	Pavt Mrkg, Polyurea, 6 inch, White	8110094	22.000	Ft
0150	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	40.000	Ft
0155	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	150.000	Ft
0160	Rem Spec Mrkg	8110343	569.000	Sft
0165	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0170	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0175	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0180	Pedestrian Type II Barricade, Temp	8120026	16.000	Ea
0185	Pedestrian Type II Channelizer, Temp	8120027	100.000	Ft
0190	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0195	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0200	Minor Traf Devices	8120170	1.000	LSUM
0205	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0210	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	360.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	360.000	Sft
0225	Pedestrian Ramp, Temp	8122251	8.000	Ea
0230	Slope Restoration, Non-Freeway, Type A	8162001	387.000	Syd
0235	Conduit, Rem	8182000	166.000	Ft
0240	Conduit, DB, 1, 1 1/2 inch	8182048	238.000	Ft
0245	Conduit, DB, 3, 3 inch	8182056	75.000	Ft
0250	Conduit, DB, 4, 3 inch	8182059	13.000	Ft
0255	Conduit, DB, 1, 1 inch	8182060	15.000	Ft
0260	Cable Pole, Sec, Dismn	8182206	1.000	Ea
0265	Cable, Sec, 600V, 1, 3/C#6	8182238	100.000	Ft
0270	Hh, Round	8182310	3.000	Ea
0275	Hh, Round, 3 foot dia	8182319	1.000	Ea
0280	Hh, Rem	8182330	6.000	Ea
0285	Serv Disconnect	8182366	1.000	Ea
0290	Serv Disconnect, Rem	8182367	1.000	Ea
0295	Case Sign, Rem	8200020	4.000	Ea
0300	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	2.000	Ea
0305	Controller and Cabinet, Rem	8200030	1.000	Ea
0310	Controller Fdn, Base Mtd	8200045	1.000	Ea
0315	Controller Fdn, Rem	8200046	1.000	Ea
0320	Fdn, Rem	8200065	4.000	Ea
0325	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	1.000	Ea
0330	Pedestal, Alum	8200100	5.000	Ea
0335	Pedestal, Fdn	8200105	7.000	Ea
0340	Pedestal Fdn, Rem	8200106	4.000	Ea
0345	Pedestal, Rem	8200110	3.000	Ea
0350	Pedestal, Pushbutton, Alum	8200118	2.000	Ea

0355	Pedestal, Pushbutton, Rem	8200119	1.000	Ea
0360	Pushbutton, Rem	8200122	4.000	Ea
0365	Push Button Station and Sign	8200128	8.000	Ea
0370	Span Wire	8200140	4.000	Ea
0375	Span Wire Tether	8200142	4.000	Ea
0380	TS, Mast Arm Mtd, Rem	8200177	8.000	Ea
0385	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	4.000	Ea
0390	TS, Pedestrian, Pedestal Mtd, Rem	8200181	3.000	Ea
0395	Cabinet, NEMA Type	8200186	1.000	Ea
0400	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0405	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0410	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0415	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	5.000	Ea
0420	TS, Antenna, Rem	8200368	1.000	Ea
0425	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
0430	Video Traf Detection Camera, Rem	8200384	2.000	Ea
0435	Bracket, Truss, Rem	8200388	2.000	Ea
0440	Junction Box, Span Wire	8200456	4.000	Ea
0445	TS Face, Bag	8200458	4.000	Ea
0450	TS Face, Bag, Rem	8200459	4.000	Ea
0455	Strain Pole, Steel, 6 bolt, Size 2	8200466	4.000	Ea
0460	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	62.000	Ft
0465	Casing, 48 inch	8200486	48.000	Ft
0470	Cellular Modem, TS, 4th G	8200498	1.000	Ea
0475	Multi-Sensor Vehicle Detection System	8200532	1.000	Ea
0480	Multi-Sensor Vehicle Detection Sensor	8200535	4.000	Ea
0485	Hh, Lightning Protection	8200540	2.000	Ea
0490	Mast Arm, Rem	8202004	4.000	Ea
0495	Mast Arm Std, Rem	8202005	4.000	Ea
0500	TS, One Way Span Wire Mtd (LED), Long Life	8202287	7.000	Ea
0505	TS, One Way Span Wire Mtd, FYA (LED), Long Life	8202299	2.000	Ea
0510	TS, One Way Span Wire Mtd, Five Sect (LED), Long Life	8202308	1.000	Ea
0515	_ Backplate, TS, Flexible	8207050	10.000	Ea
0520	_ Controller, NEMA, ATC Type	8207050	1.000	Ea
0525	Contractor Staking	8240001	1.000	LSUM
0530	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr
0535	Sanitary Structure Cover, Adj, Case 1	8252145	1.000	Ea
0540	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0545	Lightning Protection, Pole	8260021	1.000	Ea

Schedule of Pay Items

Report v1

Letting Call: 250801 020

Letting Date: August 1, 2025

Contract ID: 23000-216355

Description: 0.25 mi of hot mix asphalt reconstruction, concrete pavement, aggregate base, sidewalk and pavement markings on Knight Street from Main Street to East Street in the city of Eaton Rapids, Eaton County.
This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216355A	25A0738	N/A	STUL 23000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$45,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	276.000	Ft
0015	Sidewalk, Rem	2040055	130.000	Syd
0020	_ Pavt, Rem, Modified	2047011	4,923.000	Syd
0025	Excavation, Earth	2050016	547.000	Cyd
0030	Subgrade Undercutting, Type I	2050040	246.000	Cyd
0035	_ Machine Grading, Modified	2057002	14.000	Sta
0040	_ Subgrade Undercutting, Modified	2057011	250.000	Syd
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	16.000	Ea
0050	Erosion Control, Silt Fence	2080036	250.000	Ft
0055	Aggregate Base	3020001	1,270.000	Ton
0060	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0065	Dr Structure, Adj, Add Depth	4030280	2.000	Ft
0070	_ Dr Structure, Chimney Rehabilitation	4037050	7.000	Ea
0075	_ Sanitary Structure Cover, Adj, Case 1, Modified	4037050	4.000	Ea
0080	HMA Surface, Rem	5010005	320.000	Syd
0085	Hand Patching	5010025	10.000	Ton
0090	HMA, 3EL	5012012	700.000	Ton
0095	HMA, 4EL	5012024	425.000	Ton
0100	HMA, 5EL	5012036	440.000	Ton
0105	Curb and Gutter, Conc, Det F4	8020038	179.000	Ft
0110	Curb Ramp Opening, Conc	8030030	97.000	Ft
0115	_ Detectable Warning Surface, Modified	8037001	78.000	Ft
0120	_ Sidewalk Ramp, Conc, 6 inch	8037010	458.000	Sft
0125	_ Sidewalk, Conc, 4 inch, Modified	8037010	801.000	Sft
0130	Post, Steel, 3 pound	8100371	10.000	Ft
0135	Sign, Type III, Erect, Salv	8100402	1.000	Ea

0140	Pavt Mrkg, Waterborne, 4 inch, White	8110231	86.000	Ft
0145	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	202.000	Ft
0150	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	86.000	Ft
0155	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	202.000	Ft
0160	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0165	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	154.000	Ft
0170	_ Pavt Mrkg, Waterborne, 24 inch, Stop Bar	8117001	22.000	Ft
0175	_ Pavt Mrkg, Waterborne, 2nd Application, 12 inch, Crosswalk	8117001	154.000	Ft
0180	_ Pavt Mrkg, Waterborne, 2nd Application, 24 inch, Stop Bar	8117001	22.000	Ft
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0195	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	10.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	10.000	Ea
0210	Minor Traf Devices	8120170	1.000	LSUM
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	775.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	775.000	Sft
0225	Slope Restoration, Non-Freeway, Type A	8162001	216.000	Syd
0230	Sanitary Structure, Adj, Add Depth	8252140	2.000	Ft



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 021**Letting Date:** August 1, 2025**Contract ID:** 18000-221749

Description: 3.37 mi of hot mix asphalt overlay, shoulder trenching and pavement markings on Surrey Road from Old State Road to Harrison Road and Old-27 Road from Long Lake Road to Grant Avenue, Clare County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221749A	25A0750	N/A	STL 18000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$116,900.00	1100001	1.000	LSUM
0010	Masonry and Conc Structure, Rem	2040045	5.000	Cyd
0015	Pavt, Rem	2040050	67.000	Syd
0020	Non Haz Contaminated Material Handling and Disposal, LM	2050031	100.000	Cyd
0025	Subgrade Undercutting, Type II	2050041	100.000	Cyd
0030	Erosion Control, Silt Fence	2080036	100.000	Ft
0035	Aggregate Base, 6 inch	3020016	15,897.000	Syd
0040	Maintenance Gravel	3060020	100.000	Ton
0045	Approach, CI I	3070001	214.000	Ton
0050	Approach, CI II	3070021	299.000	Ton
0055	Shld, CI II	3070121	71.000	Ton
0060	_ Trenching, Modified	3077002	355.000	Sta
0065	_ Shld, CI II, 3.5 inch	3077011	3,932.000	Syd
0070	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0075	Dr Structure Cover, Adj, Case 2	4030006	5.000	Ea
0080	Underdrain, Subgrade, 6 inch	4040073	100.000	Ft
0085	Underdrain Outlet, 6 inch	4040093	50.000	Ft
0090	Underdrain, Outlet Ending, 6 inch	4040113	2.000	Ea
0095	Cold Milling HMA Surface	5010002	6,639.000	Syd
0100	HMA Surface, Rem	5010005	566.000	Syd
0105	Pavt for Butt Joints, Rem	5010008	3,104.000	Syd
0110	HMA Approach	5010061	345.000	Ton
0115	HMA, 4EL	5012024	1,533.000	Ton
0120	HMA, 5EL	5012036	5,185.000	Ton
0125	Driveway, Nonreinf Conc, 6 inch	8010005	67.000	Syd
0130	Post, Mailbox	8070095	62.000	Ea
0135	Pavt Mrkg, Waterborne, 4 inch, White	8110231	34,499.000	Ft

0140	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	27,496.000	Ft
0145	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	34,499.000	Ft
0150	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	27,496.000	Ft
0155	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0160	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	290.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	290.000	Ea
0170	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0175	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0180	Minor Traf Devices	8120170	1.000	LSUM
0185	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,720.000	Ft
0190	Sign Cover	8120310	24.000	Ea
0195	Sign, Type B, Temp, Prismatic, Furn	8120350	1,392.000	Sft
0200	Sign, Type B, Temp, Prismatic, Oper	8120351	1,392.000	Sft
0205	Traf Regulator Control	8120370	1.000	LSUM
0210	Monument Box	8210001	5.000	Ea
0215	Monument Preservation	8210010	5.000	Ea
0220	Gate Box, Adj, Case 1	8230431	5.000	Ea
0225	Gate Box, Adj, Case 2	8230432	5.000	Ea



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 022**Letting Date:** August 1, 2025**Contract ID:** 50000-220739**Description:** Installation of pedestal mount Level 2 EV Charging stations on Harper Avenue at Kyte Monroe Memorial Park in the city of St. Clair Shores, Macomb County. This is a Local Agency project.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220739A	25A0741	N/A	CPM 50000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Audio Visual Record of Construction Area	1027051	1.000	LSUM
0010	Mobilization, Max \$8,300.00	1100001	1.000	LSUM
0015	_ Aggregate Base, 4 inch, Modified	3027011	35.000	Syd
0020	_ Bollard	8007050	4.000	Ea
0025	Sidewalk, Conc, 4 inch	8030044	257.000	Sft
0030	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	155.000	Ft
0035	_ Pavt Mrkg, Waterborne, EV Sym, White	8117050	4.000	Ea
0040	Minor Traf Devices	8120170	1.000	LSUM
0045	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	90.000	Ft
0050	Sodding	8160055	45.000	Syd
0055	Topsoil Surface, Furn, 3 inch	8160061	45.000	Syd
0060	Water, Sodding/Seeding	8160090	3.000	Unit
0065	Cable, Equipment Grounding Wire, 1/C#8	8182292	430.000	Ft
0070	_ Cable, Sec, 600V, 1/C#3	8187001	1,290.000	Ft
0075	_ Conduit, 1, 1 1/2 inch	8187001	430.000	Ft
0080	_ 100A Twin Fused Switch Module for Switchboard	8187050	1.000	Ea
0085	_ 30A Fused Switch	8187050	2.000	Ea
0090	_ 45KVA Transformer	8187050	1.000	Ea
0095	_ Equipment Enclosure	8187050	1.000	Ea
0100	_ EV Charger	8187050	2.000	Ea
0105	_ Panelboard	8187050	1.000	Ea
0110	_ Receptacle for E-Bike Charging	8187050	1.000	Ea



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 023**Letting Date:** August 1, 2025**Contract ID:** 77000-218192

Description: Bridge reconstruction with 27 foot 5 inch by 7 foot 0 inch aluminum box culvert, steel sheet piling, drainage, guardrail and approach work on Arnold Road over Unnamed Creek, St. Clair County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218192A	25A0743	N/A	BO 77000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$149,000.00	1100001	1.000	LSUM
0010	_ Clearing, Modified	2017002	5.000	Sta
0015	Stump, Rem, 6 inch to 18 inch	2020008	1.000	Ea
0020	Culv, Rem, Less than 24 inch	2030001	4.000	Ea
0025	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0030	Exploratory Investigation, Vertical	2040080	50.000	Ft
0035	_ Pavt, Rem, Modified	2047011	40.000	Syd
0040	Embankment, CIP	2050010	503.000	Cyd
0045	Excavation, Earth	2050016	974.000	Cyd
0050	Erosion Control, Silt Fence	2080036	1,406.000	Ft
0055	Project Cleanup	2090001	1.000	LSUM
0060	Subbase, CIP	3010002	696.000	Cyd
0065	_ Aggregate Base, Modified	3027031	972.000	Ton
0070	_ Aggregate Surface Cse, Modified	3067031	379.000	Ton
0075	_ Approach, CI II, Modified	3077031	19.000	Ton
0080	_ Shoulder, CI II, Modified	3077031	34.000	Ton
0085	_ Shoulder, Cobble	3077031	59.000	Ton
0090	Geotextile, Separator, Non-Woven	3082000	142.000	Syd
0095	_ Geotextile Base Reinforcement	3087011	1,574.000	Syd
0100	_ Geotextile, Stabilization, Modified	3087011	1,308.000	Syd
0105	Culv, CI F, CSP, 15 inch	4010676	90.000	Ft
0110	_ Culv, CI A, 30 inch, Modified	4017001	58.000	Ft
0115	Sewer, CI A, 12 inch, Tr Det B	4020033	50.000	Ft
0120	Sewer, CI A, 18 inch, Tr Det B	4020035	196.000	Ft
0125	Dr Structure Cover, Type G	4030040	2.000	Ea
0130	Dr Structure, 24 inch dia	4030200	1.000	Ea
0135	Dr Structure, 48 inch dia	4030210	1.000	Ea

0140	HMA, 4EL	5012024	193.000	Ton
0145	HMA, 5EL	5012036	116.000	Ton
0150	Conc Pavt, Nonreinf, 10 inch	6020108	252.000	Syd
0155	Joint, Contraction, Cp	6020200	144.000	Ft
0160	Driveway, Reinf Conc, 6 inch	8010001	45.000	Syd
0165	Guardrail Approach Terminal, Type 2M	8070044	3.000	Ea
0170	Guardrail Departing Terminal, Type MGS	8070052	1.000	Ea
0175	Guardrail Reflector	8070080	20.000	Ea
0180	Post, Mailbox	8070095	3.000	Ea
0185	Guardrail, Curved, Type MGS-8, 72 inch Post	8072145	13.000	Ft
0190	Guardrail, Type MGS-8, 72 inch Post	8072179	313.000	Ft
0195	_ Guardrail, Culv, Modified	8077001	125.000	Ft
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0205	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0210	Minor Traf Devices	8120170	1.000	LSUM
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	215.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	215.000	Sft
0225	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	30.000	Sft
0230	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	30.000	Sft
0235	_ Riprap, Cobble	8137011	12.000	Syd
0240	Pinus heldreichii, 4 foot	8152814	8.000	Ea
0245	Slope Restoration, Non-Freeway, Type B	8162002	1,826.000	Syd
0250	Slope Restoration, Non-Freeway, Type C	8162003	1,884.000	Syd

Section: 2

0255	Structures, Rem	2040060	1.000	LSUM
0260	Excavation, Channel	2050015	903.000	Cyd
0265	Backfill, Structure, CIP	2060002	63.000	Cyd
0270	Excavation, Fdn	2060010	602.000	Cyd
0275	_ Backfill, Structure, Modified	2067021	564.000	Cyd
0280	_ Flowable Fill, Non-Structural, Modified	2067021	24.000	Cyd
0285	Erosion Control, Filter Bag	2080014	2.000	Ea
0290	_ Geocell, 6 inch	3087011	105.000	Syd
0295	_ Bypass Pumping	4017050	1.000	Ea
0300	_ Construction Dam	4017050	1.000	Ea
0305	Underdrain, Fdn, 6 inch	4040033	188.000	Ft
0310	Underdrain Outlet, 6 inch	4040093	20.000	Ft
0315	Underdrain, Outlet Ending, 6 inch	4040113	2.000	Ea
0320	_ Culv, Aluminum Box, 27 Foot 5 inch by 7 Foot 0 inch	4067001	63.000	Ft
0325	_ Steel Sheet Piling, Permanent, Galvanized	7047010	2,284.000	Sft
0330	Reinforcement, Steel, Epoxy Coated	7060092	6,772.000	Lb
0335	Substructure Conc	7060100	62.000	Cyd
0340	_ Structure Name Plate	7067050	1.000	Ea

0345	Riprap, Plain	8130010	439.000	Syd
------	---------------	---------	---------	-----

Schedule of Pay Items

Report v1

Letting Call: 250801 024

Letting Date: August 1, 2025

Contract ID: 38000-217024

Description: Bridge reconstruction includes prestress concrete box beams, cofferdams steel piling, steel sheet piling, culverts, concrete curb and gutter, drainage, guardrail and approach work on Hanover Road over the south branch of the Kalamazoo River, Townline Highway over Wolf Creek and Central Road over Coldwater River and McCabe Road over the Huron River and Lenawee County Line Road over Milan-Macon Drain, Branch, Jackson, Lenawee, Livingston and Monroe Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217024A	N/A	N/A	LBB1 38000
217026A	N/A	N/A	LBB1 46000
217039A	N/A	N/A	LBB1 47000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Compensatory Mitigation Payment	1027060	10,681.000	Dlr
0010	Mobilization, Max \$863,200.00	1100001	1.000	LSUM
0015	Clearing	2010001	0.780	Acre
0020	Tree, Rem, 19 inch to 36 inch	2020002	7.000	Ea
0025	Tree, Rem, 6 inch to 18 inch	2020004	8.000	Ea
0030	Stump, Rem, 6 inch to 18 inch	2020008	1.000	Ea
0035	Culv, Rem, Less than 24 inch	2030001	1.000	Ea
0040	Conc Barrier, Rem	2040010	18.000	Ft
0045	Fence, Rem	2040025	40.000	Ft
0050	Guardrail, Rem	2040035	434.000	Ft
0055	Embankment, CIP	2050010	2,265.000	Cyd
0060	Excavation, Earth	2050016	3,831.000	Cyd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	35.000	Cyd
0070	Subgrade Undercutting, Type II	2050041	204.000	Cyd
0075	Erosion Control, Check Dam, Stone	2080012	56.000	Ft
0080	Erosion Control, Inlet Protection, Fabric Drop	2080020	7.000	Ea
0085	Erosion Control, Inlet Protection, Sediment Trap	2080024	2.000	Ea
0090	Erosion Control, Sand Bag	2080028	5.000	Ea
0095	Erosion Control, Sediment Basin	2080032	15.000	Cyd
0100	Erosion Control, Sediment Trap	2080034	3.000	Ea
0105	Erosion Control, Silt Fence	2080036	6,597.000	Ft
0110	_ Erosion Control, Silt Fence, Spec	2087001	1,002.000	Ft
0115	Project Cleanup	2090001	1.000	LSUM

0120	Subbase, CIP	3010002	5,249.000	Cyd
0125	Aggregate Base, 6 inch	3020016	2,857.000	Syd
0130	Aggregate Base, 12 inch	3020030	259.000	Syd
0135	Open-Graded Dr Cse, 6 inch	3030006	492.000	Syd
0140	Aggregate Surface Cse, 6 inch	3060010	5,267.000	Syd
0145	Driveway Maintenance, Residential	3062001	6.000	Ea
0150	_ Shld, CI II, 6.5 inch	3077011	569.000	Syd
0155	Geotextile, Separator	3080005	859.000	Syd
0160	Geotextile, Stabilization	3080010	610.000	Syd
0165	Culv End Sect, 12 inch	4010012	3.000	Ea
0170	Culv, CI F, 12 inch	4010607	33.000	Ft
0175	Dr Marker Post	4011109	15.000	Ea
0180	Culv, Outlet Headwall, 12 inch	4012000	6.000	Ea
0185	Sewer, CI A, 12 inch, Tr Det B	4020033	138.000	Ft
0190	Dr Structure Cover, Adj, Case 2	4030006	2.000	Ea
0195	Dr Structure Cover, Type K	4030050	4.000	Ea
0200	Dr Structure Cover, Type W	4030080	3.000	Ea
0205	Dr Structure, 48 inch dia	4030210	7.000	Ea
0210	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	2.000	Ft
0215	Dr Structure, Adj, Add Depth	4030280	2.000	Ft
0220	Underdrain, Subbase, 6 inch	4040063	2,773.000	Ft
0225	Underdrain Outlet, 6 inch	4040093	187.000	Ft
0230	Underdrain, Outlet Ending, 6 inch	4040113	16.000	Ea
0235	HMA Surface, Rem	5010005	2,200.000	Syd
0240	HMA, 3EML	5012013	373.000	Ton
0245	HMA, 4EML	5012025	249.000	Ton
0250	HMA, 5EML	5012037	186.000	Ton
0255	Joint, Expansion, E2	6020207	60.000	Ft
0260	Joint, Expansion, E3	6020208	373.000	Ft
0265	Joint, Expansion, E4	6020209	6.000	Ft
0270	Conc Pavt, Nonreinf, 12 inch, High Performance	6020508	107.000	Syd
0275	Shld, Nonreinf Conc, High Performance	6020524	2.000	Syd
0280	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	464.000	Syd
0285	Curb and Gutter, Conc, Det D2	8020031	78.000	Ft
0290	Curb and Gutter, Conc, Det F5	8020039	58.000	Ft
0295	Curb and Gutter, Bridge Approach, Det 5	8022016	279.000	Ft
0300	Curb and Gutter, Bridge Approach, Det 6	8022017	224.000	Ft
0305	Guardrail Approach Terminal, Type 2M	8070044	18.000	Ea
0310	Guardrail Departing Terminal, Type MGS	8070052	2.000	Ea
0315	Guardrail Reflector	8070080	84.000	Ea
0320	Post, Mailbox	8070095	1.000	Ea
0325	Guardrail Anch, Bridge, Det M1	8070130	14.000	Ea
0330	Guardrail Anch, Bridge, Det M4	8070133	5.000	Ea
0335	Guardrail Anch, Bridge, Det M1, Curved	8072036	1.000	Ea

0340	Guardrail, Curved, Type B-CRT	8072154	13.000	Ft
0345	Guardrail, Type MGS-8, 72 inch Post	8072179	487.000	Ft
0350	Guardrail, Type MGS-8, 108 inch Post	8072180	240.000	Ft
0355	_ Hand Digging Guardrail Post	8077050	2.000	Ea
0360	Fence, Woven Wire with Steel Post	8080002	40.000	Ft
0365	Delineator Reflector, Green	8100133	20.000	Ea
0370	Post, Rigid, Delineator	8100361	20.000	Ea
0375	Post, Steel, 3 pound	8100371	142.000	Ft
0380	Sign, Type III, Rem	8100403	14.000	Ea
0385	Sign, Type IIIB	8100405	38.000	Sft
0390	Ground Mtd Sign Support, Rem	8102010	11.000	Ea
0395	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,770.000	Ft
0400	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	410.000	Ft
0405	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	131.000	Ea
0410	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	131.000	Ea
0415	Pedestrian Type II Barricade, Temp	8120026	3.000	Ea
0420	Conc Barrier, Temp, Furn	8120081	300.000	Ft
0425	Conc Barrier, Temp, Oper	8120082	300.000	Ft
0430	Minor Traf Devices	8120170	1.000	LSUM
0435	Plastic Drum, Fluorescent, Furn	8120252	17.000	Ea
0440	Plastic Drum, Fluorescent, Oper	8120253	17.000	Ea
0445	Sign Cover	8120310	386.000	Ea
0450	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	10.000	Ea
0455	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	10.000	Ea
0460	Sign, Type B, Temp, Prismatic, Furn	8120350	2,181.000	Sft
0465	Sign, Type B, Temp, Prismatic, Oper	8120351	2,181.000	Sft
0470	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	1,094.000	Sft
0475	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	1,094.000	Sft
0480	Traf Regulator Control	8120370	1.000	LSUM
0485	Riprap, Plain	8130010	546.000	Syd
0490	Ditch, Plain Cobble	8140005	34.000	Syd
0495	Slope Restoration, Non-Freeway, Type A	8162001	26.000	Syd
0500	Slope Restoration, Non-Freeway, Type E	8162005	960.000	Syd
0505	Slope Restoration, Non-Freeway, Type F	8162006	3,761.000	Syd
0510	Slope Restoration, Non-Freeway, Type G	8162007	862.000	Syd
0515	_ Mulch Blanket, Modified	8167011	465.000	Syd
0520	_ Native Grasses and Wildflowers Seeding	8167011	1,023.000	Syd
0525	_ Slope Restoration, Wetland	8167011	1,106.000	Syd
0530	Contractor Staking	8240001	1.000	LSUM
0535	Staking Plan Errors and Extras, Max \$180/hour	8240002	94.000	Hr

Section: 2

0540	Structures, Rem (SN 1109)	2040060	1.000	LSUM
0545	Structures, Rem (SN 4526)	2040060	1.000	LSUM
0550	Structures, Rem (SN 5612)	2040060	1.000	LSUM
0555	Structures, Rem (SN 5861)	2040060	1.000	LSUM
0560	Structures, Rem (SN 7254)	2040060	1.000	LSUM
0565	Excavation, Channel	2050015	96.000	Cyd
0570	Backfill, Structure, CIP	2060002	3,393.000	Cyd
0575	Excavation, Fdn	2060010	8,626.000	Cyd
0580	Erosion Control, Filter Bag	2080014	16.000	Ea
0585	Erosion Control, Gravel Filter Berm	2080018	480.000	Ft
0590	Erosion Control, Maintenance, Sediment Rem	2080026	15.000	Cyd
0595	Erosion Control, Turbidity Curtain, Deep	2080042	812.000	Ft
0600	Erosion Control, Turbidity Curtain, Shallow	2080044	250.000	Ft
0605	Aggregate Base	3020001	204.000	Ton
0610	Open-Graded Dr Cse, CIP	3030030	230.000	Cyd
0615	Underdrain, Fdn, 4 inch	4040031	1,259.000	Ft
0620	Underdrain Outlet, 4 inch	4040091	168.000	Ft
0625	Underdrain, Outlet Ending, 4 inch	4040111	12.000	Ea
0630	Steel Sheet Piling, Permanent	7040001	350.000	Sft
0635	Cofferdams (SN 5612)	7040007	1.000	LSUM
0640	Cofferdams (SN 5861)	7040007	1.000	LSUM
0645	Cofferdams (SN 7254)	7040007	1.000	LSUM
0650	Cofferdams, Left in Place (SN 1109)	7040009	1.000	LSUM
0655	Cofferdams, Left in Place (SN 4526)	7040009	1.000	LSUM
0660	Cofferdams, Left in Place (SN 5612)	7040009	1.000	LSUM
0665	_ Vibration Monitoring, Utility	7047051	1.000	LSUM
0670	Pile Driving Equipment, Furn (SN 1109)	7050002	1.000	LSUM
0675	Pile Driving Equipment, Furn (SN 4526)	7050002	1.000	LSUM
0680	Pile Driving Equipment, Furn (SN 5861)	7050002	1.000	LSUM
0685	Pile Driving Equipment, Furn (SN 7254)	7050002	1.000	LSUM
0690	Pile Point, CIP Conc	7050025	73.000	Ea
0695	Pile, Steel, Furn and Driven, 14 inch	7050034	9,080.000	Ft
0700	Test Pile, Steel, 14 inch	7050035	12.000	Ea
0705	Pile Point, Steel	7050039	105.000	Ea
0710	Pile, Steel, Splice	7050050	132.000	Ea
0715	_ Pile, CIP Conc, Furn and Driven, 20 inch	7057001	2,795.000	Ft
0720	_ Test Pile, CIP Conc, 20 inch	7057050	4.000	Ea
0725	_ Test Pile, Furn Dynamic Analysis	7057050	4.000	Ea
0730	_ Test Pile, Furn Dynamic Analysis Equipment	7057050	4.000	Ea
0735	Bridge Ltg, Furn and Rem (SN 1109)	7060001	1.000	LSUM
0740	Bridge Ltg, Furn and Rem (SN 4526)	7060001	1.000	LSUM
0745	Bridge Ltg, Furn and Rem (SN 5612)	7060001	1.000	LSUM
0750	Bridge Ltg, Furn and Rem (SN 5861)	7060001	1.000	LSUM
0755	Bridge Ltg, Furn and Rem (SN 7254)	7060001	1.000	LSUM
0760	Bridge Ltg, Oper and Maintain	7060002	350.000	Cyd

0765	Expansion Joint Device	7060050	116.000	Ft
0770	False Decking	7060060	13,338.000	Sft
0775	Reinforcement, Steel, Epoxy Coated	7060092	200,736.000	Lb
0780	Substructure Conc, High Performance	7060101	1,379.000	Cyd
0785	Superstructure Conc, Form, Finish, and Cure (SN 1109)	7060111	1.000	LSUM
0790	Superstructure Conc, Form, Finish, and Cure (SN 4526)	7060111	1.000	LSUM
0795	Superstructure Conc, Form, Finish, and Cure (SN 5612)	7060111	1.000	LSUM
0800	Superstructure Conc, Form, Finish, and Cure (SN 5861)	7060111	1.000	LSUM
0805	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 1109)	7060112	1.000	LSUM
0810	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 4526)	7060112	1.000	LSUM
0815	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 5612)	7060112	1.000	LSUM
0820	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 5861)	7060112	1.000	LSUM
0825	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 7254)	7060112	1.000	LSUM
0830	Superstructure Conc, High Performance	7060116	25.000	Cyd
0835	Superstructure Conc, Night Casting, High Performance	7060117	350.000	Cyd
0840	Sealing Localized Cracks (SN 1109)	7060220	1.000	LSUM
0845	Sealing Localized Cracks (SN 4526)	7060220	1.000	LSUM
0850	Sealing Localized Cracks (SN 5612)	7060220	1.000	LSUM
0855	Sealing Localized Cracks (SN 5861)	7060220	1.000	LSUM
0860	Sealing Localized Cracks (SN 7254)	7060220	1.000	LSUM
0865	Conc, Grade 3500	7062001	1,280.000	Cyd
0870	Conc, Grade 3500HP	7062002	380.000	Cyd
0875	Bearing, Elastomeric, 1 1/2 inch	7070014	2,605.000	Sin
0880	Bearing, Elastomeric, 1 3/4 inch	7070015	4,329.000	Sin
0885	Bearing, Elastomeric, 2 inch	7070016	4,081.000	Sin
0890	Shear Developers (SN 7254)	7070040	1.000	LSUM
0895	Steel Diaphragm, Prest Conc Beam, Furn and Fab	7070053	418.000	Lb
0900	Steel Diaphragm, Prest Conc Beam, Erect	7070054	418.000	Lb
0905	Structural Steel, Rolled Shape, Erect	7070070	16,470.000	Lb
0910	Structural Steel, Rolled Shape, Furn and Fab	7070071	16,470.000	Lb
0915	_ Structural Steel, Erect, Spec	7077051	1.000	LSUM
0920	_ Structural Steel, Furn and Fab, Spec	7077051	1.000	LSUM
0925	Prest Conc Box Beam, Furn, 21 inch	7080061	408.000	Ft
0930	Prest Conc Box Beam, Erect, 21 inch	7080062	408.000	Ft
0935	Prest Conc Box Beam, Furn, 27 inch	7080065	284.000	Ft
0940	Prest Conc Box Beam, Erect, 27 inch	7080066	284.000	Ft
0945	Joint Waterproofing	7100001	1,408.000	Sft
0950	Joint Waterproofing, Expansion	7100003	214.000	Sft
0955	Substructure Horizontal Surface Sealer (SN 1109)	7100030	30.000	Syd

0960	Substructure Horizontal Surface Sealer (SN 4526)	7100030	16.000	Syd
0965	Substructure Horizontal Surface Sealer (SN 5612)	7100030	130.000	Syd
0970	Substructure Horizontal Surface Sealer (SN 5861)	7100030	100.000	Syd
0975	Substructure Horizontal Surface Sealer (SN 7254)	7100030	130.000	Syd
0980	_ Silane Treatment	7107010	6,431.000	Sft
0985	Bridge Railing, Aesthetic Parapet Tube, High Performance	7110004	440.000	Ft
0990	Bridge Railing, Aesthetic Parapet Tube	7110005	74.000	Ft
0995	Bridge Barrier Railing, Type 6, High Performance	7110017	89.000	Ft
1000	Field Repr of Damaged Coating (SN 7254)	7160001	1.000	LSUM
1005	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM
1010	Riprap, Heavy	8130005	593.000	Syd
1015	_ Riprap, Fieldstone, Spec	8137031	551.000	Ton



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 025**Letting Date:** August 1, 2025**Contract ID:** 55021-217332

Description: 10.39 mi of hot mix asphalt base crushing, shaping, and resurfacing, joint repairs, paver placed surface seal and pavement markings on US-2 from west of the US-2/US-41 westerly to west of the Dickinson/Menominee County line, Dickinson and Menominee Counties. This project includes a 5 year materials and workmanship pavement warranty and a 3 year pavement performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217332A	25A0784	N/A	NH 55021
217334A	25A0790	N/A	NH 55021

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$362,800.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	128.000	Ft
0015	Berm Grading	2050008	18.000	Sta
0020	Erosion Control, Silt Fence	2080036	1,240.000	Ft
0025	Aggregate Base	3020001	200.000	Ton
0030	HMA Base Crushing and Shaping	3050002	38,357.000	Syd
0035	Material, Surplus and Unsuitable, Rem, LM	3050010	50.000	Cyd
0040	Salv Crushed Material, LM	3050015	350.000	Cyd
0045	Approach, CI II	3070021	400.000	Ton
0050	Shld, CI II	3070121	1,605.000	Ton
0055	Culv End Sect, 24 inch	4010024	2.000	Ea
0060	Culv End Sect, Footing	4010072	2.000	Ea
0065	Dr Marker Post	4011109	4.000	Ea
0070	_ Culv Cleanout	4017001	269.000	Ft
0075	Cold Milling HMA Surface	5010002	32,689.000	Syd
0080	HMA Quality Initiative	5010007	23,330.000	Dlr
0085	Edge Trimming	5010009	2,908.000	Ft
0090	Longit Joint Density Quality Initiative	5010018	50,772.000	Dlr
0095	Pavt Joint and Crack Repr, Det 7	5010020	244.000	Ft
0100	Pavt Joint and Crack Repr, Det 8	5010021	144.000	Ft
0105	Hand Patching	5010025	210.000	Ton
0110	HMA Approach	5010061	130.000	Ton
0115	Micro Texture Pavt Milling	5010101	10,372.000	Syd
0120	HMA, 4EL	5012024	4,041.000	Ton
0125	HMA, 4EML	5012025	4,179.000	Ton
0130	HMA, 5EML	5012037	3,105.000	Ton

0135	Overband Crack Fill, Lane	5020003	20.000	Lnmi
0140	Paver Placed Surface Seal, Type C, Warranty	5030041	228,308.000	Syd
0145	Guardrail Height, Adj	8070100	850.000	Ft
0150	Guardrail, Reconst, Type B	8070105	300.000	Ft
0155	Delineator Reflector, White	8100134	60.000	Ea
0160	Post, Rigid, Delineator	8100361	30.000	Ea
0165	Pavt Mrkg, Polyurea, Merge Arrow Sym	8110107	4.000	Ea
0170	Pavt Mrkg, Waterborne, 6 inch, White	8110233	110,588.000	Ft
0175	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	31,293.000	Ft
0180	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	107,949.000	Ft
0185	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	31,293.000	Ft
0190	Rem Spec Mrkg	8110343	900.000	Sft
0195	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0200	Recessing Pavt Mrkg, Longit	8110450	19,100.000	Ft
0205	Protective Ovly, Snowmobile Trail Crossing	8110550	68.000	Syd
0210	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	2,639.000	Ft
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0225	Connected Arrow Board, Type C, Furn	8120155	6.000	Ea
0230	Connected Arrow Board, Type C, Oper	8120156	6.000	Ea
0235	Minor Traf Devices	8120170	1.000	LSUM
0240	Plastic Drum, Fluorescent, Furn	8120252	450.000	Ea
0245	Plastic Drum, Fluorescent, Oper	8120253	450.000	Ea
0250	Sign Cover	8120310	10.000	Ea
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	2,100.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	2,100.000	Sft
0265	Traf Regulator Control	8120370	1.000	LSUM
0270	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	1,350.000	Ft
0275	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	5,400.000	Ft
0280	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	500.000	Ft
0285	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	700.000	Ft
0290	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0295	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0300	Slope Restoration, Non-Freeway, Type B	8162002	2,005.000	Syd
0305	Monument Box	8210001	2.000	Ea
0310	Monument Box, Adj	8210005	13.000	Ea
0315	Monument Preservation	8210010	2.000	Ea
0320	Centerline Corrugations, Milled, HMA	8220013	45,787.000	Ft
0325	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	99,041.000	Ft
0330	Contractor Staking	8240001	1.000	LSUM

0335	Staking Plan Errors and Extras, Max \$180/hour	8240002	14.000	Hr
------	--	---------	--------	----



7/14/2025 8:47 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 250801 026**Letting Date:** August 1, 2025**Contract ID:** 37011-217887

Description: 1.69 mi of hot mix asphalt cold milling and resurfacing, joint repairs, concrete sidewalk ramps and pavement markings on US-127BR from Old Mission Road to High Street in the city of Mount Pleasant, Isabella County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217887A	25A0797	N/A	NH 37011

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$121,500.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	278.000	Ft
0015	Pavt, Rem	2040050	6.000	Syd
0020	Sidewalk, Rem	2040055	133.000	Syd
0025	Excavation, Earth	2050016	26.000	Cyd
0030	Subbase, CIP	3010002	26.000	Cyd
0035	Aggregate Base, 3 inch	3020008	56.000	Syd
0040	_ Shld, CI II, Modified	3077031	30.000	Ton
0045	Dr Structure Cover, Adj, Case 1, Modified	4030004	34.000	Ea
0050	Cold Milling HMA Surface	5010002	64,200.000	Syd
0055	HMA Surface, Rem	5010005	40.000	Syd
0060	HMA Quality Initiative	5010007	11,540.000	Dlr
0065	Longit Joint Density Quality Initiative	5010018	36,610.000	Dlr
0070	Hand Patching	5010025	20.000	Ton
0075	HMA Approach	5010061	350.000	Ton
0080	HMA, 5EML, High Stress	5012085	5,400.000	Ton
0085	Conc Base Cse, Nonreinf, 6 inch	6020015	33.000	Syd
0090	Conc Base Cse, Nonreinf, 9 inch	6020021	6.000	Syd
0095	Curb and Gutter, Conc, Det F4	8020038	218.000	Ft
0100	Driveway Opening, Conc, Det M	8020050	10.000	Ft
0105	Detectable Warning Surface	8030010	65.000	Ft
0110	Curb Ramp Opening, Conc	8030030	103.000	Ft
0115	Sidewalk, Conc, 6 inch	8030046	489.000	Sft
0120	Curb Ramp, Conc, 6 inch	8032002	610.000	Sft
0125	_ Brick Pavers, Rem and Salv	8037010	50.000	Sft
0130	_ Reinstall Brick Pavers on Aggregate and Sand Bed	8037010	50.000	Sft
0135	Delineator, Rem	8100349	9.000	Ea

0140	Post, Steel, 3 pound	8100371	28.000	Ft
0145	Sign, Type III, Erect, Salv	8100402	2.000	Ea
0150	Sign, Type III, Rem, Salv	8102003	2.000	Ea
0155	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0160	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	16.000	Ea
0165	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	7.000	Ea
0170	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,968.000	Ft
0175	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	1,560.000	Ft
0180	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	671.000	Ft
0185	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0190	Recessing Pavt Mrkg, Longit	8110450	36,822.000	Ft
0195	Recessing Pavt Mrkg, Transv	8110451	4,990.000	Sft
0200	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	15,946.000	Ft
0205	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	20,876.000	Ft
0210	Pedestrian Type II Barricade, Temp	8120026	15.000	Ea
0215	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	275.000	Ea
0220	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	275.000	Ea
0225	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0230	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0235	Minor Traf Devices	8120170	1.000	LSUM
0240	Sign Cover	8120310	10.000	Ea
0245	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0250	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	1,400.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	1,400.000	Sft
0265	Traf Regulator Control	8120370	1.000	LSUM
0270	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	1,500.000	Ft
0275	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,500.000	Ft
0280	_ Turf Establishment, Performance, Modified	8167011	40.000	Syd
0285	TS Face, Bag	8200458	10.000	Ea
0290	TS Face, Bag, Rem	8200459	10.000	Ea
0295	Radar Vehicle Presence Stop-Bar Detector System	8200510	1.000	Ea
0300	Radar Vehicle Presence Stop-Bar Detector Sensor	8200513	4.000	Ea
0305	Monument Box, Adj	8210005	5.000	Ea
0310	Protect Corners	8210020	5.000	Ea
0315	Water Shutoff, Adj, Case 1	8230421	13.000	Ea
0320	Contractor Staking	8240001	1.000	LSUM
0325	Staking Plan Errors and Extras, Max \$180/hour	8240002	14.000	Hr