



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 001

**Letting Date:** September 5, 2025

**Contract ID:** 82073-223188

**Description:** Bridge rehabilitation including remove and replace barrier, sidewalk coating repair, drainage and mechanical repair on M-85 over Rouge River, Wayne County. This project includes a 2 year performance bridge coating warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
223188A	25A0831	N/A	BFP 82073

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$69,500.00	1100001	1.000	LSUM
0010	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0015	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0020	Pedestrian Type II Barricade, Temp	8120026	16.000	Ea
0025	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0030	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0035	Minor Traf Devices	8120170	1.000	LSUM
0040	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0045	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0050	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0055	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0060	Sign, Type B, Temp, Prismatic, Furn	8120350	235.000	Sft
0065	Sign, Type B, Temp, Prismatic, Oper	8120351	235.000	Sft

**Section: 2**

0070	_ Maintaining Navigation (B01 of 82073)	1077051	1.000	LSUM
0075	Reinforcement, Steel, Epoxy Coated	7060092	1,379.000	Lb
0080	_ Bridge Barrier Railing, Spec, High Performance	7117001	81.000	Ft
0085	Adhesive Anchoring of Vertical Bar, 1/2 inch	7120032	304.000	Ea
0090	Structures, Rehabilitation, Rem Portions (B01 of 82073)	7120070	1.000	LSUM
0095	_ Walkway Extension (B01 of 82073)	7137051	1.000	LSUM
0100	Steel Structure, Cleaning, Partial, Type 4 (B01 of 82073)	7150047	1.000	LSUM
0105	Steel Structure, Coating, Partial, Type 4 (B01 of 82073)	7150048	1.000	LSUM

0110	_ Anti-Slip Coating Repr (B01 of 82073)	7157051	1.000	LSUM
0115	_ Heating and Housing (B01 of 82073)	7157051	1.000	LSUM
0120	Field Repr of Damaged Coating (B01 of 82073)	7160001	1.000	LSUM
0125	_ Bridge Drainage System (B01 of 82073)	7177051	1.000	LSUM
0130	_ Door Installation (B01 of 82073)	8007051	1.000	LSUM
0135	_ Mechanical Repairs (B01 of 82073)	8007051	1.000	LSUM
0140	_ Warning Gate Repairs (B01 of 82073)	8007051	1.000	LSUM
0145	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 002

**Letting Date:** September 5, 2025

**Contract ID:** 08012-200167

**Description:** 5.89 mi of single course chip seal with fog seal and HMA overband crack on M-43 from the north city limits of Hastings to Osborne Road, Barry County. This project includes a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
200167A	25A0830	N/A	ST 08012

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$79,200.00	1100001	1.000	LSUM
0010	Overband Crack Fill, Lane	5020003	11.810	Lnmi
0015	Seal, Fog	5050015	146,117.000	Syd
0020	Chip Seal, Shld, Warranty	5050030	60,094.000	Syd
0025	Chip Seal, Single, Warranty	5050040	86,023.000	Syd
0030	Chip Seal Emulsion, Long Line Application	5050100	134,445.000	Ft
0035	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0040	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	61,500.000	Ft
0045	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, Yellow	8112004	38,000.000	Ft
0050	Pavt Mrkg, Wet Reflective Waterborne, 6 inch, White	8112145	61,500.000	Ft
0055	Pavt Mrkg, Wet Reflective Waterborne, 6 inch, Yellow	8112148	38,000.000	Ft
0060	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	950.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	950.000	Ea
0070	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0075	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	1,980.000	Ea
0090	Sign Cover	8120310	20.000	Ea
0095	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0100	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0105	Sign, Type B, Temp, Prismatic, Furn	8120350	1,600.000	Sft
0110	Sign, Type B, Temp, Prismatic, Oper	8120351	1,600.000	Sft
0115	Traf Regulator Control	8120370	1.000	LSUM
0120	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea

0125	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0130	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0135	Protect Corners	8210020	7.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 003

**Letting Date:** September 5, 2025

**Contract ID:** 25042-208917

**Description:** Bridge rehabilitation including deep overlay with partial deck replacement, barrier replacement, shallow overlay, epoxy overlay, expansion joint replacement, concrete and steel beam repairs, substructure patching, deck replacement of 1 structure, guardrail and approach work on I-69 at 17 structures, Genesee and Shiawassee Counties. This project includes a 2 year concrete surface coating warranty and a 5 year high friction epoxy overlay performance warranty. This is an OJT VIP Project. Please see Special Provision for Preparation and Consideration of Bids on On-the-Job-Training Voluntary Incentive Program Projects.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
208917A	25A0835	N/A	BFPI 25042
218426A	N/A	N/A	M 76023

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Conc Quality Initiative	10000030	96,000.000	Dlr
0010	Dispute Review Board, Hearing	1040010	18,800.000	Dlr
0015	Dispute Review Board, Progress Meeting	1040050	74,800.000	Dlr
0020	Critical Path Method Schedule	1080005	15,000.000	Dlr
0025	Mobilization, Max \$3,208,800.00	1100001	1.000	LSUM
0030	Clearing	2010001	0.410	Acre
0035	Culv, Rem, Less than 24 inch	2030001	8.000	Ea
0040	Culv, End, Rem, Less than 24 inch	2030005	1.000	Ea
0045	Dr Structure, Rem	2030011	2.000	Ea
0050	Sewer, Rem, Less than 24 inch	2030015	47.000	Ft
0055	Curb and Gutter, Rem	2040020	1,263.000	Ft
0060	Guardrail, Rem	2040035	13,085.000	Ft
0065	Pavt, Rem	2040050	19,038.000	Syd
0070	Embankment, CIP	2050010	450.000	Cyd
0075	Excavation, Earth	2050016	14,932.000	Cyd
0080	Non Haz Contaminated Material Handling and Disposal, LM	2050031	65.000	Cyd
0085	_ Non Haz Contaminated Material Handling and Disposal (PFAS), LM	2057021	1,571.000	Cyd
0090	Erosion Control, Check Dam, Stone	2080012	50.000	Ft
0095	Erosion Control, Inlet Protection, Fabric Drop	2080020	24.000	Ea
0100	Erosion Control, Maintenance, Sediment Rem	2080026	7.000	Cyd
0105	Erosion Control, Sand Bag	2080028	250.000	Ea
0110	Erosion Control, Sediment Basin	2080032	10.000	Cyd

0115	Erosion Control, Silt Fence	2080036	2,990.000	Ft
0120	Erosion Control, Turbidity Curtain, Deep	2080042	398.000	Ft
0125	Erosion Control, Turbidity Curtain, Shallow	2080044	100.000	Ft
0130	Project Cleanup	2090001	1.000	LSUM
0135	Subbase, CIP	3010002	16,660.000	Cyd
0140	Aggregate Base, 6 inch	3020016	12,969.000	Syd
0145	Open-Graded Dr Cse, 6 inch	3030006	20,038.000	Syd
0150	_ Shld, CI II, Modified	3077031	3,636.000	Ton
0155	Geotextile, Separator	3080005	22,232.000	Syd
0160	Culv, Downspout, 12 inch	4010795	632.000	Ft
0165	Dr Marker Post	4011109	114.000	Ea
0170	Culv, Outlet Headwall, 12 inch	4012000	22.000	Ea
0175	_ Slotted Drain, Galv, 12 inch, Temp	4027001	995.000	Ft
0180	Dr Structure Cover, Adj, Case 1	4030005	4.000	Ea
0185	Dr Structure, Tap, 6 inch	4030306	4.000	Ea
0190	Underdrain, Pipe, Open-Graded, 6 inch	4040043	13,705.000	Ft
0195	Underdrain, Subbase, 6 inch	4040063	1,400.000	Ft
0200	Underdrain Outlet, 6 inch	4040093	3,620.000	Ft
0205	Underdrain, Outlet Ending, 6 inch	4040113	123.000	Ea
0210	Video Inspection of Underdrain	4040200	18,665.000	Ft
0215	_ Underdrain, Rem	4047001	9,425.000	Ft
0220	HMA Surface, Rem	5010005	976.000	Syd
0225	HMA, 4EL	5012024	180.000	Ton
0230	HMA, 5EL	5012036	55.000	Ton
0235	HMA, Temp Pavt (4EL)	5012102	2,474.000	Ton
0240	HMA, Temp Pavt (5EL)	5012104	928.000	Ton
0245	Conc Base Cse, Nonreinf, 9 inch	6020021	290.000	Syd
0250	Joint, Contraction, Cp	6020200	3,658.000	Ft
0255	Joint, Contraction, C3p	6020201	3,051.000	Ft
0260	Joint, Expansion, E2	6020207	2,464.000	Ft
0265	Joint, Expansion, E3	6020208	1,391.000	Ft
0270	Joint, Expansion, E4	6020209	955.000	Ft
0275	Conc Pavt, Misc, Nonreinf, 9 inch, High Performance	6020514	195.000	Syd
0280	Conc Pavt, Misc, Nonreinf, 11 1/2 inch, High Performance	6020519	2,185.000	Syd
0285	Conc Pavt, Misc, Nonreinf, 12 inch, High Performance	6020520	12,690.000	Syd
0290	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	3,558.000	Syd
0295	Joint, Contraction, Crg	6030020	1,246.000	Ft
0300	Lane Tie, Epoxy Anchored	6030030	1,984.000	Ea
0305	_ Filling Shld Corrugations with Hot-Poured Rubber	6037001	3,000.000	Ft
0310	Reflective Marker, Permanent Barrier	7110003	122.000	Ea
0315	Curb and Gutter, Conc, Det D1	8020030	405.000	Ft
0320	Downspout Header, Conc	8020070	22.000	Ea
0325	Curb and Gutter, Bridge Approach, Det 5	8022016	389.000	Ft
0330	Curb and Gutter, Bridge Approach, Det 6	8022017	648.000	Ft

0335	Curb and Gutter, Bridge Approach, Det 7	8022018	664.000	Ft
0340	Curb and Gutter, Bridge Approach, Det 6A	8022019	80.000	Ft
0345	Curb and Gutter, Bridge Approach, Det 7A	8022020	82.000	Ft
0350	_ Curb and Gutter, Bridge Approach, Det 5, Modified	8027001	37.000	Ft
0355	_ Valley Gutter, Conc, Modified	8027001	914.000	Ft
0360	Conc Barrier, Single Face, Type B	8040002	824.000	Ft
0365	Guardrail Approach Terminal, Type 2M	8070044	5.000	Ea
0370	Guardrail Approach Terminal, Type 2M, Temp	8070049	7.000	Ea
0375	Guardrail Departing Terminal, Type T	8070051	8.000	Ea
0380	Guardrail Departing Terminal, Type MGS	8070052	13.000	Ea
0385	Guardrail Approach Terminal, Type 3M, Temp	8070065	3.000	Ea
0390	Guardrail Reflector	8070080	629.000	Ea
0395	Guardrail, Reconst, Type T	8070109	100.000	Ft
0400	Guardrail, Reconst, Type TD	8070110	2,370.000	Ft
0405	Guardrail Anch, Bridge, Det M1	8070130	45.000	Ea
0410	Guardrail Anch, Bridge, Det M2	8070131	2.000	Ea
0415	Guardrail Anch, Bridge, Det M3	8070132	1.000	Ea
0420	Guardrail Anch, Bridge, Det M4	8070133	8.000	Ea
0425	Cable Barrier, High Tension, Salv	8070201	1,688.000	Ft
0430	Cable Barrier, High Tension, Reconst	8070202	1,688.000	Ft
0435	Cable Barrier, High Tension, Line Post Fdn, Rem	8070220	60.000	Ea
0440	Cable Barrier, High Tension, Line Post Fdn	8070221	60.000	Ea
0445	Guardrail, Temp, Type MGS-8, 72 inch Post	8072004	1,948.000	Ft
0450	Guardrail, Temp, Type MGS-8D, 72 inch Post	8072006	87.000	Ft
0455	Guardrail Anch, Bridge, Det M2, Curved	8072037	1.000	Ea
0460	Guardrail, Curved, Type T, 84 inch Post	8072143	72.000	Ft
0465	Guardrail, Curved, Type B-CRT	8072154	50.000	Ft
0470	Guardrail, Type B, 72 inch Post	8072171	13.000	Ft
0475	Guardrail, Type T, 84 inch Post	8072175	116.000	Ft
0480	Guardrail, Type TD, 84 inch Post	8072177	75.000	Ft
0485	Guardrail, Type MGS-8, 72 inch Post	8072179	2,192.000	Ft
0490	Guardrail, Type MGS-8, 108 inch Post	8072180	2,073.000	Ft
0495	_ Impact Attenuator, Salv and Reinstall	8077050	1.000	Ea
0500	Bridge Sign Connection, Conc, Type A1	8100031	5.000	Ea
0505	Bridge Sign Connection, Steel, Type E	8100064	2.000	Ea
0510	Bridge Sign Connection, Steel, Type F	8100065	2.000	Ea
0515	Bridge Sign Connection, Type A, Rem	8100080	5.000	Ea
0520	Bridge Sign Connection, Type E, Rem	8100084	2.000	Ea
0525	Bridge Sign Connection, Type F, Rem	8100085	2.000	Ea
0530	Column, Breakaway, W8 x 13	8100120	4.000	Ea
0535	Delineator Reflector, Red	8100131	26.000	Ea
0540	Delineator Reflector, Yellow	8100132	20.000	Ea
0545	Delineator Reflector, Green	8100133	17.000	Ea
0550	Delineator Reflector, White	8100134	6.000	Ea
0555	Delineator, Reflective Sheeting, 3 inch by 12 inch, Red	8100139	2.000	Ea

0560	Delineator, Reflective Sheeting, 3 inch by 12 inch, White	8100145	2.000	Ea
0565	Delineator, Reflective Sheeting, 3 inch by 12 inch, Yellow	8100146	4.000	Ea
0570	Fdn, Breakaway, W8 x 13	8100160	4.000	Ea
0575	Fdn, Column Breakaway, Rem	8100220	4.000	Ea
0580	Fdn, Wood Support, Rem	8100280	6.000	Ea
0585	Installing MDOT Supplied Sign, Type III	8100302	4.000	Ea
0590	Delineator, Rem	8100349	32.000	Ea
0595	Post, Rigid, Delineator	8100361	43.000	Ea
0600	Post, Steel, 3 pound	8100371	353.000	Ft
0605	Post, Wood, 4 inch by 6 inch	8100380	32.000	Ft
0610	Post, Wood, 6 inch by 8 inch	8100382	36.000	Ft
0615	Sign, Type I, Rem	8100391	8.000	Ea
0620	Sign, Type IA	8100392	453.000	Sft
0625	Sign, Type IB	8100393	38.000	Sft
0630	Sign, Type II, Rem	8100397	28.000	Ea
0635	Sign, Type IIA	8100398	28.000	Sft
0640	Sign, Type IIB	8100399	244.000	Sft
0645	Sign, Type III, Rem	8100403	4.000	Ea
0650	Sign, Type IIIA	8100404	6.000	Sft
0655	Sign, Type IIIB	8100405	5.000	Sft
0660	Transporting Salv MDOT Materials	8100420	1.000	LSUM
0665	Sign, Type VB	8100425	12.000	Sft
0670	Post, Flexible, Delineator, Ground Mtd	8100555	6.000	Ea
0675	Reflective Panel for Permanent Sign Support, 3 foot	8100613	2.000	Ea
0680	Ground Mtd Sign Support, Rem	8102010	34.000	Ea
0685	_ Hand Digging Sign Post	8107050	15.000	Ea
0690	Pavt Mrkg, Waterborne, 4 inch, White	8110231	500.000	Ft
0695	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	2,000.000	Ft
0700	Pavt Mrkg, Waterborne, 6 inch, White	8110233	40,350.000	Ft
0705	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	44,650.000	Ft
0710	Pavt Mrkg, Waterborne, 12 inch, White	8110237	3,525.000	Ft
0715	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	500.000	Ft
0720	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	2,000.000	Ft
0725	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	40,350.000	Ft
0730	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	44,650.000	Ft
0735	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	3,525.000	Ft
0740	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	5,770.000	Ft
0745	Rem Curing Compound, for Longit Mrkg, 12 inch	8110310	100.000	Ft
0750	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0755	Recessing Pavt Mrkg, Longit	8110450	98,000.000	Ft
0760	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, White	8112130	15,250.000	Ft
0765	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 12 inch, White	8112131	90.000	Ft

0770	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	43.000	Ea
0775	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	43.000	Ea
0780	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0785	Conc Barrier Ending, Temp, Det 2, Adj	8120040	6.000	Ea
0790	Conc Barrier Ending, Temp, Det 2, Furn	8120041	8.000	Ea
0795	Conc Barrier Ending, Temp, Det 2, Oper	8120042	8.000	Ea
0800	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	6.000	Ea
0805	Conc Barrier, Temp, Adj	8120080	2,300.000	Ft
0810	Conc Barrier, Temp, Furn	8120081	12,670.000	Ft
0815	Conc Barrier, Temp, Oper	8120082	12,670.000	Ft
0820	Conc Barrier, Temp, Relocated	8120083	26,835.000	Ft
0825	Culv, Temp	8120090	6.000	Ea
0830	Glare Screen, Temp	8120094	10,370.000	Ft
0835	High Intensity Light, Type B, Furn	8120110	8.000	Ea
0840	High Intensity Light, Type B, Oper	8120111	8.000	Ea
0845	Connected Arrow Board, Type C, Furn	8120155	7.000	Ea
0850	Connected Arrow Board, Type C, Oper	8120156	7.000	Ea
0855	Minor Traf Devices	8120170	1.000	LSUM
0860	Mobile Attenuator	8120180	2.000	Ea
0865	Pavt Mrkg Cover, Type R, Black	8120200	60,350.000	Ft
0870	Plastic Drum, Fluorescent, Furn	8120252	550.000	Ea
0875	Plastic Drum, Fluorescent, Oper	8120253	550.000	Ea
0880	Sign Cover	8120310	25.000	Ea
0885	Sign Cover, Type I	8120320	7.000	Ea
0890	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	16.000	Ea
0895	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	16.000	Ea
0900	Sign, Type B, Temp, Prismatic, Furn	8120350	5,493.000	Sft
0905	Sign, Type B, Temp, Prismatic, Oper	8120351	5,763.000	Sft
0910	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	1,347.000	Sft
0915	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	1,347.000	Sft
0920	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	90,601.000	Ft
0925	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	86,977.000	Ft
0930	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	6,614.000	Ft
0935	Speed Radar Trailer, Temp	8122028	2.000	Ea
0940	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	1,296.000	Ft
0945	_ Traf Speed Sensor, Portable, Temp	8127050	12.000	Ea
0950	_ Control System, Dynamic Work Zone Traf Monitoring System	8127051	1.000	LSUM
0955	Riprap, Plain	8130010	66.000	Syd
0960	Slope Restoration, Freeway, Type A	8162013	10,630.000	Syd

0965	Slope Restoration, Freeway, Type B	8162014	11,095.000	Syd
0970	Slope Restoration, Freeway, Type C	8162015	5,865.000	Syd
0975	Freeway Shld Corrugations, Milled, Conc	8222000	8,655.000	Ft
0980	Freeway Shld Corrugations, Milled, HMA	8222001	1,440.000	Ft
0985	Contractor Staking	8240001	1.000	LSUM
0990	Staking Plan Errors and Extras, Max \$180/hour	8240002	90.000	Hr

**Section: 2**

0995	_ Railroad Inspection and Flagging, Grand Trunk Western Railroad	1027060	300,000.000	Dir
1000	_ Railroad Inspection and Flagging, Huron & Eastern Railway	1027060	144,000.000	Dir
1005	_ Railroad Protection, Grand Trunk Western Railroad Company	1027060	120,000.000	Dir
1010	_ Railroad Protection, Huron and Eastern Railway	1027060	40,000.000	Dir
1015	Structure Demolition Plan, Complex (R04 of 25042)	2040064	1.000	LSUM
1020	Structure Demolition Plan, Complex (R05 of 25042)	2040064	1.000	LSUM
1025	Structure Demolition Plan, Complex (R06 of 25042)	2040064	1.000	LSUM
1030	Structure Demolition Plan, Complex (R07 of 25042)	2040064	1.000	LSUM
1035	Structure Demolition Plan, Complex (S09-3 of 25042)	2040064	1.000	LSUM
1040	Structure Demolition Plan, Complex (S09-4 of 25042)	2040064	1.000	LSUM
1045	Structure Demolition Plan, Complex (S19-8 of 25042)	2040064	1.000	LSUM
1050	_ Culvert Cleanout, Box	2057021	290.000	Cyd
1055	_ Dredging	2057021	592.000	Cyd
1060	Backfill, Structure, CIP	2060002	472.000	Cyd
1065	Excavation, Fdn	2060010	509.000	Cyd
1070	Underdrain, Fdn, 4 inch	4040031	143.000	Ft
1075	Underdrain Outlet, 4 inch	4040091	100.000	Ft
1080	Underdrain, Outlet Ending, 4 inch	4040111	2.000	Ea
1085	HMA Patch, Rem	5010006	20.000	Syd
1090	Bridge Ltg, Furn and Rem (B02-3 of 25042)	7060001	1.000	LSUM
1095	Bridge Ltg, Furn and Rem (B02-4 of 25042)	7060001	1.000	LSUM
1100	Bridge Ltg, Furn and Rem (R04 of 25042)	7060001	1.000	LSUM
1105	Bridge Ltg, Furn and Rem (R05 of 25042)	7060001	1.000	LSUM
1110	Bridge Ltg, Furn and Rem (R06 of 25042)	7060001	1.000	LSUM
1115	Bridge Ltg, Furn and Rem (R07 of 25042)	7060001	1.000	LSUM
1120	Bridge Ltg, Furn and Rem (S08 of 25042)	7060001	1.000	LSUM
1125	Bridge Ltg, Furn and Rem (S09-3 of 25042)	7060001	1.000	LSUM
1130	Bridge Ltg, Furn and Rem (S09-4 of 25042)	7060001	1.000	LSUM
1135	Bridge Ltg, Furn and Rem (S18 of 25042)	7060001	1.000	LSUM
1140	Bridge Ltg, Furn and Rem (S19-8 of 25042)	7060001	1.000	LSUM
1145	Bridge Ltg, Oper and Maintain	7060002	2,674.000	Cyd
1150	Expansion Joint Device	7060050	2,075.000	Ft
1155	False Decking	7060060	83,008.000	Sft
1160	Reinforcement, Steel, Epoxy Coated	7060092	675,382.000	Lb
1165	Superstructure Conc, Form, Finish, and Cure, Night	7060112	1.000	LSUM

	Casting (B02-3 of 25042)			
1170	Superstructure Conc, Form, Finish, and Cure, Night Casting (B02-4 of 25042)	7060112	1.000	LSUM
1175	Superstructure Conc, Form, Finish, and Cure, Night Casting (R04 of 25042)	7060112	1.000	LSUM
1180	Superstructure Conc, Form, Finish, and Cure, Night Casting (R05 of 25042)	7060112	1.000	LSUM
1185	Superstructure Conc, Form, Finish, and Cure, Night Casting (R06 of 25042)	7060112	1.000	LSUM
1190	Superstructure Conc, Form, Finish, and Cure, Night Casting (R07 of 25042)	7060112	1.000	LSUM
1195	Superstructure Conc, Form, Finish, and Cure, Night Casting (S08 of 25042)	7060112	1.000	LSUM
1200	Superstructure Conc, Form, Finish, and Cure, Night Casting (S09-3 of 25042)	7060112	1.000	LSUM
1205	Superstructure Conc, Form, Finish, and Cure, Night Casting (S09-4 of 25042)	7060112	1.000	LSUM
1210	Superstructure Conc, Form, Finish, and Cure, Night Casting (S18 of 25042)	7060112	1.000	LSUM
1215	Superstructure Conc, Form, Finish, and Cure, Night Casting (S19-8 of 25042)	7060112	1.000	LSUM
1220	Superstructure Conc, Night Casting, High Performance	7060117	1,103.000	Cyd
1225	Sealing Localized Cracks (B02-3 of 25042)	7060220	1.000	LSUM
1230	Sealing Localized Cracks (B02-4 of 25042)	7060220	1.000	LSUM
1235	Sealing Localized Cracks (R04 of 25042)	7060220	1.000	LSUM
1240	Sealing Localized Cracks (R05 of 25042)	7060220	1.000	LSUM
1245	Sealing Localized Cracks (R06 of 25042)	7060220	1.000	LSUM
1250	Sealing Localized Cracks (R07 of 25042)	7060220	1.000	LSUM
1255	Sealing Localized Cracks (S06-3 of 25042)	7060220	1.000	LSUM
1260	Sealing Localized Cracks (S06-4 of 25042)	7060220	1.000	LSUM
1265	Sealing Localized Cracks (S08 of 25042)	7060220	1.000	LSUM
1270	Sealing Localized Cracks (S09-3 of 25042)	7060220	1.000	LSUM
1275	Sealing Localized Cracks (S09-4 of 25042)	7060220	1.000	LSUM
1280	Sealing Localized Cracks (S18 of 25042)	7060220	1.000	LSUM
1285	Sealing Localized Cracks (S19-8 of 25042)	7060220	1.000	LSUM
1290	Conc, Grade 4500HP	7062004	354.000	Cyd
1295	_ Expansive Waterstop	7067001	550.000	Ft
1300	_ Fiber Reinf Polymer System for Prest Conc Beam Repr	7067010	45.000	Sft
1305	Bearing, Elastomeric, 1 inch	7070012	10,256.000	Sin
1310	Bushing	7070030	264.000	Ea
1315	Joint Waterproofing	7100001	2,852.000	Sft
1320	Conc Surface Coating, Warranty (B02-3 of 25042)	7100009	1.000	LSUM
1325	Conc Surface Coating, Warranty (B02-4 of 25042)	7100009	1.000	LSUM
1330	Conc Surface Coating, Warranty (R04 of 25042)	7100009	1.000	LSUM
1335	Conc Surface Coating, Warranty (R05 of 25042)	7100009	1.000	LSUM
1340	Conc Surface Coating, Warranty (R06 of 25042)	7100009	1.000	LSUM
1345	Conc Surface Coating, Warranty (R07 of 25042)	7100009	1.000	LSUM
1350	Conc Surface Coating, Warranty (S06-3 of 25042)	7100009	1.000	LSUM

1355	Conc Surface Coating, Warranty (S06-4 of 25042)	7100009	1.000	LSUM
1360	Conc Surface Coating, Warranty (S08 of 25042)	7100009	1.000	LSUM
1365	Conc Surface Coating, Warranty (S09-3 of 25042)	7100009	1.000	LSUM
1370	Conc Surface Coating, Warranty (S09-4 of 25042)	7100009	1.000	LSUM
1375	Conc Surface Coating, Warranty (S17 of 25042)	7100009	1.000	LSUM
1380	Conc Surface Coating, Warranty (S18 of 25042)	7100009	1.000	LSUM
1385	Conc Surface Coating, Warranty (S19-4 of 25042)	7100009	1.000	LSUM
1390	Conc Surface Coating, Warranty (S19-8 of 25042)	7100009	1.000	LSUM
1395	Substructure Horizontal Surface Sealer (B02-3 of 25042)	7100030	53.000	Syd
1400	Substructure Horizontal Surface Sealer (B02-4 of 25042)	7100030	53.000	Syd
1405	Substructure Horizontal Surface Sealer (R02-3 of 76023)	7100030	40.000	Syd
1410	Substructure Horizontal Surface Sealer (R02-4 of 76023)	7100030	40.000	Syd
1415	Substructure Horizontal Surface Sealer (R04 of 25042)	7100030	17.000	Syd
1420	Substructure Horizontal Surface Sealer (R06 of 25042)	7100030	13.000	Syd
1425	Substructure Horizontal Surface Sealer (S08 of 25042)	7100030	29.000	Syd
1430	Substructure Horizontal Surface Sealer (S09-3 of 25042)	7100030	22.000	Syd
1435	Substructure Horizontal Surface Sealer (S09-4 of 25042)	7100030	22.000	Syd
1440	Substructure Horizontal Surface Sealer (S17 of 25042)	7100030	24.000	Syd
1445	Substructure Horizontal Surface Sealer (S18 of 25042)	7100030	29.000	Syd
1450	Substructure Horizontal Surface Sealer (S19-4 of 25042)	7100030	20.000	Syd
1455	Substructure Horizontal Surface Sealer (S19-8 of 25042)	7100030	9.000	Syd
1460	_ Silane Treatment	7107010	21,480.000	Sft
1465	Bridge Barrier Railing, Type 6, High Performance	7110017	2,341.000	Ft
1470	Bridge Barrier Railing, Aesthetic, Type 6, Det 2, High Performance	7112062	1,870.000	Ft
1475	Bridge Barrier Railing, Aesthetic, Type 6, Det 2, Replacement, High Performance	7112110	550.000	Ft
1480	Scarifying	7120001	39.000	Syd
1485	Hand Chipping, Shallow	7120003	41.000	Syd
1490	Hand Chipping, Deep	7120004	10.000	Syd
1495	Hand Chipping, Other Than Deck	7120007	690.000	Cft
1500	Patch, Full Depth	7120010	33.000	Cyd
1505	Patch, Forming	7120017	2,482.000	Sft
1510	Epoxy Ovly, Rem	7120021	3,746.000	Syd
1515	Conc, Bridge Deck Ovly	7120023	250.000	Cyd
1520	Bridge Deck Surface Construction	7120025	10,617.000	Syd
1525	Adhesive Anchoring of Vertical Bar, 1/2 inch	7120032	1,568.000	Ea
1530	Adhesive Anchoring of Vertical Bar, 3/4 inch	7120034	272.000	Ea
1535	Structures, Rehabilitation, Rem Portions, Modified (R04 of 25042)	7120060	1.000	LSUM

1540	Structures, Rehabilitation, Rem Portions, Modified (R05 of 25042)	7120060	1.000	LSUM
1545	Structures, Rehabilitation, Rem Portions, Modified (R06 of 25042)	7120060	1.000	LSUM
1550	Structures, Rehabilitation, Rem Portions, Modified (R07 of 25042)	7120060	1.000	LSUM
1555	Structures, Rehabilitation, Rem Portions, Modified (S09-3 of 25042)	7120060	1.000	LSUM
1560	Structures, Rehabilitation, Rem Portions, Modified (S09-4 of 25042)	7120060	1.000	LSUM
1565	Structures, Rehabilitation, Rem Portions, Modified (S19-8 of 25042)	7120060	1.000	LSUM
1570	Shear Developer, Rem	7120061	823.000	Ea
1575	Shear Developer, Spec	7120062	11,998.000	Ea
1580	Structures, Rehabilitation, Rem Portions (B02-3 of 25042)	7120070	1.000	LSUM
1585	Structures, Rehabilitation, Rem Portions (B02-4 of 25042)	7120070	1.000	LSUM
1590	Structures, Rehabilitation, Rem Portions (R02-3 of 76023)	7120070	1.000	LSUM
1595	Structures, Rehabilitation, Rem Portions (S06-3 of 25042)	7120070	1.000	LSUM
1600	Structures, Rehabilitation, Rem Portions (S06-4 of 25042)	7120070	1.000	LSUM
1605	Structures, Rehabilitation, Rem Portions (S08 of 25042)	7120070	1.000	LSUM
1610	Structures, Rehabilitation, Rem Portions (S17 of 25042)	7120070	1.000	LSUM
1615	Structures, Rehabilitation, Rem Portions (S18 of 25042)	7120070	1.000	LSUM
1620	Structures, Rehabilitation, Rem Portions (S19-4 of 25042)	7120070	1.000	LSUM
1625	Deck Joint, Rem	7120071	2,063.000	Ft
1630	Latex Conc Surface, Rem	7120072	4,825.000	Syd
1635	Hydrodemolition, First Pass	7120076	6,907.000	Syd
1640	Hydrodemolition, 2nd Pass	7120077	451.000	Syd
1645	Reinforcement, Mechanical Splice	7120084	80.000	Ea
1650	Flushing Cracks, Water	7120098	64.000	Ft
1655	Structural Crack, Repr	7120099	64.000	Ft
1660	Top Flanges and Beam Ends, Clean and Coat	7120100	403.000	Syd
1665	Patching Conc, C-L	7120112	42.000	Cyd
1670	Embedded Galvanic Anode	7120120	9,168.000	Ea
1675	Hand Chipping, Full Depth	7122000	775.000	Cft
1680	_ Bridge Joints, Clean and Seal	7127001	489.000	Ft
1685	_ Hand Chipping, Spec	7127010	1,892.000	Sft
1690	_ Conc Ovly Surface, Rem	7127011	1,436.000	Syd
1695	_ High Friction Epoxy Ovly, Warranty	7127011	4,166.000	Syd
1700	_ Conc, Deep Bridge Deck Ovly	7127021	1,571.000	Cyd
1705	_ Latex Modified Conc, Spec	7127021	49.000	Cyd
1710	Beam Plate, Seal Perimeter	7130010	12,119.000	Ft
1715	Hanger Assembly, Field Measurement	7130030	66.000	Ea

1720	Hanger Assembly, Rem and Erect	7130031	66.000	Ea
1725	Structural Steel, Furn and Fab, Pin and Hanger	7130070	15,940.000	Lb
1730	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	24,081.000	Lb
1735	Structural Steel, Welded Repr, Furn, Fab, and Erect	7130072	101.000	Lb
1740	Support, Column, Temp	7130080	142.000	Ea
1745	Support, Diaphragm, Temp	7130081	1.000	Ea
1750	Steel Structure, Cleaning, Partial, Type 4 (R02-3 of 76023)	7150047	1.000	LSUM
1755	Steel Structure, Cleaning, Partial, Type 4 (R02-4 of 76023)	7150047	1.000	LSUM
1760	Steel Structure, Cleaning, Partial, Type 4 (R04 of 25042)	7150047	1.000	LSUM
1765	Steel Structure, Cleaning, Partial, Type 4 (R05 of 25042)	7150047	1.000	LSUM
1770	Steel Structure, Cleaning, Partial, Type 4 (R06 of 25042)	7150047	1.000	LSUM
1775	Steel Structure, Cleaning, Partial, Type 4 (R07 of 25042)	7150047	1.000	LSUM
1780	Steel Structure, Cleaning, Partial, Type 4 (S06-3 of 25042)	7150047	1.000	LSUM
1785	Steel Structure, Cleaning, Partial, Type 4 (S06-4 of 25042)	7150047	1.000	LSUM
1790	Steel Structure, Cleaning, Partial, Type 4 (S09-3 of 25042)	7150047	1.000	LSUM
1795	Steel Structure, Cleaning, Partial, Type 4 (S09-4 of 25042)	7150047	1.000	LSUM
1800	Steel Structure, Cleaning, Partial, Type 4 (S17 of 25042)	7150047	1.000	LSUM
1805	Steel Structure, Cleaning, Partial, Type 4 (S19-4 of 25042)	7150047	1.000	LSUM
1810	Steel Structure, Cleaning, Partial, Type 4 (S19-8 of 25042)	7150047	1.000	LSUM
1815	Steel Structure, Coating, Partial, Type 4 (R02-3 of 76023)	7150048	1.000	LSUM
1820	Steel Structure, Coating, Partial, Type 4 (R02-4 of 76023)	7150048	1.000	LSUM
1825	Steel Structure, Coating, Partial, Type 4 (R04 of 25042)	7150048	1.000	LSUM
1830	Steel Structure, Coating, Partial, Type 4 (R05 of 25042)	7150048	1.000	LSUM
1835	Steel Structure, Coating, Partial, Type 4 (R06 of 25042)	7150048	1.000	LSUM
1840	Steel Structure, Coating, Partial, Type 4 (R07 of 25042)	7150048	1.000	LSUM
1845	Steel Structure, Coating, Partial, Type 4 (S06-3 of 25042)	7150048	1.000	LSUM
1850	Steel Structure, Coating, Partial, Type 4 (S06-4 of 25042)	7150048	1.000	LSUM
1855	Steel Structure, Coating, Partial, Type 4 (S09-3 of 25042)	7150048	1.000	LSUM
1860	Steel Structure, Coating, Partial, Type 4 (S09-4 of 25042)	7150048	1.000	LSUM
1865	Steel Structure, Coating, Partial, Type 4 (S17 of 25042)	7150048	1.000	LSUM
1870	Steel Structure, Coating, Partial, Type 4 (S19-4 of 25042)	7150048	1.000	LSUM

	25042)			
1875	Steel Structure, Coating, Partial, Type 4 (S19-8 of 25042)	7150048	1.000	LSUM
1880	_ Bridge Bearing Plate, Clean and Coat	7157050	36.000	Ea
1885	Field Repr of Damaged Coating (R02-3 of 76023)	7160001	1.000	LSUM
1890	Field Repr of Damaged Coating (R02-4 of 76023)	7160001	1.000	LSUM
1895	Field Repr of Damaged Coating (R04 of 25042)	7160001	1.000	LSUM
1900	Field Repr of Damaged Coating (R05 of 25042)	7160001	1.000	LSUM
1905	Field Repr of Damaged Coating (R06 of 25042)	7160001	1.000	LSUM
1910	Field Repr of Damaged Coating (R07 of 25042)	7160001	1.000	LSUM
1915	Field Repr of Damaged Coating (S09-3 of 25042)	7160001	1.000	LSUM
1920	Field Repr of Damaged Coating (S09-4 of 25042)	7160001	1.000	LSUM
1925	Field Repr of Damaged Coating (S17 of 25042)	7160001	1.000	LSUM
1930	Field Repr of Damaged Coating (S19-4 of 25042)	7160001	1.000	LSUM
1935	Field Repr of Damaged Coating (S19-8 of 25042)	7160001	1.000	LSUM
1940	_ Maintainable Drain, Steel, 3 inch	7177050	100.000	Ea
1945	_ Temp Haul Road	8007051	1.000	LSUM
1950	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM
1955	Slope Paving Header	8130015	425.000	Ft
1960	Slope Paving, Conc	8130020	680.000	Syd
1965	_ Riprap, Spec, CI II	8137031	531.000	Ton
1970	_ Riprap, Spec, CI III	8137031	672.000	Ton
1975	_ Riprap, Under Structures, CI II	8137031	572.000	Ton
1980	Structure Survey During Construction (S19-8 of 25042)	8240020	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 004

**Letting Date:** September 5, 2025

**Contract ID:** 45011-220356

**Description:** 103.25 mi of installing non-freeway curve warning signs on M-22, M-37, M-109, M-204, US-31, M-113, M-22 and M-42, Missaukee, Wexford, Grand Traverse, Leelanau, Manistee and Benzie Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220356A	25A0824	N/A	HSIP 45011

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$43,900.00	1100001	1.000	LSUM
0010	Post, Steel, 3 pound	8100371	22,099.000	Ft
0015	Sign, Type III, Rem	8100403	10.000	Ea
0020	Sign, Type IIIB	8100405	7,720.000	Sft
0025	Sign, Type VB	8100425	264.000	Sft
0030	_ Reflective Panel for Permanent Sign Support, 3 Foot, Modified	8107050	604.000	Ea
0035	_ Reflective Panel for Permanent Sign Support, 6 Foot, Modified	8107050	859.000	Ea
0040	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0045	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Sign Cover	8120310	6.000	Ea
0060	Sign, Type B, Temp, Prismatic, Furn	8120350	552.000	Sft
0065	Sign, Type B, Temp, Prismatic, Oper	8120351	552.000	Sft
0070	Contractor Staking	8240001	1.000	LSUM
0075	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 005

**Letting Date:** September 5, 2025

**Contract ID:** 53032-211167

**Description:** 4.28 mi of hot mix asphalt cold milling and resurfacing, chip and fog seal, drainage improvements and pavement markings on US-10/US-31 from Brye Road east to US-31 (East Junction), Mason County. This project includes a 5 year materials and workmanship pavement warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
211167A	25A0840	N/A	NH 53032

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$563,500.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	3.000	Ea
0015	Sewer, Rem, Less than 24 inch	2030015	460.000	Ft
0020	_ Monitoring Well, Adj	2037050	5.000	Ea
0025	Curb and Gutter, Rem	2040020	1,700.000	Ft
0030	Guardrail, Rem	2040035	200.000	Ft
0035	Masonry and Conc Structure, Rem	2040045	10.000	Cyd
0040	Pavt, Rem	2040050	50.000	Syd
0045	Sidewalk, Rem	2040055	25.000	Syd
0050	Exploratory Investigation, Vertical	2040080	90.000	Ft
0055	Excavation, Earth	2050016	71.000	Cyd
0060	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0065	Subgrade Undercutting, Type II	2050041	110.000	Cyd
0070	_ Embankment, CIP, Spec	2057021	84.000	Cyd
0075	Erosion Control, Inlet Protection, Fabric Drop	2080020	200.000	Ea
0080	Erosion Control, Maintenance, Sediment Rem	2080026	4.000	Cyd
0085	Erosion Control, Silt Fence	2080036	350.000	Ft
0090	Project Cleanup	2090001	1.000	LSUM
0095	Subbase, CIP	3010002	130.000	Cyd
0100	Aggregate Base, 6 inch	3020016	942.000	Syd
0105	Driveway Maintenance, Commercial	3062000	1.000	Ea
0110	Sewer, CI A, 12 inch, Tr Det B	4020033	24.000	Ft
0115	_ Slotted Drain, Galv, 12 inch	4027001	560.000	Ft
0120	Dr Structure Cover, Adj, Case 1, Modified	4030004	8.000	Ea
0125	Dr Structure Cover, Type C	4030015	9.000	Ea
0130	Dr Structure Lead, Cleaning, 12 inch	4030112	200.000	Ft
0135	Dr Structure, 48 inch dia	4030210	5.000	Ea

0140	Dr Structure, Cleaning	4030290	10.000	Ea
0145	Dr Structure, Temp Lowering	4030390	8.000	Ea
0150	_ Dr Structure Repr, Add Depth	4037001	3.000	Ft
0155	_ Dr Structure Repr	4037050	33.000	Ea
0160	Pavt, Cleaning	5010001	1.000	LSUM
0165	Cold Milling HMA Surface	5010002	154,800.000	Syd
0170	Bump Grinding	5010004	200.000	Syd
0175	HMA Surface, Rem	5010005	1,005.000	Syd
0180	HMA Quality Initiative	5010007	68,320.000	Dlr
0185	Longit Joint Density Quality Initiative	5010018	180,600.000	Dlr
0190	Hand Patching	5010025	220.000	Ton
0195	HMA Approach	5010061	310.000	Ton
0200	HMA Approach, High Stress	5010520	200.000	Ton
0205	HMA, 4EML	5012025	15,930.000	Ton
0210	HMA, 5EML	5012037	12,980.000	Ton
0215	HMA, 4EML, High Stress	5012073	2,550.000	Ton
0220	HMA, 5EML, High Stress	5012085	1,970.000	Ton
0225	Overband Crack Fill, Lane	5020003	8.290	Lnmi
0230	Seal, Shld Chip	5050010	43,800.000	Syd
0235	Seal, Fog	5050015	43,800.000	Syd
0240	Cement	6030005	5.000	Ton
0245	_ Pavt Sensor, Invasive Condition	8007050	2.000	Ea
0250	_ Pavt Sensor, Invasive Condition, Rem	8007050	2.000	Ea
0255	_ Subsurface Temperature Probe	8007050	1.000	Ea
0260	_ Subsurface Temperature Probe, Rem and Salv	8007050	1.000	Ea
0265	Curb and Gutter, Conc, Det D2	8020031	1,560.000	Ft
0270	Sidewalk, Conc, 6 inch	8030046	1,602.000	Sft
0275	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0280	Guardrail Departing Terminal, Type B	8070050	2.000	Ea
0285	Guardrail Reflector	8070080	8.000	Ea
0290	Post, Mailbox	8070095	10.000	Ea
0295	Guardrail, Type MGS-8, 108 inch Post	8072180	70.000	Ft
0300	Fence, Protective	8080007	100.000	Ft
0305	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	320.000	Ft
0310	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0315	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	9.000	Ea
0320	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	5.000	Ea
0325	Recessing Pavt Mrkg, Longit	8110450	119,000.000	Ft
0330	Recessing Pavt Mrkg, Transv	8110451	640.000	Sft
0335	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	59,500.000	Ft
0340	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	59,500.000	Ft
0345	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	30.000	Ea
0350	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	30.000	Ea

0355	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,200.000	Ea
0360	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,200.000	Ea
0365	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0370	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0375	Minor Traf Devices	8120170	1.000	LSUM
0380	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	59,200.000	Ft
0385	Sign Cover	8120310	10.000	Ea
0390	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0395	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0400	Sign, Type B, Temp, Prismatic, Furn	8120350	746.000	Sft
0405	Sign, Type B, Temp, Prismatic, Oper	8120351	746.000	Sft
0410	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	50.000	Sft
0415	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	50.000	Sft
0420	Traf Regulator Control	8120370	1.000	LSUM
0425	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	5,640.000	Ft
0430	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	7,520.000	Ft
0435	Speed Radar Trailer, Temp	8122028	2.000	Ea
0440	Slope Restoration, Non-Freeway, Type F	8162006	1,120.000	Syd
0445	Traf Loop	8200170	8.000	Ea
0450	TS Face, Bag	8200458	2.000	Ea
0455	TS Face, Bag, Rem	8200459	2.000	Ea
0460	Monument Box	8210001	5.000	Ea
0465	Monument Preservation	8210010	5.000	Ea
0470	Contractor Staking	8240001	1.000	LSUM
0475	Staking Plan Errors and Extras, Max \$180/hour	8240002	59.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 006

**Letting Date:** September 5, 2025

**Contract ID:** 50031-220278

**Description:** Pedestrian crossing upgrades including signal work, concrete sidewalk, ramps and pavement markings on M-59 at crossover at Heydenreich Road, M-59 at crossover at Chateau Thierry, M-97 at Metro Parkway and M-1 at Long Lake Road in the city of Bloomfield Hills, Macomb and Oakland Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220278A	25A0857	N/A	VRU 50031

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$36,400.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	165.000	Ft
0015	Pavt, Rem	2040050	19.000	Syd
0020	Sidewalk, Rem	2040055	50.000	Syd
0025	Exploratory Investigation, Vertical	2040080	30.000	Ft
0030	Embankment, CIP	2050010	21.000	Cyd
0035	Excavation, Earth	2050016	161.000	Cyd
0040	Non Haz Contaminated Material Handling and Disposal, LM	2050031	5.000	Cyd
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0050	Erosion Control, Silt Fence	2080036	200.000	Ft
0055	Project Cleanup	2090001	1.000	LSUM
0060	Subbase, CIP	3010002	44.000	Cyd
0065	Aggregate Base, 4 inch	3020010	56.000	Syd
0070	HMA Surface, Rem	5010005	2.000	Syd
0075	Hand Patching	5010025	4.000	Ton
0080	Lane Tie, Epoxy Anchored	6030030	17.000	Ea
0085	_ Curb and Gutter, Conc, Det B2, Modified	8027001	38.000	Ft
0090	_ Curb and Gutter, Conc, Det F4, Modified	8027001	17.000	Ft
0095	_ Curb and Gutter, Conc, Det F6, Modified	8027001	54.000	Ft
0100	Detectable Warning Surface	8030010	88.000	Ft
0105	Curb Ramp Opening, Conc	8030030	92.000	Ft
0110	Sidewalk, Conc, 4 inch	8030044	2,091.000	Sft
0115	Sidewalk, Conc, 6 inch	8030046	133.000	Sft
0120	Curb Ramp, Conc, 6 inch	8032002	1,355.000	Sft
0125	Post, Steel, 3 pound	8100371	345.000	Ft
0130	Sign, Type III, Erect, Salv	8100402	2.000	Ea
0135	Sign, Type III, Rem	8100403	17.000	Ea

0140	Sign, Type IIIA	8100404	30.000	Sft
0145	Sign, Type IIIB	8100405	109.000	Sft
0150	Sign, Type III, Rem, Salv	8102003	2.000	Ea
0155	Ground Mtd Sign Support, Rem	8102010	14.000	Ea
0160	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0165	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,025.000	Ft
0170	Pavt Mrkg, Polyurea, 6 inch, White	8110094	5.000	Ft
0175	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	223.000	Ft
0180	Rem Spec Mrkg	8110343	522.000	Sft
0185	Recessing Pavt Mrkg, Transv	8110451	235.000	Sft
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0200	Pedestrian Type II Barricade, Temp	8120026	15.000	Ea
0205	Pedestrian Type II Channelizer, Temp	8120027	50.000	Ft
0210	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0215	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0220	Minor Traf Devices	8120170	1.000	LSUM
0225	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	116.000	Ft
0230	Plastic Drum, Fluorescent, Furn	8120252	132.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	132.000	Ea
0240	Sign Cover	8120310	12.000	Ea
0245	Sign, Type A, Temp, Prismatic, Furn	8120340	120.000	Sft
0250	Sign, Type A, Temp, Prismatic, Oper	8120341	120.000	Sft
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	480.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	480.000	Sft
0265	Pedestrian Path, Temp	8122250	50.000	Ft
0270	_ Turf Establishment, Performance	8167011	780.000	Syd
0275	Conduit, Rem	8182000	50.000	Ft
0280	Conduit, Directional Bore, 1, 1 1/2 inch	8182034	245.000	Ft
0285	Conduit, DB, 1, 1 1/2 inch	8182048	640.000	Ft
0290	Conduit, DB, 3, 3 inch	8182056	40.000	Ft
0295	Hh, Round	8182310	10.000	Ea
0300	Wood Pole, Fit Up, TS Cable Pole	8182387	3.000	Ea
0305	Pedestal, Alum	8200100	23.000	Ea
0310	Pedestal, Fdn	8200105	23.000	Ea
0315	Pedestal Fdn, Rem	8200106	2.000	Ea
0320	Pedestal, Rem	8200110	2.000	Ea
0325	Push Button Station and Sign	8200128	24.000	Ea
0330	TS, Pedestal Mtd, Rem	8200179	2.000	Ea
0335	Pedestrian Signal System, Accessible	8200240	4.000	Ea
0340	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0345	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	23.000	Ea

0350	TS Head, Adj	8200452	1.000	Ea
0355	TS, One Way Pedestal Mtd (LED), Long Life	8202251	2.000	Ea
0360	Contractor Staking	8240001	1.000	LSUM
0365	Staking Plan Errors and Extras, Max \$180/hour	8240002	4.000	Hr
0370	Sanitary Structure Cover, Adj, Case 2	8252146	1.000	Ea
0375	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 007

**Letting Date:** September 5, 2025

**Contract ID:** 33034-211985

**Description:** Traffic signal modernization at five locations on Old US-27 and I-96BL in the city of Lansing, Ingham and Clinton Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
211985A	25A0850	N/A	STG 33034

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$179,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	606.000	Ft
0015	Masonry and Conc Structure, Rem	2040045	5.000	Cyd
0020	Pavt, Rem	2040050	138.000	Syd
0025	Sidewalk, Rem	2040055	532.000	Syd
0030	Exploratory Investigation, Vertical	2040080	50.000	Ft
0035	Embankment, CIP	2050010	10.000	Cyd
0040	Excavation, Earth	2050016	28.000	Cyd
0045	Non Haz Contaminated Material Handling and Disposal, LM	2050031	12.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0055	Erosion Control, Maintenance, Sediment Rem	2080026	8.000	Cyd
0060	Erosion Control, Silt Fence	2080036	500.000	Ft
0065	Aggregate Base, 6 inch	3020016	885.000	Syd
0070	Maintenance Gravel	3060020	30.000	Ton
0075	Dr Structure Cover, Adj, Case 1	4030005	10.000	Ea
0080	Dr Structure, Adj, Add Depth	4030280	20.000	Ft
0085	HMA Surface, Rem	5010005	32.000	Syd
0090	Hand Patching	5010025	42.000	Ton
0095	Conc Base Cse, Nonreinf, 7 inch	6020017	148.000	Syd
0100	Lane Tie, Epoxy Anchored	6030030	262.000	Ea
0105	_ Restricted Excavation Marker, Relocate	8007050	1.000	Ea
0110	Curb and Gutter, Conc, Det F3	8020037	224.000	Ft
0115	Detectable Warning Surface	8030010	288.000	Ft
0120	Curb Ramp Opening, Conc	8030030	365.000	Ft
0125	Sidewalk, Conc, 6 inch	8030046	1,465.000	Sft
0130	Curb Ramp, Conc, 6 inch	8032002	4,115.000	Sft
0135	Band, Sign	8100010	32.000	Ea

0140	Post, Steel, 3 pound	8100371	102.000	Ft
0145	Sign, Type III, Erect, Salv	8100402	34.000	Ea
0150	Sign, Type III, Rem, Salv	8102003	32.000	Ea
0155	Ground Mtd Sign Support, Rem	8102010	5.000	Ea
0160	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,347.000	Ft
0165	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	1,248.000	Ft
0170	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	552.000	Ft
0175	Rem Spec Mrkg	8110343	2,624.000	Sft
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	30.000	Ea
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	30.000	Ea
0190	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0195	Pedestrian Type II Channelizer, Temp	8120027	100.000	Ft
0200	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0205	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0210	Minor Traf Devices	8120170	1.000	LSUM
0215	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0220	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0225	Sign Cover	8120310	10.000	Ea
0230	Sign, Type A, Temp, Prismatic, Furn	8120340	80.000	Sft
0235	Sign, Type A, Temp, Prismatic, Oper	8120341	80.000	Sft
0240	Sign, Type B, Temp, Prismatic, Furn	8120350	800.000	Sft
0245	Sign, Type B, Temp, Prismatic, Oper	8120351	800.000	Sft
0250	Traf Regulator Control	8120370	1.000	LSUM
0255	Pedestrian Path, Temp	8122250	100.000	Ft
0260	Pedestrian Ramp, Temp	8122251	10.000	Ea
0265	Slope Restoration, Non-Freeway, Type B	8162002	536.000	Syd
0270	Power Company (Estimated Cost to Contractor)	8180001	8,000.000	Dlr
0275	Conduit, Rem	8182000	130.000	Ft
0280	Conduit, Directional Bore, 2, 3 inch	8182037	470.000	Ft
0285	Conduit, DB, 1, 1 1/2 inch	8182048	700.000	Ft
0290	Conduit, DB, 3, 3 inch	8182056	220.000	Ft
0295	Conduit, DB, 4, 3 inch	8182059	55.000	Ft
0300	Conduit, DB, 1, 1 inch	8182060	110.000	Ft
0305	Cable Pole, TS, Disman	8182210	7.000	Ea
0310	Cable, Sec, 600V, 1, 3/C#6	8182238	360.000	Ft
0315	Hh, Round	8182310	15.000	Ea
0320	Hh, Round, 3 foot dia	8182319	5.000	Ea
0325	Hh, Adj	8182328	9.000	Ea
0330	Serv Disconnect	8182366	5.000	Ea
0335	Case Sign (LED), Changeable Message, One Way, 24 inch by 30 inch	8200017	1.000	Ea
0340	Case Sign, Rem	8200020	5.000	Ea
0345	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	11.000	Ea
0350	Controller and Cabinet, Rem	8200030	5.000	Ea

0355	Controller Fdn, Base Mtd	8200045	5.000	Ea
0360	Fdn, Rem	8200065	8.000	Ea
0365	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	5.000	Ea
0370	Pedestal, Alum	8200100	17.000	Ea
0375	Pedestal, Fdn	8200105	34.000	Ea
0380	Pedestal Fdn, Rem	8200106	7.000	Ea
0385	Pedestal, Rem	8200110	7.000	Ea
0390	Pedestal, Pushbutton, Alum	8200118	17.000	Ea
0395	Pushbutton, Rem	8200122	12.000	Ea
0400	Push Button Station and Sign	8200128	40.000	Ea
0405	Span Wire	8200140	12.000	Ea
0410	Span Wire, Rem	8200141	5.000	Ea
0415	Span Wire Tether	8200142	12.000	Ea
0420	Steel Pole, Rem	8200145	8.000	Ea
0425	Steel Pole, Rem (Embedded)	8200146	3.000	Ea
0430	TS, Bracket Arm Mtd, Rem	8200175	3.000	Ea
0435	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	13.000	Ea
0440	TS, Pedestrian, Pedestal Mtd, Rem	8200181	7.000	Ea
0445	TS, Span Wire Mtd, Rem	8200182	10.000	Ea
0450	Cabinet, NEMA Type	8200186	5.000	Ea
0455	Pedestrian Signal System, Accessible	8200240	5.000	Ea
0460	TS, Wireless Link, Rem	8200280	1.000	Ea
0465	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0470	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	7.000	Ea
0475	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	9.000	Ea
0480	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	8.000	Ea
0485	Bracket, Truss, with 18 foot Arm	8200378	5.000	Ea
0490	Emergency Pre-emption, Rem	8200415	5.000	Ea
0495	Emergency Pre-emption, Salv	8200416	5.000	Ea
0500	Hemispherical Video Detection Camera	8200444	5.000	Ea
0505	Hemispherical Video Detection System	8200445	5.000	Ea
0510	Junction Box, Rem	8200457	4.000	Ea
0515	Strain Pole, Steel, 6 bolt, Size 1A	8200463	7.000	Ea
0520	Strain Pole, Steel, 6 bolt, Size 2	8200466	5.000	Ea
0525	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	132.000	Ft
0530	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	100.000	Ft
0535	Casing, 42 inch	8200485	146.000	Ft
0540	Casing, 48 inch	8200486	82.000	Ft
0545	Cellular Modem, TS, 4th G	8200498	5.000	Ea
0550	Hh, Lightning Protection	8200540	10.000	Ea
0555	Mast Arm Pole, Cat I	8202010	4.000	Ea
0560	Mast Arm, 40 foot, Cat I	8202017	2.000	Ea

0565	Mast Arm, 45 foot, Cat I	8202018	4.000	Ea
0570	Mast Arm Pole Fdn, 6 Bolt	8202034	52.000	Ft
0575	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	14.000	Ea
0580	TS, One Way Mast Arm Mtd, FYA (LED), Long Life	8202239	1.000	Ea
0585	TS, One Way Span Wire Mtd (LED), Long Life	8202287	24.000	Ea
0590	TS, One Way Span Wire Mtd, Five Sect (LED), Long Life	8202308	1.000	Ea
0595	TS, One Way Span Wire Mtd, LTGA (LED), Long Life	8202314	2.000	Ea
0600	_ Backplate, TS, Flexible	8207050	39.000	Ea
0605	_ Controller, NEMA, ATC Type	8207050	5.000	Ea
0610	Water Shutoff, Adj, Case 1	8230421	1.000	Ea
0615	Gate Box, Adj, Case 1	8230431	1.000	Ea
0620	Contractor Staking	8240001	1.000	LSUM
0625	Staking Plan Errors and Extras, Max \$180/hour	8240002	20.000	Hr
0630	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0635	Lightning Protection, Pole	8260021	5.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 008

**Letting Date:** September 5, 2025

**Contract ID:** 10032-204053

**Description:** 7.80 mi of removal of existing composite pavement full-depth and replace with hot mix asphalt widening for center left turn lane and eight-foot shoulders, concrete curb and gutter, signing and pavement markings on US-31 from Reynolds Road easterly to Sullivan Road, Benzie and Grand Traverse Counties. This project includes a 5 year materials and workmanship pavement warranty and a 5 year epoxy performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
204053A	25A0846	N/A	NH 10032
209359A	25A0847	N/A	HSIP 28011

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Great Lakes Central Railroad	1027060	2,500.000	Dir
0010	Mobilization, Max \$2,361,500.00	1100001	1.000	LSUM
0015	Clearing	2010001	1.900	Acre
0020	_ Clearing, Spec	2017012	0.100	Acre
0025	Tree, Rem, 19 inch to 36 inch	2020002	38.000	Ea
0030	Tree, Rem, 37 inch or Larger	2020003	2.000	Ea
0035	Tree, Rem, 6 inch to 18 inch	2020004	110.000	Ea
0040	Stump, Rem, 19 inch to 36 inch	2020006	1.000	Ea
0045	Culv, Rem, Less than 24 inch	2030001	36.000	Ea
0050	Dr Structure, Rem	2030011	3.000	Ea
0055	Sewer, Rem, Less than 24 inch	2030015	85.000	Ft
0060	Curb and Gutter, Rem	2040020	8,654.000	Ft
0065	Fence, Rem	2040025	1,677.000	Ft
0070	Guardrail, Rem	2040035	1,793.000	Ft
0075	Masonry and Conc Structure, Rem	2040045	20.000	Cyd
0080	Pavt, Rem	2040050	104,192.000	Syd
0085	Exploratory Investigation, Vertical	2040080	100.000	Ft
0090	_ Salv and Rem Misc Appurtenances	2047051	1.000	LSUM
0095	Embankment, CIP	2050010	10,366.000	Cyd
0100	Excavation, Earth	2050016	93,260.000	Cyd
0105	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0110	Subgrade Undercutting, Type II	2050041	500.000	Cyd
0115	Erosion Control, Check Dam, Stone	2080012	680.000	Ft
0120	Erosion Control, Gravel Access Approach	2080016	5.000	Ea

0125	Erosion Control, Inlet Protection, Fabric Drop	2080020	35.000	Ea
0130	Erosion Control, Inlet Protection, Sediment Trap	2080024	8.000	Ea
0135	Erosion Control, Maintenance, Sediment Rem	2080026	112.000	Cyd
0140	Erosion Control, Sediment Trap	2080034	69.000	Ea
0145	Erosion Control, Silt Fence	2080036	59,474.000	Ft
0150	_ Erosion Control, Check Dam, Stone, Spec	2087001	246.000	Ft
0155	_ Straw Wattle	2087001	713.000	Ft
0160	Subbase, CIP	3010002	68,967.000	Cyd
0165	Aggregate Base	3020001	490.000	Ton
0170	Aggregate Base, 6 inch	3020016	254,795.000	Syd
0175	_ Aggregate Base, 13 inch	3027011	622.000	Syd
0180	Driveway Maintenance, Commercial	3062000	34.000	Ea
0185	Driveway Maintenance, Residential	3062001	98.000	Ea
0190	Intersection Maintenance	3062002	12.000	Ea
0195	Approach, CI I	3070001	13,129.000	Ton
0200	Approach, CI II	3070021	1,240.000	Ton
0205	Shld, CI II	3070121	194.000	Ton
0210	Shld, CI II, 3 inch	3070125	524.000	Syd
0215	Shld, CI II, 5 inch	3070127	15,110.000	Syd
0220	Road Grade Biaxial Geogrid	3082002	16,613.000	Syd
0225	Culv End Sect, 12 inch	4010012	3.000	Ea
0230	Culv End Sect, 15 inch	4010015	38.000	Ea
0235	Culv End Sect, 18 inch	4010018	6.000	Ea
0240	Culv End Sect, 24 inch	4010024	1.000	Ea
0245	Culv End Sect, Conc, 30 inch	4010052	3.000	Ea
0250	Culv End Sect, Footing	4010072	72.000	Ea
0255	Culv, CI A, Conc, 30 inch	4010169	67.000	Ft
0260	Culv, CI E, 18 inch	4010541	145.000	Ft
0265	Culv, CI F, 15 inch	4010608	1,090.000	Ft
0270	Culv, CI F, 18 inch	4010609	455.000	Ft
0275	Culv, CI F, 30 inch	4010611	25.000	Ft
0280	Culv, Reinf Conc Ellip, HE CI II, 19 inch by 30 inch	4010856	22.000	Ft
0285	Culv, Reinf Conc Ellip, HE CI IV, 19 inch by 30 inch	4010902	47.000	Ft
0290	Culv, Slp End Sect, 1 on 4, 15 inch, Longit	4010917	2.000	Ea
0295	Culv, Slp End Sect, 1 on 4, 18 inch, Transv	4010920	4.000	Ea
0300	Culv, Slp End Sect, 1 on 4, 24 inch, Longit	4010923	1.000	Ea
0305	Culv, Slp End Sect, 1 on 4, 24 inch, Transv	4010924	3.000	Ea
0310	Culv, Slp End Sect, 1 on 4, 30 inch, Transv	4010928	3.000	Ea
0315	Culv, Slp End Sect, 1 on 6, 15 inch, Longit	4010949	2.000	Ea
0320	Culv, Slp End Sect, 1 on 6, 18 inch, Longit	4010951	4.000	Ea
0325	Culv, Slp End Sect, 1 on 6, 30 inch, Longit	4010959	2.000	Ea
0330	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 19 inch by 30 inch, Longit	4011051	2.000	Ea
0335	Culv, Slp End Sect, Ellip Pipe, 1 on 6, 19 inch by 30 inch, Longit	4011081	2.000	Ea

0340	Dr Marker Post	4011109	71.000	Ea
0345	_ Culv End Sect 30 inch, Grate	4017050	2.000	Ea
0350	Sewer, CI A, 15 inch, Tr Det A	4020005	102.000	Ft
0355	Sewer, CI A, 24 inch, Tr Det A	4020007	124.000	Ft
0360	Sewer, CI A, 12 inch, Tr Det B	4020033	544.000	Ft
0365	Sewer, CI A, 15 inch, Tr Det B	4020034	190.000	Ft
0370	Sewer, CI A, 18 inch, Tr Det B	4020035	199.000	Ft
0375	Sewer, CI A, 24 inch, Tr Det B	4020036	299.000	Ft
0380	Sewer, CI A, 30 inch, Tr Det B	4020037	58.000	Ft
0385	Sewer, CI E, 12 inch, Tr Det B	4020600	803.000	Ft
0390	Sewer, CI E, 15 inch, Tr Det B	4020601	462.000	Ft
0395	Sewer, CI E, 18 inch, Tr Det B	4020602	170.000	Ft
0400	Sewer, CI E, 24 inch, Tr Det B	4020603	59.000	Ft
0405	Sewer, CI E, 30 inch, Tr Det B	4020604	88.000	Ft
0410	Video Taping Sewer and Culv Pipe	4021275	2,026.000	Ft
0415	Dr Structure Cover, Adj, Case 1	4030005	7.000	Ea
0420	Dr Structure Cover, Type B	4030010	9.000	Ea
0425	Dr Structure Cover, Type D	4030025	1.000	Ea
0430	Dr Structure Cover, Type G	4030040	1.000	Ea
0435	Dr Structure Cover, Type J	4030045	29.000	Ea
0440	Dr Structure Cover, Type R	4030070	5.000	Ea
0445	Dr Structure, 24 inch dia	4030200	7.000	Ea
0450	Dr Structure, 48 inch dia	4030210	31.000	Ea
0455	Dr Structure, 60 inch dia	4030220	4.000	Ea
0460	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	4.000	Ft
0465	Dr Structure, Add Depth of 60 inch dia, 8 foot to 15 foot	4030260	1.000	Ft
0470	Underdrain, Subgrade, 6 inch	4040073	600.000	Ft
0475	Underdrain Outlet, 6 inch	4040093	100.000	Ft
0480	Underdrain, Outlet Ending, 6 inch	4040113	3.000	Ea
0485	Video Inspection of Underdrain	4040200	600.000	Ft
0490	HMA Surface, Rem	5010005	208,794.000	Syd
0495	HMA Quality Initiative	5010007	148,764.000	Dlr
0500	Longit Joint Density Quality Initiative	5010018	244,221.000	Dlr
0505	Hand Patching	5010025	190.000	Ton
0510	HMA Approach	5010061	9,239.000	Ton
0515	HMA, 3EML	5012013	38,409.000	Ton
0520	HMA, 4EML	5012025	24,370.000	Ton
0525	HMA, 4EML, High Stress	5012073	1,242.000	Ton
0530	HMA, 5EML, High Stress	5012085	932.000	Ton
0535	HMA, Temp Pavt (3EML)	5012101	627.000	Ton
0540	_ Ride Incentive	5017060	75,000.000	Dlr
0545	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	48.000	Syd
0550	_ Conc Pavt, Decorative, Nonreinf, 12 inch	6027011	494.000	Syd

0555	_ Conc Pavt, Decorative, Nonreinf, 6 inch	6027011	622.000	Syd
0560	_ Pavt Sensor, Non-Invasive Condition	8007050	1.000	Ea
0565	Driveway, Nonreinf Conc, 6 inch	8010005	16.000	Syd
0570	Curb, Conc, Det E1	8020001	270.000	Ft
0575	Curb, Conc, Det E2	8020002	163.000	Ft
0580	Curb and Gutter, Conc, Det B2	8020016	11,707.000	Ft
0585	Curb and Gutter, Conc, Det D2	8020031	30.000	Ft
0590	Curb and Gutter, Conc, Det F4	8020038	301.000	Ft
0595	Driveway Opening, Conc, Det M	8020050	1,886.000	Ft
0600	Shld Gutter, Conc, Det 1	8020055	4.000	Ea
0605	Shld Gutter, Conc, Det 2	8020056	9.000	Ea
0610	Shld Gutter, Conc, Det 3	8020057	3.000	Ea
0615	Spillway, Conc	8020075	99.000	Ft
0620	Curb and Gutter, Bridge Approach, Det 1A	8022013	182.000	Ft
0625	_ Curb and Gutter, Conc, Det B2, Modified	8027001	2,557.000	Ft
0630	Detectable Warning Surface	8030010	135.000	Ft
0635	Curb Ramp Opening, Conc	8030030	249.000	Ft
0640	Sidewalk, Conc, 4 inch	8030044	17,808.000	Sft
0645	Curb Ramp, Conc, 6 inch	8032002	3,371.000	Sft
0650	_ Sidewalk, Conc, 5 inch	8037010	808.000	Sft
0655	Curb Slp, HMA	8050010	7,298.000	Ft
0660	Guardrail Anch, Bridge, Det T1	8070022	8.000	Ea
0665	Guardrail Approach Terminal, Type 2M	8070044	10.000	Ea
0670	Post, Mailbox	8070095	94.000	Ea
0675	Guardrail, Type MGS-8, 72 inch Post	8072179	1,192.000	Ft
0680	Fence, Chain Link, 72 inch	8080013	181.000	Ft
0685	_ Wood Fence	8087001	744.000	Ft
0690	Delineator Reflector, Yellow	8100132	40.000	Ea
0695	Delineator Reflector, Green	8100133	66.000	Ea
0700	Delineator Reflector, White	8100134	810.000	Ea
0705	Fdn, Wood Support, Rem	8100280	61.000	Ea
0710	Installing MDOT Supplied Sign, Type III	8100302	10.000	Ea
0715	Perforated Steel Square Tube Breakaway System	8100330	28.000	Ea
0720	Post Hole Through Conc for Steel Post	8100340	28.000	Ea
0725	Delineator, Rem	8100349	443.000	Ea
0730	Post, Rigid, Delineator	8100361	511.000	Ea
0735	Post, Steel, 3 pound	8100371	5,311.000	Ft
0740	Post, Wood, 4 inch by 6 inch	8100380	566.000	Ft
0745	Post, Wood, 6 inch by 8 inch	8100382	228.000	Ft
0750	Sign, Type II, Rem	8100397	53.000	Ea
0755	Sign, Type IIA	8100398	538.000	Sft
0760	Sign, Type IIB	8100399	64.000	Sft
0765	Sign, Type III, Erect, Salv	8100402	76.000	Ea
0770	Sign, Type III, Rem	8100403	191.000	Ea
0775	Sign, Type IIIA	8100404	448.000	Sft

0780	Sign, Type IIIB	8100405	1,023.000	Sft
0785	Sign, Type VB	8100425	58.000	Sft
0790	Reflective Panel for Permanent Sign Support, 6 foot	8100616	8.000	Ea
0795	Sign, Type III, Rem, Salv	8102003	62.000	Ea
0800	Ground Mtd Sign Support, Rem	8102010	345.000	Ea
0805	_ Enhanced Delineation, Bidirectional, Guardrail, Post Mtd	8107001	1,351.000	Ft
0810	_ Reflective Panel for Permanent Sign Support, 6 foot, Modified	8107050	104.000	Ea
0815	Pavt Mrkg, Ovly Cold Plastic, Yield	8110048	6.000	Ea
0820	Pavt Mrkg, Ovly Cold Plastic, Merge Arrow Sym	8110050	2.000	Ea
0825	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	4.000	Ea
0830	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	2.000	Ea
0835	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym	8110078	2.000	Ea
0840	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Roundabout Arrow Sym	8110086	2.000	Ea
0845	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, White	8110108	1,000.000	Ft
0850	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	850.000	Ft
0855	Pavt Mrkg, Polyurea, 18 inch, Stop Bar	8110113	233.000	Ft
0860	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	8,524.000	Ft
0865	Pavt Mrkg, Waterborne, 6 inch, White	8110233	92,207.000	Ft
0870	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	101,375.000	Ft
0875	Pavt Mrkg, Waterborne, 12 inch, White	8110237	200.000	Ft
0880	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	1,826.000	Ft
0885	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	87,148.000	Ft
0890	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	101,375.000	Ft
0895	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	200.000	Ft
0900	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Yellow	8110295	700.000	Ft
0905	Rem Spec Mrkg	8110343	1,535.000	Sft
0910	Recessing Pavt Mrkg, Longit	8110450	195,112.000	Ft
0915	Recessing Pavt Mrkg, Transv	8110451	1,380.000	Sft
0920	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	95.000	Ea
0925	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	95.000	Ea
0930	Pedestrian Type II Barricade, Temp	8120026	5.000	Ea
0935	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	121.000	Ea
0940	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	121.000	Ea
0945	Conc Barrier Ending, Temp, Det 2, Furn	8120041	2.000	Ea
0950	Conc Barrier Ending, Temp, Det 2, Oper	8120042	2.000	Ea
0955	Conc Barrier, Temp, Furn	8120081	1,309.000	Ft
0960	Conc Barrier, Temp, Oper	8120082	1,309.000	Ft
0965	High Intensity Light, Type B, Furn	8120110	2.000	Ea
0970	High Intensity Light, Type B, Oper	8120111	2.000	Ea

0975	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0980	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0985	Minor Traf Devices	8120170	1.000	LSUM
0990	Mobile Attenuator	8120180	1.000	Ea
0995	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	49,170.000	Ft
1000	Pavt Mrkg, Type NR, Paint, 24 inch, Stop Bar	8120216	66.000	Ft
1005	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,012.000	Ft
1010	Plastic Drum, Fluorescent, Furn	8120252	650.000	Ea
1015	Plastic Drum, Fluorescent, Oper	8120253	650.000	Ea
1020	Sign Cover	8120310	465.000	Ea
1025	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
1030	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
1035	Sign, Type A, Temp, Prismatic, Furn	8120340	866.000	Sft
1040	Sign, Type A, Temp, Prismatic, Oper	8120341	866.000	Sft
1045	Sign, Type B, Temp, Prismatic, Furn	8120350	5,920.000	Sft
1050	Sign, Type B, Temp, Prismatic, Oper	8120351	5,920.000	Sft
1055	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	270.000	Sft
1060	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	270.000	Sft
1065	Traf Regulator Control	8120370	1.000	LSUM
1070	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	49,830.000	Ft
1075	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	48,411.000	Ft
1080	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	46,453.000	Ft
1085	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	46,640.000	Ft
1090	Temp Rumble Strips (Orange), Stop Condition	8122186	360.000	Ft
1095	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
1100	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
1105	Riprap, Plain	8130010	481.000	Syd
1110	Ditch, Plain Cobble	8140005	26.000	Syd
1115	Paved Ditch, HMA	8140010	333.000	Syd
1120	Site Preparation, Max \$11,050.00	8150001	1.000	LSUM
1125	Watering and Cultivating, First Season, Min \$5,370.00	8150002	1.000	LSUM
1130	Watering and Cultivating, 2nd Season, Min \$6,630.00	8150003	1.000	LSUM
1135	Acer saccharum 'Commemoration', 1 1/2 inch	8150181	12.000	Ea
1140	Juniperus chinensis 'Sea Green', #3 cont.	8151941	155.000	Ea
1145	Picea glauca 'Densata', 5 foot	8152755	34.000	Ea
1150	_ Physocarpus opulifolius Mindia, #5 cont.	8157050	19.000	Ea
1155	_ Picea Abies, 12 foot	8157050	2.000	Ea
1160	Slope Restoration, Non-Freeway, Type E	8162005	52,945.000	Syd
1165	Slope Restoration, Non-Freeway, Type F	8162006	132,615.000	Syd
1170	Slope Restoration, Non-Freeway, Type G	8162007	13,700.000	Syd

1175	_ Bioretention Seeding	8167011	17,000.000	Syd
1180	_ Mulch, Shredded Bark	8167011	980.000	Syd
1185	_ Slope Restoration, Wetland	8167011	1,000.000	Syd
1190	Power Company (Estimated Cost to Contractor)	8180001	3,000.000	Dlr
1195	Conduit, Rem	8182000	280.000	Ft
1200	Conduit, Directional Bore, 1, 3 inch	8182035	55.000	Ft
1205	Conduit, DB, 1, 1 1/2 inch	8182048	35.000	Ft
1210	Conduit, DB, 1, 3 inch	8182050	3,105.000	Ft
1215	Conduit, DB, 3, 3 inch	8182056	200.000	Ft
1220	DB Cable, in Conduit, 600V, 1/C#6	8182187	7,600.000	Ft
1225	Cable, Sec, Rem	8182199	540.000	Ft
1230	Cable Pole, Sec, Dismant	8182206	2.000	Ea
1235	Cable, Sec, 600V, 1, 3/C#6	8182238	310.000	Ft
1240	Cable, Equipment Grounding Wire, 1/C#6	8182291	2,950.000	Ft
1245	Hh, Heavy Duty Cover	8182308	24.000	Ea
1250	Hh, Round	8182310	10.000	Ea
1255	Hh, Rem	8182330	2.000	Ea
1260	Metered Serv	8182338	2.000	Ea
1265	Metered Serv, Rem	8182339	6.000	Ea
1270	Wood Pole, Cl 4, 30 foot	8182349	2.000	Ea
1275	Wood Pole, Cl 4, 40 foot	8182351	3.000	Ea
1280	Wood Pole, Rem	8182363	17.000	Ea
1285	Serv Disconnect	8182366	3.000	Ea
1290	Serv Disconnect, Rem	8182367	7.000	Ea
1295	Wood Pole, Fit Up, TS Cable Pole	8182387	2.000	Ea
1300	Light Std Arm, 8 foot	8190266	2.000	Ea
1305	Light Std Arm, 17 foot	8190270	15.000	Ea
1310	Light Std Fdn	8190279	17.000	Ea
1315	Light Std, Frangible Transformer Base	8190281	17.000	Ea
1320	Light Std Shaft, 31 foot to 40 foot	8190286	17.000	Ea
1325	_ Ltg Control Panel	8197050	1.000	Ea
1330	_ Luminaire, Roadway	8197050	17.000	Ea
1335	Case Sign, Rem	8200020	2.000	Ea
1340	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	1.000	Ea
1345	Controller and Cabinet, Rem	8200030	7.000	Ea
1350	Fdn, Rem	8200065	2.000	Ea
1355	Flsh Beacon, Controller and Cabinet, Solid State	8200070	2.000	Ea
1360	Pedestal, Fdn	8200105	1.000	Ea
1365	Pedestal Fdn, Rem	8200106	2.000	Ea
1370	Pedestal, Rem	8200110	1.000	Ea
1375	Pedestal, Underground Serv, Metered	8200111	1.000	Ea
1380	Pedestal, Underground Serv, Rem	8200113	1.000	Ea
1385	Pushbutton, Rem	8200122	4.000	Ea
1390	Span Wire	8200140	2.000	Ea
1395	Span Wire, Rem	8200141	16.000	Ea

1400	Steel Pole, Rem	8200145	2.000	Ea
1405	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	3.000	Ea
1410	TS, Pedestrian, Pedestal Mtd, Rem	8200181	1.000	Ea
1415	TS, Span Wire Mtd, Rem	8200182	29.000	Ea
1420	Cabinet, NEMA Type	8200186	1.000	Ea
1425	Warning Sign	8200260	2.000	Ea
1430	Warning Sign, Rem	8200261	2.000	Ea
1435	Wireless Vehicle Detection System	8200422	1.000	Ea
1440	Wireless Vehicle Sensor Node	8200425	3.000	Ea
1445	Wireless Vehicle Sensor Node, Rem	8200426	29.000	Ea
1450	TS Face, Bag, Rem	8200459	15.000	Ea
1455	TS, One Way Span Wire Mtd (LED), Long Life	8202287	4.000	Ea
1460	_ Controller, NEMA, ATC Type	8207050	1.000	Ea
1465	Monument Box	8210001	14.000	Ea
1470	Monument Preservation	8210010	27.000	Ea
1475	Protect Corners	8210020	52.000	Ea
1480	Centerline Corrugations, Milled, HMA	8220013	6,848.000	Ft
1485	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	59,268.000	Ft
1490	Fire Hydrant	8230040	3.000	Ea
1495	Gate Valve and Box, 6 inch	8230051	3.000	Ea
1500	Gate Valve and Box, 12 inch	8230054	7.000	Ea
1505	Water Main, DI, 6 inch, Tr Det G	8230151	60.000	Ft
1510	_ Water Main, HDPE, 12 inch, Tr Det G	8237001	1,750.000	Ft
1515	_ Connect to Existing, 12 inch	8237050	1.000	Ea
1520	Contractor Staking	8240001	1.000	LSUM
1525	Staking Plan Errors and Extras, Max \$180/hour	8240002	246.000	Hr

**Section: 2**

1530	_ Silane Treatment	7067010	1,194.000	Sft
1535	Epoxy Ovly, Rem	7120021	384.000	Syd
1540	Epoxy Ovly, Warranty	7120022	384.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 009

**Letting Date:** September 5, 2025

**Contract ID:** 57000-213727

**Description:** 5.80 mi of construction of mountain bike optimized single track trail off of Boon Road north of M-55 and east of US-131, Missaukee and Wexford Counties. A mandatory pre-bid meeting will be held Thursday, August 7, 2025 at 9:00 am at the Carl T. Johnson Hunting and Fishing Visitor Center, 6087 East M-115, Cadillac, Michigan 49601.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
213727A	25A0834	N/A	NRT 57000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$40,700.00	1100001	1.000	LSUM
0010	_ Clearing, Special for Job Number 213727	2017002	306.000	Sta
0015	Tree, Rem, 19 inch to 36 inch	2020002	3.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	15.000	Ea
0025	_ Climbing Turn	2057001	1,400.000	Ft
0030	_ Insloped Berm Turn	2057001	250.000	Ft
0035	_ Trail Grading, Type A	2057002	203.000	Sta
0040	_ Trail Grading, Type B	2057002	9.000	Sta
0045	_ Trail Grading, Type C	2057002	129.000	Sta
0050	_ Obliterate Old Trail	2077002	267.000	Sta
0055	Erosion Control, Silt Fence	2080036	2,000.000	Ft
0060	_ Confidence Marker	8107050	52.000	Ea
0065	_ Intersection Sign	8107050	104.000	Ea
0070	_ Wayfinding Sign	8107050	20.000	Ea
0075	Pedestrian Type II Barricade, Temp	8120026	5.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0090	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	300.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	300.000	Sft
0105	Traf Regulator Control	8120370	1.000	LSUM
0110	_ Trail Armoring	8137011	250.000	Syd
0115	_ Riprap, Trail	8137031	20.000	Ton
0120	_ Horticultural Work	8157040	100.000	Hr
0125	Topsoil Surface, Furn, LM	8160071	93.000	Cyd
0130	_ Mulch Blanket, Modified	8167011	200.000	Syd
0135	_ Seeding, Trail Mixture A	8167030	135.000	Lb

---

0140	_ Singletrack Trail Staking	8247051	1.000	LSUM
------	-----------------------------	---------	-------	------

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 010

**Letting Date:** September 5, 2025

**Contract ID:** 22000-213489

**Description:** 1.90 mi of soft surface shared-use path, new entrance, parking area, trail overlooks, signing and furniture, Dickinson County. A mandatory pre-bid meeting will be held Wednesday August 13, 2025 at the Norway Lake County Park at 10:00 am at 9592 Pete's Road, Felch, Michigan 49831.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
213489A	25A0833	N/A	NRT 22000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$55,000.00	1100001	1.000	LSUM
0010	_ Clearing, Special for Job Number 213489	2017002	124.000	Sta
0015	Tree, Rem, 19 inch to 36 inch	2020002	20.000	Ea
0020	Tree, Rem, 37 inch or Larger	2020003	2.000	Ea
0025	Tree, Rem, 6 inch to 18 inch	2020004	55.000	Ea
0030	Stump, Rem, 19 inch to 36 inch	2020006	5.000	Ea
0035	Stump, Rem, 37 inch or Larger	2020007	2.000	Ea
0040	Stump, Rem, 6 inch to 18 inch	2020008	10.000	Ea
0045	Embankment, LM	2050011	75.000	Cyd
0050	Excavation, Earth	2050016	65.000	Cyd
0055	Erosion Control, Check Dam, Stone	2080012	125.000	Ft
0060	Erosion Control, Maintenance, Sediment Rem	2080026	25.000	Cyd
0065	Erosion Control, Silt Fence	2080036	2,000.000	Ft
0070	_ Aggregate Surface Cse, 4 inch	3067011	7,500.000	Syd
0075	Approach, CI II, 6 inch	3070028	100.000	Syd
0080	Geotextile, Separator	3080005	7,650.000	Syd
0085	Culv End Sect, Conc, 12 inch	4010047	10.000	Ea
0090	Culv End Sect, Conc, 18 inch	4010049	4.000	Ea
0095	Culv End Sect, Footing	4010072	14.000	Ea
0100	Culv, CI A, 12 inch	4010131	60.000	Ft
0105	Culv, CI A, 18 inch	4010133	24.000	Ft
0110	_ Shared Use Path, Grading, Special	8067001	12,206.000	Ft
0115	Fence, Protective	8080007	250.000	Ft
0120	Pedestrian Type II Barricade, Temp	8120026	25.000	Ea
0125	Minor Traf Devices	8120170	1.000	LSUM
0130	_ Modular Wall	8157001	181.000	Ft
0135	_ Horticultural Work	8157040	100.000	Hr

---

0140	_ Barrier Free Sign	8157050	1.000	Ea
0145	_ Boulder Barrier	8157050	19.000	Ea
0150	_ Composite Bench	8157050	7.000	Ea
0155	_ Composite Picnic Table	8157050	2.000	Ea
0160	_ Confidence Marker	8157050	45.000	Ea
0165	_ Intersection Sign	8157050	35.000	Ea
0170	_ Trailhead Sign	8157050	1.000	Ea
0175	_ Wayfinding Sign	8157050	7.000	Ea
0180	Topsoil Surface, Furn, LM	8160071	250.000	Cyd
0185	_ Mulch Blanket, Modified	8167011	2,500.000	Syd
0190	_ Seeding, Trail Mixture A	8167030	100.000	Lb
0195	_ Trail Staking	8247051	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 011

**Letting Date:** September 5, 2025

**Contract ID:** 47064-217341

**Description:** 4.49 mi of hot mix asphalt cold milling and resurfacing, joint repairs and pavement markings on I-96 from US-23 easterly to Kent Lake Road, Livingston and Oakland Counties. This project includes a 3 year materials and workmanship pavement warranty and a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217341A	N/A	N/A	M 47064

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$649,500.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	200.000	Ea
0015	Project Cleanup	2090001	1.000	LSUM
0020	Pavt, Cleaning	5010001	1.000	LSUM
0025	Cold Milling HMA Surface	5010002	238,055.000	Syd
0030	HMA Quality Initiative	5010007	55,446.000	Dlr
0035	Longit Joint Density Quality Initiative	5010018	104,588.000	Dlr
0040	Pavt Joint and Crack Repr, Det 7	5010020	3,755.000	Ft
0045	Pavt Joint and Crack Repr, Det 8	5010021	370.000	Ft
0050	Hand Patching	5010025	215.000	Ton
0055	HMA Approach	5010061	763.000	Ton
0060	HMA, 4EMH	5012026	2,988.000	Ton
0065	_ Stone Matrix Asphalt (1/2 inch Nominal Max)	5017031	23,757.000	Ton
0070	Seal, Fog	5050015	127,716.000	Syd
0075	Chip Seal, Shld, Warranty	5050030	127,716.000	Syd
0080	Delineator Reflector, Red	8100131	80.000	Ea
0085	Delineator Reflector, Yellow	8100132	120.000	Ea
0090	Delineator Reflector, Green	8100133	45.000	Ea
0095	Delineator Reflector, White	8100134	305.000	Ea
0100	Delineator, Reflective Sheeting, 3 inch by 12 inch, Red	8100139	45.000	Ea
0105	Delineator, Reflective Sheeting, 3 inch by 12 inch, White	8100145	20.000	Ea
0110	Delineator, Reflective Sheeting, 3 inch by 12 inch, Yellow	8100146	85.000	Ea
0115	Delineator, Rem	8100349	575.000	Ea
0120	Post, Rigid, Delineator	8100361	470.000	Ea
0125	Post, Flexible, Delineator, Ground Mtd	8100555	105.000	Ea
0130	_ Enhanced Delineation, Unidirectional, Conc Barrier, Side Mtd	8107001	49,530.000	Ft

0135	_ Enhanced Delineation, Unidirectional, Guardrail, Channel Mtd	8107001	10,730.000	Ft
0140	Pavt Mrkg, Polyurea, 6 inch, White	8110094	86,491.000	Ft
0145	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	55,065.000	Ft
0150	Pavt Mrkg, Polyurea, Wrong Way Arrow Sym	8110098	4.000	Ea
0155	Pavt Mrkg, Polyurea, 12 inch, White	8110111	4,118.000	Ft
0160	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	98.000	Ft
0165	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0170	Pavt Mrkg, Polyurea, Only	8110410	4.000	Ea
0175	Recessing Pavt Mrkg, Longit	8110450	145,674.000	Ft
0180	Recessing Pavt Mrkg, Transv	8110451	732.000	Sft
0185	Pavt Mrkg, Polyurea, Right	8112177	2.000	Ea
0190	Pavt Mrkg, Polyurea, Left	8112178	2.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	50.000	Ea
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	50.000	Ea
0205	Connected Arrow Board, Type C, Furn	8120155	8.000	Ea
0210	Connected Arrow Board, Type C, Oper	8120156	8.000	Ea
0215	Ltg for Night Work	8120160	1.000	LSUM
0220	Minor Traf Devices	8120170	1.000	LSUM
0225	Mobile Attenuator	8120180	3.000	Ea
0230	Plastic Drum, Fluorescent, Furn	8120252	560.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	560.000	Ea
0240	Sign Cover	8120310	12.000	Ea
0245	Sign, Portable, Changeable Message, NTCIP- Compliant, Furn	8120332	12.000	Ea
0250	Sign, Portable, Changeable Message, NTCIP- Compliant, Oper	8120333	12.000	Ea
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	2,806.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	2,806.000	Sft
0265	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	86,491.000	Ft
0270	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	55,065.000	Ft
0275	Freeway Shld Corrugations, Milled, HMA	8222001	74,265.000	Ft
0280	Contractor Staking	8240001	1.000	LSUM
0285	Staking Plan Errors and Extras, Max \$180/hour	8240002	74.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 012

**Letting Date:** September 5, 2025

**Contract ID:** 67051-214961

**Description:** Bridge rehabilitation including deck patching, epoxy overlay, concrete T-beam and barrier repairs, substructure patching, guardrail work and approach work on M-115 over the west branch of the Middle Branch River, Osceola County. This project includes a 5 year thin epoxy overlay performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
214961A	25A0855	N/A	BFP 67051

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$68,800.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	12.000	Ft
0015	Guardrail, Rem	2040035	150.000	Ft
0020	Pavt, Rem	2040050	237.000	Syd
0025	Excavation, Earth	2050016	117.000	Cyd
0030	Erosion Control, Silt Fence	2080036	110.000	Ft
0035	Subbase, CIP	3010002	110.000	Cyd
0040	Open-Graded Dr Cse, 6 inch	3030006	313.000	Syd
0045	Geotextile, Separator, Non-Woven	3082000	277.000	Syd
0050	HMA Surface, Rem	5010005	78.000	Syd
0055	Hand Patching	5010025	10.000	Ton
0060	Joint, Expansion, E3	6020208	93.000	Ft
0065	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	254.000	Syd
0070	Curb and Gutter, Bridge Approach, Det 5	8022016	50.000	Ft
0075	Curb and Gutter, Bridge Approach, Det 6	8022017	48.000	Ft
0080	Guardrail Anch, Bridge, Det T3	8070024	3.000	Ea
0085	Guardrail Anch, Bridge, Det T4	8070025	1.000	Ea
0090	Guardrail Departing Terminal, Type T	8070051	1.000	Ea
0095	Guardrail Reflector	8070080	10.000	Ea
0100	Guardrail, Reconst, Type B	8070105	75.000	Ft
0105	Guardrail, Curved, Type T, 84 inch Post	8072143	13.000	Ft
0110	Delineator Reflector, Green	8100133	1.000	Ea
0115	Post, Rigid, Delineator	8100361	1.000	Ea
0120	Recessing Pavt Mrkg, Longit	8110450	430.000	Ft
0125	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	367.000	Ft
0130	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, Yellow	8112004	58.000	Ft

0135	Pavt Mrkg, Wet Reflective Waterborne, 6 inch, White	8112145	367.000	Ft
0140	Pavt Mrkg, Wet Reflective Waterborne, 6 inch, Yellow	8112148	58.000	Ft
0145	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0150	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0155	Minor Traf Devices	8120170	1.000	LSUM
0160	Plastic Drum, Fluorescent, Furn	8120252	6.000	Ea
0165	Plastic Drum, Fluorescent, Oper	8120253	6.000	Ea
0170	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	18.000	Ft
0175	Sign Cover	8120310	5.000	Ea
0180	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0185	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0190	Sign, Type A, Temp, Prismatic, Furn	8120340	7.000	Sft
0195	Sign, Type A, Temp, Prismatic, Oper	8120341	7.000	Sft
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	259.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	259.000	Sft
0210	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	1,200.000	Ft
0215	Temp Rumble Strips (Orange), Stop Condition	8122186	660.000	Ft
0220	Riprap, Plain	8130010	6.000	Syd
0225	Slope Restoration, Non-Freeway, Type F	8162006	227.000	Syd

**Section: 2**

0230	Backfill, Structure, CIP	2060002	25.000	Cyd
0235	Excavation, Fdn	2060010	132.000	Cyd
0240	Erosion Control, Turbidity Curtain, Deep	2080042	195.000	Ft
0245	Underdrain, Fdn, 4 inch	4040031	148.000	Ft
0250	Underdrain Outlet, 4 inch	4040091	20.000	Ft
0255	Underdrain, Outlet Ending, 4 inch	4040111	4.000	Ea
0260	False Decking	7060060	1,053.000	Sft
0265	Reinforcement, Steel, Epoxy Coated	7060092	847.000	Lb
0270	Substructure Conc, High Performance	7060101	6.000	Cyd
0275	_ Fiber Reinf Polymer System for Conc Repr	7067010	97.000	Sft
0280	Joint Waterproofing	7100001	120.000	Sft
0285	_ Silane Treatment	7107010	2,336.000	Sft
0290	Hand Chipping, Deep	7120004	23.000	Syd
0295	Hand Chipping, Other Than Deck	7120007	25.000	Cft
0300	Patch, Forming	7120017	100.000	Sft
0305	Epoxy Ovly, Rem	7120021	136.000	Syd
0310	Epoxy Ovly, Warranty	7120022	234.000	Syd
0315	Adhesive Anchoring of Horizontal Bar, 3/4 inch	7120028	8.000	Ea
0320	Adhesive Anchoring of Vertical Bar, 3/4 inch	7120034	36.000	Ea
0325	Structures, Rehabilitation, Rem Portions	7120070	1.000	LSUM

---

0330	Flushing Cracks, Water	7120098	200.000	Ft
0335	Structural Crack, Repr	7120099	200.000	Ft
0340	Patching Conc, C-L	7120112	4.000	Cyd
0345	_ Hand Chipping, Spec	7127010	77.000	Sft
0350	_ Latex Modified Conc, Spec	7127021	1.000	Cyd
0355	_ Riprap, Spec, CI II	8137031	181.000	Ton
0360	_ Riprap, Under Structures, Class I	8137031	20.000	Ton

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 013

**Letting Date:** September 5, 2025

**Contract ID:** 63000-219296

**Description:** 0.10 mi of hot mix asphalt road reconstruction, aggregate base, concrete sidewalk ramps, permanent signing, and pavement markings on Narrin Street from Ortonville Road to Mill Street in the village of Ortonville, Oakland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219296A	25A0747	N/A	STUL 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$12,900.00	1100001	1.000	LSUM
0010	Sidewalk, Rem	2040055	34.000	Syd
0015	Subgrade Undercutting, Type IV	2050043	50.000	Cyd
0020	_ Machine Grading, Modified	2057002	5.000	Sta
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0030	Subbase, CIP	3010002	4.000	Cyd
0035	Aggregate Base, 6 inch	3020016	121.000	Syd
0040	Aggregate Base, 8 inch	3020020	1,430.000	Syd
0045	Maintenance Gravel	3060020	25.000	Ton
0050	Shld, CI II, 4 inch	3070126	85.000	Syd
0055	HMA Surface, Rem	5010005	1,450.000	Syd
0060	Hand Patching	5010025	1.000	Ton
0065	HMA Approach	5010061	38.000	Ton
0070	HMA, 4EML	5012025	167.000	Ton
0075	HMA, 5EML	5012037	167.000	Ton
0080	Sidewalk, Conc, 4 inch	8030044	70.000	Sft
0085	Curb Ramp, Conc, 6 inch	8032002	234.000	Sft
0090	_ Detectable Warning Surface, Cast Iron, Spec	8037001	36.000	Ft
0095	Post, Steel, 3 pound	8100371	68.000	Ft
0100	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0105	Sign, Type III, Rem	8100403	5.000	Ea
0110	Sign, Type IIIA	8100404	7.000	Sft
0115	Sign, Type IIIB	8100405	8.000	Sft
0120	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	55.000	Ft
0125	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	24.000	Ft
0130	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0135	Barricade, Type III, High Intensity, Double Sided,	8120013	4.000	Ea

Lighted, Oper				
0140	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	20.000	Ea
0150	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	20.000	Ea
0155	Dust Palliative, Applied	8120100	3.000	Ton
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Sign, Type B, Temp, Prismatic, Furn	8120350	66.000	Sft
0170	Sign, Type B, Temp, Prismatic, Oper	8120351	66.000	Sft
0175	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	17.000	Sft
0180	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	17.000	Sft
0185	Traf Regulator Control	8120370	1.000	LSUM
0190	_ Turf Establishment, Performance	8167002	5.000	Sta
0195	_ Audio-Video Construction Area Survey	8507051	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 014

**Letting Date:** September 5, 2025

**Contract ID:** 28000-222008

**Description:** Traffic signal modernization, concrete curb and gutter, sidewalk, sidewalk ramps and pavement markings on Long Lake Road at the intersection of Herkner Road, Grand Traverse County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222008A	25A0773	N/A	HSIP 28000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$34,200.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	41.000	Ft
0015	Pavt, Rem	2040050	10.000	Syd
0020	Sidewalk, Rem	2040055	23.000	Syd
0025	Embankment, CIP	2050010	20.000	Cyd
0030	Excavation, Earth	2050016	14.000	Cyd
0035	Erosion Control, Silt Fence	2080036	50.000	Ft
0040	Aggregate Base, 6 inch	3020016	47.000	Syd
0045	Hand Patching	5010025	3.000	Ton
0050	Curb and Gutter, Conc, Det B2	8020016	33.000	Ft
0055	Detectable Warning Surface	8030010	16.000	Ft
0060	Curb Ramp Opening, Conc	8030030	8.000	Ft
0065	Curb Ramp, Conc, 6 inch	8032002	199.000	Sft
0070	Post, Steel, 3 pound	8100371	84.000	Ft
0075	Sign, Type III, Rem	8100403	2.000	Ea
0080	Sign, Type IIIB	8100405	38.000	Sft
0085	Ground Mtd Sign Support, Rem	8102010	1.000	Ea
0090	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	3.000	Ea
0095	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	3.000	Ea
0100	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	120.000	Ft
0105	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	150.000	Ft
0110	Rem Spec Mrkg	8110343	358.000	Sft
0115	Recessing Pavt Mrkg, Longit	8110450	2,221.000	Ft
0120	Recessing Pavt Mrkg, Transv	8110451	235.000	Sft
0125	Pavt Mrkg, Wet Reflective Waterborne, 6 inch, White	8112145	1,058.000	Ft
0130	Pavt Mrkg, Wet Reflective Waterborne, 4 inch, Yellow	8112147	1,203.000	Ft
0135	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	2.000	Ea

0140	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	2.000	Ea
0145	Pedestrian Type II Barricade, Temp	8120026	5.000	Ea
0150	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0155	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0160	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0165	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0170	Minor Traf Devices	8120170	1.000	LSUM
0175	Mobile Attenuator	8120180	1.000	Ea
0180	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	1,745.000	Ft
0185	Sign Cover	8120310	5.000	Ea
0190	Sign, Type B, Temp, Prismatic, Furn	8120350	450.000	Sft
0195	Sign, Type B, Temp, Prismatic, Oper	8120351	450.000	Sft
0200	Traf Regulator Control	8120370	1.000	LSUM
0205	Slope Restoration, Non-Freeway, Type B	8162002	63.000	Syd
0210	Power Company (Estimated Cost to Contractor)	8180001	500.000	Dlr
0215	Conduit, DB, 1, 1 1/2 inch	8182048	54.000	Ft
0220	Conduit, DB, 1, 3 inch	8182050	12.000	Ft
0225	Conduit, DB, 3, 3 inch	8182056	23.000	Ft
0230	Conduit, DB, 4, 3 inch	8182059	5.000	Ft
0235	Cable, Sec, 600V, 1, 3/C#6	8182238	50.000	Ft
0240	Hh, Round	8182310	1.000	Ea
0245	Hh, Round, 3 foot dia	8182319	1.000	Ea
0250	Metered Serv	8182338	1.000	Ea
0255	Metered Serv, Rem	8182339	1.000	Ea
0260	Wood Pole, Rem	8182363	4.000	Ea
0265	Serv Disconnect	8182366	1.000	Ea
0270	Case Sign, Rem	8200020	1.000	Ea
0275	Controller and Cabinet, Rem	8200030	1.000	Ea
0280	Case Sign, Salv	8200039	1.000	Ea
0285	Controller Fdn, Base Mtd	8200045	1.000	Ea
0290	Pedestal, Alum	8200100	2.000	Ea
0295	Pedestal, Fdn	8200105	2.000	Ea
0300	Pushbutton and Sign	8200121	2.000	Ea
0305	Span Wire	8200140	4.000	Ea
0310	Span Wire, Rem	8200141	2.000	Ea
0315	Span Wire Tether	8200142	4.000	Ea
0320	TS, Bracket Arm Mtd, Rem	8200175	1.000	Ea
0325	TS, Span Wire Mtd, Rem	8200182	4.000	Ea
0330	Cabinet, NEMA Type	8200186	1.000	Ea
0335	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	2.000	Ea
0340	Bracket, Truss, with 18 foot Arm	8200378	1.000	Ea
0345	Wireless Repeater, Rem	8200418	2.000	Ea
0350	Wireless Repeater	8200421	2.000	Ea

0355	Wireless Vehicle Detection System, Rem	8200423	1.000	Ea
0360	Hemispherical Video Detection Camera	8200444	1.000	Ea
0365	Hemispherical Video Detection System	8200445	1.000	Ea
0370	Hemispherical Video Detection Camera, Rem	8200446	2.000	Ea
0375	Hemispherical Video Detection System, Rem	8200447	1.000	Ea
0380	Strain Pole, Steel, 6 bolt, Size 2	8200466	4.000	Ea
0385	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	72.000	Ft
0390	Casing, 48 inch	8200486	58.000	Ft
0395	Backplate, TS	8200501	12.000	Ea
0400	TS, One Way Span Wire Mtd (LED), Long Life	8202287	7.000	Ea
0405	TS, One Way Span Wire Mtd, FYA (LED), Long Life	8202299	4.000	Ea
0410	TS, One Way Span Wire Mtd, Five Sect (LED), Long Life	8202308	1.000	Ea
0415	_ Controller, NEMA, ATC Type, Modified	8207050	1.000	Ea
0420	_ Street Name Sign, Non-Illuminated, Two Way, 8 foot	8207050	4.000	Ea
0425	Power Serv, Underground, 60AMP, 120/240V	8260101	1.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 015

**Letting Date:** September 5, 2025

**Contract ID:** 37000-214159

**Description:** 1.98 mi of hot mix asphalt base crushing, shaping and resurfacing, aggregate shoulders and pavement markings on Coleman Road from Mission Road to Summerton Road, Isabella County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
214159A	25A0757	N/A	STL 37000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$107,000.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	13.000	Ea
0015	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0020	Sewer, Rem, Less than 24 inch	2030015	54.000	Ft
0025	_ Pavt, Rem, Modified	2047011	346.000	Syd
0030	Embankment, CIP	2050010	2,230.000	Cyd
0035	Excavation, Earth	2050016	465.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	3.000	Ea
0045	Erosion Control, Silt Fence	2080036	13,639.000	Ft
0050	Subbase, CIP	3010002	80.000	Cyd
0055	Aggregate Base	3020001	2,863.000	Ton
0060	HMA Base Crushing and Shaping	3050002	34,097.000	Syd
0065	Salv Crushed Material, LM	3050015	175.000	Cyd
0070	Approach, CI I	3070001	255.000	Ton
0075	Approach, CI II	3070021	596.000	Ton
0080	Shld, CI II	3070121	1,066.000	Ton
0085	Trenching	3070200	101.000	Sta
0090	Culv, CI A, 15 inch	4010132	406.000	Ft
0095	Culv, CI A, 18 inch	4010133	45.000	Ft
0100	Culv, CI A, 30 inch	4010135	52.000	Ft
0105	Culv, Slp End Sect, 1 on 4, 15 inch, Longit	4010917	14.000	Ea
0110	Culv, Slp End Sect, 1 on 4, 15 inch, Transv	4010918	9.000	Ea
0115	Culv, Slp End Sect, 1 on 4, 18 inch, Transv	4010920	2.000	Ea
0120	Sewer, CI A, 15 inch, Tr Det B	4020034	117.000	Ft
0125	Dr Structure Cover, Adj, Case 2	4030006	1.000	Ea
0130	Dr Structure, Tap, 15 inch	4030315	3.000	Ea
0135	HMA Surface, Rem	5010005	494.000	Syd

0140	HMA Approach	5010061	182.000	Ton
0145	HMA, 4EL	5012024	6,337.000	Ton
0150	Driveway, Nonreinf Conc, 6 inch	8010005	109.000	Syd
0155	Curb Slp, HMA	8050010	2,477.000	Ft
0160	Post, Mailbox	8070095	26.000	Ea
0165	Guardrail Height, Adj	8070100	2,669.000	Ft
0170	Post, Steel, 3 pound	8100371	270.000	Ft
0175	Sign, Type III, Erect, Salv	8100402	5.000	Ea
0180	Sign, Type III, Rem	8100403	7.000	Ea
0185	Sign, Type IIIA	8100404	55.000	Sft
0190	Sign, Type IIIB	8100405	45.000	Sft
0195	Reflective Panel for Permanent Sign Support, 6 foot	8100616	4.000	Ea
0200	Sign, Type III, Rem, Salv	8102003	7.000	Ea
0205	Ground Mtd Sign Support, Rem	8102010	11.000	Ea
0210	Pavt Mrkg, Waterborne, 4 inch, White	8110231	21,000.000	Ft
0215	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	13,200.000	Ft
0220	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0225	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	22.000	Ea
0230	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	22.000	Ea
0235	Minor Traf Devices	8120170	1.000	LSUM
0240	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0245	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0250	Sign Cover	8120310	6.000	Ea
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	483.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	483.000	Sft
0265	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	150.000	Sft
0270	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	150.000	Sft
0275	Slope Restoration, Non-Freeway, Type B	8162002	5,878.000	Syd
0280	Slope Restoration, Non-Freeway, Type C	8162003	5,295.000	Syd
0285	Monument Box	8210001	3.000	Ea
0290	Monument Preservation	8210010	3.000	Ea
0295	_ Dust Palliative, Applied, Modified	8507022	8,910.000	Gal



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 016

**Letting Date:** September 5, 2025

**Contract ID:** 25000-207708

**Description:** 1.88 mi of constructing shared-use path and timber boardwalk along Silver Lake Road Connector Trail from Jennings Road to East Broad Street in the city of Fenton, Genesee County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
207708A	25A0758	N/A	TA 25000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Permit / Private Utility Fees	1027060	10,000.000	Dir
0010	Mobilization, Max \$450,000.00	1100001	1.000	LSUM
0015	Clearing	2010001	6.000	Acre
0020	Stump, Rem, 19 inch to 36 inch	2020006	6.000	Ea
0025	Stump, Rem, 37 inch or Larger	2020007	1.000	Ea
0030	Stump, Rem, 6 inch to 18 inch	2020008	31.000	Ea
0035	Culv, Rem, Less than 24 inch	2030001	11.000	Ea
0040	Culv, End, Rem, Less than 24 inch	2030005	3.000	Ea
0045	Sewer, Rem, Less than 24 inch	2030015	132.000	Ft
0050	Curb and Gutter, Rem	2040020	746.000	Ft
0055	Fence, Rem	2040025	490.000	Ft
0060	Pavt, Rem	2040050	1,939.000	Syd
0065	Sidewalk, Rem	2040055	40.000	Syd
0070	Structures, Rem Portions	2040061	1.000	LSUM
0075	Utility Pole, Rem	2040070	2.000	Ea
0080	Exploratory Investigation, Vertical	2040080	9.000	Ft
0085	Embankment, CIP	2050010	320.000	Cyd
0090	Embankment, Structure, CIP	2050012	250.000	Cyd
0095	Excavation, Earth	2050016	500.000	Cyd
0100	Excavation, Peat	2050017	319.000	Cyd
0105	Subgrade Undercutting, Type II	2050041	74.000	Cyd
0110	Erosion Control, Check Dam, Stone	2080012	100.000	Ft
0115	Erosion Control, Gravel Access Approach	2080016	3.000	Ea
0120	Erosion Control, Gravel Filter Berm	2080018	37.000	Ft
0125	Erosion Control, Inlet Protection, Fabric Drop	2080020	33.000	Ea
0130	Erosion Control, Silt Fence	2080036	18,712.000	Ft
0135	Erosion Control, Turbidity Curtain, Shallow	2080044	1,674.000	Ft

0140	Aggregate Base, 4 inch	3020010	12,000.000	Syd
0145	Aggregate Base, 6 inch	3020016	200.000	Syd
0150	Aggregate Base, 8 inch	3020020	2,200.000	Syd
0155	Aggregate Surface Cse, 8 inch	3060012	200.000	Syd
0160	Maintenance Gravel	3060020	200.000	Ton
0165	Culv End Sect, 12 inch	4010012	1.000	Ea
0170	Culv End Sect, Metal, 12 inch	4010094	17.000	Ea
0175	Culv, CI A, 24 inch	4010134	100.000	Ft
0180	Culv, CI F, 12 inch	4010607	180.000	Ft
0185	Culv, Outlet Headwall, 12 inch	4012000	1.000	Ea
0190	Sewer, CI A, 6 inch, Tr Det A	4020001	400.000	Ft
0195	Sewer, CI E, 12 inch, Tr Det B	4020600	1,300.000	Ft
0200	Sewer Tap, 4 inch	4021200	3.000	Ea
0205	Sewer Tap, 6 inch	4021201	8.000	Ea
0210	Dr Structure Cover, Adj, Case 2	4030006	10.000	Ea
0215	Dr Structure Cover, Type B	4030010	1.000	Ea
0220	Dr Structure Cover, Type K	4030050	6.000	Ea
0225	Dr Structure, 48 inch dia	4030210	7.000	Ea
0230	Dr Structure, Adj, Add Depth	4030280	12.000	Ft
0235	Underdrain, Subgrade, Open-Graded, 6 inch	4040083	3,600.000	Ft
0240	Culv Bedding, Box Culv	4060005	20.000	Cyd
0245	_ Culv, Precast Conc Box, 3 foot by 3 foot	4067001	21.000	Ft
0250	HMA Surface, Rem	5010005	2,441.000	Syd
0255	Pavt for Butt Joints, Rem	5010008	778.000	Syd
0260	Hand Patching	5010025	110.000	Ton
0265	HMA Approach	5010061	200.000	Ton
0270	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	500.000	Syd
0275	Conc Pavt with Integral Curb, Nonreinf, 6 inch	6020160	600.000	Syd
0280	Lane Tie, Epoxy Anchored	6030030	150.000	Ea
0285	Steel Sheet Piling, Permanent	7040001	13,700.000	Sft
0290	_ Helical Pile	7057001	4,200.000	Ft
0295	_ Conc Boardwalk	7067001	56.000	Ft
0300	_ Gravity Boulder Retaining Wall	7067010	2,100.000	Sft
0305	_ Substructure Conc, Modified	7067021	200.000	Cyd
0310	_ Pressure Treated Wood Boardwalk & Railing, 12 foot Wide	7097001	1,189.000	Ft
0315	_ Timber Rub Rail	7097001	1,150.000	Ft
0320	Driveway, Nonreinf Conc, 6 inch	8010005	50.000	Syd
0325	Curb and Gutter, Conc, Det F4	8020038	380.000	Ft
0330	_ Curb and Gutter, Conc, Det B2, Modified	8027001	2,900.000	Ft
0335	_ Bumper Blocks, Conc, 84 inch	8027050	3.000	Ea
0340	Detectable Warning Surface	8030010	300.000	Ft
0345	Curb Ramp Opening, Conc	8030030	300.000	Ft
0350	Sidewalk, Conc, 4 inch	8030044	5,000.000	Sft
0355	Sidewalk, Conc, 6 inch	8030046	3,000.000	Sft

0360	Curb Ramp, Conc, 6 inch	8032002	5,900.000	Sft
0365	Shared use Path, HMA	8060040	2,000.000	Ton
0370	_ Shared Use Path, Grading, Modified	8067001	10,800.000	Ft
0375	Post, Mailbox	8070095	15.000	Ea
0380	_ Fence, Chain Link, 48 inch, Modified	8087001	280.000	Ft
0385	_ Fence, Chain Link, 72 inch, Modified	8087001	240.000	Ft
0390	_ Post & Rail Wood Fence	8087001	150.000	Ft
0395	_ Fence Gate, 12 foot, for 72 inch Chain Link Fence, Modified	8087050	1.000	Ea
0400	_ Fence Gate, 4 foot, for 72 inch Chain Link Fence, Modified	8087050	1.000	Ea
0405	Post, Steel, 3 pound	8100371	220.000	Ft
0410	Sign, Type I, Rem	8100391	1.000	Ea
0415	Sign, Type III, Erect, Salv	8100402	18.000	Ea
0420	Sign, Type IIIA	8100404	94.000	Sft
0425	Sign, Type IIIB	8100405	200.000	Sft
0430	Post, Flexible, Delineator, Surface Mtd, 48 inch	8100552	10.000	Ea
0435	Post, Flexible, Delineator, Ground Mtd	8100555	100.000	Ea
0440	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0445	Pavt Mrkg, Modified Epoxy, 6 inch, Crosswalk	8112230	1,800.000	Ft
0450	Pavt Mrkg, Modified Epoxy, 12 inch, Crosswalk	8112231	180.000	Ft
0455	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0460	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0465	Minor Traf Devices	8120170	1.000	LSUM
0470	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0475	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0480	Sign, Type B, Temp, Prismatic, Furn	8120350	360.000	Sft
0485	Sign, Type B, Temp, Prismatic, Oper	8120351	360.000	Sft
0490	Traf Regulator Control	8120370	1.000	LSUM
0495	Riprap, Plain	8130010	200.000	Syd
0500	_ Riprap, Plain, LM, Modified	8137021	1,000.000	Cyd
0505	_ 3-Seat Table	8157050	3.000	Ea
0510	_ Bench, 72 inch	8157050	3.000	Ea
0515	_ Bike Rack	8157050	14.000	Ea
0520	_ Picnic Table	8157050	2.000	Ea
0525	_ Trash Receptacle	8157050	8.000	Ea
0530	_ Multi Urban Eco Counter	8157051	1.000	LSUM
0535	_ Trailhead Kiosk	8157051	1.000	LSUM
0540	Fertilizer, Chemical Nutrient, CI A	8160020	200.000	Lb
0545	Mulch	8160025	19,000.000	Syd
0550	Mulch Blanket	8160027	500.000	Syd
0555	Seeding, Mixture TUF	8160042	900.000	Lb
0560	Topsoil Surface, Furn, 3 inch	8160061	18,000.000	Syd
0565	Conduit, DB, 1, 2 1/2 inch	8182049	150.000	Ft
0570	Cable, St Ltg, 2kV, 3, 1/C#2 and 1, #2 Neutral	8182280	150.000	Ft

0575	Hh, Polymer Conc	8182309	1.000	Ea
0580	Metered Serv	8182338	1.000	Ea
0585	_ Fish Beacon, Ractangular Rapid, Solar Power	8197050	4.000	Ea
0590	_ LED Light Pole	8197050	1.000	Ea
0595	Pedestal, Alum	8200100	4.000	Ea
0600	Pedestal Fdn, Flush	8200103	4.000	Ea
0605	Pedestal Fdn, Rem	8200106	1.000	Ea
0610	Pushbutton and Sign	8200121	4.000	Ea
0615	Contractor Staking	8240001	1.000	LSUM
0620	Staking Plan Errors and Extras, Max \$180/hour	8240002	40.000	Hr
0625	Sanitary Structure, Adj, Add Depth	8252140	6.000	Ft
0630	Sanitary Structure Cover, Adj, Case 2	8252146	6.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 017

**Letting Date:** September 5, 2025

**Contract ID:** 50000-220416

**Description:** 1.14 mi of hot mix asphalt shared-use path including crack sealing, joint repair, and concrete sidewalk ramp upgrade along Clinton River Spillway from Gratiot Parkway to Metropolitan Parkway, Macomb County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220416A	25A0774	N/A	TAU 50000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1027060	5,250.000	Dir
0010	Mobilization, Max \$58,000.00	1100001	1.000	LSUM
0015	Sidewalk, Rem	2040055	64.000	Syd
0020	_ Bollard, Rem	2047050	3.000	Ea
0025	Embankment, CIP	2050010	25.000	Cyd
0030	Excavation, Earth	2050016	50.000	Cyd
0035	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0040	Erosion Control, Inlet Protection, Sediment Trap	2080024	6.000	Ea
0045	Project Cleanup	2090001	1.000	LSUM
0050	Aggregate Base, 4 inch	3020010	63.000	Syd
0055	Aggregate Base, 6 inch	3020016	11.000	Syd
0060	Maintenance Gravel	3060020	100.000	Ton
0065	HMA Surface, Rem	5010005	175.000	Syd
0070	Joint and Crack, Cleanout	5010015	5,520.000	Ft
0075	Pavt Joint and Crack Repr, Det 7	5010020	3,015.000	Ft
0080	Pavt Joint and Crack Repr, Det 8	5010021	2,505.000	Ft
0085	Hand Patching	5010025	100.000	Ton
0090	Detectable Warning Surface	8030010	49.000	Ft
0095	Curb Ramp Opening, Conc	8030030	28.000	Ft
0100	Sidewalk, Conc, 4 inch	8030044	197.000	Sft
0105	Curb Ramp, Conc, 6 inch	8032002	528.000	Sft
0110	Shared use Path, Grading	8060030	5,933.000	Ft
0115	Shared use Path, HMA	8060040	850.000	Ton
0120	Post, Steel, 3 pound	8100371	70.000	Ft
0125	Sign, Type III, Rem	8100403	3.000	Ea
0130	Sign, Type IIIA	8100404	45.000	Sft
0135	Pavt Mrkg, Waterborne, 6 inch, White	8110233	100.000	Ft

0140	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0145	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	4.000	Ea
0150	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0155	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0160	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0165	Minor Traf Devices	8120170	1.000	LSUM
0170	Pavt Mrkg, Longit, Water Blasting, 6 inch or less Width, Rem	8120212	100.000	Ft
0175	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0180	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0185	Sign, Type A, Temp, Prismatic, Furn	8120340	100.000	Sft
0190	Sign, Type A, Temp, Prismatic, Oper	8120341	100.000	Sft
0195	Topsoil Surface, Furn, 3 inch	8160061	4,495.000	Syd
0200	Water, Sodding/Seeding	8160090	125.000	Unit
0205	_ Hydroseeding	8167011	4,495.000	Syd
0210	_ Bollard, Conc, 6 inch	8507050	2.000	Ea
0215	_ Audio-Visual Record of Construction Area	8507051	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 018

**Letting Date:** September 5, 2025

**Contract ID:** 47000-220161

**Description:** 0.21 mi of hot mix asphalt reconstruction, intersection realignment and widening, drainage and guardrail improvements, permanent signing, pavement markings and tree removals on Rushton Road at Doane Road, Livingston County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220161A	25A0776	N/A	HSIP 47000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$96,000.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.270	Acre
0015	Culv, Rem, Less than 24 inch	2030001	2.000	Ea
0020	Culv, End, Rem, Less than 24 inch	2030005	4.000	Ea
0025	Dr Structure, Rem	2030011	3.000	Ea
0030	Sewer, Rem, Less than 24 inch	2030015	571.000	Ft
0035	Curb and Gutter, Rem	2040020	60.000	Ft
0040	Fence, Rem	2040025	50.000	Ft
0045	Backfill, Swamp	2050001	937.000	Cyd
0050	Embankment, CIP	2050010	1,860.000	Cyd
0055	Excavation, Earth	2050016	4,670.000	Cyd
0060	Excavation, Peat	2050017	587.000	Cyd
0065	Erosion Control, Check Dam, Stone	2080012	19.000	Ft
0070	Erosion Control, Inlet Protection, Fabric Drop	2080020	4.000	Ea
0075	Erosion Control, Inlet Protection, Sediment Trap	2080024	2.000	Ea
0080	Erosion Control, Sediment Trap	2080034	2.000	Ea
0085	_ Erosion Control, Silt Fence, Spec	2087001	2,028.000	Ft
0090	Subbase, CIP	3010002	2,770.000	Cyd
0095	Aggregate Base	3020001	2,898.000	Ton
0100	Shld, CI II	3070121	188.000	Ton
0105	Culv End Sect, 12 inch	4010012	9.000	Ea
0110	Culv End Sect, 15 inch	4010015	1.000	Ea
0115	Culv End Sect, 18 inch	4010018	1.000	Ea
0120	Culv End Sect, Footing	4010072	4.000	Ea
0125	Culv, CI F, 12 inch	4010607	133.000	Ft
0130	Dr Marker Post	4011109	11.000	Ea
0135	Sewer, CI A, 12 inch, Tr Det A	4020004	43.000	Ft

0140	Sewer, CI A, 12 inch, Tr Det B	4020033	131.000	Ft
0145	Sewer, CI A, 15 inch, Tr Det B	4020034	62.000	Ft
0150	Sewer, CI A, 18 inch, Tr Det B	4020035	220.000	Ft
0155	Sewer Tap, 12 inch	4021204	1.000	Ea
0160	Video Taping Sewer and Culv Pipe	4021275	589.000	Ft
0165	Dr Structure Cover, Type B	4030010	2.000	Ea
0170	Dr Structure Cover, Type G	4030040	3.000	Ea
0175	Dr Structure, 24 inch dia	4030200	2.000	Ea
0180	Dr Structure, 48 inch dia	4030210	3.000	Ea
0185	Underdrain, Subbase, 6 inch	4040063	2,923.000	Ft
0190	Underdrain Outlet, 6 inch	4040093	275.000	Ft
0195	Underdrain, Outlet Ending, 6 inch	4040113	9.000	Ea
0200	Video Inspection of Underdrain	4040200	2,923.000	Ft
0205	HMA Surface, Rem	5010005	4,899.000	Syd
0210	HMA Approach	5010061	373.000	Ton
0215	HMA, 3EML	5012013	919.000	Ton
0220	HMA, 4EML	5012025	628.000	Ton
0225	HMA, 5EML	5012037	471.000	Ton
0230	Curb and Gutter, Conc, Det B2	8020016	137.000	Ft
0235	Curb and Gutter, Conc, Det D2	8020031	385.000	Ft
0240	Shld Gutter, Conc, Det 2	8020056	1.000	Ea
0245	Shld Gutter, Conc, Det 3	8020057	1.000	Ea
0250	Spillway, Conc	8020075	7.000	Ft
0255	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0260	Guardrail Reflector	8070080	22.000	Ea
0265	Post, Mailbox	8070095	6.000	Ea
0270	Guardrail, Curved, Type MGS-8, 72 inch Post	8072145	75.000	Ft
0275	Guardrail, Type MGS-8, 72 inch Post	8072179	463.000	Ft
0280	Delineator Reflector, Green	8100133	2.000	Ea
0285	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	137.000	Ft
0290	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	15.000	Ft
0295	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0300	Pavt Mrkg, Waterborne, 4 inch, White	8110231	2,889.000	Ft
0305	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	3,878.000	Ft
0310	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	2,889.000	Ft
0315	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	3,878.000	Ft
0320	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Dotted Turning Guide Line, White	8110562	90.000	Ft
0325	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0330	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0335	Minor Traf Devices	8120170	1.000	LSUM
0340	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0345	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea

---

0350	Sign Cover	8120310	10.000	Ea
0355	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0360	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0365	Sign, Type B, Temp, Prismatic, Furn	8120350	540.000	Sft
0370	Sign, Type B, Temp, Prismatic, Oper	8120351	540.000	Sft
0375	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	315.000	Sft
0380	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	315.000	Sft
0385	Traf Regulator Control	8120370	1.000	LSUM
0390	Riprap, Plain	8130010	53.000	Syd
0395	Slope Restoration, Non-Freeway, Type E	8162005	6,353.000	Syd
0400	Monument Box	8210001	1.000	Ea
0405	Monument Preservation	8210010	2.000	Ea
0410	Protect Corners	8210020	5.000	Ea
0415	Contractor Staking	8240001	1.000	LSUM
0420	Staking Plan Errors and Extras, Max \$180/hour	8240002	11.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 019

**Letting Date:** September 5, 2025

**Contract ID:** 25000-216225

**Description:** 0.98 mi of hot mix asphalt cold milling and reconstruction, concrete curb and gutter, drainage, signing and pavement markings on Clio Road from Coldwater Road to Stanley Road, Genesee County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216225A	25A0756	N/A	ST 25000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$323,000.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	1.000	Ea
0015	Sewer, Rem, Less than 24 inch	2030015	185.000	Ft
0020	Curb and Gutter, Rem	2040020	2,605.000	Ft
0025	Guardrail, Rem	2040035	1,324.000	Ft
0030	_ Pavt, Rem, Modified	2047011	33,614.000	Syd
0035	Embankment, CIP	2050010	4,022.000	Cyd
0040	Excavation, Earth	2050016	4,312.000	Cyd
0045	Non Haz Contaminated Material Handling and Disposal, LM	2050031	200.000	Cyd
0050	_ Subgrade Undercutting, Type IV, Modified	2057021	450.000	Cyd
0055	Erosion Control, Inlet Protection, Fabric Drop	2080020	48.000	Ea
0060	Erosion Control, Silt Fence	2080036	10,524.000	Ft
0065	_ Aggregate Base, Modified	3027031	10,043.000	Ton
0070	_ Maintenance Gravel, Modified	3067031	850.000	Ton
0075	_ Approach, CI II, Modified	3077031	32.000	Ton
0080	Geotextile, Stabilization	3080010	11,500.000	Syd
0085	Culv, Slp End Sect, 1 on 4, 15 inch, Longit	4010917	1.000	Ea
0090	Sewer, CI A, 15 inch, Tr Det A	4020005	10.000	Ft
0095	Sewer, CI III, 12 inch, Tr Det B	4020866	293.000	Ft
0100	Sewer Tap, 15 inch	4021205	1.000	Ea
0105	Dr Structure Cover, Adj, Case 2	4030006	22.000	Ea
0110	Dr Structure Cover, Type B	4030010	22.000	Ea
0115	Dr Structure Cover, Type D	4030025	1.000	Ea
0120	Dr Structure Cover, Type E	4030035	2.000	Ea
0125	Dr Structure Cover, Type J	4030045	3.000	Ea
0130	Dr Structure Cover, Type K	4030050	21.000	Ea
0135	Dr Structure, 24 inch dia	4030200	8.000	Ea

0140	Dr Structure, 48 inch dia	4030210	12.000	Ea
0145	Dr Structure, Adj, Add Depth	4030280	4.000	Ft
0150	Dr Structure, Tap, 12 inch	4030312	10.000	Ea
0155	Drop Inlet, Type 1	4030395	1.000	Ea
0160	_ Dr Structure Cover, Adj, Case 1, GCRC	4037050	6.000	Ea
0165	Underdrain, Subgrade, 6 inch	4040073	4,800.000	Ft
0170	Cold Milling HMA Surface	5010002	4,902.000	Syd
0175	HMA Surface, Rem	5010005	3,108.000	Syd
0180	Edge Trimming	5010009	4,000.000	Ft
0185	HMA Approach	5010061	590.000	Ton
0190	HMA, 3EML	5012013	2,732.000	Ton
0195	HMA, 4EML	5012025	3,319.000	Ton
0200	HMA, 5EML	5012037	2,894.000	Ton
0205	Conc Base Cse, Nonreinf, 8 inch	6020019	3,415.000	Syd
0210	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	1,257.000	Syd
0215	Lane Tie, Epoxy Anchored	6030030	5,000.000	Ea
0220	_ Driveway, Nonreinf Conc, 5 inch, Modified	8017011	68.000	Syd
0225	_ Driveway, Nonreinf Conc, 8 inch, Modified	8017011	346.000	Syd
0230	Curb and Gutter, Conc, Det B1	8020015	423.000	Ft
0235	Curb and Gutter, Conc, Det B2	8020016	1,880.000	Ft
0240	Curb and Gutter, Conc, Det F3	8020037	3,959.000	Ft
0245	Curb and Gutter, Conc, Det F4	8020038	3,580.000	Ft
0250	Driveway Opening, Conc, Det M	8020050	511.000	Ft
0255	Shld Gutter, Conc, Det 2	8020056	1.000	Ea
0260	Shld Gutter, Conc, Det 3	8020057	3.000	Ea
0265	Spillway, Conc	8020075	68.000	Ft
0270	_ Curb and Gutter, Conc, Det B2, Modified	8027001	384.000	Ft
0275	_ Curb and Gutter, Conc, Det F4, Modified	8027001	2,675.000	Ft
0280	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0285	Guardrail Departing Terminal, Type MGS	8070052	2.000	Ea
0290	Guardrail Reflector	8070080	14.000	Ea
0295	Post, Mailbox	8070095	16.000	Ea
0300	Guardrail, Type MGS-8, 72 inch Post	8072179	575.000	Ft
0305	_ Impact Attenuator, Test Level-3, Furn and Install, Type 2	8077050	2.000	Ea
0310	Delineator Reflector, Yellow	8100132	2.000	Ea
0315	Delineator Reflector, Green	8100133	5.000	Ea
0320	Delineator Reflector, White	8100134	17.000	Ea
0325	Delineator, Rem	8100349	14.000	Ea
0330	Post, Rigid, Delineator	8100361	24.000	Ea
0335	Post, Steel, 3 pound	8100371	672.000	Ft
0340	Post, Wood, 4 inch by 6 inch	8100380	136.000	Ft
0345	Sign, Type II, Rem	8100397	9.000	Ea
0350	Sign, Type IIA	8100398	99.000	Sft
0355	Sign, Type III, Erect, Salv	8100402	8.000	Ea

0360	Sign, Type III, Rem	8100403	36.000	Ea
0365	Sign, Type IIIA	8100404	260.000	Sft
0370	Reflective Panel for Permanent Sign Support, 3 foot	8100613	8.000	Ea
0375	Ground Mtd Sign Support, Rem	8102010	46.000	Ea
0380	_ Post Hole Through Conc for Steel Post, Modified	8107050	6.000	Ea
0385	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	187.000	Ft
0390	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	218.000	Ft
0395	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	9.000	Ea
0400	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	4.000	Ea
0405	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,655.000	Ft
0410	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	13,990.000	Ft
0415	Pavt Mrkg, Waterborne, 6 inch, White	8110233	3,340.000	Ft
0420	Pavt Mrkg, Waterborne, 12 inch, White	8110237	1,618.000	Ft
0425	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	1,655.000	Ft
0430	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	13,990.000	Ft
0435	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	3,340.000	Ft
0440	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	1,618.000	Ft
0445	Rem Spec Mrkg	8110343	236.000	Sft
0450	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	24.000	Ea
0455	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	24.000	Ea
0460	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	275.000	Ea
0465	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	275.000	Ea
0470	Lighted Arrow, Type C, Furn	8120140	6.000	Ea
0475	Lighted Arrow, Type C, Oper	8120141	6.000	Ea
0480	Minor Traf Devices	8120170	1.000	LSUM
0485	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	3,619.000	Ft
0490	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	236.000	Ft
0495	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	240.000	Ft
0500	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	17,576.000	Ft
0505	Sign Cover	8120310	4.000	Ea
0510	Sign, Type B, Temp, Prismatic, Furn	8120350	787.000	Sft
0515	Sign, Type B, Temp, Prismatic, Oper	8120351	787.000	Sft
0520	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	507.000	Sft
0525	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	507.000	Sft
0530	Riprap, Plain	8130010	12.000	Syd
0535	_ Slope Restoration, Modified	8167002	104.000	Sta
0540	Monument Box	8210001	1.000	Ea
0545	Monument Preservation	8210010	1.000	Ea
0550	_ Adj Watermain Valve Mh, Spec	8237050	1.000	Ea
0555	_ Adj Sanitary Sewer Mh, Spec	8257050	2.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 020

**Letting Date:** September 5, 2025

**Contract ID:** 38000-221961

**Description:** Horizontal curve and intersection sign upgrades on various routes, Jackson County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221961A	25A0789	N/A	HSIP 38000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$46,000.00	1100001	1.000	LSUM
0010	Post, Steel, 3 pound	8100371	27,020.000	Ft
0015	Sign, Type III, Erect, Salv	8100402	37.000	Ea
0020	Sign, Type III, Rem	8100403	475.000	Ea
0025	Sign, Type IIIA	8100404	732.000	Sft
0030	Sign, Type IIIB	8100405	7,608.000	Sft
0035	Sign, Type V, Rem	8100421	70.000	Ea
0040	Sign, Type VB	8100425	376.000	Sft
0045	Reflective Panel for Permanent Sign Support, 6 foot	8100616	1,614.000	Ea
0050	Sign, Type III, Rem, Salv	8102003	37.000	Ea
0055	Ground Mtd Sign Support, Rem	8102010	523.000	Ea
0060	Lighted Arrow, Type B, Furn	8120130	2.000	Ea
0065	Lighted Arrow, Type B, Oper	8120131	2.000	Ea
0070	Minor Traf Devices	8120170	1.000	LSUM
0075	Sign, Type B, Temp, Prismatic, Furn	8120350	200.000	Sft
0080	Sign, Type B, Temp, Prismatic, Oper	8120351	200.000	Sft



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 021

**Letting Date:** September 5, 2025

**Contract ID:** 56000-216505

**Description:** 1.66 mi of hot mix asphalt base crushing, shaping, and resurfacing, shoulder widening, intersection improvements, and permanent pavement markings on Eastman Road from Baker Road to Bombay Road, Midland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216505A	25A0783	N/A	STL 56000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$81,000.00	1100001	1.000	LSUM
0010	Embankment, LM	2050011	177.000	Cyd
0015	Erosion Control, Silt Fence	2080036	3,502.000	Ft
0020	Aggregate Base	3020001	100.000	Ton
0025	HMA Base Crushing and Shaping	3050002	31,728.000	Syd
0030	Salv Crushed Material, LM	3050015	111.000	Cyd
0035	Approach, CI II	3070021	257.000	Ton
0040	_ Trenching, Spec	3077002	176.000	Sta
0045	_ Shld, CI II, Modified	3077031	748.000	Ton
0050	Cold Milling HMA Surface	5010002	311.000	Syd
0055	HMA Approach	5010061	172.000	Ton
0060	HMA, 4EL	5012024	3,839.000	Ton
0065	HMA, 5EL	5012036	2,303.000	Ton
0070	Post, Mailbox	8070095	58.000	Ea
0075	Post, Steel, 3 pound	8100371	180.000	Ft
0080	Sign, Type III, Erect, Salv	8100402	2.000	Ea
0085	Sign, Type IIIB	8100405	48.000	Sft
0090	Sign, Type III, Rem, Salv	8102003	2.000	Ea
0095	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0100	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0105	Pavt Mrkg, Waterborne, 6 inch, White	8110233	17,510.000	Ft
0110	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	3,648.000	Ft
0115	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	17,510.000	Ft
0120	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	3,648.000	Ft
0125	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0130	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0135	Barricade, Type III, High Intensity, Double Sided,	8120013	4.000	Ea

	Lighted, Oper			
0140	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0150	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0155	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	5,000.000	Ft
0170	Sign Cover	8120310	33.000	Ea
0175	Sign, Type B, Temp, Prismatic, Furn	8120350	630.000	Sft
0180	Sign, Type B, Temp, Prismatic, Oper	8120351	630.000	Sft
0185	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0190	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft
0195	Traf Regulator Control	8120370	1.000	LSUM
0200	Slope Restoration, Non-Freeway, Type G	8162007	3,891.000	Syd
0205	Monument Box	8210001	2.000	Ea
0210	Monument Preservation	8210010	2.000	Ea
0215	Gate Box, Adj, Case 2	8230432	7.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 022

**Letting Date:** September 5, 2025

**Contract ID:** 41000-222098

**Description:** 0.15 mi of mid-block sidewalk crossing enhancements, concrete sidewalk ramps, curb and gutter island, permanent signage, and pavement markings in the city of Walker, Kent County. This is a Small Business Program project. Only those approved by MDOT as a Small Business may be eligible to bid as a prime contractor. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222098A	25A0777	N/A	TAU 41000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$31,600.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	1.000	Ea
0015	Curb and Gutter, Rem	2040020	240.000	Ft
0020	Sidewalk, Rem	2040055	290.000	Syd
0025	Embankment, CIP	2050010	40.000	Cyd
0030	Excavation, Earth	2050016	190.000	Cyd
0035	Erosion Control, Inlet Protection, Fabric Drop	2080020	4.000	Ea
0040	Subbase, CIP	3010002	150.000	Cyd
0045	_ Aggregate Base, 4 inch, 21AA, Modified	3027011	120.000	Syd
0050	_ Aggregate Base, 6 inch, 21AA, Modified	3027011	200.000	Syd
0055	_ Aggregate Base, 8 inch, 21AA, Modified	3027011	130.000	Syd
0060	Culv End Sect, Conc, 12 inch	4010047	5.000	Ea
0065	Culv, CI E, Conc, 12 inch	4010573	104.000	Ft
0070	HMA Surface, Rem	5010005	630.000	Syd
0075	Hand Patching	5010025	100.000	Ton
0080	Divider, Conc, Type I	8022000	1,385.000	Sft
0085	_ Curb and Gutter, Conc, Det F4, Modified	8027001	185.000	Ft
0090	_ Curb Ramp Opening, Conc, Modified	8027001	62.000	Ft
0095	_ Curb, Conc, Det E4, Modified	8027001	385.000	Ft
0100	Detectable Warning Surface	8030010	160.000	Ft
0105	Sidewalk, Conc, 6 inch	8030046	1,840.000	Sft
0110	Curb Ramp, Conc, 6 inch	8032002	1,810.000	Sft
0115	_ Sidewalk, Conc, 4 inch, Decorative	8037010	255.000	Sft
0120	Shared use Path, Grading	8060030	175.000	Ft
0125	Shared use Path, HMA	8060040	35.000	Ton
0130	Post Hole Through Conc for Steel Post	8100340	18.000	Ea
0135	Post, Steel, 3 pound	8100371	756.000	Ft

0140	Sign, Type III, Rem	8100403	33.000	Ea
0145	Sign, Type IIIA	8100404	15.000	Sft
0150	Sign, Type IIIB	8100405	285.000	Sft
0155	Pavt Mrkg, Waterborne, 4 inch, White	8110231	15.000	Ft
0160	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	200.000	Ft
0165	Rem Spec Mrkg	8110343	660.000	Sft
0170	_ Pavt Mrkg, Waterborne, 12 inch, Cross Hatching, Yellow	8117001	115.000	Ft
0175	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	570.000	Ft
0180	_ Pavt Mrkg, Waterborne, Bike, Large Sym	8117050	2.000	Ea
0185	_ Pavt Mrkg, Waterborne, Xing	8117050	2.000	Ea
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	6.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	6.000	Ea
0200	Pedestrian Type II Barricade, Temp	8120026	12.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	205.000	Ea
0210	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	205.000	Ea
0215	Minor Traf Devices	8120170	1.000	LSUM
0220	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	45.000	Ft
0225	Sign, Portable, Changeable Message, Furn	8120330	6.000	Ea
0230	Sign, Portable, Changeable Message, Oper	8120331	6.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	588.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	588.000	Sft
0245	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	15.000	Sft
0250	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	15.000	Sft
0255	Traf Regulator Control	8120370	1.000	LSUM
0260	_ Turf Establishment	8167011	650.000	Syd
0265	Monument Box	8210001	1.000	Ea
0270	Monument Preservation	8210010	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 023

**Letting Date:** September 5, 2025

**Contract ID:** 16000-221396

**Description:** 0.27 mi of hot mix asphalt base crush, shape and resurface, aggregate shoulders, signing and pavement markings on Straits Highway from the south village limits of Wolverine to Baird Road in the village of Wolverine, Cheboygan County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221396A	25A0804	N/A	STL 16000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$12,130.00	1100001	1.000	LSUM
0010	Erosion Control, Silt Fence	2080036	1,425.000	Ft
0015	Aggregate Base	3020001	640.000	Ton
0020	HMA Base Crushing and Shaping	3050002	3,540.000	Syd
0025	_ HMA Base Crushing and Shaping, Spec	3057011	540.000	Syd
0030	Approach, CI II, 3 inch	3070025	1,200.000	Syd
0035	Shld, CI II, 3 inch	3070125	1,900.000	Syd
0040	Pavt for Butt Joints, Rem	5010008	580.000	Syd
0045	HMA, 4EL	5012024	330.000	Ton
0050	HMA, 5EL	5012036	330.000	Ton
0055	Post, Steel, 3 pound	8100371	48.000	Ft
0060	Sign, Type III, Rem	8100403	3.000	Ea
0065	Sign, Type IIIB	8100405	26.000	Sft
0070	Reflective Panel for Permanent Sign Support, 6 foot	8100616	3.000	Ea
0075	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	2,850.000	Ft
0080	Pavt Mrkg, Waterborne, 6 inch, White	8110233	2,850.000	Ft
0085	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0090	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0095	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0100	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0105	Minor Traf Devices	8120170	1.000	LSUM
0110	Sign, Type B, Temp, Prismatic, Furn	8120350	157.000	Sft
0115	Sign, Type B, Temp, Prismatic, Oper	8120351	157.000	Sft
0120	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	12.000	Sft
0125	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	12.000	Sft
0130	Slope Restoration, Non-Freeway, Type A	8162001	200.000	Syd



8/7/2025 1:14 PM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 024

**Letting Date:** September 5, 2025

**Contract ID:** 49000-224608

**Description:** 166.90 mi of countywide pavement markings on various routes, Mackinac County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
224608A	25A0775	N/A	STL 49000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Wisconsin Central	1027060	5,000.000	Dir
0010	Mobilization, Max \$22,380.00	1100001	1.000	LSUM
0015	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	336.000	Ft
0020	Pavt Mrkg, Polyurea, Railroad Sym	8110411	9.000	Ea
0025	_ Pavt Mrkg, Regular Dry, 4 inch, White, Modified	8117001	1,762,462.000	Ft
0030	_ Pavt Mrkg, Regular Dry, 4 inch, Yellow, Modified	8117001	881,231.000	Ft
0035	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	26.000	Ea
0040	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	26.000	Ea
0045	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0050	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0055	Minor Traf Devices	8120170	1.000	LSUM
0060	Sign, Type B, Temp, Prismatic, Furn	8120350	260.000	Sft
0065	Sign, Type B, Temp, Prismatic, Oper	8120351	260.000	Sft
0070	Traf Regulator Control	8120370	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 025

**Letting Date:** September 5, 2025

**Contract ID:** 50000-218436

**Description:** 2.90 mi of hot mix asphalt shared-use path including installation of boardwalk, pedestrian signal upgrades and drainage work along Dobry Drive, a service road for M-59, from Dequindre Road to Utica Road in the city of Sterling Heights, Macomb County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218436A	25A0802	N/A	TAU 50000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Conrail	1027060	1,000.000	Dlr
0010	_ Reimbursed Permit Fees	1077060	5,000.000	Dlr
0015	Mobilization, Max \$260,000.00	1100001	1.000	LSUM
0020	Clearing	2010001	0.400	Acre
0025	Stump, Rem, 19 inch to 36 inch	2020006	3.000	Ea
0030	Stump, Rem, 6 inch to 18 inch	2020008	12.000	Ea
0035	Culv, Rem, Less than 24 inch	2030001	1.000	Ea
0040	Dr Structure, Rem	2030011	2.000	Ea
0045	Curb and Gutter, Rem	2040020	572.000	Ft
0050	Fence, Rem	2040025	215.000	Ft
0055	Pavt, Rem	2040050	764.000	Syd
0060	Sidewalk, Rem	2040055	3,872.000	Syd
0065	_ Subgrade Undercutting, Type III, Modified	2057021	200.000	Cyd
0070	Backfill, Structure, CIP	2060002	200.000	Cyd
0075	Excavation, Fdn	2060010	200.000	Cyd
0080	Erosion Control, Inlet Protection, Fabric Drop	2080020	49.000	Ea
0085	Erosion Control, Silt Fence	2080036	8,000.000	Ft
0090	_ Maintenance Gravel, Modified	3067031	100.000	Ton
0095	Culv End Sect, Metal, 12 inch	4010094	5.000	Ea
0100	Culv, CI B, CSP, 12 inch	4010301	249.000	Ft
0105	Sewer, CI IV, 12 inch, Tr Det A	4020960	14.000	Ft
0110	Dr Structure Cover, Adj, Case 2	4030006	20.000	Ea
0115	Dr Structure Cover, Type E	4030035	2.000	Ea
0120	Dr Structure, 24 inch dia	4030200	3.000	Ea
0125	Dr Structure, Adj, Add Depth	4030280	5.000	Ft
0130	_ Dr Structure Cover, Type Q, Modified	4037050	4.000	Ea
0135	Underdrain, Bank, Open-Graded, 6 inch	4040013	320.000	Ft

0140	HMA Surface, Rem	5010005	211.000	Syd
0145	Conc Pavt, Nonreinf, 8 inch	6020104	52.000	Syd
0150	Conc Pavt with Integral Curb, Nonreinf, 8 inch	6020164	994.000	Syd
0155	_ Steel Helical Pier	7057050	122.000	Ea
0160	_ Steel Helical Pier, Add 7 foot Sect	7057050	50.000	Ea
0165	_ Steel Helical Pier, Load Testing	7057050	2.000	Ea
0170	_ Helical Pier, Installation, Modified	7057051	1.000	LSUM
0175	_ Reinf Conc, Approach Sidewalk	7067050	2.000	Ea
0180	_ Pier Bent	7077050	13.000	Ea
0185	_ Railing	7097001	840.000	Ft
0190	_ Boardwalk	7097010	5,880.000	Sft
0195	Curb and Gutter, Conc, Det F3	8020037	12.000	Ft
0200	Curb and Gutter, Conc, Det F4	8020038	22.000	Ft
0205	Curb and Gutter, Conc, Det F5	8020039	44.000	Ft
0210	Driveway Opening, Conc, Det M	8020050	232.000	Ft
0215	Curb Ramp Opening, Conc	8030030	310.000	Ft
0220	Sidewalk, Conc, 4 inch	8030044	1,416.000	Sft
0225	Curb Ramp, Conc, 6 inch	8032002	3,555.000	Sft
0230	_ Detectable Warning Surface, Modified	8037001	293.000	Ft
0235	Shared use Path, Aggregate	8060010	5,196.000	Ton
0240	Shared use Path, Conc	8060020	45.000	Syd
0245	Shared use Path, Grading	8060030	12,616.000	Ft
0250	Shared use Path, HMA	8060040	2,832.000	Ton
0255	Fence, Chain Link, 48 inch, Vinyl Coated	8082001	142.000	Ft
0260	Post, Steel, 3 pound	8100371	352.000	Ft
0265	Sign, Type III, Erect, Salv	8100402	7.000	Ea
0270	Sign, Type IIIA	8100404	74.000	Sft
0275	Post, Flexible, Delineator, Ground Mtd	8100555	8.000	Ea
0280	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	340.000	Ft
0285	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	460.000	Ft
0290	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	40.000	Ft
0295	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0300	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0305	Pedestrian Type II Barricade, Temp	8120026	40.000	Ea
0310	Pedestrian Type II Channelizer, Temp	8120027	100.000	Ft
0315	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0320	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0325	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0330	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0335	Minor Traf Devices	8120170	1.000	LSUM
0340	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	340.000	Ft
0345	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	280.000	Ft
0350	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea

0355	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0360	Sign Cover	8120310	50.000	Ea
0365	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0370	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0375	Sign, Type B, Temp, Prismatic, Furn	8120350	300.000	Sft
0380	Sign, Type B, Temp, Prismatic, Oper	8120351	300.000	Sft
0385	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	83.000	Sft
0390	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	83.000	Sft
0395	Traf Regulator Control	8120370	1.000	LSUM
0400	Site Preparation, Max \$4,600.00	8150001	1.000	LSUM
0405	Watering and Cultivating, First Season, Min \$2,300.00	8150002	1.000	LSUM
0410	Watering and Cultivating, 2nd Season, Min \$2,800.00	8150003	1.000	LSUM
0415	Malus 'Donald Wyman', 2 inch	8152303	3.000	Ea
0420	Malus 'Prairie Fire', 2 inch	8152315	14.000	Ea
0425	Malus 'Spring Snow', 2 inch	8152333	12.000	Ea
0430	_ Bench, 6 foot	8157050	7.000	Ea
0435	_ Trash Receptacle	8157050	7.000	Ea
0440	Fertilizer, Chemical Nutrient, CI A	8160020	342.000	Lb
0445	Mulch	8160025	7,325.000	Syd
0450	Seeding, Mixture TUF	8160042	326.000	Lb
0455	Sodding	8160055	1,696.000	Syd
0460	Topsoil Surface, Furn, 3 inch	8160061	7,325.000	Syd
0465	Water, Sodding/Seeding	8160090	159.000	Unit
0470	Slope Restoration, Non-Freeway, Type A	8162001	16,671.000	Syd
0475	_ Maintaining Water Sprinkler System	8167050	6.000	Ea
0480	Conduit, DB, 1, 1/2 inch	8182046	10.000	Ft
0485	Conduit, DB, 1, 2 1/2 inch	8182049	10.000	Ft
0490	Conduit, DB, 1, 3 inch	8182050	80.000	Ft
0495	Hh, Round	8182310	2.000	Ea
0500	Pedestal, Alum	8200100	2.000	Ea
0505	Pedestal, Fdn	8200105	3.000	Ea
0510	Pedestal Fdn, Rem	8200106	3.000	Ea
0515	Pedestal, Rem	8200110	1.000	Ea
0520	Pedestal, Pushbutton, Alum	8200118	1.000	Ea
0525	Pedestal, Pushbutton, Rem	8200119	2.000	Ea
0530	Pushbutton and Sign, Salv	8200126	4.000	Ea
0535	TS, Pedestal Mtd, Rem	8200179	1.000	Ea
0540	TS, Pedestrian, Pedestal Mtd, Rem	8200181	3.000	Ea
0545	TS, One Way Pedestal Mtd (LED)	8200340	1.000	Ea
0550	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	1.000	Ea
0555	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	2.000	Ea
0560	Hydrant, Relocate, Case 2	8230096	1.000	Ea
0565	_ Audio Visual Filming	8507051	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 026

**Letting Date:** September 5, 2025

**Contract ID:** 21024-219522

**Description:** 19.28 mi of hot mix asphalt micro-cold milling, shallow hot mix asphalt repairs, paver placed surface seal, shoulder aggregate, centerline and shoulder corrugations and pavement markings on US-2 from the east end of Rapid River to the east end of Isabella passing relief lanes, Delta County. This project includes a 3 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219522A	25A0873	N/A	NH 21024

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$488,000.00	1100001	1.000	LSUM
0010	Berm Grading	2050008	33.000	Sta
0015	Shld, CI II, LM	3070123	2,000.000	Cyd
0020	Cold Milling HMA Surface	5010002	1,115.000	Syd
0025	Hand Patching	5010025	122.000	Ton
0030	Micro Texture Pavt Milling	5010101	385,565.000	Syd
0035	Overband Crack Fill, Lane	5020003	47.590	Lnmi
0040	Paver Placed Surface Seal, Type C, Warranty	5030041	540,391.000	Syd
0045	Pavt Mrkg, Polyurea, Merge Arrow Sym	8110107	8.000	Ea
0050	Pavt Mrkg, Waterborne, 6 inch, White	8110233	213,370.000	Ft
0055	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	75,923.000	Ft
0060	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	202,892.000	Ft
0065	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	75,923.000	Ft
0070	Rem Spec Mrkg	8110343	500.000	Sft
0075	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0080	Pavt Mrkg, Polyurea, School	8110414	2.000	Ea
0085	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	10,478.000	Ft
0090	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0095	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0100	Minor Traf Devices	8120170	1.000	LSUM
0105	Plastic Drum, Fluorescent, Furn	8120252	350.000	Ea
0110	Plastic Drum, Fluorescent, Oper	8120253	350.000	Ea
0115	Sign Cover	8120310	25.000	Ea
0120	Sign, Type B, Temp, Prismatic, Furn	8120350	1,575.000	Sft
0125	Sign, Type B, Temp, Prismatic, Oper	8120351	1,575.000	Sft
0130	Traf Regulator Control	8120370	1.000	LSUM

0135	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	3,500.000	Ft
0140	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	10,750.000	Ft
0145	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	3,500.000	Ft
0150	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	8,750.000	Ft
0155	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0160	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0165	Monument Box	8210001	3.000	Ea
0170	Monument Box, Adj	8210005	59.000	Ea
0175	Monument Preservation	8210010	3.000	Ea
0180	Centerline Corrugations, Milled, HMA	8220013	95,843.000	Ft
0185	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	181,888.000	Ft

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 027

**Letting Date:** September 5, 2025

**Contract ID:** 54014-217245

**Description:** 7.35 mi of hot mix asphalt micro-cold milling and overlay with fibermat Type B, guardrail and pavement markings on US-131 from north of 6 Mile Road northerly to south of 13 Mile Road, Mecosta County. This project includes a 3 year materials and workmanship pavement warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217245A	25A0881	N/A	NH 54014

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$292,900.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	1.000	Ea
0015	Erosion Control, Inlet Protection, Geotextile and Stone	2080022	8.000	Ea
0020	Shld, CI II	3070121	3,083.000	Ton
0025	Cold Milling HMA Surface	5010002	2,108.000	Syd
0030	HMA Quality Initiative	5010007	32,374.000	Dlr
0035	Pavt for Butt Joints, Rem	5010008	6,956.000	Syd
0040	Longit Joint Density Quality Initiative	5010018	93,265.000	Dlr
0045	HMA Approach	5010061	126.000	Ton
0050	Micro Texture Pavt Milling	5010101	96,832.000	Syd
0055	HMA, 5EMH	5012038	16,061.000	Ton
0060	Overband Crack Fill, Lane	5020003	16.000	Lnmi
0065	_ Fiber Reinf Bituminous Membrane, Type B	5047011	96,832.000	Syd
0070	Guardrail Height, Adj	8070100	1,313.000	Ft
0075	Guardrail, Reconst, Type T	8070109	2,363.000	Ft
0080	Pavt Mrkg, Polyurea, Wrong Way Arrow Sym	8110098	1.000	Ea
0085	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	43.000	Ft
0090	Pavt Mrkg, Waterborne, 6 inch, White	8110233	52,768.000	Ft
0095	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	42,484.000	Ft
0100	Pavt Mrkg, Waterborne, 12 inch, White	8110237	4,286.000	Ft
0105	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	52,768.000	Ft
0110	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	42,484.000	Ft
0115	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	4,286.000	Ft
0120	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0125	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea
0130	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	2.000	Ea
0135	Recessing Pavt Mrkg, Transv	8110451	203.000	Sft

0140	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	249.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	249.000	Ea
0150	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0155	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Pavt Mrkg Cover, Type R, Black	8120200	500.000	Ft
0170	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	70,882.000	Ft
0175	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	2,133.000	Ft
0180	Plastic Drum, Fluorescent, Furn	8120252	10.000	Ea
0185	Plastic Drum, Fluorescent, Oper	8120253	10.000	Ea
0190	Sign Cover	8120310	6.000	Ea
0195	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0200	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0205	Sign, Type A, Temp, Prismatic, Furn	8120340	14.000	Sft
0210	Sign, Type A, Temp, Prismatic, Oper	8120341	14.000	Sft
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	860.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	860.000	Sft
0225	Traf Regulator Control	8120370	1.000	LSUM
0230	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	900.000	Ft
0235	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	900.000	Ft
0240	Speed Radar Trailer, Temp	8122028	1.000	Ea
0245	Freeway Shld Corrugations, Milled, HMA	8222001	76,359.000	Ft



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 028

**Letting Date:** September 5, 2025

**Contract ID:** 77051-217673

**Description:** 6.49 mi of a single course hot mix asphalt overlay with selective cold milling, concrete sidewalk ramp replacements and pavement markings on M-29 from east of Palms Road to the west city limits of Algona, St. Clair County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217673A	N/A	N/A	M 77051

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$209,700.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	130.000	Ft
0015	Pavt, Rem	2040050	30.000	Syd
0020	Sidewalk, Rem	2040055	60.000	Syd
0025	Excavation, Earth	2050016	115.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	18.000	Ea
0035	Subbase, CIP	3010002	50.000	Cyd
0040	Aggregate Base	3020001	70.000	Ton
0045	_ Shld, CI II, Modified	3077031	500.000	Ton
0050	Dr Structure Cover, Adj, Case 1, Modified	4030004	12.000	Ea
0055	Cold Milling HMA Surface	5010002	19,800.000	Syd
0060	Bump Grinding	5010004	350.000	Syd
0065	HMA Surface, Rem	5010005	30.000	Syd
0070	HMA Quality Initiative	5010007	31,220.000	Dlr
0075	Pavt for Butt Joints, Rem	5010008	6,480.000	Syd
0080	Longit Joint Density Quality Initiative	5010018	155,977.000	Dlr
0085	Hand Patching	5010025	60.000	Ton
0090	HMA, 5EL	5012036	14,600.000	Ton
0095	HMA, 5EL, High Stress	5012084	1,000.000	Ton
0100	Curb and Gutter, Conc, Det D2	8020031	162.000	Ft
0105	Curb and Gutter, Conc, Det F2	8020036	15.000	Ft
0110	Detectable Warning Surface	8030010	27.000	Ft
0115	Curb Ramp Opening, Conc	8030030	27.000	Ft
0120	Curb Ramp, Conc, 6 inch	8032002	400.000	Sft
0125	Sign, Type I, Erect, Salv	8100390	1.000	Ea
0130	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	4.000	Ea
0135	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	4.000	Ea

0140	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0145	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	214.000	Ft
0150	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	98.000	Ft
0155	Pavt Mrkg, Waterborne, 6 inch, White	8110233	69,800.000	Ft
0160	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	31,700.000	Ft
0165	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	69,800.000	Ft
0170	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	31,700.000	Ft
0175	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0180	Recessing Pavt Mrkg, Longit	8110450	101,500.000	Ft
0185	Recessing Pavt Mrkg, Transv	8110451	724.000	Sft
0190	Pedestrian Type II Barricade, Temp	8120026	15.000	Ea
0195	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0205	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0210	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0215	Minor Traf Devices	8120170	1.000	LSUM
0220	Plastic Drum, Fluorescent, Furn	8120252	40.000	Ea
0225	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0230	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	450.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	450.000	Sft
0245	Traf Regulator Control	8120370	1.000	LSUM
0250	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	1,300.000	Ft
0255	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	3,900.000	Ft
0260	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0265	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0270	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0275	Slope Restoration, Non-Freeway, Type B	8162002	72.000	Syd
0280	Monument Box	8210001	4.000	Ea
0285	Monument Preservation	8210010	4.000	Ea
0290	Centerline Corrugations, Milled, HMA	8220013	5,900.000	Ft
0295	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	66,200.000	Ft
0300	Contractor Staking	8240001	1.000	LSUM
0305	Staking Plan Errors and Extras, Max \$180/hour	8240002	24.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 029

**Letting Date:** September 5, 2025

**Contract ID:** 81103-209147

**Description:** 13.50 mi of installation of Intelligent Transportation System (ITS) including queue detection and warning control devices on M-14 and US-23 from Plymouth Road northerly to M-14, along M-14 then onto the Washtenaw/Wayne County line in the city of Ann Arbor, Washtenaw County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
209147A	25A0858	N/A	NHFP 81103

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$208,200.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.300	Acre
0015	Guardrail, Rem	2040035	113.000	Ft
0020	Exploratory Investigation, Vertical	2040080	130.000	Ft
0025	Embankment, CIP	2050010	55.000	Cyd
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	100.000	Cyd
0035	Erosion Control, Silt Fence	2080036	4,380.000	Ft
0040	Culv, CI E, 18 inch	4010541	40.000	Ft
0045	Culv, Slp End Sect, 1 on 4, 18 inch, Longit	4010919	2.000	Ea
0050	Dr Marker Post	4011109	2.000	Ea
0055	_ Antenna Support, Install on Dynamic Message Sign	8007050	1.000	Ea
0060	_ Cabinet Equipment, Cabinet Monitoring System, Rem	8007050	1.000	Ea
0065	_ Cabinet Equipment, Power Distribution Unit, Rem	8007050	1.000	Ea
0070	_ Cable Modem, Integrate	8007050	1.000	Ea
0075	_ Cellular Modem, 4G	8007050	7.000	Ea
0080	_ Cellular Modem, Rem and Salv	8007050	1.000	Ea
0085	_ Digital Video Encoder, Rem	8007050	4.000	Ea
0090	_ Dynamic Message Sign Controller, Rem	8007050	1.000	Ea
0095	_ Dynamic Message Sign, Full Color, 20 mm, 96 by 400	8007050	1.000	Ea
0100	_ Dynamic Message Sign, Large, Rem	8007050	1.000	Ea
0105	_ Dynamic Message Sign, Roadside, Full Color, 8 mm, 160 by 160	8007050	7.000	Ea
0110	_ Field Security Appliance	8007050	1.000	Ea
0115	_ Power Distribution Unit	8007050	9.000	Ea
0120	_ Surveillance System, Remote Site, Type A, Rem	8007050	2.000	Ea
0125	_ Surveillance System, Remote Site, Type B, Rem	8007050	1.000	Ea

0130	_ Wireless Link, 5.8 gigahertz, Access Point	8007050	1.000	Ea
0135	_ Wireless Link, 5.8 gigahertz, Subscriber Unit	8007050	1.000	Ea
0140	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
0145	_ Cable Internet Company (Estimated Cost to Contractor)	8007060	150.000	Dlr
0150	Guardrail Approach Terminal, Type 2M	8070044	6.000	Ea
0155	Guardrail Departing Terminal, Type MGS	8070052	5.000	Ea
0160	Guardrail Reflector	8070080	46.000	Ea
0165	Guardrail, Type MGS-8, 108 inch Post	8072180	1,812.000	Ft
0170	Delineator Reflector, Green	8100133	11.000	Ea
0175	Fdn, Wood Support, Rem	8100280	4.000	Ea
0180	Post, Rigid, Delineator	8100361	11.000	Ea
0185	Post, Steel, 3 pound	8100371	34.000	Ft
0190	Post, Wood, 6 inch by 8 inch	8100382	252.000	Ft
0195	Sign, Type III, Erect, Salv	8100402	2.000	Ea
0200	Sign, Type III, Rem, Salv	8102003	2.000	Ea
0205	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0210	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0220	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0225	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0230	Minor Traf Devices	8120170	1.000	LSUM
0235	Mobile Attenuator	8120180	1.000	Ea
0240	Plastic Drum, Fluorescent, Furn	8120252	600.000	Ea
0245	Plastic Drum, Fluorescent, Oper	8120253	600.000	Ea
0250	Sign Cover	8120310	20.000	Ea
0255	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0260	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0265	Sign, Type B, Temp, Prismatic, Furn	8120350	2,000.000	Sft
0270	Sign, Type B, Temp, Prismatic, Oper	8120351	2,000.000	Sft
0275	Riprap, Plain	8130010	10.000	Syd
0280	Slope Restoration, Freeway, Type A	8162013	250.000	Syd
0285	Slope Restoration, Freeway, Type F	8162018	845.000	Syd
0290	Slope Restoration, Freeway, Type G	8162019	70.000	Syd
0295	Power Company (Estimated Cost to Contractor)	8180001	41,211.000	Dlr
0300	Conduit, Rem	8182000	85.000	Ft
0305	Conduit, Directional Bore, 1, 1 1/2 inch	8182034	510.000	Ft
0310	Conduit, Directional Bore, 1, 3 inch	8182035	1,635.000	Ft
0315	Conduit, Directional Bore, 2, 3 inch	8182037	1,185.000	Ft
0320	Conduit, DB, 1, 1 1/2 inch	8182048	625.000	Ft
0325	Conduit, DB, 1, 3 inch	8182050	1,710.000	Ft
0330	Conduit, DB, 2, 3 inch	8182053	585.000	Ft

0335	Conduit, DB, 4, 3 inch	8182059	100.000	Ft
0340	Conduit, DB, 1, 1 inch	8182060	20.000	Ft
0345	DB Cable, in Conduit, 600V, 1/C#2	8182182	5,205.000	Ft
0350	DB Cable, in Conduit, 600V, 1/C#6	8182187	2,310.000	Ft
0355	DB Cable, in Conduit, Rem	8182197	270.000	Ft
0360	Cable, Equipment Grounding Wire, 1/C#1	8182287	990.000	Ft
0365	Cable, Equipment Grounding Wire, 1/C#2	8182288	1,735.000	Ft
0370	Cable, Equipment Grounding Wire, 1/C#6	8182291	695.000	Ft
0375	Hh, Polymer Conc	8182309	2.000	Ea
0380	Hh, Round, 3 foot dia	8182319	11.000	Ea
0385	Hh, Rem	8182330	1.000	Ea
0390	_ Conduit, DB, 1, 2 inch	8187001	375.000	Ft
0395	_ Conduit, DB, 2, 1 1/2 inch	8187001	190.000	Ft
0400	_ Conduit, Directional Bore, 1, 2 inch	8187001	565.000	Ft
0405	_ Conduit, Directional Bore, 2, 1 1/2 inch	8187001	310.000	Ft
0410	_ DB Cable, in Conduit, 600V, 1/C#1	8187001	2,970.000	Ft
0415	_ DB Cable, in Conduit, 600V, 1/C#12	8187001	3,135.000	Ft
0420	_ Hh, Round, Commun	8187050	4.000	Ea
0425	_ Hh, Round, Elec	8187050	33.000	Ea
0430	Light Std Fdn	8190279	7.000	Ea
0435	Light Std, Frangible Transformer Base	8190281	7.000	Ea
0440	Light Std Shaft, 30 foot or less	8190285	7.000	Ea
0445	Cabinet, Rem	8200184	1.000	Ea
0450	Warning Sign, Rem	8200261	2.000	Ea
0455	Strain Pole, Steel, 6 bolt, Size 3	8200467	1.000	Ea
0460	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	12.000	Ft
0465	Casing, 48 inch	8200486	8.000	Ft
0470	Contractor Staking	8240001	1.000	LSUM
0475	Staking Plan Errors and Extras, Max \$180/hour	8240002	23.000	Hr
0480	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0485	Lightning Protection, Pole	8260021	8.000	Ea
0490	Lightning Protection, Structure, Large Dynamic Message Sign	8260022	1.000	Ea
0495	Hh, Clean	8260030	3.000	Ea
0500	Conduit, Clean and Test	8260031	255.000	Ft
0505	Microwave Vehicle Detection System	8260040	8.000	Ea
0510	Fiber Optic, Cable, Single Mode Fiber, 12 Strand	8260047	740.000	Ft
0515	Fiber Optic, Hardware Assembly, Small	8260065	2.000	Ea
0520	Tracer Wire	8260070	740.000	Ft
0525	Fiber Optic, Pigtail	8260071	4.000	Ea
0530	Fiber Optic, Jumper	8260072	4.000	Ea
0535	Managed Field Ethernet Switch, Layer 2	8260080	9.000	Ea
0540	Managed Field Ethernet Switch, Rem	8260087	1.000	Ea
0545	Power Serv, Underground, 30AMP, 120/240V	8260100	8.000	Ea
0550	Safety Switch, Non-Fusible	8260108	2.000	Ea

---

0555	Elec Rack	8260110	2.000	Ea
0560	Power Serv, Refurbish, 30AMP, 120/240V	8260111	1.000	Ea
0565	Power Serv, Refurbish, 60AMP, 120/240V	8260112	1.000	Ea
0570	ITS Cabinet, Ground Mtd	8260130	9.000	Ea
0575	Cabinet Modification	8260138	2.000	Ea
0580	Uninterruptible Power Supply, Rem	8260146	1.000	Ea
0585	Surveillance System, Remote Site, Type A	8260157	4.000	Ea
0590	Surveillance System, Remote Site, Type B	8260158	1.000	Ea
0595	System Integration and Testing	8260160	1.000	LSUM
0600	Camera Lowering Device	8260161	4.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 030

**Letting Date:** September 5, 2025

**Contract ID:** 25073-217116

**Description:** 0.07 mi of culvert replacement including hot mix asphalt reconstruction, drainage, guardrail and pavement markings on M-54 over the Blackmore and Alpine Drain, Genesee County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217116A	N/A	N/A	M 25073

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Critical Path Method Schedule	1080005	15,000.000	Dir
0010	Mobilization, Max \$221,200.00	1100001	1.000	LSUM
0015	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0020	Dr Structure, Rem	2030011	1.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	107.000	Ft
0030	Guardrail, Rem	2040035	154.000	Ft
0035	Pavt, Rem	2040050	2,325.000	Syd
0040	Exploratory Investigation, Vertical	2040080	70.000	Ft
0045	Excavation, Earth	2050016	1,763.000	Cyd
0050	Non Haz Contaminated Material Handling and Disposal, LM	2050031	271.000	Cyd
0055	_ Embankment, CIP, Spec	2057021	575.000	Cyd
0060	Erosion Control, Check Dam, Stone	2080012	24.000	Ft
0065	Erosion Control, Filter Bag	2080014	4.000	Ea
0070	Erosion Control, Gravel Filter Berm	2080018	180.000	Ft
0075	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0080	Erosion Control, Inlet Protection, Sediment Trap	2080024	1.000	Ea
0085	Erosion Control, Maintenance, Sediment Rem	2080026	37.000	Cyd
0090	Erosion Control, Sediment Basin	2080032	5.000	Cyd
0095	Erosion Control, Silt Fence	2080036	1,223.000	Ft
0100	Erosion Control, Stone Bag	2080038	120.000	Ea
0105	Erosion Control, Temp Plastic Sheet/Geotextile Cover	2080040	200.000	Syd
0110	Erosion Control, Turbidity Curtain, Shallow	2080044	85.000	Ft
0115	Subbase, CIP	3010002	1,662.000	Cyd
0120	Aggregate Base, 6 inch	3020016	2,557.000	Syd
0125	Approach, CI II	3070021	129.000	Ton
0130	Shld, CI II, 6 inch, Temp	3070183	156.000	Syd
0135	_ Shld, CI II, Modified	3077031	154.000	Ton

0140	Road Grade Biaxial Geogrid	3082002	2,506.000	Syd
0145	Culv End Sect, 18 inch	4010018	1.000	Ea
0150	Culv End Sect, 24 inch	4010024	1.000	Ea
0155	Culv End Sect, Footing	4010072	2.000	Ea
0160	Dr Marker Post	4011109	2.000	Ea
0165	_ Wireless Water Level Monitoring System	4017050	1.000	Ea
0170	Sewer, Cl A, 12 inch, Tr Det B	4020033	23.000	Ft
0175	Sewer, Cl A, 18 inch, Tr Det B	4020035	179.000	Ft
0180	Sewer, Cl A, 24 inch, Tr Det B	4020036	19.000	Ft
0185	Sewer Tap, 10 inch	4021203	1.000	Ea
0190	Sewer Tap, 18 inch	4021206	1.000	Ea
0195	Sewer Tap, 24 inch	4021207	1.000	Ea
0200	Video Taping Sewer and Culv Pipe	4021275	221.000	Ft
0205	Dr Structure Cover, Type B	4030010	1.000	Ea
0210	Dr Structure Cover, Type E	4030035	1.000	Ea
0215	Dr Structure, 24 inch dia	4030200	1.000	Ea
0220	Dr Structure, 48 inch dia	4030210	3.000	Ea
0225	Dr Structure, 60 inch dia	4030220	1.000	Ea
0230	_ Dr Structure Cover, Type B, Modified	4037050	1.000	Ea
0235	Underdrain, Subbase, 6 inch	4040063	223.000	Ft
0240	Video Inspection of Underdrain	4040200	541.000	Ft
0245	HMA Surface, Rem	5010005	2,496.000	Syd
0250	HMA Quality Initiative	5010007	1,386.000	Dlr
0255	Longit Joint Density Quality Initiative	5010018	1,924.000	Dlr
0260	HMA Approach	5010061	693.000	Ton
0265	HMA, Temp Pavt (3EML)	5012101	28.000	Ton
0270	HMA, Temp Pavt (5EL)	5012104	14.000	Ton
0275	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	395.000	Syd
0280	Joint, Contraction, Cp	6020200	207.000	Ft
0285	_ Conc Slab, Reinf, 9 inch	6027011	20.000	Syd
0290	Curb and Gutter, Conc, Det D2	8020031	230.000	Ft
0295	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0300	Guardrail Departing Terminal, Type B	8070050	3.000	Ea
0305	Guardrail Reflector	8070080	26.000	Ea
0310	Post, Mailbox	8070095	2.000	Ea
0315	Guardrail, Curved, Type B-CRT	8072154	76.000	Ft
0320	Guardrail, Type B, 72 inch Post	8072171	100.000	Ft
0325	Guardrail, Type B, 96 inch Post	8072172	13.000	Ft
0330	Guardrail, Type MGS-8, 72 inch Post	8072179	210.000	Ft
0335	_ Guardrail Post, Slab, Adhesive Anchored	8077050	5.000	Ea
0340	_ Hand Digging Guardrail Post	8077050	1.000	Ea
0345	Delineator Reflector, Green	8100133	4.000	Ea
0350	Fdn, Wood Support, Rem	8100280	1.000	Ea
0355	Post, Rigid, Delineator	8100361	4.000	Ea
0360	Post, Wood, 4 inch by 6 inch	8100380	18.000	Ft

0365	Sign, Type III, Rem	8100403	7.000	Ea
0370	Sign, Type IIIA	8100404	9.000	Sft
0375	Sign, Type IIIB	8100405	10.000	Sft
0380	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0385	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	60.000	Ft
0390	Pavt Mrkg, Waterborne, 6 inch, White	8110233	804.000	Ft
0395	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	566.000	Ft
0400	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	804.000	Ft
0405	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	566.000	Ft
0410	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	29.000	Ea
0415	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	29.000	Ea
0420	Conc Barrier Ending, Temp, Det 2, Adj	8120040	2.000	Ea
0425	Conc Barrier Ending, Temp, Det 2, Furn	8120041	4.000	Ea
0430	Conc Barrier Ending, Temp, Det 2, Oper	8120042	4.000	Ea
0435	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	4.000	Ea
0440	Conc Barrier, Temp, Limited Deflection, Reflector Replacement	8120086	9.000	Ea
0445	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0450	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0455	Minor Traf Devices	8120170	1.000	LSUM
0460	Mobile Attenuator	8120180	1.000	Ea
0465	Pavt Mrkg Cover, Type R, Black	8120200	3,812.000	Ft
0470	Plastic Drum, Fluorescent, Furn	8120252	152.000	Ea
0475	Plastic Drum, Fluorescent, Oper	8120253	152.000	Ea
0480	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	40.000	Ft
0485	Sign Cover	8120310	5.000	Ea
0490	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0495	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0500	Sign, Type B, Temp, Prismatic, Furn	8120350	1,043.000	Sft
0505	Sign, Type B, Temp, Prismatic, Oper	8120351	1,043.000	Sft
0510	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	78.000	Sft
0515	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	78.000	Sft
0520	Traf Regulator Control	8120370	1.000	LSUM
0525	Conc Barrier, Temp, Limited Deflection, Det 2, Furn	8121100	858.000	Ft
0530	Conc Barrier, Temp, Limited Deflection, Det 2, Oper	8121101	858.000	Ft
0535	Conc Barrier, Temp, Limited Deflection, Det 2, Relocated	8121103	858.000	Ft
0540	Conc Barrier, Temp, Limited Deflection, Det 4A, Furn	8121300	278.000	Ft
0545	Conc Barrier, Temp, Limited Deflection, Det 4A, Oper	8121301	278.000	Ft
0550	Conc Barrier, Temp, Limited Deflection, Det 4A, Adj	8121302	258.000	Ft
0555	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	8,120.000	Ft
0560	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch,	8122002	7,760.000	Ft

	Yellow, Temp			
0565	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0570	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0575	_ Turf Establishment, Performance	8167011	1,756.000	Syd
0580	Contractor Staking	8240001	1.000	LSUM
0585	Staking Plan Errors and Extras, Max \$180/hour	8240002	23.000	Hr

**Section: 2**

0590	Structures, Rem (C03 of 25073)	2040060	1.000	LSUM
0595	Backfill, Structure, CIP	2060002	1,224.000	Cyd
0600	Excavation, Fdn	2060010	2,080.000	Cyd
0605	_ Liner, PVC, 30 mil, Spec	2087011	530.000	Syd
0610	Underdrain, Fdn, 6 inch	4040033	264.000	Ft
0615	Underdrain Outlet, 6 inch	4040093	54.000	Ft
0620	Underdrain, Outlet Ending, 6 inch	4040113	5.000	Ea
0625	Culv Bedding, Box Culv	4060005	212.000	Cyd
0630	Culv, Precast Conc Box, 12 foot by 8 foot	4060149	132.000	Ft
0635	_ Steel Sheet Piling, Temp, Left in Place, Spec	7047010	2,111.000	Sft
0640	_ Construction Dam	7047050	1.000	Ea
0645	_ Dewatering and Maintaining Stream Flow	7047050	1.000	Ea
0650	_ Cofferdam, Left In Place, Spec (C03 of 25073)	7047051	1.000	LSUM
0655	Water Repellent Treatment, Penetrating	7060140	24.000	Syd
0660	_ Geotextile Retaining Wall	8007011	3.000	Syd
0665	Riprap, Plain	8130010	324.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 031

**Letting Date:** September 5, 2025

**Contract ID:** 48032-221787

**Description:** 3.67 mi of paver placed surface seal, hot mix asphalt overlay, cold milling, overband crack seal, aggregate shoulder, guardrail, signage, detectable warning surfaces and pavement markings on M-123 from M-28 northerly to the railroad crossing in the village of Newberry, Luce County. This project includes a 3 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221787A	25A0892	N/A	ST 48032

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Grand Elk Railroad	1027060	10,000.000	Dlr
0010	Mobilization, Max \$126,400.00	1100001	1.000	LSUM
0015	Guardrail, Rem	2040035	3,917.000	Ft
0020	Sidewalk, Rem	2040055	5.000	Syd
0025	Embankment, CIP	2050010	50.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	72.000	Ea
0035	Shld, CI II	3070121	520.000	Ton
0040	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0045	Cold Milling HMA Surface	5010002	31,230.000	Syd
0050	Bump Grinding	5010004	100.000	Syd
0055	HMA Quality Initiative	5010007	3,900.000	Dlr
0060	Pavt for Butt Joints, Rem	5010008	1,990.000	Syd
0065	Longit Joint Density Quality Initiative	5010018	11,298.000	Dlr
0070	HMA Approach	5010061	100.000	Ton
0075	HMA, 5EL	5012036	1,850.000	Ton
0080	Overband Crack Fill, Lane	5020003	7.140	Lnmi
0085	Paver Placed Surface Seal, Type C, Warranty	5030041	76,377.000	Syd
0090	Seal, Fog	5050015	5,220.000	Syd
0095	Detectable Warning Surface	8030010	337.000	Ft
0100	_ Curb Ramp, Conc, 6 inch, Decorative	8037010	20.000	Sft
0105	Guardrail Approach Terminal, Type 2M	8070044	10.000	Ea
0110	Guardrail Departing Terminal, Type B	8070050	4.000	Ea
0115	Guardrail, Curved, Type B-CRT	8072154	125.000	Ft
0120	Guardrail, Type MGS-8, 108 inch Post	8072180	3,588.000	Ft
0125	Band, Sign	8100010	6.000	Ea
0130	Post, Steel, 3 pound	8100371	17.000	Ft

0135	Sign, Type IIIB	8100405	23.000	Sft
0140	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	600.000	Ft
0145	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	36.000	Ft
0150	Pavt Mrkg, Waterborne, 6 inch, White	8110233	38,676.000	Ft
0155	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	29,150.000	Ft
0160	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	38,676.000	Ft
0165	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	29,150.000	Ft
0170	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0175	Pavt Mrkg, Polyurea, Railroad Sym	8110411	1.000	Ea
0180	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	1.000	Ea
0185	Pavt Mrkg, Polyurea, School	8110414	2.000	Ea
0190	Protective Ovly, Snowmobile Trail Crossing	8110550	110.000	Syd
0195	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0200	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0205	Minor Traf Devices	8120170	1.000	LSUM
0210	Plastic Drum, Fluorescent, Furn	8120252	165.000	Ea
0215	Plastic Drum, Fluorescent, Oper	8120253	165.000	Ea
0220	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	24.000	Ft
0225	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	1,901.000	Ea
0230	Sign Cover	8120310	6.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	603.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	603.000	Sft
0245	Traf Regulator Control	8120370	1.000	LSUM
0250	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	592.000	Ft
0255	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	592.000	Ft
0260	Rumble Strip, Temp, Portable, Furn	8122188	18.000	Ea
0265	Rumble Strip, Temp, Portable, Oper	8122189	18.000	Ea
0270	Slope Restoration, Non-Freeway, Type B	8162002	100.000	Syd
0275	Monument Box	8210001	1.000	Ea
0280	Monument Box, Adj	8210005	12.000	Ea
0285	Monument Preservation	8210010	1.000	Ea
0290	Centerline Corrugations, Milled, HMA	8220013	7,832.000	Ft
0295	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	15,604.000	Ft
0300	Gate Box, Adj, Case 1	8230431	5.000	Ea
0305	Contractor Staking	8240001	1.000	LSUM
0310	Staking Plan Errors and Extras, Max \$180/hour	8240002	14.000	Hr



8/14/2025 12:40 PM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 032

**Letting Date:** September 5, 2025

**Contract ID:** 14000-222065

**Description:** 4.36 mi of tree removal and clearing on Rudy Road from the city limits of Dowagiac northerly to Dewey Lake Street, Cass County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222065A	25A0828	N/A	HSIP 14000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$35,700.00	1100001	1.000	LSUM
0010	_ Clearing, Modified	2017012	9.270	Acre
0015	Tree, Rem, 19 inch to 36 inch	2020002	20.000	Ea
0020	Tree, Rem, 37 inch or Larger	2020003	4.000	Ea
0025	Tree, Rem, 6 inch to 18 inch	2020004	16.000	Ea
0030	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0035	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0040	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0045	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Sign, Type B, Temp, Prismatic, Furn	8120350	128.000	Sft
0060	Sign, Type B, Temp, Prismatic, Oper	8120351	128.000	Sft
0065	Traf Regulator Control	8120370	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 033

**Letting Date:** September 5, 2025

**Contract ID:** 41000-220124

**Description:** Overhead rapid flashing beacons, curb extensions, pedestrian crossing beacons and pavement markings on various routes in the city of Grand Rapids, Kent County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220124A	25A0808	N/A	VRU 41000
220136A	25A0823	N/A	VRU 41000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$112,200.00	1100001	1.000	LSUM
0010	Tree, Rem, 6 inch to 18 inch	2020004	4.000	Ea
0015	_ Abandon and Fill Underground Utility, 12 inch Dia.	2037001	17.000	Ft
0020	_ Mh, Valve Chamber, or Catch Basin, Remove	2037050	1.000	Ea
0025	_ Conc Curb and Gutter, Rem	2047001	701.000	Ft
0030	_ Conc Sidewalk, Driveway and Approach, Rem	2047010	3,408.000	Sft
0035	_ Pavt, Rem, Full Depth	2047011	364.000	Syd
0040	Non Haz Contaminated Material Handling and Disposal, LM	2050031	30.000	Cyd
0045	_ Stormwater Operator's Inspection	2087050	2.000	Ea
0050	_ Soil Erosion and Sedimentation Control	2087051	1.000	LSUM
0055	_ Soil Erosion and Sedimentation Control Plan	2087051	1.000	LSUM
0060	Aggregate Base, 6 inch	3020016	497.000	Syd
0065	Sewer Tap, 12 inch	4021204	1.000	Ea
0070	_ Storm Sewer, C76 Cl III, 12 inch	4027001	10.000	Ft
0075	Dr Structure Cover, Adj, Case 1	4030005	3.000	Ea
0080	_ Catch basin casting, Furnish	4037050	1.000	Ea
0085	_ Catch Basin, 4 foot Dia, per Detail S-3	4037050	1.000	Ea
0090	Hand Patching	5010025	70.000	Ton
0095	Driveway, Nonreinf Conc, 6 inch	8010005	8.000	Syd
0100	_ Curb and Gutter, (24) x (18) inch pan, per Detail P-5	8027001	398.000	Ft
0105	_ Roll Curb and Gutter, (18) x (10) inch pan, Per Detail P-5B	8027001	34.000	Ft
0110	_ Sidewalk Ramp, ADA Curb	8027001	26.000	Ft
0115	_ Median Island End Treatment, per Detail P-5D	8027050	2.000	Ea
0120	Detectable Warning Surface	8030010	216.000	Ft
0125	Curb Ramp Opening, Conc	8030030	330.000	Ft
0130	Sidewalk, Conc, 6 inch	8030046	157.000	Sft

0135	Curb Ramp, Conc, 6 inch	8032002	3,483.000	Sft
0140	_ Removable Bollard	8077050	1.000	Ea
0145	_ Sign	8107010	652.000	Sft
0150	_ Gateway Element, R1-6a Sign, Double-Sided	8107050	10.000	Ea
0155	_ Sign Post	8107050	7.000	Ea
0160	_ Sign, Rem and Salv	8107050	80.000	Ea
0165	Pavt Mrkg, Polyurea, 6 inch, White	8110094	38.000	Ft
0170	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	1,370.000	Ft
0175	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	48.000	Ft
0180	Pavt Mrkg, Polyurea, Sharrow Sym	8110115	2.000	Ea
0185	Rem Spec Mrkg	8110343	890.000	Sft
0190	Recessing Pavt Mrkg, Transv	8110451	352.000	Sft
0195	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0200	Pedestrian Type II Channelizer, Temp	8120027	10.000	Ft
0205	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0210	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0215	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0220	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0225	Minor Traf Devices	8120170	1.000	LSUM
0230	Sign, Type B, Temp, Prismatic, Furn	8120350	100.000	Sft
0235	Sign, Type B, Temp, Prismatic, Oper	8120351	100.000	Sft
0240	Pedestrian Ramp, Temp	8122251	10.000	Ea
0245	_ Turf Establishment	8167011	553.000	Syd
0250	_ Turf Watering	8167050	36.000	Ea
0255	Serv Disconnect	8182366	14.000	Ea
0260	_ DB Conduit, 1, 1.5-Inch, Schedule 40 PVC	8187001	165.000	Ft
0265	_ DB Conduit, 1, 2-Inch, Schedule 40 PVC	8187001	360.000	Ft
0270	_ DB Conduit, 2, 3-Inch, Schedule 40 PVC	8187001	10.000	Ft
0275	_ Directional Bored Conduit, 2, 2-Inch, Schedule 40 PVC	8187001	1,800.000	Ft
0280	_ Signal /C, IMSA 3C #14 CU	8187001	1,410.000	Ft
0285	_ Underground Sec /C, 3 -#6 CU U.S.E.	8187001	1,565.000	Ft
0290	_ Conduit(s) Connect to Existing	8187050	6.000	Ea
0295	_ Dry-Type Transformer, Pole Mtd, Single Phase, 3 KVA, 480-120/240V	8187050	5.000	Ea
0300	_ Guy Installation for Wood Pole	8187050	9.000	Ea
0305	_ Hh, Polymer 17-Inch by 30-Inch	8187050	1.000	Ea
0310	_ Hh, Precast Conc. 24-Inch Round x 36-Inch Deep	8187050	31.000	Ea
0315	_ Sec Riser, 1 - 2 Inch	8187050	14.000	Ea
0320	_ Overhead Sec /C, #4 Triplex	8197001	7,235.000	Ft
0325	Pedestal, Alum	8200100	21.000	Ea
0330	Pedestal, Fdn	8200105	24.000	Ea
0335	Pedestal, Pushbutton, Alum	8200118	3.000	Ea
0340	Pushbutton and Sign	8200121	26.000	Ea
0345	Push Button Station and Sign	8200128	2.000	Ea

---

0350	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0355	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0360	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	1.000	Ea
0365	Casing, 42 inch	8200485	45.000	Ft
0370	Mast Arm Pole, Cat I	8202010	4.000	Ea
0375	Mast Arm, 30 foot, Cat I	8202015	1.000	Ea
0380	Mast Arm, 35 foot, Cat I	8202016	2.000	Ea
0385	Mast Arm, 45 foot, Cat I	8202018	1.000	Ea
0390	Mast Arm Pole Fdn, 6 Bolt	8202034	59.000	Ft
0395	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	4.000	Ea
0400	_ Cabinet, NEMA Type, Modified	8207050	1.000	Ea
0405	_ Controller, NEMA, ATC Type, Modified	8207050	1.000	Ea
0410	_ Flsh Beacon, Rectangular Rapid	8207050	29.000	Ea
0415	_ Steel Pole Mounting Hub	8207050	2.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 034

**Letting Date:** September 5, 2025

**Contract ID:** 11000-216485

**Description:** 0.75 mi of hot mix asphalt cold milling and resurfacing, concrete sidewalk and ramps and pavement markings on Elm Street from US-12 to the north village limits of Three Oaks, Berrien County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216485A	25A0814	N/A	STL 11000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Amtrak	1027060	35,000.000	Dir
0010	Mobilization, Max \$45,000.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	190.000	Ft
0020	Sidewalk, Rem	2040055	120.000	Syd
0025	Subgrade Undercutting, Type II	2050041	50.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	30.000	Ea
0035	Erosion Control, Silt Fence	2080036	500.000	Ft
0040	Maintenance Gravel, LM	3060021	100.000	Cyd
0045	Dr Structure Cover, Adj, Case 1, Modified	4030004	34.000	Ea
0050	Dr Structure, Temp Lowering	4030390	33.000	Ea
0055	Cold Milling HMA Surface	5010002	16,120.000	Syd
0060	Hand Patching	5010025	6.000	Ton
0065	HMA Approach	5010061	175.000	Ton
0070	HMA, 5EML	5012037	1,615.000	Ton
0075	Conc Base Cse, Nonreinf, 6 inch	6020015	65.000	Syd
0080	Curb and Gutter, Conc, Det C4	8020023	190.000	Ft
0085	Curb Ramp Opening, Conc	8030030	60.000	Ft
0090	Curb Ramp, Conc, 6 inch	8032002	1,085.000	Sft
0095	_ Detectable Warning Surface, Composite	8037001	40.000	Ft
0100	_ Detectable Warning Surface, Composite, Retrofit	8037001	190.000	Ft
0105	Band, Sign	8100010	30.000	Ea
0110	Post, Steel, 3 pound	8100371	720.000	Ft
0115	Sign, Type III, Erect, Salv	8100402	14.000	Ea
0120	Sign, Type III, Rem	8100403	109.000	Ea
0125	Sign, Type IIIA	8100404	130.000	Sft
0130	Sign, Type IIIB	8100405	120.000	Sft
0135	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	885.000	Ft

0140	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	25.000	Ft
0145	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	8110058	12.000	Ea
0150	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	1.000	Ea
0155	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	2.000	Ea
0160	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	1.000	Ea
0165	Pavt Mrkg, Ovly Cold Plastic, Sharrow Sym	8110079	12.000	Ea
0170	Pavt Mrkg, Waterborne, 4 inch, White	8110231	5,000.000	Ft
0175	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	6,705.000	Ft
0180	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	1,575.000	Ft
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0195	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	60.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	60.000	Ea
0210	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0215	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0220	Minor Traf Devices	8120170	1.000	LSUM
0225	Sign, Type B, Temp, Prismatic, Furn	8120350	310.000	Sft
0230	Sign, Type B, Temp, Prismatic, Oper	8120351	310.000	Sft
0235	Traf Regulator Control	8120370	1.000	LSUM
0240	Slope Restoration, Non-Freeway, Type E	8162005	200.000	Syd
0245	Gate Box, Adj, Temp, Case 1	8230391	24.000	Ea
0250	Gate Box, Adj, Case 1	8230431	24.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 035

**Letting Date:** September 5, 2025

**Contract ID:** 46000-218475

**Description:** 0.50 mi of full depth road reconstruction, hot mix asphalt, concrete curb and gutter, structure adjustments, and pavement markings in the city of Adrian, Lenawee County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218475A	25A0778	N/A	STUL 46000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Adrian & Blissfield Railroad	1027060	1.000	Dir
0010	Mobilization, Max \$84,600.00	1100001	1.000	LSUM
0015	_ Tree Trimming, Modified	2027002	26.000	Sta
0020	Dr Structure, Rem	2030011	3.000	Ea
0025	_ Exterior Coating for Manholes	2037050	5.000	Ea
0030	Pavt, Rem	2040050	757.000	Syd
0035	Sidewalk, Rem	2040055	76.000	Syd
0040	Embankment, LM	2050011	200.000	Cyd
0045	Excavation, Earth	2050016	3.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	24.000	Ea
0055	Aggregate Base, 6 inch	3020016	274.000	Syd
0060	Aggregate Base, Conditioning	3020050	469.000	Syd
0065	Aggregate Surface Cse, 6 inch	3060010	105.000	Syd
0070	Maintenance Gravel	3060020	100.000	Ton
0075	Trenching	3070200	23.000	Sta
0080	Dr Structure Cover, Adj, Case 1, Modified	4030004	31.000	Ea
0085	Dr Structure Cover, Type K	4030050	3.000	Ea
0090	Dr Structure, 24 inch dia	4030200	3.000	Ea
0095	Dr Structure, Temp Lowering	4030390	31.000	Ea
0100	HMA Surface, Rem	5010005	151.000	Syd
0105	HMA, 13A	5010033	2,559.000	Ton
0110	HMA Approach	5010061	899.000	Ton
0115	Cement	6030005	275.000	Ton
0120	_ Cement Treated Full Depth Reclamation, 12 inch	6037011	11,401.000	Syd
0125	_ Removing Excess Pavement Materials	6037011	11,401.000	Syd
0130	Driveway, Nonreinf Conc, 6 inch	8010005	345.000	Syd
0135	Curb and Gutter, Conc, Det B2	8020016	1,058.000	Ft

0140	Curb and Gutter, Conc, Det C4	8020023	3,755.000	Ft
0145	Detectable Warning Surface	8030010	35.000	Ft
0150	Curb Ramp Opening, Conc	8030030	35.000	Ft
0155	Sidewalk, Conc, 4 inch	8030044	344.000	Sft
0160	Curb Ramp, Conc, 6 inch	8032002	311.000	Sft
0165	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	412.000	Ft
0170	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	96.000	Ft
0175	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	181.000	Ft
0180	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	2.000	Ea
0185	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	4,546.000	Ft
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	45.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	45.000	Ea
0210	Minor Traf Devices	8120170	1.000	LSUM
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	800.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	800.000	Sft
0225	Pedestrian Ramp, Temp	8122251	8.000	Ea
0230	Slope Restoration, Non-Freeway, Type A	8162001	1,014.000	Syd
0235	Gate Box, Adj, Temp, Case 1	8230391	8.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 036

**Letting Date:** September 5, 2025

**Contract ID:** 16000-221464

**Description:** 0.25 mi of culvert replacement including excavation, embankment, hot mix asphalt paving and guardrail work on Lincoln Avenue from the city limits of Cheboygan to Loomis Street in the city of Cheboygan, Cheboygan County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221464A	25A0810	N/A	STUL 16000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$51,000.00	1100001	1.000	LSUM
0010	Culv, Rem, Over 48 inch	2030003	1.000	Ea
0015	Guardrail, Rem	2040035	261.000	Ft
0020	Embankment, CIP	2050010	235.000	Cyd
0025	Excavation, Earth	2050016	321.000	Cyd
0030	Erosion Control, Silt Fence	2080036	350.000	Ft
0035	Aggregate Base, 10 inch	3020026	1,714.000	Syd
0040	Maintenance Gravel	3060020	75.000	Ton
0045	Approach, CI II	3070021	17.000	Ton
0050	Shld, CI II	3070121	97.000	Ton
0055	_ Culv, Alum Multi-Plate Pipe Arch, 167 inch by 113 inch, Tr Det B1	4017001	73.000	Ft
0060	_ Bedding, Natural Stream Material	4017021	50.000	Cyd
0065	HMA Surface, Rem	5010005	1,351.000	Syd
0070	HMA, 4EML	5012025	341.000	Ton
0075	HMA, 5EML	5012037	114.000	Ton
0080	Guardrail Departing Terminal, Type MGS	8070052	3.000	Ea
0085	Guardrail Reflector	8070080	7.000	Ea
0090	Guardrail, Type MGS-8, 72 inch Post	8072179	225.000	Ft
0095	Pavt Mrkg, Waterborne, 4 inch, White	8110231	840.000	Ft
0100	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	113.000	Ft
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0125	Minor Traf Devices	8120170	1.000	LSUM
0130	Sign, Portable, Changeable Message, NTCIP-	8120332	2.000	Ea

	Compliant, Furn			
0135	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0140	Sign, Type B, Temp, Prismatic, Furn	8120350	730.000	Sft
0145	Sign, Type B, Temp, Prismatic, Oper	8120351	730.000	Sft
0150	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	520.000	Sft
0155	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	520.000	Sft
0160	Traf Regulator Control	8120370	1.000	LSUM
0165	Slope Restoration, Non-Freeway, Type E	8162005	249.000	Syd
0170	Slope Restoration, Non-Freeway, Type F	8162006	876.000	Syd

---



8/14/2025 12:40 PM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 037

**Letting Date:** September 5, 2025

**Contract ID:** 63201-219353

**Description:** Installation of LED streetlights on various routes in the city of Pontiac, Oakland County. This is as Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219353A	25A0827	N/A	CRU 63201

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$125,000.00	1100001	1.000	LSUM
0010	Minor Traf Devices	8120170	1.000	LSUM
0015	Traf Regulator Control	8120370	1.000	LSUM
0020	Luminaire, Rem	8190360	1,092.000	Ea
0025	_ Luminaire, 136W LED, Rectangular	8197050	652.000	Ea
0030	_ Luminaire, 39W LED, Decorative	8197050	68.000	Ea
0035	_ Luminaire, 58W LED, Rectangular	8197050	372.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 038

**Letting Date:** September 5, 2025

**Contract ID:** 23000-218254

**Description:** Bridge rehabilitation including superstructure replacement, hot mix asphalt full-depth widening, cold-milling and resurfacing, concrete sidewalk, curb and gutter and pavement markings on Webster Road over the Grand River, Eaton County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218254A	25A0803	N/A	BHT 23000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$523,300.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.450	Acre
0015	Culv, Rem, Less than 24 inch	2030001	2.000	Ea
0020	Sewer, Rem, Less than 24 inch	2030015	14.000	Ft
0025	Curb and Gutter, Rem	2040020	31.000	Ft
0030	Guardrail, Rem	2040035	1,270.000	Ft
0035	Pavt, Rem	2040050	25.000	Syd
0040	Embankment, CIP	2050010	637.000	Cyd
0045	Excavation, Earth	2050016	1,690.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0055	Erosion Control, Silt Fence	2080036	1,652.000	Ft
0060	Project Cleanup	2090001	1.000	LSUM
0065	Subbase, CIP	3010002	1,079.000	Cyd
0070	Aggregate Base	3020001	1,558.000	Ton
0075	Maintenance Gravel	3060020	5.000	Ton
0080	Approach, CI II	3070021	3.000	Ton
0085	Shld, CI II, 4 inch	3070126	191.000	Syd
0090	Culv End Sect, 15 inch	4010015	2.000	Ea
0095	Culv End Sect, 18 inch	4010018	2.000	Ea
0100	Culv, CI E, 15 inch	4010540	44.000	Ft
0105	Dr Marker Post	4011109	2.000	Ea
0110	Sewer, CI A, 12 inch, Tr Det B	4020033	25.000	Ft
0115	Sewer, CI A, 18 inch, Tr Det B	4020035	182.000	Ft
0120	Dr Structure Cover, Type B	4030010	3.000	Ea
0125	Dr Structure Cover, Type D	4030025	1.000	Ea
0130	Dr Structure Cover, Type G	4030040	2.000	Ea
0135	Dr Structure Cover, Type K	4030050	2.000	Ea

0140	Dr Structure, 24 inch dia	4030200	2.000	Ea
0145	Dr Structure, 48 inch dia	4030210	6.000	Ea
0150	Pavt, Cleaning	5010001	1.000	LSUM
0155	HMA Surface, Rem	5010005	2,310.000	Syd
0160	Hand Patching	5010025	20.000	Ton
0165	HMA Approach	5010061	67.000	Ton
0170	HMA, 4EL	5012024	236.000	Ton
0175	HMA, 5EL	5012036	178.000	Ton
0180	Curb and Gutter, Conc, Det F4	8020038	90.000	Ft
0185	Curb and Gutter, Bridge Approach, Det 1	8022010	68.000	Ft
0190	Detectable Warning Surface	8030010	15.000	Ft
0195	Curb Ramp Opening, Conc	8030030	18.000	Ft
0200	Curb Ramp, Conc, 6 inch	8032002	222.000	Sft
0205	Shared use Path, HMA	8060040	75.000	Ton
0210	Guardrail Approach Terminal, Type 2M	8070044	3.000	Ea
0215	Guardrail Departing Terminal, Type B	8070050	1.000	Ea
0220	Guardrail Reflector	8070080	19.000	Ea
0225	Post, Mailbox	8070095	1.000	Ea
0230	Guardrail Anch, Bridge, Det M4	8070133	4.000	Ea
0235	Guardrail, Curved, Type B, 96 inch Post	8072142	13.000	Ft
0240	Guardrail, Type MGS-8, 108 inch Post	8072180	500.000	Ft
0245	_ Timber Rub Rail	8077001	210.000	Ft
0250	Fence, Chain Link, 48 inch, Vinyl Coated	8082001	250.000	Ft
0255	Delineator Reflector, Green	8100133	4.000	Ea
0260	Post, Steel, 3 pound	8100371	126.000	Ft
0265	Sign, Type III, Rem	8100403	13.000	Ea
0270	Sign, Type IIIB	8100405	29.000	Sft
0275	Ground Mtd Sign Support, Rem	8102010	8.000	Ea
0280	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	1,326.000	Ft
0285	Pavt Mrkg, Waterborne, 6 inch, White	8110233	2,000.000	Ft
0290	Rem Curing Compound, for Longit Mrkg, 4 inch	8110307	1,326.000	Ft
0295	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	2,000.000	Ft
0300	Recessing Pavt Mrkg, Longit	8110450	2,350.000	Ft
0305	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	11.000	Ea
0310	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	11.000	Ea
0315	Minor Traf Devices	8120170	1.000	LSUM
0320	Sign, Type B, Temp, Prismatic, Furn	8120350	504.000	Sft
0325	Sign, Type B, Temp, Prismatic, Oper	8120351	504.000	Sft
0330	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	323.000	Sft
0335	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	323.000	Sft
0340	Traf Regulator Control	8120370	1.000	LSUM
0345	_ Barrier Float, Temp	8127001	475.000	Ft
0350	_ Regulatory Buoy, Closed Area, Temp	8127050	10.000	Ea

0355	_ Regulatory Buoy, Danger, Temp	8127050	10.000	Ea
0360	Riprap, Plain	8130010	110.000	Syd
0365	Site Preparation, Max \$51.00	8150001	1.000	LSUM
0370	Watering and Cultivating, First Season, Min \$25.00	8150002	1.000	LSUM
0375	Watering and Cultivating, 2nd Season, Min \$31.00	8150003	1.000	LSUM
0380	Echinacea purpurea, #1 cont.	8151268	5.000	Ea
0385	Sporobolus heterolepis 'Tara', #1 cont.	8153639	7.000	Ea
0390	Mulch	8160025	15.000	Syd
0395	Topsoil Surface, Furn, 12 inch	8160070	15.000	Syd
0400	Slope Restoration, Non-Freeway, Type A	8162001	150.000	Syd
0405	Slope Restoration, Non-Freeway, Type F	8162006	670.000	Syd
0410	Slope Restoration, Non-Freeway, Type G	8162007	1,060.000	Syd

**Section: 2**

0415	Asbestos Materials, Rem and Disposal	2040001	13,000.000	Dir
0420	Excavation, Fdn	2060010	60.000	Cyd
0425	Underdrain, Fdn, 4 inch	4040031	270.000	Ft
0430	Underdrain Outlet, 4 inch	4040091	80.000	Ft
0435	Underdrain, Outlet Ending, 4 inch	4040111	8.000	Ea
0440	Bridge Ltg, Furn and Rem (SN 2362)	7060001	1.000	LSUM
0445	Bridge Ltg, Oper and Maintain	7060002	460.000	Cyd
0450	Conc, Low Temperature Protection	7060020	42.000	Cyd
0455	Expansion Joint Device	7060050	94.000	Ft
0460	Expansion Joint Device, Cover Plate	7060051	25.000	Ft
0465	Reinforcement, Steel, Epoxy Coated	7060092	106,566.000	Lb
0470	Substructure Conc	7060100	39.000	Cyd
0475	Superstructure Conc	7060110	84.000	Cyd
0480	Superstructure Conc, Form, Finish, and Cure (SN 2362)	7060111	1.000	LSUM
0485	Superstructure Conc, Form, Finish, and Cure, Night Casting (SN 2362)	7060112	1.000	LSUM
0490	Superstructure Conc, Night Casting	7060113	460.000	Cyd
0495	Sealing Localized Cracks (SN 2362)	7060220	1.000	LSUM
0500	_ Bridge Name Plate	7067050	1.000	Ea
0505	Bearing, Elastomeric, 1 3/4 inch	7070015	7,840.000	Sin
0510	Structural Steel, Mixed, Erect	7070050	5,612.000	Lb
0515	Structural Steel, Mixed, Furn and Fab	7070051	5,612.000	Lb
0520	_ Steel Tub Girder, Erect	7077051	1.000	LSUM
0525	_ Steel Tub Girder, Furn and Fab	7077051	1.000	LSUM
0530	Joint Waterproofing	7100001	227.000	Sft
0535	Joint Waterproofing, Expansion	7100003	144.000	Sft
0540	_ Silane Treatment	7107010	3,878.000	Sft
0545	Bridge Railing, Aesthetic Parapet Tube	7110005	603.000	Ft
0550	Hand Chipping, Other Than Deck	7120007	75.000	Cft
0555	Patch, Forming	7120017	150.000	Sft

0560	Adhesive Anchoring of Vertical Bar, 5/8 inch	7120033	302.000	Ea
0565	Structures, Rehabilitation, Rem Portions (SN 2362)	7120070	1.000	LSUM
0570	Reinforcement, Mechanical Splice	7120084	168.000	Ea
0575	Patching Conc, C-L	7120112	3.000	Cyd
0580	Embedded Galvanic Anode	7120120	50.000	Ea
0585	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM
0590	_ Fence, Chain Link, 48 inch, Modified	8087001	325.000	Ft
0595	Riprap, Heavy	8130006	120.000	Ton

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 039

**Letting Date:** September 5, 2025

**Contract ID:** 52000-220598

**Description:** 0.23 mi of culvert replacement including hot mix asphalt reconstruction, storm sewer work, aggregate shoulders and pavement markings on County Route 492 east of Morgan Meadows Road, Marquette County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220598A	25A0744	N/A	ER 52000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$15,700.00	1100001	1.000	LSUM
0010	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0015	Embankment, CIP	2050010	17.000	Cyd
0020	Excavation, Earth	2050016	266.000	Cyd
0025	Erosion Control, Silt Fence	2080036	150.000	Ft
0030	Aggregate Base	3020001	205.000	Ton
0035	Aggregate Base, Conditioning	3020050	1,095.000	Syd
0040	Approach, CI II	3070021	15.000	Ton
0045	Shld, CI II	3070121	22.000	Ton
0050	Culv End Sect, Conc, 12 inch	4010047	3.000	Ea
0055	Culv End Sect, Conc, 36 inch	4010053	2.000	Ea
0060	Culv, CI E, Conc, 36 inch	4010578	64.000	Ft
0065	Sewer, CI E, 12 inch, Tr Det B	4020600	209.000	Ft
0070	Dr Structure Cover, Type E	4030035	3.000	Ea
0075	Dr Structure, 48 inch dia	4030210	3.000	Ea
0080	HMA Surface, Rem	5010005	1,061.000	Syd
0085	HMA, 4EML	5012025	161.000	Ton
0090	HMA, 5EML	5012037	121.000	Ton
0095	Post, Steel, 3 pound	8100371	45.000	Ft
0100	Sign, Type III, Erect, Salv	8100402	3.000	Ea
0105	Ground Mtd Sign Support, Rem	8102010	3.000	Ea
0110	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0115	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0120	Minor Traf Devices	8120170	1.000	LSUM
0125	Plastic Drum, Fluorescent, Furn	8120252	18.000	Ea
0130	Plastic Drum, Fluorescent, Oper	8120253	18.000	Ea
0135	Sign, Type B, Temp, Prismatic, Furn	8120350	328.000	Sft

0140	Sign, Type B, Temp, Prismatic, Oper	8120351	328.000	Sft
0145	Traf Regulator Control	8120370	1.000	LSUM
0150	Riprap, Plain	8130010	139.000	Syd
0155	Slope Restoration, Non-Freeway, Type B	8162002	500.000	Syd
0160	Slope Restoration, Non-Freeway, Type C	8162003	99.000	Syd
0165	Slope Restoration, Non-Freeway, Type D	8162004	945.000	Syd

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 040

**Letting Date:** September 5, 2025

**Contract ID:** 33000-215163

**Description:** Bridge reconstruction including replacement with a 22-foot by 9.5-foot precast box and approach work on Aurelius Road over Pawlowski Creek Drain in the city of Lansing, Ingham County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215163A	N/A	N/A	MCS 33000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Audio Visual Filming	1047051	1.000	LSUM
0010	Mobilization, Max \$159,800.00	1100001	1.000	LSUM
0015	Sewer, Rem, Less than 24 inch	2030015	15.000	Ft
0020	Sewer, Rem, 24 inch to 48 inch	2030016	54.000	Ft
0025	Curb and Gutter, Rem	2040020	155.000	Ft
0030	Guardrail, Rem	2040035	155.000	Ft
0035	Embankment, CIP	2050010	50.000	Cyd
0040	Subgrade Undercutting, Type II	2050041	10.000	Cyd
0045	_ Erosion Control, Inlet Protection, Fabric Drop, Modified	2087050	4.000	Ea
0050	_ Street Sweeping	2087050	5.000	Ea
0055	Project Cleanup	2090001	1.000	LSUM
0060	Subbase, CIP	3010002	145.000	Cyd
0065	Aggregate Base, 8 inch	3020020	435.000	Syd
0070	Culv End Sect, Conc, 42 inch	4010054	1.000	Ea
0075	Sewer, Cl A, 12 inch, Tr Det B	4020033	15.000	Ft
0080	Sewer, Cl A, 42 inch, Tr Det B	4020039	61.000	Ft
0085	Dr Structure, 72 inch dia	4030230	1.000	Ea
0090	Dr Structure, Cleaning	4030290	4.000	Ea
0095	_ Dr Structure Cover, Modified	4037050	1.000	Ea
0100	HMA Surface, Rem	5010005	435.000	Syd
0105	HMA, 2EMH	5012002	108.000	Ton
0110	HMA, 4EMH	5012026	60.000	Ton
0115	HMA, 5EMH	5012038	48.000	Ton
0120	Curb and Gutter, Conc, Det F4	8020038	155.000	Ft
0125	Guardrail, Type B, 72 inch Post	8072171	155.000	Ft
0130	Pavt Mrkg, Waterborne, 4 inch, White	8110231	200.000	Ft
0135	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	250.000	Ft

0140	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	200.000	Ft
0145	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	250.000	Ft
0150	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0170	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0175	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0180	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0185	Sign, Type B, Temp, Prismatic, Furn	8120350	250.000	Sft
0190	Sign, Type B, Temp, Prismatic, Oper	8120351	250.000	Sft
0195	_ Water Main, 16 Inch, Tr Det G, Modified	8237001	98.000	Ft
0200	_ Water Main, Rem, Less than 24 inch	8237001	98.000	Ft
0205	_ Water Main Fitting, 16 Inch, 45 Deg Bend	8237050	6.000	Ea
0210	_ Water Main Fitting, 16 Inch, Cap Off	8237050	2.000	Ea
0215	_ Water Main Fitting, 16 Inch, Sleeve	8237050	2.000	Ea
0220	_ Water Main, Connect to Existing	8237050	2.000	Ea

**Section: 2**

0225	Culv, Rem, Over 48 inch	2030003	2.000	Ea
0230	Masonry and Conc Structure, Rem	2040045	210.000	Cyd
0235	Excavation, Earth	2050016	1,910.000	Cyd
0240	Backfill, Structure, CIP	2060002	1,184.000	Cyd
0245	_ Bypass Pumping	4017050	1.000	Ea
0250	_ Construction Dam	4017050	1.000	Ea
0255	Underdrain, Fdn, 6 inch	4040033	230.000	Ft
0260	Culv Bedding, Box Culv	4060005	105.000	Cyd
0265	_ Culv, Precast Conc Box, 22 foot by 9.5 foot	4067001	107.000	Ft
0270	Riprap, Heavy	8130005	270.000	Syd
0275	_ Turf Establishment, Performance	8167011	1,100.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 041

**Letting Date:** September 5, 2025

**Contract ID:** 82000-212779

**Description:** 1.00 mi of hot mix asphalt shared-use path including concrete curb, gutter and sidewalk, a boardwalk, rain gardens, signing and a bike repair station in Venoy Dorsey Park between Venoy Road and Merriman Road in the city of Wayne, Wayne County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
212779A	25A0816	N/A	TAU 82000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	5,000.000	Dir
0010	Mobilization, Max \$200,940.00	1100001	1.000	LSUM
0015	Clearing	2010001	4.000	Acre
0020	Curb and Gutter, Rem	2040020	38.000	Ft
0025	Pavt, Rem	2040050	54.000	Syd
0030	Embankment, CIP	2050010	1,088.000	Cyd
0035	Excavation, Earth	2050016	2,185.000	Cyd
0040	Machine Grading	2050030	6.000	Sta
0045	Erosion Control, Gravel Access Approach	2080016	1.000	Ea
0050	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0055	Erosion Control, Silt Fence	2080036	9,908.000	Ft
0060	Erosion Control, Turbidity Curtain, Shallow	2080044	602.000	Ft
0065	Project Cleanup	2090001	1.000	LSUM
0070	_ Litter and Debris, Rem	2097051	1.000	LSUM
0075	_ Aggregate Base, 6 inch, Modified	3027011	170.000	Syd
0080	_ Aggregate Base, 8 inch, Modified	3027011	1,519.000	Syd
0085	_ Aggregate Base, Conditioning, Modified	3027011	4,610.000	Syd
0090	_ Aggregate Base, Dr Cse, 6AA	3027031	354.000	Ton
0095	Aggregate Surface Cse, 12 inch	3060016	24.000	Syd
0100	Geotextile, Separator	3080005	10,457.000	Syd
0105	Culv End Sect, Conc, 12 inch	4010047	12.000	Ea
0110	Culv, CI E, 12 inch	4010539	240.000	Ft
0115	Underdrain, Pipe, Open-Graded, 6 inch	4040043	4,147.000	Ft
0120	Underdrain Outlet, 6 inch	4040093	165.000	Ft
0125	Underdrain, Outlet Ending, 6 inch	4040113	16.000	Ea
0130	Culv Bedding, Box Culv	4060005	105.000	Cyd
0135	Culv, Precast Conc Box, 4 foot by 3 foot	4060100	165.000	Ft

0140	_ Culv End Sect, Conc, Box, 4 foot by 3 foot	4067050	2.000	Ea
0145	_ Culv, Conc, Box, 4 foot by 3 foot, Mitered	4067050	1.000	Ea
0150	Pavt, Cleaning	5010001	1.000	LSUM
0155	HMA Patch, Rem	5010006	11.000	Syd
0160	HMA, 3EML	5012013	345.000	Ton
0165	HMA, 4EML	5012025	173.000	Ton
0170	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	80.000	Syd
0175	Joint, Contraction, C	6020202	1,139.000	Ft
0180	Joint, Expansion, E3	6020208	699.000	Ft
0185	_ Modular Block Wall	8007010	576.000	Sft
0190	_ Bollard	8007050	4.000	Ea
0195	_ Bollard, Collapsible	8007050	1.000	Ea
0200	_ Marker, Relocate	8007050	1.000	Ea
0205	Curb and Gutter, Conc, Det B3	8020017	52.000	Ft
0210	Curb and Gutter, Conc, Det F2	8020036	979.000	Ft
0215	Curb and Gutter, Conc, Det F5	8020039	14.000	Ft
0220	Spillway, Conc	8020075	12.000	Ft
0225	Detectable Warning Surface	8030010	35.000	Ft
0230	Curb Ramp Opening, Conc	8030030	37.000	Ft
0235	Sidewalk, Conc, 8 inch	8030048	6,621.000	Sft
0240	Curb Ramp, Conc, 6 inch	8032002	628.000	Sft
0245	Shared use Path, Aggregate	8060010	1,831.000	Ton
0250	Shared use Path, Grading	8060030	4,600.000	Ft
0255	Shared use Path, HMA	8060040	1,112.000	Ton
0260	_ Wood Fence	8087001	387.000	Ft
0265	Post, Steel, 3 pound	8100371	216.000	Ft
0270	Sign, Type IA	8100392	52.000	Sft
0275	_ Interpretive Sign	8107050	2.000	Ea
0280	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	70.000	Ft
0285	Pavt Mrkg, Sprayable Thermopl, 4 inch, White	8110153	646.000	Ft
0290	Pavt Mrkg, Sprayable Thermopl, 6 inch, Yellow	8110156	1,876.000	Ft
0295	_ Pavt Mrkg, Sprayable Thermopl, 4 inch, Blue	8117001	127.000	Ft
0300	Minor Traf Devices	8120170	1.000	LSUM
0305	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	40.000	Ft
0310	Traf Regulator Control	8120370	1.000	LSUM
0315	_ Ledge Rock, 18 inch	8127050	130.000	Ea
0320	_ Ledge Rock, 8 inch	8127050	270.000	Ea
0325	Riprap, Heavy	8130005	1,203.000	Syd
0330	Riprap, Plain	8130010	350.000	Syd
0335	_ Riprap, Salv	8137011	61.000	Syd
0340	Site Preparation, Max \$31,400.00	8150001	1.000	LSUM
0345	Watering and Cultivating, First Season, Min \$15,300.00	8150002	1.000	LSUM
0350	Watering and Cultivating, 2nd Season, Min \$18,800.00	8150003	1.000	LSUM
0355	Cercis canadensis, tree form, 2 inch	8150808	12.000	Ea

0360	Cornus florida, 2 inch	8150983	11.000	Ea
0365	Gymnocladus dioicus, 1 1/2 inch	8151674	33.000	Ea
0370	Hamamelis virginiana, #5 cont.	8151699	3.000	Ea
0375	Liquidambar styraciflua, 1 1/2 inch	8152162	33.000	Ea
0380	Liriodendron tulipifera, 1 1/2 inch	8152175	35.000	Ea
0385	Ostrya virginiana, 2 inch	8152528	11.000	Ea
0390	Quercus bicolor, 1 1/2 inch	8153042	33.000	Ea
0395	Quercus rubra, 1 1/2 inch	8153124	33.000	Ea
0400	Ulmus americana 'Valley Forge', 1 1/2 inch	8153910	33.000	Ea
0405	_ Live Staking	8157011	324.000	Syd
0410	_ Bench	8157050	5.000	Ea
0415	_ Bike Repair Station	8157050	1.000	Ea
0420	_ Boulder, Relocate	8157050	90.000	Ea
0425	_ Trash Receptacle	8157050	1.000	Ea
0430	Mulch Blanket	8160027	4,517.000	Syd
0435	Seeding, Mixture THM	8160039	511.000	Lb
0440	Topsoil Surface, Furn, 4 inch	8160062	6,465.000	Syd
0445	Topsoil Surface, Salv, 12 inch	8160085	13,705.000	Syd
0450	_ Slope Restoration, Non-Freeway, Type G	8167011	9,930.000	Syd
0455	Gate Box, Adj, Case 2	8230432	5.000	Ea
0460	Staking Plan Errors and Extras, Max \$180/hour	8240002	4.000	Hr
0465	_ Contractor, Staking, Modified	8247051	1.000	LSUM
0470	Sanitary Structure, Adj, Add Depth	8252140	1.000	Ft
0475	Sanitary Structure Cover, Adj, Case 2	8252146	8.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 250905 042

**Letting Date:** September 5, 2025

**Contract ID:** 50000-217662

**Description:** 0.75 mi of hot mix asphalt cold milling and resurfacing, concrete sidewalk and curb ramps and pavement markings on 13 Mile Road from the southbound lanes of Gratiot Avenue to the east city limits of Roseville, Macomb County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217662A	25A0742	N/A	STU 50000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1027060	10,000.000	Dir
0010	Mobilization, Max \$203,000.00	1100001	1.000	LSUM
0015	Dr Structure, Rem	2030011	3.000	Ea
0020	Sewer, Rem, Less than 24 inch	2030015	78.000	Ft
0025	Curb and Gutter, Rem	2040020	6,313.000	Ft
0030	Sidewalk, Rem	2040055	574.000	Syd
0035	Erosion Control, Inlet Protection, Fabric Drop	2080020	28.000	Ea
0040	Subbase, LM	3010003	39.000	Cyd
0045	Aggregate Base, LM	3020002	250.000	Cyd
0050	Aggregate Base, 6 inch	3020016	767.000	Syd
0055	Aggregate Base, 8 inch	3020020	2,850.000	Syd
0060	Maintenance Gravel	3060020	350.000	Ton
0065	Driveway Maintenance, Commercial	3062000	16.000	Ea
0070	Intersection Maintenance	3062002	4.000	Ea
0075	Sewer, CI IV, 12 inch, Tr Det B	4020987	91.000	Ft
0080	Sewer Tap, 12 inch	4021204	1.000	Ea
0085	Dr Structure Cover, Adj, Case 1	4030005	44.000	Ea
0090	Dr Structure Cover, Adj, Case 2	4030006	4.000	Ea
0095	Dr Structure Cover, Type B	4030010	5.000	Ea
0100	Dr Structure, 48 inch dia	4030210	4.000	Ea
0105	Dr Structure, Adj, Add Depth	4030280	94.000	Ft
0110	Dr Structure, Tap, 12 inch	4030312	1.000	Ea
0115	Dr Structure, Temp Lowering	4030390	44.000	Ea
0120	_ Catch Basin Cover, Roseville	4037050	23.000	Ea
0125	_ Dr Structure, 36 inch dia	4037050	1.000	Ea
0130	_ External Structure Wrap, 18 inch	4037050	51.000	Ea
0135	_ Sanitary Mh Cover, Roseville	4037050	12.000	Ea

0140	_ Storm Mh Cover, Roseville	4037050	14.000	Ea
0145	Pavt, Cleaning	5010001	1.000	LSUM
0150	Cold Milling HMA Surface	5010002	21,595.000	Syd
0155	HMA Surface, Rem	5010005	481.000	Syd
0160	Joint and Crack, Cleanout	5010015	12,765.000	Ft
0165	Pavt Joint and Crack Repr, Det 7	5010020	5,905.000	Ft
0170	Hand Patching	5010025	325.000	Ton
0175	HMA, 4EML	5012025	2,370.000	Ton
0180	HMA, 5EML	5012037	2,370.000	Ton
0185	_ Geosynthetic Paving Fabric	5017011	21,595.000	Syd
0190	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	341.000	Syd
0195	Conc Pavt, Misc, Nonreinf, 9 inch	6020056	467.000	Syd
0200	Joint, Plane-of-Weakness, W, Intersection	6020310	618.000	Ft
0205	Cold Milling Conc Pavt	6030014	5,300.000	Syd
0210	Lane Tie, Epoxy Anchored	6030030	4,550.000	Ea
0215	Pavt Repr, Nonreinf Conc, 9 inch	6030046	2,575.000	Syd
0220	_ Pavt Repr, Rem, Modified	6037011	3,383.000	Syd
0225	Driveway, Nonreinf Conc, 8 inch	8010007	882.000	Syd
0230	Curb and Gutter, Conc, Det F1	8020035	151.000	Ft
0235	Curb and Gutter, Conc, Det F4	8020038	1,271.000	Ft
0240	Curb and Gutter, Conc, Det F5	8020039	30.000	Ft
0245	Driveway Opening, Conc, Det M	8020050	426.000	Ft
0250	_ Curb and Gutter, Conc, Det F1, Modified	8027001	2,812.000	Ft
0255	_ Curb and Gutter, Conc, Det F1, Spec	8027001	874.000	Ft
0260	_ Driveway Opening, Conc, Det M, Modified	8027001	746.000	Ft
0265	Detectable Warning Surface	8030010	40.000	Ft
0270	Curb Ramp Opening, Conc	8030030	112.000	Ft
0275	Sidewalk, Conc, 4 inch	8030044	1,525.000	Sft
0280	Curb Ramp, Conc, 4 inch	8032001	623.000	Sft
0285	_ Curb Ramp, Conc, 8 inch	8037010	570.000	Sft
0290	_ Splashwalk, Conc, 4 inch	8037010	3,074.000	Sft
0295	Fence, Protective	8080007	100.000	Ft
0300	Post Hole Through Conc for Steel Post	8100340	4.000	Ea
0305	Post, Steel, 3 pound	8100371	466.000	Ft
0310	Sign, Type III, Rem	8100403	32.000	Ea
0315	Sign, Type IIIB	8100405	107.000	Sft
0320	Ground Mtd Sign Support, Rem	8102010	21.000	Ea
0325	Pavt Mrkg, Waterborne, 4 inch, White	8110231	3,165.000	Ft
0330	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	9,420.000	Ft
0335	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	3,165.000	Ft
0340	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	9,420.000	Ft
0345	Rem Curing Compound, for Spec Mrkg	8110321	116.000	Sft
0350	Rem Spec Mrkg	8110343	88.000	Sft
0355	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	142.000	Ft
0360	_ Pavt Mrkg, Waterborne, 18 inch, Stop Bar	8117001	29.000	Ft

0365	_ Pavt Mrkg, Waterborne, 24 inch, Stop Bar	8117001	219.000	Ft
0370	_ Pavt Mrkg, Waterborne, 24 inch, Stop Bar, 2nd Application	8117001	219.000	Ft
0375	_ Pavt Mrkg, Waterborne, 2nd Application, 12 inch, Crosswalk	8117001	142.000	Ft
0380	_ Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Crosswalk	8117001	143.000	Ft
0385	_ Pavt Mrkg, Waterborne, 2nd Application, 18 inch, Stop Bar	8117001	29.000	Ft
0390	_ Pavt Mrkg, Waterborne, 6 inch, Crosswalk	8117001	143.000	Ft
0395	_ Pavt Mrkg, Waterborne, 2nd Application, Lt Turn Arrow Sym	8117050	6.000	Ea
0400	_ Pavt Mrkg, Waterborne, 2nd Application, Rt Turn Arrow Sym	8117050	7.000	Ea
0405	_ Pavt Mrkg, Waterborne, Lt Turn Arrow Sym	8117050	6.000	Ea
0410	_ Pavt Mrkg, Waterborne, Rt Turn Arrow Sym	8117050	7.000	Ea
0415	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	18.000	Ea
0420	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	18.000	Ea
0425	Pedestrian Type II Barricade, Temp	8120026	16.000	Ea
0430	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0435	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0440	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0445	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0450	Minor Traf Devices	8120170	1.000	LSUM
0455	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	440.000	Ft
0460	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	100.000	Ft
0465	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	600.000	Ft
0470	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0475	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0480	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	75.000	Ft
0485	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0490	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0495	Sign, Type B, Temp, Prismatic, Furn	8120350	250.000	Sft
0500	Sign, Type B, Temp, Prismatic, Oper	8120351	250.000	Sft
0505	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0510	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft
0515	Traf Regulator Control	8120370	1.000	LSUM
0520	Slope Restoration, Non-Freeway, Type A	8162001	2,100.000	Syd
0525	Hh, Adj	8182328	1.000	Ea
0530	TS Face, Bag	8200458	9.000	Ea
0535	TS Face, Bag, Rem	8200459	9.000	Ea
0540	Gate Valve, 8 inch	8230062	1.000	Ea
0545	Gate Well, Abandon	8230075	1.000	Ea
0550	Water Main, DI, 8 inch, Tr Det G	8230156	20.000	Ft

0555	Gate Well, 60 inch dia	8230360	1.000	Ea
0560	_ Gate Well Cover, Adj, Case 1	8237050	3.000	Ea
0565	_ Gate Well Cover, Roseville	8237050	3.000	Ea
0570	_ Audio Visual Record of the Construction Influence Area	8507051	1.000	LSUM

---