



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 001

**Letting Date:** October 3, 2025

**Contract ID:** 56023-208489

**Description:** 1.80 mi of road reconstruction including concrete curb, gutter, sidewalk and ramps, storm sewer, sanitary sewer, water main, signal modernization, lighting upgrades, signing and pavement markings on M-20/US-10BR from Jerome Street to east of Washington Street in the city of Midland, Midland County. This project includes a 5 year materials and workmanship pavement warranty. This is an OJT VIP Pilot Project. Please see Special Provision for Preparation and Consideration of Bids on On-the-Job-Training Voluntary Incentive Program Projects.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
208489A	FED/STATE/LOCAL	N/A	NH 56023

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Conc Quality Initiative	10000030	655.000	Dir
0010	Mobilization, Max \$2,897,500.00	1100001	1.000	LSUM
0015	Tree, Rem, 19 inch to 36 inch	2020002	26.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	72.000	Ea
0025	Stump, Rem, 19 inch to 36 inch	2020006	2.000	Ea
0030	Stump, Rem, 6 inch to 18 inch	2020008	8.000	Ea
0035	Dr Structure, Rem	2030011	227.000	Ea
0040	Sewer, Rem, Less than 24 inch	2030015	8,776.000	Ft
0045	Sewer, Rem, 24 inch to 48 inch	2030016	3,978.000	Ft
0050	_ Monitoring Well, Adj	2037050	5.000	Ea
0055	Curb and Gutter, Rem	2040020	12,591.000	Ft
0060	Pavt, Rem	2040050	63,797.000	Syd
0065	Sidewalk, Rem	2040055	7,133.000	Syd
0070	Exploratory Investigation, Vertical	2040080	100.000	Ft
0075	_ Pavt, Rem, Spec	2047011	3,190.000	Syd
0080	Embankment, CIP	2050010	6,911.000	Cyd
0085	Excavation, Earth	2050016	54,721.000	Cyd
0090	Non Haz Contaminated Material Handling and Disposal, LM	2050031	2,113.000	Cyd
0095	Subgrade Undercutting, Type I	2050040	1,000.000	Cyd
0100	Subgrade Undercutting, Type II	2050041	500.000	Cyd
0105	Flowable Fill, Non-Structural	2050148	20.000	Cyd
0110	Erosion Control, Gravel Access Approach	2080016	6.000	Ea
0115	Erosion Control, Inlet Protection, Fabric Drop	2080020	501.000	Ea
0120	Erosion Control, Inlet Protection, Sediment Trap	2080024	119.000	Ea
0125	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd

0130	Erosion Control, Silt Fence	2080036	9,410.000	Ft
0135	Subbase, CIP	3010002	55,015.000	Cyd
0140	Aggregate Base, 4 inch	3020010	3,732.000	Syd
0145	Aggregate Base, 6 inch	3020016	90,894.000	Syd
0150	Aggregate Surface Cse, 6 inch	3060010	22.000	Syd
0155	Driveway Maintenance, Commercial	3062000	23.000	Ea
0160	Driveway Maintenance, Residential	3062001	34.000	Ea
0165	Intersection Maintenance	3062002	74.000	Ea
0170	Shld, CI II, 6 inch	3070128	111.000	Syd
0175	Sewer, CI A, 12 inch, Tr Det A	4020004	205.000	Ft
0180	Sewer, CI A, 18 inch, Tr Det A	4020006	33.000	Ft
0185	Sewer, CI A, 24 inch, Tr Det A	4020007	973.000	Ft
0190	Sewer, CI A, 12 inch, Tr Det B	4020033	3,678.000	Ft
0195	Sewer, CI A, 15 inch, Tr Det B	4020034	410.000	Ft
0200	Sewer, CI A, 18 inch, Tr Det B	4020035	1,058.000	Ft
0205	Sewer, CI A, 24 inch, Tr Det B	4020036	2,971.000	Ft
0210	Sewer, CI A, 30 inch, Tr Det B	4020037	509.000	Ft
0215	Sewer, CI A, 36 inch, Tr Det B	4020038	620.000	Ft
0220	Sewer, CI A, 12 inch, Tr Det C	4020063	5,464.000	Ft
0225	Sewer, CI A, 15 inch, Tr Det C	4020064	188.000	Ft
0230	Sewer, CI A, 18 inch, Tr Det C	4020065	548.000	Ft
0235	Sewer, CI E, 12 inch, Tr Det B	4020600	2,049.000	Ft
0240	Sewer, CI E, 18 inch, Tr Det B	4020602	128.000	Ft
0245	Sewer, CI E, 36 inch, Tr Det B	4020605	42.000	Ft
0250	Sewer, CI E, 12 inch, Tr Det C	4020630	49.000	Ft
0255	Sewer, CI E, 18 inch, Tr Det C	4020632	15.000	Ft
0260	Sewer, CI E, 12 inch, Tr Det D	4020660	4,075.000	Ft
0265	Sewer, CI E, 18 inch, Tr Det D	4020662	31.000	Ft
0270	Sewer Tap, 4 inch	4021200	1.000	Ea
0275	Sewer Tap, 6 inch	4021201	1.000	Ea
0280	Sewer Tap, 8 inch	4021202	3.000	Ea
0285	Sewer Tap, 10 inch	4021203	5.000	Ea
0290	Sewer Tap, 12 inch	4021204	33.000	Ea
0295	Sewer Tap, 15 inch	4021205	4.000	Ea
0300	Sewer Tap, 18 inch	4021206	10.000	Ea
0305	Sewer Tap, 24 inch	4021207	8.000	Ea
0310	Video Taping Sewer and Culv Pipe	4021275	23,060.000	Ft
0315	Dr Structure Cover, Adj, Case 1, Modified	4030004	11.000	Ea
0320	Dr Structure Cover, Adj, Case 1	4030005	61.000	Ea
0325	Dr Structure Cover, Adj, Case 2	4030006	2.000	Ea
0330	Dr Structure Cover, Type B	4030010	136.000	Ea
0335	Dr Structure Cover, Type G	4030040	1.000	Ea
0340	Dr Structure Cover, Type J	4030045	17.000	Ea
0345	Dr Structure Cover, Type K	4030050	429.000	Ea
0350	Dr Structure Cover, Type R	4030070	8.000	Ea

0355	Dr Structure Cover, Type W	4030080	2.000	Ea
0360	Dr Structure, 24 inch dia	4030200	163.000	Ea
0365	Dr Structure, 48 inch dia	4030210	342.000	Ea
0370	Dr Structure, 60 inch dia	4030220	18.000	Ea
0375	Dr Structure, 72 inch dia	4030230	10.000	Ea
0380	Dr Structure, 84 inch dia	4030231	6.000	Ea
0385	Dr Structure, Add Depth of 84 inch dia, 8 foot to 15 foot	4030232	9.000	Ft
0390	Dr Structure, 96 inch dia	4030234	1.000	Ea
0395	Dr Structure, 108 inch dia	4030237	2.000	Ea
0400	Dr Structure, Add Depth of 108 inch dia, 8 foot to 15 foot	4030238	2.000	Ft
0405	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	134.000	Ft
0410	Dr Structure, Add Depth of 60 inch dia, 8 foot to 15 foot	4030260	32.000	Ft
0415	Dr Structure, Add Depth of 72 inch dia, 8 foot to 15 foot	4030270	10.000	Ft
0420	Dr Structure, Tap, 12 inch	4030312	12.000	Ea
0425	Dr Structure, Tap, 18 inch	4030318	4.000	Ea
0430	Dr Structure, Tap, 24 inch	4030324	2.000	Ea
0435	_ Accessible Dr Structure Cover	4037050	13.000	Ea
0440	Underdrain, Subbase, 6 inch	4040063	40,638.000	Ft
0445	Underdrain Outlet, 6 inch	4040093	1,812.000	Ft
0450	Video Inspection of Underdrain	4040200	40,638.000	Ft
0455	Cold Milling HMA Surface	5010002	15,079.000	Syd
0460	Bump Grinding	5010004	4,475.000	Syd
0465	HMA Surface, Rem	5010005	24,292.000	Syd
0470	HMA Quality Initiative	5010007	53,436.000	Dlr
0475	Longit Joint Density Quality Initiative	5010018	113,250.000	Dlr
0480	Pavt Joint and Crack Repr, Det 7	5010020	348.000	Ft
0485	Pavt Joint and Crack Repr, Det 8	5010021	126.000	Ft
0490	Hand Patching	5010025	43.000	Ton
0495	HMA Approach	5010061	239.000	Ton
0500	HMA Approach, High Stress	5010520	4,271.000	Ton
0505	HMA, 4EML, High Stress	5012073	15,857.000	Ton
0510	HMA, 5EML, High Stress	5012085	6,338.000	Ton
0515	HMA, Temp Pavt (3EML)	5012101	38.000	Ton
0520	HMA, Temp Pavt (4EML)	5012103	25.000	Ton
0525	_ Ride Incentive	5017060	45,822.000	Dlr
0530	Conc Base Cse, Nonreinf, 10 inch	6020023	737.000	Syd
0535	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	51.000	Syd
0540	Cold Milling Conc Pavt	6030014	38.000	Syd
0545	Coating Galvanized Support Structures	7160010	25.000	Ea
0550	_ Dewatering System for Contaminated Groundwater, Site	8007051	1.000	LSUM
0555	Driveway, Nonreinf Conc, 8 inch	8010007	1,339.000	Syd

0560	Curb, Conc, Det E2	8020002	100.000	Ft
0565	Curb and Gutter, Conc, Det B2	8020016	1,395.000	Ft
0570	Curb and Gutter, Conc, Det F3	8020037	672.000	Ft
0575	Curb and Gutter, Conc, Det F4	8020038	31,174.000	Ft
0580	Driveway Opening, Conc, Det M	8020050	1,456.000	Ft
0585	_ Curb and Gutter, Conc, Det F4, Modified	8027001	3,388.000	Ft
0590	Detectable Warning Surface	8030010	1,642.000	Ft
0595	Curb Ramp Opening, Conc	8030030	2,261.000	Ft
0600	Sidewalk, Conc, 4 inch	8030044	54,663.000	Sft
0605	Sidewalk, Conc, 6 inch	8030046	5,483.000	Sft
0610	Curb Ramp, Conc, 6 inch	8032002	31,937.000	Sft
0615	_ Decorative Conc, Surface, 4 inch	8037010	1,844.000	Sft
0620	_ Decorative Conc, Surface, 6 inch	8037010	3,666.000	Sft
0625	_ Sidewalk, Brick Pavers, Rem and Salv	8037010	664.000	Sft
0630	Post, Mailbox	8070095	12.000	Ea
0635	_ Post, Mailbox, Bracket	8077050	9.000	Ea
0640	_ Post, Mailbox, Multiple Mailbox Support System	8077050	1.000	Ea
0645	Field Office, CI 2	8090002	21.000	Mo
0650	Field Office, Utility Fees	8090010	20,000.000	Dir
0655	Band, Sign	8100010	33.000	Ea
0660	Fdn, Column Breakaway, Rem	8100220	20.000	Ea
0665	Fdn, Wood Support, Rem	8100280	53.000	Ea
0670	Post Hole Through Conc for Steel Post	8100340	4.000	Ea
0675	Post, Steel, 3 pound	8100371	4,664.000	Ft
0680	Post, Wood, 4 inch by 6 inch	8100380	846.000	Ft
0685	Post, Wood, 6 inch by 8 inch	8100382	30.000	Ft
0690	Sign, Type II, Rem	8100397	24.000	Ea
0695	Sign, Type IIA	8100398	240.000	Sft
0700	Sign, Type III, Erect, Salv	8100402	70.000	Ea
0705	Sign, Type III, Rem	8100403	546.000	Ea
0710	Sign, Type IIIA	8100404	451.000	Sft
0715	Sign, Type IIIB	8100405	1,764.000	Sft
0720	Sign, Type VB	8100425	43.000	Sft
0725	Reflective Panel for Permanent Sign Support, 3 foot	8100613	82.000	Ea
0730	Reflective Panel for Permanent Sign Support, 6 foot	8100616	28.000	Ea
0735	Bracket, H	8100650	1.000	Ea
0740	Sign, Type III, Rem, Salv	8102003	28.000	Ea
0745	Ground Mtd Sign Support, Rem	8102010	383.000	Ea
0750	_ Hand Digging Sign Post	8107050	460.000	Ea
0755	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	1,277.000	Ft
0760	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	567.000	Ft
0765	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	12.000	Ea
0770	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	11.000	Ea
0775	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	10.000	Ea
0780	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym	8110078	5.000	Ea

0785	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	3,473.000	Ft
0790	Pavt Mrkg, Polyurea, Bike, Small Sym	8110105	1.000	Ea
0795	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	234.000	Ft
0800	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	3,670.000	Ft
0805	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	1,299.000	Ft
0810	Pavt Mrkg, Regular Dry, 4 inch, White	8110125	1,034.000	Ft
0815	Pavt Mrkg, Regular Dry, 4 inch, Yellow	8110126	1,311.000	Ft
0820	Pavt Mrkg, Regular Dry, 6 inch, White	8110127	3,934.000	Ft
0825	Pavt Mrkg, Regular Dry, 6 inch, Yellow	8110128	300.000	Ft
0830	Pavt Mrkg, Regular Dry, 12 inch, White	8110131	686.000	Ft
0835	Pavt Mrkg, Regular Dry, 2nd Application, 4 inch, White	8110133	1,034.000	Ft
0840	Pavt Mrkg, Regular Dry, 2nd Application, 4 inch, Yellow	8110134	1,311.000	Ft
0845	Pavt Mrkg, Regular Dry, 2nd Application, 6 inch, White	8110135	3,934.000	Ft
0850	Pavt Mrkg, Regular Dry, 2nd Application, 6 inch, Yellow	8110136	300.000	Ft
0855	Pavt Mrkg, Regular Dry, 2nd Application, 12 inch, White	8110139	686.000	Ft
0860	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	22.000	Ea
0865	Pavt Mrkg, Polyurea, Only	8110410	28.000	Ea
0870	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	10.000	Ea
0875	Pavt Mrkg, Polyurea, Thru and Lt Turn Arrow Sym	8110416	4.000	Ea
0880	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	2.000	Ea
0885	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	12.000	Ea
0890	Recessing Pavt Mrkg, Longit	8110450	20,861.000	Ft
0895	Recessing Pavt Mrkg, Transv	8110451	4,579.000	Sft
0900	Recessing Pavt Mrkg, Guide Line	8110453	52.000	Ft
0905	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Dotted Turning Guide Line, White	8110562	52.000	Ft
0910	Pavt Mrkg, Wet Reflective Polyurea, 4 inch, White	8112114	1,734.000	Ft
0915	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	10,130.000	Ft
0920	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	1,194.000	Ft
0925	Pavt Mrkg, Wet Reflective Polyurea, 4 inch, Yellow	8112117	3,157.000	Ft
0930	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	4,646.000	Ft
0935	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	218.000	Ea
0940	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	218.000	Ea
0945	Pedestrian Type II Barricade, Temp	8120026	44.000	Ea
0950	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	500.000	Ea
0955	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	500.000	Ea
0960	Conc Barrier Ending, Temp, Det 2, Furn	8120041	1.000	Ea
0965	Conc Barrier Ending, Temp, Det 2, Oper	8120042	1.000	Ea
0970	Conc Barrier, Temp, Furn	8120081	35.000	Ft
0975	Conc Barrier, Temp, Oper	8120082	35.000	Ft
0980	Connected Arrow Board, Type C, Furn	8120155	5.000	Ea
0985	Connected Arrow Board, Type C, Oper	8120156	5.000	Ea
0990	Ltg for Night Work	8120160	1.000	LSUM

0995	Minor Traf Devices	8120170	1.000	LSUM
1000	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	39,116.000	Ft
1005	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	700.000	Ft
1010	Pavt Mrkg, Type NR, Paint, 24 inch, Stop Bar	8120216	158.000	Ft
1015	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	700.000	Ft
1020	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,846.000	Ft
1025	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	1,480.000	Ft
1030	Pavt Mrkg, Wet Reflective, Type R, Tape, Lt Turn Arrow	8120257	24.000	Ea
1035	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt Turn Arrow	8120258	1.000	Ea
1040	Pavt Mrkg, Wet Reflective, Type R, Tape, Thru Arrow	8120259	28.000	Ea
1045	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	721.000	Ft
1050	Sign Cover	8120310	20.000	Ea
1055	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	7.000	Ea
1060	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	7.000	Ea
1065	Sign, Type B, Temp, Prismatic, Furn	8120350	5,224.000	Sft
1070	Sign, Type B, Temp, Prismatic, Oper	8120351	5,224.000	Sft
1075	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	320.000	Sft
1080	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	320.000	Sft
1085	Traf Regulator Control	8120370	1.000	LSUM
1090	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	15,034.000	Ft
1095	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	38,457.000	Ft
1100	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	2,910.000	Ft
1105	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	23,298.000	Ft
1110	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	405.000	Ft
1115	Pavt Mrkg, Wet Reflective, Type NR, Paint, 12 inch, White, Temp	8122016	370.000	Ft
1120	Pavt Mrkg, Wet Reflective, Type R, Tape, Only	8122111	7.000	Ea
1125	Pavt Mrkg, Wet Reflective, Type R, Tape, Bike, Small Sym	8122142	1.000	Ea
1130	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt and Lt Turn Arrow Sym	8122145	2.000	Ea
1135	Pavt Mrkg, Wet Reflective, Type R, Tape, Thru and Lt Turn Arrow Sym	8122147	3.000	Ea
1140	Pavt Mrkg, Wet Reflective, Type R, Tape, Thru and Rt Turn Arrow Sym	8122148	4.000	Ea
1145	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, Cross Hatching, Yellow	8122181	66.000	Ft
1150	Pedestrian Path, Temp	8122250	1,030.000	Ft
1155	Pedestrian Ramp, Temp	8122251	16.000	Ea
1160	Site Preparation, Max \$28,800.00	8150001	1.000	LSUM

1165	Watering and Cultivating, First Season, Min \$14,000.00	8150002	1.000	LSUM
1170	Watering and Cultivating, 2nd Season, Min \$17,300.00	8150003	1.000	LSUM
1175	Acer rubrum, 2 inch	8150149	10.000	Ea
1180	Acer x freemanii 'Autumn Blaze', 2 inch	8150222	21.000	Ea
1185	Celtis occidentalis, 2 inch	8150780	20.000	Ea
1190	Ginko biloba 'Autumn Gold', 2 inch	8151632	39.000	Ea
1195	Tilia americana, 2 inch	8153843	8.000	Ea
1200	Ulmus x 'Homestead', 2 inch	8153960	28.000	Ea
1205	Zelkova serratta 'Green Vase', 2 inch	8154216	37.000	Ea
1210	_ Turf Establishment, Performance, Modified	8167011	35,907.000	Syd
1215	Conduit, Rem	8182000	8,765.000	Ft
1220	Conduit, Directional Bore, 1, 1 1/2 inch	8182034	35.000	Ft
1225	Conduit, Directional Bore, 1, 3 inch	8182035	840.000	Ft
1230	Conduit, Directional Bore, 2, 3 inch	8182037	2,600.000	Ft
1235	Conduit, DB, 1, 1 1/2 inch	8182048	1,795.000	Ft
1240	Conduit, DB, 1, 3 inch	8182050	285.000	Ft
1245	Conduit, DB, 2, 3 inch	8182053	16,725.000	Ft
1250	Conduit, DB, 3, 3 inch	8182056	390.000	Ft
1255	Conduit, DB, 4, 3 inch	8182059	160.000	Ft
1260	Conduit, DB, 1, 1 inch	8182060	205.000	Ft
1265	DB Cable, in Conduit, 600V, 1/C#6	8182187	6,570.000	Ft
1270	DB Cable, in Conduit, 600V, 1/C#8	8182188	29,860.000	Ft
1275	Cable, Rem	8182196	4,075.000	Ft
1280	Cable, Sec, Rem	8182199	25,385.000	Ft
1285	Cable Pole, TS, Disman	8182210	1.000	Ea
1290	Cable, Sec, 600V, 1, 3/C#6	8182238	1,550.000	Ft
1295	Cable, Equipment Grounding Wire, 1/C#8	8182292	17,070.000	Ft
1300	Hh, Heavy Duty Cover	8182308	123.000	Ea
1305	Hh, Polymer Conc	8182309	30.000	Ea
1310	Hh, Round	8182310	62.000	Ea
1315	Hh, Round, 3 foot dia	8182319	138.000	Ea
1320	Hh, Rem	8182330	78.000	Ea
1325	Wood Pole, Cl 4, 35 foot	8182350	9.000	Ea
1330	Wood Pole, Cl 4, 40 foot	8182351	3.000	Ea
1335	Wood Pole, Rem	8182363	13.000	Ea
1340	Serv Disconnect	8182366	14.000	Ea
1345	Serv Disconnect, Rem	8182367	15.000	Ea
1350	Wood Pole, Fit Up, Sec Cable Pole	8182381	1.000	Ea
1355	_ Cable, P.J., 600V, 1, 5/C#16	8187001	1,330.000	Ft
1360	_ Cable, P.J., 600V, 1, 7/C#16	8187001	3,115.000	Ft
1365	_ Cable, Shielded, P.J., 600V, 1, 2/C#16	8187001	380.000	Ft
1370	Light Std Fdn	8190279	82.000	Ea
1375	Light Std Fdn, Rem	8190280	19.000	Ea
1380	Light Std, Frangible Transformer Base	8190281	79.000	Ea

1385	Light Std Shaft, Rem	8190305	7.000	Ea
1390	Luminaire, Rem	8190360	7.000	Ea
1395	_ Decorative Light Fixture	8197050	79.000	Ea
1400	_ Light Std Municipal	8197050	12.000	Ea
1405	_ Light Std Municipal, Install Salv	8197050	28.000	Ea
1410	_ Light Std Municipal, Rem and Salv	8197050	30.000	Ea
1415	_ Ltg Control Panel	8197050	2.000	Ea
1420	_ Luminaire Municipal	8197050	47.000	Ea
1425	_ Luminaire Municipal, Rem and Salv	8197050	38.000	Ea
1430	_ Utility, Ltg	8197060	30,000.000	Dlr
1435	Case Sign Panel	8200003	4.000	Ea
1440	Case Sign Panel, Rem	8200004	4.000	Ea
1445	Case Sign, Rem	8200020	50.000	Ea
1450	Case Sign (LED), Two Way, 24 inch by 30 inch	8200022	12.000	Ea
1455	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	40.000	Ea
1460	Controller and Cabinet, Rem	8200030	15.000	Ea
1465	Controller Fdn, Base Mtd	8200045	15.000	Ea
1470	Controller Fdn, Rem	8200046	14.000	Ea
1475	Global Positioning System Module, Rem	8200053	2.000	Ea
1480	Fdn, Rem	8200065	35.000	Ea
1485	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	16.000	Ea
1490	Pedestal, Alum	8200100	69.000	Ea
1495	Pedestal, Fdn	8200105	94.000	Ea
1500	Pedestal Fdn, Rem	8200106	4.000	Ea
1505	Pedestal, Rem	8200110	4.000	Ea
1510	Pedestal, Underground Serv, Unmetered	8200112	4.000	Ea
1515	Pedestal, Pushbutton, Alum	8200118	22.000	Ea
1520	Pushbutton, Rem	8200122	6.000	Ea
1525	Push Button Station and Sign	8200128	100.000	Ea
1530	Span Wire	8200140	31.000	Ea
1535	Span Wire, Rem	8200141	70.000	Ea
1540	Steel Pole, Rem	8200145	33.000	Ea
1545	TS, Mast Arm Mtd, Rem	8200177	5.000	Ea
1550	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	58.000	Ea
1555	TS, Pedestrian, Pedestal Mtd, Rem	8200181	3.000	Ea
1560	TS, Span Wire Mtd, Rem	8200182	137.000	Ea
1565	Cabinet, NEMA Type	8200186	16.000	Ea
1570	TS, One Way Span Wire Mtd, Salv	8200191	23.000	Ea
1575	TS, Pedestrian, One Way Bracket Arm Mtd, Salv	8200226	1.000	Ea
1580	Pedestrian Signal System, Accessible	8200240	15.000	Ea
1585	TS, One Way Mast Arm Mtd, Salv	8200251	6.000	Ea
1590	TS, One Way Span Wire Mtd (LED)	8200313	18.000	Ea
1595	TS, Three Way Span Wire Mtd (LED)	8200325	3.000	Ea
1600	TS, Four Way Span Wire Mtd (LED)	8200327	2.000	Ea
1605	TS, Pedestrian, One Way Bracket Arm Mtd (LED)	8200336	5.000	Ea

Countdown				
1610	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	6.000	Ea
1615	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	49.000	Ea
1620	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	19.000	Ea
1625	Wireless Intercn, Closed Loop, Remote	8200395	1.000	Ea
1630	Wireless Intercn, Closed Loop, Rem	8200396	14.000	Ea
1635	TS Head, Adj	8200452	40.000	Ea
1640	TS Head, Temp	8200453	1.000	Ea
1645	TS Face, Bag	8200458	81.000	Ea
1650	TS Face, Bag, Rem	8200459	28.000	Ea
1655	Casing, 42 inch	8200485	299.000	Ft
1660	Cellular Modem, TS, 4th G	8200498	16.000	Ea
1665	Backplate, TS	8200501	84.000	Ea
1670	Radar Vehicle Presence Stop-Bar Detector System	8200510	15.000	Ea
1675	Radar Vehicle Presence Stop-Bar Detector System, Rem	8200511	9.000	Ea
1680	Radar Vehicle Presence Stop-Bar Detector System, Salv	8200512	7.000	Ea
1685	Radar Vehicle Presence Stop-Bar Detector Sensor	8200513	25.000	Ea
1690	Radar Vehicle Presence Stop-Bar Detector Sensor, Rem	8200514	14.000	Ea
1695	Radar Vehicle Presence Stop-Bar Detector Sensor, Salv	8200515	10.000	Ea
1700	Mast Arm Pole, Cat I	8202010	25.000	Ea
1705	Mast Arm, 25 foot, Cat I	8202014	1.000	Ea
1710	Mast Arm, 30 foot, Cat I	8202015	3.000	Ea
1715	Mast Arm, 35 foot, Cat I	8202016	3.000	Ea
1720	Mast Arm, 40 foot, Cat I	8202017	11.000	Ea
1725	Mast Arm, 45 foot, Cat I	8202018	13.000	Ea
1730	Mast Arm, 50 foot, Cat I	8202019	8.000	Ea
1735	Mast Arm Pole Fdn, 6 Bolt	8202034	386.000	Ft
1740	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	84.000	Ea
1745	TS, One Way Span Wire Mtd (LED), Long Life	8202287	14.000	Ea
1750	_ Controller, NEMA, ATC Type	8207050	16.000	Ea
1755	_ Pedestal Painting	8207050	91.000	Ea
1760	Monument Box	8210001	2.000	Ea
1765	Monument Preservation	8210010	2.000	Ea
1770	Protect Corners	8210020	34.000	Ea
1775	Fire Hydrant	8230040	6.000	Ea
1780	Gate Valve and Box, 6 inch	8230051	7.000	Ea
1785	Gate Valve and Box, 8 inch	8230052	10.000	Ea
1790	Gate Valve and Box, 10 inch	8230053	18.000	Ea
1795	Gate Well, Rem	8230076	4.000	Ea
1800	Hydrant, Rem	8230091	5.000	Ea
1805	Water Shutoff, Adj, Case 1	8230421	2.000	Ea

1810	Water Shutoff, Adj, Case 2	8230422	15.000	Ea
1815	Gate Box, Adj, Case 1	8230431	20.000	Ea
1820	Gate Box, Adj, Case 2	8230432	2.000	Ea
1825	Polyethylene Encasement	8230440	3,923.000	Ft
1830	_ Water Main, DI, 10 inch, Tr Det F, Modified	8237001	3,224.000	Ft
1835	_ Water Main, DI, 10 inch, Tr Det G, Modified	8237001	803.000	Ft
1840	_ Water Main, DI, 6 inch, Tr Det F, Modified	8237001	31.000	Ft
1845	_ Water Main, DI, 6 inch, Tr Det G, Modified	8237001	43.000	Ft
1850	_ Water Main, DI, 8 inch, Tr Det F, Modified	8237001	322.000	Ft
1855	_ Water Main, DI, 8 inch, Tr Det G, Modified	8237001	581.000	Ft
1860	_ Water Main, Rem	8237001	9,892.000	Ft
1865	_ Water Main Conflict, 10 inch, Spec	8237050	2.000	Ea
1870	_ Water Main Conflict, 6 inch, Spec	8237050	5.000	Ea
1875	_ Water Main Conflict, 8 inch, Spec	8237050	3.000	Ea
1880	_ Water Main, 11.25 Degree Bend, 10 inch	8237050	32.000	Ea
1885	_ Water Main, 11.25 Degree Bend, 6 inch	8237050	2.000	Ea
1890	_ Water Main, 11.25 Degree Bend, 8 inch	8237050	30.000	Ea
1895	_ Water Main, 22.5 Degree Bend, 10 inch	8237050	11.000	Ea
1900	_ Water Main, 22.5 Degree Bend, 8 inch	8237050	2.000	Ea
1905	_ Water Main, 45 Degree Bend, 10 inch	8237050	24.000	Ea
1910	_ Water Main, 45 Degree Bend, 6 inch	8237050	2.000	Ea
1915	_ Water Main, 45 Degree Bend, 8 inch	8237050	30.000	Ea
1920	_ Water Main, Cross, 10 inch by 10 inch by 10 inch by 10 inch	8237050	2.000	Ea
1925	_ Water Main, Cross, 10 inch by 10 inch by 8 inch by 8 inch	8237050	3.000	Ea
1930	_ Water Main, Cross, 8 inch by 8 inch by 4 inch by 4 inch	8237050	3.000	Ea
1935	_ Water Main, Tee, 10 inch by 10 inch by 10 inch	8237050	1.000	Ea
1940	_ Water Main, Tee, 10 inch by 10 inch by 6 inch	8237050	7.000	Ea
1945	_ Water Main, Tee, 10 inch by 10 inch by 8 inch	8237050	4.000	Ea
1950	_ Water Main, Tee, 8 inch by 8 inch by 6 inch	8237050	2.000	Ea
1955	_ Water Serv, Excavate and Backfill	8237050	6.000	Ea
1960	Contractor Staking	8240001	1.000	LSUM
1965	Staking Plan Errors and Extras, Max \$180/hour	8240002	442.000	Hr
1970	Sanitary Sewer, Conc, 12 inch, Tr Det B1	8252063	10.000	Ft
1975	Sanitary Structure Cover, Type Q	8252098	70.000	Ea
1980	Sanitary Structure Cover, Adj, Case 1	8252145	70.000	Ea
1985	Lightning Protection, Pole	8260021	15.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 002

**Letting Date:** October 3, 2025

**Contract ID:** 39024-210812

**Description:** 2.28 mi of hot mix asphalt cold milling and resurfacing including widening for additional ramp lane, roadway reconstruction, noise wall construction, signing, guardrail, drainage work and pavement markings on the I-94 Westbound ramp to US-131 Northbound in the cities of Portage and Kalamazoo, Kalamazoo County. This project includes two 5 year materials and workmanship pavement warranties and a 2 year concrete surface coating warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
210812A	FED/STATE	N/A	NH 39024

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Conc Quality Initiative	10000030	120.000	Dir
0010	Mobilization, Max \$1,365,000.00	1100001	1.000	LSUM
0015	Clearing	2010001	2.030	Acre
0020	Tree, Rem, 6 inch to 18 inch	2020004	2.000	Ea
0025	Culv, Rem, Less than 24 inch	2030001	7.000	Ea
0030	Dr Structure, Rem	2030011	1.000	Ea
0035	Sewer, Rem, Less than 24 inch	2030015	89.000	Ft
0040	Guardrail, Rem	2040035	3,142.000	Ft
0045	Pavt, Rem	2040050	19,923.000	Syd
0050	_ Pavt, Rem, Modified	2047011	3,883.000	Syd
0055	Embankment, CIP	2050010	25,590.000	Cyd
0060	Excavation, Earth	2050016	55,112.000	Cyd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	500.000	Cyd
0070	Subgrade Undercutting, Type II	2050041	100.000	Cyd
0075	Backfill, Structure, CIP	2060002	350.000	Cyd
0080	Excavation, Fdn	2060010	400.000	Cyd
0085	Erosion Control, Check Dam, Stone	2080012	2,080.000	Ft
0090	Erosion Control, Gravel Access Approach	2080016	3.000	Ea
0095	Erosion Control, Inlet Protection, Fabric Drop	2080020	12.000	Ea
0100	Erosion Control, Inlet Protection, Sediment Trap	2080024	2.000	Ea
0105	Erosion Control, Maintenance, Sediment Rem	2080026	55.000	Cyd
0110	Erosion Control, Sediment Trap	2080034	104.000	Ea
0115	Erosion Control, Silt Fence	2080036	7,329.000	Ft
0120	Subbase, CIP	3010002	33,545.000	Cyd
0125	Aggregate Base, 6 inch	3020016	52,527.000	Syd

0130	_ Shld, CI II, 4 1/2 inch	3077011	1,112.000	Syd
0135	_ Shld, CI II, 6 1/2 inch, Temp	3077011	200.000	Syd
0140	_ Shld, CI II, 8 1/4 inch	3077011	746.000	Syd
0145	_ Shld, CI II, 9 inch	3077011	3,777.000	Syd
0150	Road Grade Biaxial Geogrid	3082002	4,862.000	Syd
0155	Culv End Sect, 12 inch	4010012	1.000	Ea
0160	Culv End Sect, 15 inch	4010015	1.000	Ea
0165	Culv End Sect, 24 inch	4010024	4.000	Ea
0170	Culv End Sect, Footing	4010072	7.000	Ea
0175	Culv, CI A, 18 inch	4010133	78.000	Ft
0180	Culv, CI A, 24 inch	4010134	51.000	Ft
0185	Culv, Reinf Conc Ellip, HE CI IV, 19 inch by 30 inch	4010902	85.000	Ft
0190	Culv, Slp End Sect, 1 on 4, 18 inch, Longit	4010919	2.000	Ea
0195	Culv, Slp End Sect, 1 on 4, 24 inch, Longit	4010923	6.000	Ea
0200	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 19 inch by 30 inch, Transv	4011052	1.000	Ea
0205	Dr Marker Post	4011109	45.000	Ea
0210	Outfall Label	4011115	3.000	Ea
0215	_ Culv Cleanout	4017001	205.000	Ft
0220	_ Culv End Sect, Conc, Ellip Pipe, 19 inch x 30 inch	4017050	1.000	Ea
0225	Sewer, CI A, 24 inch, Tr Det A	4020007	254.000	Ft
0230	Sewer, CI A, 12 inch, Tr Det B	4020033	877.000	Ft
0235	Sewer, CI A, 15 inch, Tr Det B	4020034	350.000	Ft
0240	Sewer, CI A, 24 inch, Tr Det B	4020036	163.000	Ft
0245	Video Taping Sewer and Culv Pipe	4021275	1,858.000	Ft
0250	Dr Structure Cover, Type B	4030010	2.000	Ea
0255	Dr Structure Cover, Type CX	4030020	5.000	Ea
0260	Dr Structure Cover, Type G	4030040	5.000	Ea
0265	Dr Structure Cover, Type W	4030080	1.000	Ea
0270	Dr Structure, 48 inch dia	4030210	13.000	Ea
0275	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	37.000	Ft
0280	Dr Structure, Add Depth of 48 inch dia, more than 15 foot	4030251	4.000	Ft
0285	Underdrain, Subbase, 6 inch	4040063	17,835.000	Ft
0290	Underdrain Outlet, 6 inch	4040093	1,200.000	Ft
0295	Underdrain, Outlet Ending, 6 inch	4040113	48.000	Ea
0300	Video Inspection of Underdrain	4040200	19,035.000	Ft
0305	Cold Milling HMA Surface	5010002	18,193.000	Syd
0310	Bump Grinding	5010004	125.000	Syd
0315	HMA Surface, Rem	5010005	28,140.000	Syd
0320	HMA Quality Initiative	5010007	57,164.000	Dlr
0325	Longit Joint Density Quality Initiative	5010018	46,100.000	Dlr
0330	Hand Patching	5010025	77.000	Ton
0335	HMA Approach	5010061	655.000	Ton
0340	HMA, 2EML	5012001	2,406.000	Ton

0345	HMA, 2EMH	5012002	9,409.000	Ton
0350	HMA, 4EML	5012025	3,504.000	Ton
0355	HMA, 4EMH	5012026	12,531.000	Ton
0360	HMA, Temp Pavt (3EML)	5012101	80.000	Ton
0365	HMA, Temp Pavt (4EML)	5012103	50.000	Ton
0370	HMA, Temp Pavt (5EML)	5012105	40.000	Ton
0375	_ Ride Incentive	5017060	22,581.000	Dir
0380	Steel Sheet Piling, Permanent	7040001	70.000	Sft
0385	_ Noise Barrier Wall, Precast Conc, Erect	7087010	38,000.000	Sft
0390	_ Noise Barrier Wall, Precast Conc, Furn	7087010	38,000.000	Sft
0395	Conc Surface Coating, Warranty (NW01 of 39014)	7100009	1.000	LSUM
0400	Substructure Horizontal Surface Sealer (NW01 of 39014)	7100030	300.000	Syd
0405	Drilled Shaft Equipment, Furn (NW01 of 39014)	7180010	1.000	LSUM
0410	Drilled Shaft, 42 inch	7180042	2,400.000	Ft
0415	Temp Casing-Left in Place	7180121	2,400.000	Ft
0420	_ Temp Haul Road	8007051	1.000	LSUM
0425	Curb, Conc, Det G1	8020005	267.000	Ft
0430	Curb and Gutter, Conc, Det D2	8020031	1,254.000	Ft
0435	Shld Gutter, Conc, Det 2	8020056	1.000	Ea
0440	Spillway, Conc	8020075	8.000	Ft
0445	Guardrail Approach Terminal, Type 2M	8070044	7.000	Ea
0450	Guardrail Departing Terminal, Type MGS	8070052	6.000	Ea
0455	Guardrail Reflector	8070080	90.000	Ea
0460	Guardrail Anch, Bridge, Det M7	8070136	1.000	Ea
0465	Guardrail, Type MGS-8, 72 inch Post	8072179	3,964.000	Ft
0470	_ Guardrail, Type MGS-8, 72 inch Post, Nested, Spec	8077001	38.000	Ft
0475	Fence, Protective	8080007	1,273.000	Ft
0480	Bridge Sign Connection, Conc, Type C	8100033	1.000	Ea
0485	Cantilever, Type E	8100104	2.000	Ea
0490	Column, Breakaway, W8 x 13	8100120	10.000	Ea
0495	Delineator Reflector, Yellow	8100132	25.000	Ea
0500	Delineator Reflector, Green	8100133	20.000	Ea
0505	Delineator Reflector, White	8100134	78.000	Ea
0510	Fdn, Breakaway, W8 x 13	8100160	10.000	Ea
0515	Fdn, Cantilever Sign Structure Type E, 48 inch dia, Cased	8100170	54.000	Ft
0520	Fdn, Column Breakaway, Rem	8100220	14.000	Ea
0525	Fdn, Wood Support, Rem	8100280	19.000	Ea
0530	Delineator, Rem	8100349	104.000	Ea
0535	Post, Rigid, Delineator	8100361	123.000	Ea
0540	Post, Steel, 3 pound	8100371	628.000	Ft
0545	Post, Wood, 4 inch by 6 inch	8100380	138.000	Ft
0550	Post, Wood, 6 inch by 8 inch	8100382	146.000	Ft
0555	Sign, Type I, Erect, Salv	8100390	7.000	Ea

0560	Sign, Type I, Rem	8100391	7.000	Ea
0565	Sign, Type IA	8100392	1,333.000	Sft
0570	Sign, Type IB	8100393	135.000	Sft
0575	Sign, Type II, Erect, Salv	8100396	5.000	Ea
0580	Sign, Type II, Rem	8100397	1.000	Ea
0585	Sign, Type IIB	8100399	16.000	Sft
0590	Sign, Type III, Erect, Salv	8100402	22.000	Ea
0595	Sign, Type III, Rem	8100403	2.000	Ea
0600	Sign, Type IIIB	8100405	67.000	Sft
0605	Sign, Type IVB	8100411	34.000	Sft
0610	Transporting Salv MDOT Materials	8100420	1.000	LSUM
0615	Sign, Type V, Rem	8100421	4.000	Ea
0620	Sign, Type V, Erect, Salv	8100422	1.000	Ea
0625	Sign, Type VB	8100425	144.000	Sft
0630	Post, Flexible, Delineator, Ground Mtd	8100555	23.000	Ea
0635	Reflective Panel for Permanent Sign Support, 3 foot	8100613	4.000	Ea
0640	Reflective Panel for Permanent Sign Support, 6 foot	8100616	12.000	Ea
0645	Sign, Type I, Rem, Salv	8102001	7.000	Ea
0650	Sign, Type II, Rem, Salv	8102002	5.000	Ea
0655	Sign, Type III, Rem, Salv	8102003	22.000	Ea
0660	Sign, Type V, Rem, Salv	8102005	1.000	Ea
0665	Ground Mtd Sign Support, Rem	8102010	50.000	Ea
0670	Pavt Mrkg, Ovly Cold Plastic, Merge Arrow Sym	8110050	2.000	Ea
0675	Pavt Mrkg, Waterborne, 6 inch, White	8110233	20,725.000	Ft
0680	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	12,374.000	Ft
0685	Pavt Mrkg, Waterborne, 12 inch, White	8110237	3,970.000	Ft
0690	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	20,725.000	Ft
0695	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	12,374.000	Ft
0700	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	3,970.000	Ft
0705	Recessing Pavt Mrkg, Longit	8110450	31,869.000	Ft
0710	Recessing Pavt Mrkg, Transv	8110451	94.000	Sft
0715	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0720	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0725	Conc Barrier Ending, Temp, Det 2, Adj	8120040	3.000	Ea
0730	Conc Barrier Ending, Temp, Det 2, Furn	8120041	4.000	Ea
0735	Conc Barrier Ending, Temp, Det 2, Oper	8120042	4.000	Ea
0740	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	1.000	Ea
0745	Conc Barrier Reflector Replacement	8120070	125.000	Ea
0750	Conc Barrier, Temp, Adj	8120080	11,380.000	Ft
0755	Conc Barrier, Temp, Furn	8120081	11,600.000	Ft
0760	Conc Barrier, Temp, Oper	8120082	11,600.000	Ft
0765	Conc Barrier, Temp, Relocated	8120083	1,500.000	Ft
0770	Delineator, Flexible, Temp, Furn	8120091	132.000	Ea

0775	Delineator, Flexible, Temp, Oper	8120092	132.000	Ea
0780	High Intensity Light, Type B, Furn	8120110	7.000	Ea
0785	High Intensity Light, Type B, Oper	8120111	7.000	Ea
0790	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0795	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0800	Ltg for Night Work	8120160	1.000	LSUM
0805	Minor Traf Devices	8120170	1.000	LSUM
0810	Mobile Attenuator	8120180	1.000	Ea
0815	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	15,675.000	Ft
0820	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	1,000.000	Ft
0825	Pavt Mrkg, Longit, Water Blasting, 6 inch or less Width, Rem	8120212	2,554.000	Ft
0830	Plastic Drum, Fluorescent, Furn	8120252	250.000	Ea
0835	Plastic Drum, Fluorescent, Oper	8120253	250.000	Ea
0840	Sign Cover	8120310	30.000	Ea
0845	Sign Cover, Type I	8120320	2.000	Ea
0850	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	5.000	Ea
0855	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	5.000	Ea
0860	Sign, Type B, Temp, Prismatic, Furn	8120350	2,000.000	Sft
0865	Sign, Type B, Temp, Prismatic, Oper	8120351	2,000.000	Sft
0870	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	1,000.000	Sft
0875	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	1,000.000	Sft
0880	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	16,350.000	Ft
0885	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	13,100.000	Ft
0890	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	14,100.000	Ft
0895	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	11,400.000	Ft
0900	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	2,000.000	Ft
0905	Speed Radar Trailer, Temp	8122028	2.000	Ea
0910	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	1,500.000	Ft
0915	_ Filling Shld Corrugations with Micro-Surface	8127001	3,060.000	Ft
0920	_ Hand Chipping Shld Corrugations	8127001	3,060.000	Ft
0925	Riprap, Plain	8130010	165.000	Syd
0930	Site Preparation, Max \$7,200.00	8150001	1.000	LSUM
0935	Watering and Cultivating, First Season, Min \$3,500.00	8150002	1.000	LSUM
0940	Watering and Cultivating, 2nd Season, Min \$4,300.00	8150003	1.000	LSUM
0945	Ginko biloba 'Autumn Gold', 2 inch	8151632	6.000	Ea
0950	Liriodendron tulipifera, 2 inch	8152177	6.000	Ea
0955	Picea omorika, 5 foot	8152787	7.000	Ea
0960	Pinus nigra, 5 foot	8152842	7.000	Ea
0965	Quercus bicolor, 2 inch	8153044	4.000	Ea

---

0970	Ulmus parvifolia 'Emer II', 2 inch	8153944	4.000	Ea
0975	_ Acer rubrum 'Franksred', 2 inch	8157050	6.000	Ea
0980	Topsoil Surface, Furn, 3 inch	8160061	5,384.000	Syd
0985	Water, Sodding/Seeding	8160090	1.000	Unit
0990	Slope Restoration, Freeway, Type D	8162016	8,290.000	Syd
0995	Slope Restoration, Freeway, Type F	8162018	87,480.000	Syd
1000	Slope Restoration, Freeway, Type G	8162019	13,480.000	Syd
1005	_ Wildflower Seeding	8167011	5,384.000	Syd
1010	_ Sinusoidal Corrugations, Freeway, Milled, HMA Shld	8227001	20,892.000	Ft
1015	Contractor Staking	8240001	1.000	LSUM
1020	Staking Plan Errors and Extras, Max \$180/hour	8240002	143.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 003

**Letting Date:** October 3, 2025

**Contract ID:** 82191-216898

**Description:** 0.33 mi of noise wall construction and 0.34 mi of existing noise wall rehabilitation including concrete surface coating of existing and proposed walls, construction of proposed ditch and existing ditch cleanout on I-75 Northbound from north of Northline Road to south of Goddard Road in the city of Southgate, Wayne County. This project includes a 2 year concrete surface coating warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216898A	N/A	N/A	M 82191

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$461,800.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.600	Acre
0015	Structures, Rem Portions (NW-000139 of 82191)	2040061	1.000	LSUM
0020	Exploratory Investigation, Vertical	2040080	60.000	Ft
0025	Ditch Cleanout	2050006	18.000	Sta
0030	Embankment, CIP	2050010	1,824.000	Cyd
0035	Excavation, Earth	2050016	908.000	Cyd
0040	Non Haz Contaminated Material Handling and Disposal, LM	2050031	30.000	Cyd
0045	_ Phragmites Plant Material Handling and Disposal, LM	2057021	600.000	Cyd
0050	Erosion Control, Check Dam, Stone	2080012	392.000	Ft
0055	Erosion Control, Inlet Protection, Sediment Trap	2080024	1.000	Ea
0060	Erosion Control, Maintenance, Sediment Rem	2080026	20.000	Cyd
0065	Erosion Control, Sediment Trap	2080034	20.000	Ea
0070	Erosion Control, Silt Fence	2080036	7,220.000	Ft
0075	Project Cleanup	2090001	1.000	LSUM
0080	Culv End Sect, 24 inch	4010024	2.000	Ea
0085	Dr Marker Post	4011109	18.000	Ea
0090	Sewer, Cl A, 24 inch, Tr Det B	4020036	18.000	Ft
0095	Dr Structure Cover, Type B	4030010	1.000	Ea
0100	Dr Structure, 48 inch dia	4030210	1.000	Ea
0105	Underdrain Outlet, 6 inch	4040093	128.000	Ft
0110	Underdrain, Outlet Ending, 6 inch	4040113	16.000	Ea
0115	Video Inspection of Underdrain	4040200	128.000	Ft
0120	Reinforcement, Steel, Epoxy Coated	7060092	140,500.000	Lb
0125	_ Transporting Form Liners	7067051	1.000	LSUM

0130	_ Noise Barrier Wall, Precast Conc, Erect	7087010	45,200.000	Sft
0135	_ Noise Barrier Wall, Precast Conc, Furn	7087010	45,200.000	Sft
0140	Conc Surface Coating, Warranty (NW-000139 of 82191)	7100009	1.000	LSUM
0145	Conc Surface Coating, Warranty (NW-000357 of 82191)	7100009	1.000	LSUM
0150	Conc Surface Coating, Warranty (NW-000360 of 82191)	7100009	1.000	LSUM
0155	Substructure Horizontal Surface Sealer (NW-000357 of 82191)	7100030	2.000	Syd
0160	Substructure Horizontal Surface Sealer (NW-000360 of 82191)	7100030	15.000	Syd
0165	Drilled Shaft Equipment, Furn (NW-000357 of 82191)	7180010	1.000	LSUM
0170	Drilled Shaft Equipment, Furn (NW-000360 of 82191)	7180010	1.000	LSUM
0175	Drilled Shaft, 42 inch	7180042	2,460.000	Ft
0180	Obstruction Rem	7180100	10,000.000	Dlr
0185	Temp Casing-Left in Place	7180121	111.000	Ft
0190	Guardrail Departing Terminal, Type MGS	8070052	1.000	Ea
0195	Guardrail Reflector	8070080	3.000	Ea
0200	Guardrail, Type MGS-8, 72 inch Post	8072179	65.000	Ft
0205	Delineator Reflector, Green	8100133	19.000	Ea
0210	Fdn, Wood Support, Rem	8100280	2.000	Ea
0215	Post, Rigid, Delineator	8100361	1.000	Ea
0220	Post, Steel, 3 pound	8100371	32.000	Ft
0225	Post, Wood, 4 inch by 6 inch	8100380	64.000	Ft
0230	Sign, Type III, Rem	8100403	4.000	Ea
0235	Sign, Type IIIA	8100404	20.000	Sft
0240	Sign, Type IIIB	8100405	7.000	Sft
0245	Sign, Type V, Rem	8100421	2.000	Ea
0250	Sign, Type VB	8100425	32.000	Sft
0255	Reflective Panel for Permanent Sign Support, 3 foot	8100613	2.000	Ea
0260	Ground Mtd Sign Support, Rem	8102010	6.000	Ea
0265	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0270	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0275	Conc Barrier Ending, Temp, Det 2, Furn	8120041	1.000	Ea
0280	Conc Barrier Ending, Temp, Det 2, Oper	8120042	1.000	Ea
0285	Conc Barrier Reflector Replacement	8120070	20.000	Ea
0290	Conc Barrier, Temp, Furn	8120081	1,725.000	Ft
0295	Conc Barrier, Temp, Oper	8120082	1,725.000	Ft
0300	High Intensity Light, Type B, Furn	8120110	1.000	Ea
0305	High Intensity Light, Type B, Oper	8120111	1.000	Ea
0310	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0315	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0320	Minor Traf Devices	8120170	1.000	LSUM
0325	Mobile Attenuator	8120180	1.000	Ea

---

0330	Plastic Drum, Fluorescent, Furn	8120252	133.000	Ea
0335	Plastic Drum, Fluorescent, Oper	8120253	133.000	Ea
0340	Sign Cover	8120310	6.000	Ea
0345	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0350	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0355	Sign, Type B, Temp, Prismatic, Furn	8120350	708.000	Sft
0360	Sign, Type B, Temp, Prismatic, Oper	8120351	708.000	Sft
0365	Speed Radar Trailer, Temp	8122028	1.000	Ea
0370	Riprap, Plain	8130010	5.000	Syd
0375	Ditch, Plain Cobble	8140005	40.000	Syd
0380	Mulch Blanket, High Velocity	8160028	107.000	Syd
0385	_ Turf Establishment, Performance	8167011	14,550.000	Syd
0390	Contractor Staking	8240001	1.000	LSUM
0395	Staking Plan Errors and Extras, Max \$180/hour	8240002	50.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 004

**Letting Date:** October 3, 2025

**Contract ID:** 61075-215033

**Description:** Bridge rehabilitation including dual deck sealing system, deck patching, expansion joint replacement, structural steel repairs, partial and complete painting, silane treatment, substructure horizontal surface sealer, slope paving repair, substructure patching, thrie beam retrofit replacement and approach work on 4 structures, Muskegon County. This project includes a 2 year warranty on bridge coating.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215033A	25A0922	N/A	BFP 61075

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Conc Quality Initiative	1000030	1,568.000	Dir
0010	Mobilization, Max \$292,000.00	1100001	1.000	LSUM
0015	Culv, Rem, Less than 24 inch	2030001	4.000	Ea
0020	Curb and Gutter, Rem	2040020	196.000	Ft
0025	Pavt, Rem	2040050	587.000	Syd
0030	Excavation, Earth	2050016	345.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	5.000	Cyd
0040	Subgrade Undercutting, Type II	2050041	150.000	Cyd
0045	_ Embankment, CIP, Spec	2057021	120.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	50.000	Ea
0055	Erosion Control, Maintenance, Sediment Rem	2080026	10.000	Cyd
0060	Erosion Control, Sand Fence	2080030	400.000	Ft
0065	Erosion Control, Silt Fence	2080036	560.000	Ft
0070	Subbase, CIP	3010002	300.000	Cyd
0075	Aggregate Base, 6 inch	3020016	1,705.000	Syd
0080	Open-Graded Dr Cse, 6 inch	3030006	912.000	Syd
0085	Trenching	3070200	24.000	Sta
0090	Geotextile, Separator, Non-Woven	3082000	912.000	Syd
0095	Culv, Downspout, 15 inch	4010796	230.000	Ft
0100	_ Culv, Outlet Headwall, 15 inch	4017050	4.000	Ea
0105	Pavt, Cleaning	5010001	1.000	LSUM
0110	Cold Milling HMA Surface	5010002	2,336.000	Syd
0115	Bump Grinding	5010004	100.000	Syd
0120	HMA Surface, Rem	5010005	1,822.000	Syd
0125	HMA Quality Initiative	5010007	1,300.000	Dir
0130	Longit Joint Density Quality Initiative	5010018	4,800.000	Dir

0135	Hand Patching	5010025	12.000	Ton
0140	HMA Approach	5010061	638.000	Ton
0145	Joint, Expansion, E3	6020208	472.000	Ft
0150	Conc Pavt, Misc, Nonreinf, 9 1/2 inch, High Performance	6020515	128.000	Syd
0155	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	784.000	Syd
0160	Downspout Header, Conc	8020070	4.000	Ea
0165	Curb and Gutter, Bridge Approach, Det 1	8022010	37.000	Ft
0170	Curb and Gutter, Bridge Approach, Det 2	8022011	107.000	Ft
0175	Curb and Gutter, Bridge Approach, Det 3	8022012	63.000	Ft
0180	Curb and Gutter, Bridge Approach, Det 5	8022016	119.000	Ft
0185	Curb and Gutter, Bridge Approach, Det 7	8022018	40.000	Ft
0190	Guardrail Post, Furn and Install, 96 inch	8070103	48.000	Ea
0195	Guardrail, Reconst, Type B	8070105	339.000	Ft
0200	Guardrail, Reconst, Type T	8070109	247.000	Ft
0205	Pavt Mrkg, Sprayable Thermopl, 6 inch, White	8110155	770.000	Ft
0210	Pavt Mrkg, Sprayable Thermopl, 6 inch, Yellow	8110156	600.000	Ft
0215	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0225	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0230	Conc Barrier Ending, Temp, Det 2, Furn	8120041	4.000	Ea
0235	Conc Barrier Ending, Temp, Det 2, Oper	8120042	4.000	Ea
0240	Conc Barrier Ending, Temp, Det 4, Furn	8120051	4.000	Ea
0245	Conc Barrier Ending, Temp, Det 4, Oper	8120052	4.000	Ea
0250	Conc Barrier, Temp, Adj	8120080	4,050.000	Ft
0255	Conc Barrier, Temp, Furn	8120081	4,050.000	Ft
0260	Conc Barrier, Temp, Oper	8120082	4,050.000	Ft
0265	High Intensity Light, Type B, Furn	8120110	4.000	Ea
0270	High Intensity Light, Type B, Oper	8120111	4.000	Ea
0275	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0280	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0285	Minor Traf Devices	8120170	1.000	LSUM
0290	Pavt Mrkg Cover, Type R, Black	8120200	1,000.000	Ft
0295	Plastic Drum, Fluorescent, Furn	8120252	300.000	Ea
0300	Plastic Drum, Fluorescent, Oper	8120253	300.000	Ea
0305	Sign Cover	8120310	8.000	Ea
0310	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0315	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0320	Sign, Type B, Temp, Prismatic, Furn	8120350	2,410.000	Sft
0325	Sign, Type B, Temp, Prismatic, Oper	8120351	2,410.000	Sft
0330	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	29.000	Sft
0335	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	29.000	Sft
0340	TS, Temp, Furn	8120400	2.000	Ea

0345	TS, Temp, Oper	8120401	2.000	Ea
0350	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	6,400.000	Ft
0355	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	6,400.000	Ft
0360	Speed Radar Trailer, Temp	8122028	2.000	Ea
0365	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	432.000	Ft
0370	_ Filling Shld Corrugations with Micro-Surface	8127001	1,200.000	Ft
0375	Riprap, Plain	8130010	24.000	Syd
0380	Slope Restoration, Freeway, Type B	8162014	3,260.000	Syd
0385	Freeway Shld Corrugations, Milled, HMA	8222001	3,800.000	Ft
0390	Contractor Staking	8240001	1.000	LSUM
0395	Staking Plan Errors and Extras, Max \$180/hour	8240002	20.000	Hr

**Section: 2**

0400	Backfill, Structure, CIP	2060002	93.000	Cyd
0405	Excavation, Fdn	2060010	174.000	Cyd
0410	Underdrain, Fdn, 4 inch	4040031	146.000	Ft
0415	Underdrain, Outlet Ending, 4 inch	4040111	4.000	Ea
0420	Video Inspection of Underdrain	4040200	146.000	Ft
0425	HMA Patch, Rem	5010006	10.000	Syd
0430	Steel Sheet Piling, Temp	7040002	302.000	Sft
0435	Expansion Joint Device	7060050	375.000	Ft
0440	False Decking	7060060	4,134.000	Sft
0445	Reinforcement, Steel, Epoxy Coated	7060092	18,256.000	Lb
0450	Superstructure Conc, Form, Finish, and Cure (S14 of 61075)	7060111	1.000	LSUM
0455	Superstructure Conc, High Performance	7060116	19.000	Cyd
0460	Conc, Grade 4500HP	7062004	101.000	Cyd
0465	Shear Developers (S14 of 61075)	7070040	1.000	LSUM
0470	Joint Waterproofing	7100001	652.000	Sft
0475	Substructure Horizontal Surface Sealer (S11 of 61075)	7100030	23.000	Syd
0480	Substructure Horizontal Surface Sealer (S12 of 61075)	7100030	25.000	Syd
0485	Substructure Horizontal Surface Sealer (S13 of 61075)	7100030	27.000	Syd
0490	Substructure Horizontal Surface Sealer (S14 of 61075)	7100030	27.000	Syd
0495	_ Silane Treatment	7107010	4,175.000	Sft
0500	_ Dual Sealing System	7107011	2,219.000	Syd
0505	Bridge Railing, Thrie Beam Retrofit	7110006	441.000	Ft
0510	Hand Chipping, Deep	7120004	34.000	Syd
0515	Hand Chipping, Other Than Deck	7120007	544.000	Cft
0520	Patch, Forming	7120017	1,692.000	Sft
0525	Bolt, Adhesive Anchored, 1 inch	7120044	62.000	Ea
0530	Structures, Rehabilitation, Rem Portions (S11 of 61075)	7120070	1.000	LSUM
0535	Structures, Rehabilitation, Rem Portions (S12 of 61075)	7120070	1.000	LSUM

0540	Structures, Rehabilitation, Rem Portions (S13 of 61075)	7120070	1.000	LSUM
0545	Structures, Rehabilitation, Rem Portions (S14 of 61075)	7120070	1.000	LSUM
0550	Deck Joint, Rem	7120071	371.000	Ft
0555	Top Flanges and Beam Ends, Clean and Coat	7120100	27.000	Syd
0560	Patching Conc, C-L	7120112	26.000	Cyd
0565	Embedded Galvanic Anode	7120120	504.000	Ea
0570	_ Deck, Scaling	7127010	873.000	Sft
0575	Beam Plate, Seal Perimeter	7130010	870.000	Ft
0580	Cutting Beam Ends, Simple Span	7130020	2.000	Ea
0585	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	1,537.000	Lb
0590	Structural Steel, Welded Repr, Furn, Fab, and Erect	7130072	1,945.000	Lb
0595	Support, Column, Temp	7130080	16.000	Ea
0600	Steel Structure, Cleaning, Type 4 (S14 of 61075)	7150045	1.000	LSUM
0605	Steel Structure, Coating, Type 4 (S14 of 61075)	7150046	1.000	LSUM
0610	Steel Structure, Cleaning, Partial, Type 4 (S11 of 61075)	7150047	1.000	LSUM
0615	Steel Structure, Cleaning, Partial, Type 4 (S12 of 61075)	7150047	1.000	LSUM
0620	Steel Structure, Cleaning, Partial, Type 4 (S13 of 61075)	7150047	1.000	LSUM
0625	Steel Structure, Coating, Partial, Type 4 (S11 of 61075)	7150048	1.000	LSUM
0630	Steel Structure, Coating, Partial, Type 4 (S12 of 61075)	7150048	1.000	LSUM
0635	Steel Structure, Coating, Partial, Type 4 (S13 of 61075)	7150048	1.000	LSUM
0640	_ Heating and Housing (S11 of 61075)	7157051	1.000	LSUM
0645	_ Heating and Housing (S12 of 61075)	7157051	1.000	LSUM
0650	_ Heating and Housing (S13 of 61075)	7157051	1.000	LSUM
0655	_ Heating and Housing (S14 of 61075)	7157051	1.000	LSUM
0660	Field Repr of Damaged Coating (S11 of 61075)	7160001	1.000	LSUM
0665	Field Repr of Damaged Coating (S12 of 61075)	7160001	1.000	LSUM
0670	Guardrail Reflector	8070080	24.000	Ea
0675	Bridge Sign Connection, Conc, Type A1	8100031	2.000	Ea
0680	Bridge Sign Connection, Type A, Rem	8100080	2.000	Ea
0685	Sign, Type II, Rem	8100397	2.000	Ea
0690	Sign, Type IIB	8100399	22.000	Sft
0695	Slope Paving Header	8130015	115.000	Ft
0700	Slope Paving, Conc	8130020	290.000	Syd
0705	_ Slope Protection, Replace	8137011	80.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 005

**Letting Date:** October 3, 2025

**Contract ID:** 61023-215062

**Description:** Bridge reconstruction including removal and replacement with steel plate girders and approach work on M-46 over Crockery Creek, Muskegon County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215062A	25A0937	N/A	BFP 61023

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$367,800.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	2.000	Ea
0015	Pavt, Rem	2040050	440.000	Syd
0020	Excavation, Earth	2050016	2,580.000	Cyd
0025	Subgrade Undercutting, Type II	2050041	250.000	Cyd
0030	_ Embankment, CIP, Spec	2057021	656.000	Cyd
0035	Erosion Control, Check Dam, Stone	2080012	168.000	Ft
0040	Erosion Control, Filter Bag	2080014	4.000	Ea
0045	Erosion Control, Gravel Filter Berm	2080018	180.000	Ft
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	8.000	Ea
0055	Erosion Control, Inlet Protection, Sediment Trap	2080024	4.000	Ea
0060	Erosion Control, Maintenance, Sediment Rem	2080026	15.000	Cyd
0065	Erosion Control, Sand Bag	2080028	100.000	Ea
0070	Erosion Control, Sediment Basin	2080032	6.000	Cyd
0075	Erosion Control, Sediment Trap	2080034	4.000	Ea
0080	Erosion Control, Silt Fence	2080036	2,130.000	Ft
0085	Erosion Control, Turbidity Curtain, Deep	2080042	300.000	Ft
0090	Project Cleanup	2090001	1.000	LSUM
0095	Subbase, CIP	3010002	1,922.000	Cyd
0100	Aggregate Base, 6 inch	3020016	3,030.000	Syd
0105	Shld, CI II	3070121	158.000	Ton
0110	Culv End Sect, 12 inch	4010012	2.000	Ea
0115	Culv End Sect, Footing	4010072	2.000	Ea
0120	Dr Marker Post	4011109	2.000	Ea
0125	Sewer, CI A, 12 inch, Tr Det B	4020033	97.000	Ft
0130	Dr Structure Cover, Type C	4030015	4.000	Ea
0135	Dr Structure, 24 inch dia	4030200	2.000	Ea
0140	Dr Structure, 48 inch dia	4030210	2.000	Ea

0145	Underdrain, Subbase, 6 inch	4040063	1,216.000	Ft
0150	Underdrain, Subgrade, 6 inch	4040073	500.000	Ft
0155	Underdrain Outlet, 6 inch	4040093	102.000	Ft
0160	Underdrain, Outlet Ending, 6 inch	4040113	6.000	Ea
0165	Video Inspection of Underdrain	4040200	1,216.000	Ft
0170	Cold Milling HMA Surface	5010002	570.000	Syd
0175	Bump Grinding	5010004	100.000	Syd
0180	HMA Surface, Rem	5010005	2,750.000	Syd
0185	HMA Quality Initiative	5010007	1,954.000	Dlr
0190	Longit Joint Density Quality Initiative	5010018	5,256.000	Dlr
0195	HMA Approach	5010061	977.000	Ton
0200	Joint, Expansion, E3	6020208	90.000	Ft
0205	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	246.000	Syd
0210	Curb and Gutter, Conc, Det D2	8020031	217.000	Ft
0215	Curb and Gutter, Bridge Approach, Det 5	8022016	149.000	Ft
0220	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0225	Guardrail, Salv	8070075	814.000	Ft
0230	Guardrail Reflector	8070080	44.000	Ea
0235	Guardrail Anch, Bridge, Det M1	8070130	4.000	Ea
0240	Guardrail, Type MGS-8, 72 inch Post	8072179	276.000	Ft
0245	Guardrail, Type MGS-8, 108 inch Post	8072180	375.000	Ft
0250	Delineator Reflector, Green	8100133	4.000	Ea
0255	Post, Rigid, Delineator	8100361	4.000	Ea
0260	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	420.000	Ft
0265	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0270	Recessing Pavt Mrkg, Longit	8110450	1,500.000	Ft
0275	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, White	8112130	1,680.000	Ft
0280	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, Yellow	8112133	210.000	Ft
0285	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	24.000	Ea
0290	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	24.000	Ea
0295	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0300	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0305	Minor Traf Devices	8120170	1.000	LSUM
0310	Plastic Drum, Fluorescent, Furn	8120252	30.000	Ea
0315	Plastic Drum, Fluorescent, Oper	8120253	30.000	Ea
0320	Sign Cover	8120310	2.000	Ea
0325	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0330	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0335	Sign, Type B, Temp, Prismatic, Furn	8120350	806.000	Sft
0340	Sign, Type B, Temp, Prismatic, Oper	8120351	806.000	Sft
0345	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	144.000	Ft

0350	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	100.000	Ft
0355	Riprap, Plain	8130010	5.000	Syd
0360	Slope Restoration, Non-Freeway, Type B	8162002	1,535.000	Syd
0365	Slope Restoration, Non-Freeway, Type C	8162003	1,439.000	Syd
0370	Protect Corners	8210020	4.000	Ea
0375	Centerline Corrugations, Milled, HMA	8220013	615.000	Ft
0380	Non-Freeway Shld Corrugations, Milled, HMA	8220025	1,230.000	Ft
0385	Contractor Staking	8240001	1.000	LSUM
0390	Staking Plan Errors and Extras, Max \$180/hour	8240002	40.000	Hr

**Section: 2**

0395	Structures, Rem (B03 of 61023)	2040060	1.000	LSUM
0400	Backfill, Structure, CIP	2060002	1,710.000	Cyd
0405	Excavation, Fdn	2060010	4,570.000	Cyd
0410	Aggregate Base, LM	3020002	100.000	Cyd
0415	Underdrain, Fdn, 4 inch	4040031	370.000	Ft
0420	Underdrain Outlet, 4 inch	4040091	200.000	Ft
0425	Underdrain, Outlet Ending, 4 inch	4040111	4.000	Ea
0430	Steel Sheet Piling, Temp	7040002	100.000	Sft
0435	_ Cofferdam, Left in Place, Spec (B03 of 61023)	7047051	1.000	LSUM
0440	Pile Driving Equipment, Furn (B03 of 61023)	7050002	1.000	LSUM
0445	Pile, Steel, Furn and Driven, 14 inch	7050034	2,890.000	Ft
0450	_ Test Pile, Dynamic Analysis	7057050	6.000	Ea
0455	_ Test Pile, Furn Dynamic Analysis Equipment	7057050	4.000	Ea
0460	Bridge Ltg, Furn and Rem (B03 of 61023)	7060001	1.000	LSUM
0465	Bridge Ltg, Oper and Maintain	7060002	108.000	Cyd
0470	Expansion Joint Device	7060050	49.000	Ft
0475	False Decking	7060060	4,740.000	Sft
0480	Reinforcement, Steel, Epoxy Coated	7060092	35,656.000	Lb
0485	Substructure Conc, High Performance	7060101	440.000	Cyd
0490	Superstructure Conc, Form, Finish, and Cure (B03 of 61023)	7060111	1.000	LSUM
0495	Superstructure Conc, Form, Finish, and Cure, Night Casting (B03 of 61023)	7060112	1.000	LSUM
0500	Superstructure Conc, High Performance	7060116	36.000	Cyd
0505	Superstructure Conc, Night Casting, High Performance	7060117	108.000	Cyd
0510	Sealing Localized Cracks (B03 of 61023)	7060220	1.000	LSUM
0515	Conc, Grade 3500	7062001	1,270.000	Cyd
0520	_ Reinforcement, Steel, Low Carbon Chromium	7067030	35,152.000	Lb
0525	Bearing, Elastomeric, 1 3/4 inch	7070015	1,836.000	Sin
0530	Structural Steel, Plate, Erect	7070060	52,706.000	Lb
0535	_ Structural Steel, Plate, Furn and Fab, Galvanized	7077030	52,706.000	Lb
0540	_ Shear Developers, Galvanized (B03 of 61023)	7077051	1.000	LSUM
0545	Joint Waterproofing	7100001	170.000	Sft

---

0550	Joint Waterproofing, Expansion	7100003	216.000	Sft
0555	_ Silane Treatment	7107010	360.000	Sft
0560	Reflective Marker, Permanent Barrier	7110003	4.000	Ea
0565	Bridge Railing, Aesthetic Parapet Tube, High Performance	7110004	120.000	Ft
0570	Field Repr of Damaged Coating (B03 of 61023)	7160001	1.000	LSUM
0575	_ Riprap, Spec, Cl II	8137031	420.000	Ton
0580	Structure Survey During Construction (B03 of 61023)	8240020	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 006

**Letting Date:** October 3, 2025

**Contract ID:** 16033-220318

**Description:** 93.22 mi of application of shoulder and edgeline corrugations and pavement markings on various routes, Antrim, Charlevoix, Cheboygan, Crawford, Emmet, Iosco, Ogemaw, Otsego, and Roscommon Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220318A	25A0941	N/A	HSIP 16033

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$71,800.00	1100001	1.000	LSUM
0010	Pavt Mrkg, Waterborne, 6 inch, White	8110233	806,300.000	Ft
0015	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	14,700.000	Ft
0020	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0025	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	300.000	Ea
0030	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	300.000	Ea
0035	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0040	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0045	Minor Traf Devices	8120170	1.000	LSUM
0050	Mobile Attenuator	8120180	2.000	Ea
0055	Sign Cover	8120310	10.000	Ea
0060	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0065	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0070	Sign, Type B, Temp, Prismatic, Furn	8120350	1,700.000	Sft
0075	Sign, Type B, Temp, Prismatic, Oper	8120351	1,700.000	Sft
0080	Traf Regulator Control	8120370	1.000	LSUM
0085	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0090	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0095	_ Automated Flagger Assistance Device	8127050	6.000	Ea
0100	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	68,000.000	Ft
0105	_ Sinusoidal Corrugations, Milled, HMA Edgeline	8227001	821,000.000	Ft

**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 007**Letting Date:** October 3, 2025**Contract ID:** 52000-202921

**Description:** 177.55 mi of non-freeway sign upgrading on US-41 from M-28 westerly to Houghton County line, on M-28 from Alger County line westerly to US-41, on M-28 from US-41 westerly to Gogebic County line and on M-28 BR from US-41 southerly to US-41 in the cities of Ishpeming, Marquette and Negaunee, villages of Baraga and L'anse, Ontonagon, Marquette and Baraga Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
202921A	25A0926	N/A	STG 52000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$213,000.00	1100001	1.000	LSUM
0010	Sidewalk, Rem	2040055	100.000	Syd
0015	Sidewalk, Conc, 4 inch	8030044	900.000	Sft
0020	Band, Sign	8100010	197.000	Ea
0025	Bridge Sign Connection, Conc, Type A1	8100031	10.000	Ea
0030	Bridge Sign Connection, Type A, Rem	8100080	10.000	Ea
0035	Fdn, Wood Support, Rem	8100280	1,729.000	Ea
0040	Installing MDOT Supplied Sign, Type III	8100302	75.000	Ea
0045	Post Hole Through Conc for Steel Post	8100340	31.000	Ea
0050	Post Hole Through Conc for Wood Post	8100341	29.000	Ea
0055	Post, Steel, 3 pound	8100371	55,526.000	Ft
0060	Post, Wood, 4 inch by 6 inch	8100380	7,268.000	Ft
0065	Post, Wood, 6 inch by 8 inch	8100382	3,672.000	Ft
0070	Sign, Type I, Rem	8100391	7.000	Ea
0075	Sign, Type IA	8100392	916.000	Sft
0080	Sign, Type II, Erect, Salv	8100396	12.000	Ea
0085	Sign, Type II, Rem	8100397	515.000	Ea
0090	Sign, Type IIA	8100398	5,413.000	Sft
0095	Sign, Type IIB	8100399	222.000	Sft
0100	Sign, Type III, Erect, Salv	8100402	168.000	Ea
0105	Sign, Type III, Rem	8100403	2,755.000	Ea
0110	Sign, Type IIIA	8100404	6,560.000	Sft
0115	Sign, Type IIIB	8100405	9,922.000	Sft
0120	Transporting Salv MDOT Materials	8100420	1.000	LSUM
0125	Sign, Type V, Rem	8100421	32.000	Ea
0130	Sign, Type VA	8100424	404.000	Sft
0135	Sign, Type VB	8100425	1,602.000	Sft

0140	Reflective Panel for Permanent Sign Support, 3 foot	8100613	274.000	Ea
0145	Reflective Panel for Permanent Sign Support, 6 foot	8100616	1,208.000	Ea
0150	Bracket, H	8100650	104.000	Ea
0155	Sign, Type II, Rem, Salv	8102002	12.000	Ea
0160	Sign, Type III, Rem, Salv	8102003	168.000	Ea
0165	Ground Mtd Sign Support, Rem	8102010	2,785.000	Ea
0170	_ Post Hole Through Rock for Steel Post	8107050	40.000	Ea
0175	_ Post Hole Through Rock for Wood Post	8107050	40.000	Ea
0180	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0185	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0190	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0195	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0200	Minor Traf Devices	8120170	1.000	LSUM
0205	Mobile Attenuator	8120180	1.000	Ea
0210	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0215	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0220	Sign Cover	8120310	30.000	Ea
0225	Sign, Type B, Temp, Prismatic, Furn	8120350	700.000	Sft
0230	Sign, Type B, Temp, Prismatic, Oper	8120351	700.000	Sft
0235	Traf Regulator Control	8120370	1.000	LSUM
0240	Contractor Staking	8240001	1.000	LSUM
0245	Staking Plan Errors and Extras, Max \$180/hour	8240002	23.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 008

**Letting Date:** October 3, 2025

**Contract ID:** 72014-219902

**Description:** 13.42 mi of single course chip seal, fog seal, asphalt repair mastic and pavement markings on US-127 from north of the Muskegon River northerly to I-75, Roscommon and Crawford Counties. This project includes a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219902A	25A0939	N/A	NH 72014

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$241,300.00	1100001	1.000	LSUM
0010	_ Asphalt Repr Mastic	5027001	22,000.000	Ft
0015	Seal, Fog	5050015	652,500.000	Syd
0020	Chip Seal, Single, Warranty	5050040	652,500.000	Syd
0025	Pavt Mrkg, Ovly Cold Plastic, Merge Arrow Sym	8110050	2.000	Ea
0030	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	4.000	Ea
0035	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	4.000	Ea
0040	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	4.000	Ea
0045	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	450.000	Ft
0050	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	170.000	Ft
0055	Pavt Mrkg, Waterborne, 6 inch, White	8110233	190,000.000	Ft
0060	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	154,500.000	Ft
0065	Pavt Mrkg, Waterborne, 12 inch, White	8110237	6,400.000	Ft
0070	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	155,300.000	Ft
0075	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	154,500.000	Ft
0080	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	6,400.000	Ft
0085	Rem Spec Mrkg	8110343	1,160.000	Sft
0090	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0095	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	34,700.000	Ft
0100	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,600.000	Ea
0105	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,600.000	Ea
0110	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0115	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0120	Minor Traf Devices	8120170	1.000	LSUM
0125	Mobile Attenuator	8120180	1.000	Ea
0130	Sign Cover	8120310	10.000	Ea

0135	Sign, Type A, Temp, Prismatic, Furn	8120340	28.000	Sft
0140	Sign, Type A, Temp, Prismatic, Oper	8120341	28.000	Sft
0145	Sign, Type B, Temp, Prismatic, Furn	8120350	3,400.000	Sft
0150	Sign, Type B, Temp, Prismatic, Oper	8120351	3,400.000	Sft
0155	Speed Radar Trailer, Temp	8122028	2.000	Ea
0160	Contractor Staking	8240001	1.000	LSUM
0165	Staking Plan Errors and Extras, Max \$180/hour	8240002	29.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 009

**Letting Date:** October 3, 2025

**Contract ID:** 59032-201198

**Description:** 2.98 mi of hot mix asphalt shoulder widening, guardrail replacement, edgeline corrugations, one course hot mix asphalt overlay, minor pavement repairs and pavement markings on M-91 from Colby Road northerly to Stanton Road, Montcalm County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
201198A	25A0934	N/A	VRU 59032
221785A	25A0935	N/A	ST 59032

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$142,600.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	217.000	Ft
0015	Pavt, Rem	2040050	16.000	Syd
0020	Non Haz Contaminated Material Handling and Disposal, LM	2050031	15.000	Cyd
0025	Subgrade Undercutting, Type II	2050041	300.000	Cyd
0030	Subgrade Undercutting, Type IV	2050043	200.000	Cyd
0035	_ Embankment, CIP, Spec	2057021	732.000	Cyd
0040	Erosion Control, Silt Fence	2080036	2,300.000	Ft
0045	Aggregate Base, 6 inch	3020016	9,025.000	Syd
0050	Driveway Maintenance, Commercial	3062000	7.000	Ea
0055	Driveway Maintenance, Residential	3062001	63.000	Ea
0060	Approach, CI I, 6 inch	3070008	12.000	Syd
0065	Approach, CI II, 4 inch	3070026	904.000	Syd
0070	Shld, CI II	3070121	1,644.000	Ton
0075	Trenching	3070200	152.000	Sta
0080	Pavt, Cleaning	5010001	1.000	LSUM
0085	Cold Milling HMA Surface	5010002	2,057.000	Syd
0090	Bump Grinding	5010004	90.000	Syd
0095	HMA Surface, Rem	5010005	2,312.000	Syd
0100	HMA Quality Initiative	5010007	14,616.000	Dlr
0105	Pavt for Butt Joints, Rem	5010008	412.000	Syd
0110	Longit Joint Density Quality Initiative	5010018	31,426.000	Dlr
0115	HMA Approach	5010061	196.000	Ton
0120	HMA, 4EML	5012025	1,047.000	Ton
0125	HMA, 5EML	5012037	6,074.000	Ton
0130	Driveway, Nonreinf Conc, 6 inch	8010005	15.000	Syd

0135	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0140	Guardrail Reflector	8070080	32.000	Ea
0145	Post, Mailbox	8070095	27.000	Ea
0150	Guardrail Height, Adj	8070100	1,025.000	Ft
0155	Guardrail, Type MGS-8D, 108 inch Post	8072182	525.000	Ft
0160	Delineator Reflector, Green	8100133	4.000	Ea
0165	Delineator, Rem	8100349	2.000	Ea
0170	Post, Rigid, Delineator	8100361	4.000	Ea
0175	Post, Steel, 3 pound	8100371	29.000	Ft
0180	Sign, Type V, Erect, Salv	8100422	1.000	Ea
0185	Sign, Type V, Rem, Salv	8102005	1.000	Ea
0190	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0195	Pavt Mrkg, Waterborne, 6 inch, White	8110233	32,239.000	Ft
0200	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	18,319.000	Ft
0205	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	32,239.000	Ft
0210	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	18,319.000	Ft
0215	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	310.000	Ea
0220	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	310.000	Ea
0225	Minor Traf Devices	8120170	1.000	LSUM
0230	Plastic Drum, Fluorescent, Furn	8120252	15.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	15.000	Ea
0240	Sign Cover	8120310	20.000	Ea
0245	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0250	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0255	Sign, Type B, Temp, Prismatic, Furn	8120350	352.000	Sft
0260	Sign, Type B, Temp, Prismatic, Oper	8120351	352.000	Sft
0265	Traf Regulator Control	8120370	1.000	LSUM
0270	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,468.000	Ft
0275	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0280	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0285	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0290	Slope Restoration, Non-Freeway, Type F	8162006	6,923.000	Syd
0295	Monument Box, Adj	8210005	1.000	Ea
0300	Centerline Corrugations, Milled, HMA	8220013	17,304.000	Ft
0305	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	34,608.000	Ft
0310	Contractor Staking	8240001	1.000	LSUM
0315	Staking Plan Errors and Extras, Max \$180/hour	8240002	16.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 010

**Letting Date:** October 3, 2025

**Contract ID:** 53034-216141

**Description:** 4.58 mi of hot mix asphalt cold milling and resurfacing on US-31 from south of Chauvez Road to US-10, Mason County. This project includes a 3 year materials and workmanship pavement warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216141A	25A0944	N/A	NH 53034

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$312,000.00	1100001	1.000	LSUM
0010	Shld, CI II	3070121	450.000	Ton
0015	Cold Milling HMA Surface	5010002	247,000.000	Syd
0020	Bump Grinding	5010004	500.000	Syd
0025	HMA Quality Initiative	5010007	42,200.000	Dlr
0030	Longit Joint Density Quality Initiative	5010018	108,000.000	Dlr
0035	HMA Approach	5010061	200.000	Ton
0040	HMA, 5EML	5012037	20,900.000	Ton
0045	Pavt Mrkg, Polyurea, Wrong Way Arrow Sym	8110098	3.000	Ea
0050	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	110.000	Ft
0055	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0060	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea
0065	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	4.000	Ea
0070	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	88,000.000	Ft
0075	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	1,600.000	Ft
0080	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	74,000.000	Ft
0085	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	24.000	Ea
0090	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	24.000	Ea
0095	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0100	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0105	Minor Traf Devices	8120170	1.000	LSUM
0110	Plastic Drum, Fluorescent, Furn	8120252	400.000	Ea
0115	Plastic Drum, Fluorescent, Oper	8120253	400.000	Ea
0120	Sign Cover	8120310	6.000	Ea
0125	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0130	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea

0135	Sign, Type B, Temp, Prismatic, Furn	8120350	1,510.000	Sft
0140	Sign, Type B, Temp, Prismatic, Oper	8120351	1,510.000	Sft
0145	Pavt Mrkg, Wet Reflective, Type NR, Tape, 6 inch, White, Temp	8122008	2,000.000	Ft
0150	Speed Radar Trailer, Temp	8122028	2.000	Ea
0155	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	1,296.000	Ft
0160	_ Sinusoidal Corrugations, Freeway, Milled, HMA Shld	8227001	95,000.000	Ft
0165	Contractor Staking	8240001	1.000	LSUM
0170	Staking Plan Errors and Extras, Max \$180/hour	8240002	19.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 011

**Letting Date:** October 3, 2025

**Contract ID:** 10011-220322

**Description:** 95.56 mi installation of shoulder corrugations on various routes in Benzie, Grand Traverse, Kalkaska, Leelanau, Manistee, Missaukee and Wexford Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220322A	25A0940	N/A	HSIP 10011

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$60,600.00	1100001	1.000	LSUM
0010	Pavt Mrkg, Waterborne, 6 inch, White	8110233	939,184.000	Ft
0015	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0020	Connected Arrow Board, Type C, Furn	8120155	6.000	Ea
0025	Connected Arrow Board, Type C, Oper	8120156	6.000	Ea
0030	Minor Traf Devices	8120170	1.000	LSUM
0035	Mobile Attenuator	8120180	2.000	Ea
0040	Sign Cover	8120310	6.000	Ea
0045	Sign, Type B, Temp, Prismatic, Furn	8120350	736.000	Sft
0050	Sign, Type B, Temp, Prismatic, Oper	8120351	736.000	Sft
0055	Traf Regulator Control	8120370	1.000	LSUM
0060	Pavt Mrkg, Wet Reflective, Type R, Tape, Railroad Sym	8122144	1.000	Ea
0065	_ Pilot Car	8127051	1.000	LSUM
0070	_ Sinusoidal Corrugations, Milled, HMA Edgeline	8227001	939,184.000	Ft



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 012

**Letting Date:** October 3, 2025

**Contract ID:** 32021-202644

**Description:** 93.38 mi of non-freeway sign upgrading on M-142 from M-25 easterly to M-53, M-138 from Reese Road easterly to M-24 and M-81 from Reese Road to M-53 in the cities of Bad Axe, Caro, Harbor Beach, villages of Cass City, Elkton, Fairgrove, Pigeon and Reese, Huron and Tuscola Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
202644A	25A0927	N/A	STG 32021
202668A	25A0929	N/A	STG 79061

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$112,800.00	1100001	1.000	LSUM
0010	Sidewalk, Rem	2040055	50.000	Syd
0015	Exploratory Investigation, Vertical	2040080	20.000	Ft
0020	Sidewalk, Conc, 4 inch	8030044	450.000	Sft
0025	Band, Sign	8100010	160.000	Ea
0030	Fdn, Wood Support, Rem	8100280	116.000	Ea
0035	Installing MDOT Supplied Sign, Type III	8100302	129.000	Ea
0040	Post Hole Through Conc for Steel Post	8100340	125.000	Ea
0045	Post Hole Through Conc for Wood Post	8100341	19.000	Ea
0050	Post, Steel, 3 pound	8100371	38,312.000	Ft
0055	Post, Wood, 4 inch by 6 inch	8100380	4,366.000	Ft
0060	Post, Wood, 6 inch by 8 inch	8100382	1,120.000	Ft
0065	Sign, Type II, Erect, Salv	8100396	6.000	Ea
0070	Sign, Type II, Rem	8100397	304.000	Ea
0075	Sign, Type IIA	8100398	3,202.000	Sft
0080	Sign, Type IIB	8100399	130.000	Sft
0085	Sign, Type III, Erect, Salv	8100402	153.000	Ea
0090	Sign, Type III, Rem	8100403	2,076.000	Ea
0095	Sign, Type IIIA	8100404	3,475.000	Sft
0100	Sign, Type IIIB	8100405	8,107.000	Sft
0105	Sign, Type V, Rem	8100421	21.000	Ea
0110	Sign, Type VA	8100424	168.000	Sft
0115	Sign, Type VB	8100425	612.000	Sft
0120	Reflective Panel for Permanent Sign Support, 3 foot	8100613	210.000	Ea
0125	Reflective Panel for Permanent Sign Support, 6 foot	8100616	1,019.000	Ea
0130	Bracket, H	8100650	12.000	Ea

0135	Sign, Type II, Rem, Salv	8102002	12.000	Ea
0140	Sign, Type III, Rem, Salv	8102003	181.000	Ea
0145	Ground Mtd Sign Support, Rem	8102010	2,471.000	Ea
0150	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0155	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0160	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0165	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0170	Minor Traf Devices	8120170	1.000	LSUM
0175	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0180	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0185	Sign Cover	8120310	24.000	Ea
0190	Sign, Type B, Temp, Prismatic, Furn	8120350	700.000	Sft
0195	Sign, Type B, Temp, Prismatic, Oper	8120351	700.000	Sft
0200	Traf Regulator Control	8120370	1.000	LSUM
0205	Contractor Staking	8240001	1.000	LSUM
0210	Staking Plan Errors and Extras, Max \$180/hour	8240002	12.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 013

**Letting Date:** October 3, 2025

**Contract ID:** 13021-217013

**Description:** 5.49 mi of hot mix asphalt cold milling and resurfacing, concrete sidewalk ramps, carpool lot resurfacing and pavement markings on M-86 from Nottawa Street to Shimmel Road, M-60 from Glendale Avenue to East Main Street, the M-60 Carpool Lot east of I-69 and M-99 from Powers Street to M-60 in the villages of Centreville, Burlington and Homer, Saint Joseph and Calhoun Counties.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217013A	N/A	N/A	M 13021

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$196,500.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	352.000	Ft
0015	Pavt, Rem	2040050	66.000	Syd
0020	Sidewalk, Rem	2040055	196.000	Syd
0025	Embankment, CIP	2050010	37.000	Cyd
0030	Excavation, Earth	2050016	57.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	72.000	Ea
0045	Aggregate Base, 3 inch	3020008	160.000	Syd
0050	Aggregate Base, 4 inch	3020010	259.000	Syd
0055	Aggregate Base, Conditioning	3020050	15.000	Syd
0060	Dr Structure Cover, Adj, Case 1, Modified	4030004	3.000	Ea
0065	Dr Structure Cover, Adj, Case 1	4030005	16.000	Ea
0070	Dr Structure Cover, Type B	4030010	2.000	Ea
0075	Dr Structure Cover, Type Q	4030065	2.000	Ea
0080	Dr Structure, Adj, Add Depth	4030280	30.000	Ft
0085	Cold Milling HMA Surface	5010002	136,987.000	Syd
0090	HMA Surface, Rem	5010005	65.000	Syd
0095	HMA Quality Initiative	5010007	24,728.000	Dlr
0100	Longit Joint Density Quality Initiative	5010018	33,530.000	Dlr
0105	Hand Patching	5010025	16.000	Ton
0110	HMA Approach	5010061	745.000	Ton
0115	HMA, 5EML	5012037	11,603.000	Ton
0120	Conc Base Cse, Nonreinf, 7 1/2 inch	6020018	71.000	Syd
0125	_ Curb and Gutter, Conc, Det F4, Modified	8027001	41.000	Ft
0130	_ Curb and Gutter, Conc, Det F6, Modified	8027001	155.000	Ft

0135	Detectable Warning Surface	8030010	137.000	Ft
0140	Curb Ramp Opening, Conc	8030030	156.000	Ft
0145	Curb Ramp, Conc, 4 inch	8032001	1,549.000	Sft
0150	Curb Ramp, Conc, 6 inch	8032002	395.000	Sft
0155	_ Brick Pavers, Rem	8037010	428.000	Sft
0160	_ Reinstall Sidewalk, Brick Pavers on Conc and Sand Bed	8037010	288.000	Sft
0165	Fence, Protective	8080007	1,170.000	Ft
0170	_ Fence, Protective, Temp Base	8087050	185.000	Ea
0175	Delineator Reflector, Green	8100133	26.000	Ea
0180	Delineator, Rem	8100349	3.000	Ea
0185	Post, Rigid, Delineator	8100361	26.000	Ea
0190	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	34.000	Ft
0195	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	7.000	Ea
0200	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0205	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	2.000	Ea
0210	Pavt Mrkg, Waterborne, 6 inch, White	8110233	47,900.000	Ft
0215	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	22,850.000	Ft
0220	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	47,900.000	Ft
0225	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	22,850.000	Ft
0230	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	80.000	Ft
0235	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	565.000	Ft
0240	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0245	Recessing Pavt Mrkg, Transv	8110451	1,536.000	Sft
0250	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	400.000	Ft
0255	_ Pavt Mrkg, Waterborne, 2nd Application, 12 inch, Crosswalk	8117001	400.000	Ft
0260	_ Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Crosswalk	8117001	1,004.000	Ft
0265	_ Pavt Mrkg, Waterborne, 6 inch, Crosswalk	8117001	1,004.000	Ft
0270	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0275	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0280	Pedestrian Type II Barricade, Temp	8120026	78.000	Ea
0285	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,270.000	Ea
0290	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,270.000	Ea
0295	Connected Arrow Board, Type C, Furn	8120155	1.000	Ea
0300	Connected Arrow Board, Type C, Oper	8120156	1.000	Ea
0305	Minor Traf Devices	8120170	1.000	LSUM
0310	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	1,004.000	Ft
0315	Pavt Mrkg, Wet Reflective, Type R, Tape, Lt Turn Arrow	8120257	7.000	Ea
0320	Sign Cover	8120310	10.000	Ea
0325	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	9.000	Ea

0330	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	9.000	Ea
0335	Sign, Type B, Temp, Prismatic, Furn	8120350	2,320.000	Sft
0340	Sign, Type B, Temp, Prismatic, Oper	8120351	2,320.000	Sft
0345	Traf Regulator Control	8120370	1.000	LSUM
0350	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	840.000	Ft
0355	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,828.000	Ft
0360	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	240.000	Ft
0365	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, Cross Hatching, White	8122180	160.000	Ft
0370	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0375	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0380	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0385	Site Preparation, Max \$1,000.00	8150001	1.000	LSUM
0390	Fertilizer, Chemical Nutrient, CI B	8160021	6.000	Lb
0395	Mulch Blanket	8160027	190.000	Syd
0400	Seeding, Mixture TUF	8160042	10.000	Lb
0405	Topsoil Surface, Furn, 4 inch	8160062	190.000	Syd
0410	Monument Box	8210001	1.000	Ea
0415	Monument Box, Adj	8210005	5.000	Ea
0420	Monument Preservation	8210010	2.000	Ea
0425	Protect Corners	8210020	7.000	Ea
0430	Centerline Corrugations, Milled, HMA	8220013	12,855.000	Ft
0435	Non-Freeway Shld Corrugations, Milled, HMA	8220025	24,810.000	Ft
0440	Gate Box, Adj, Case 1	8230431	2.000	Ea
0445	Contractor Staking	8240001	1.000	LSUM
0450	Staking Plan Errors and Extras, Max \$180/hour	8240002	23.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 014

**Letting Date:** October 3, 2025

**Contract ID:** 23071-217482

**Description:** 1.43 mi of hot mix asphalt cold milling, single course overlay and pavement markings on M-100 from Doane Highway to Strange Highway, Eaton County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217482A	N/A	N/A	M 23071

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$45,100.00	1100001	1.000	LSUM
0010	Shld, CI II	3070121	629.000	Ton
0015	Cold Milling HMA Surface	5010002	23,784.000	Syd
0020	HMA Quality Initiative	5010007	3,924.000	Dlr
0025	Longit Joint Density Quality Initiative	5010018	22,651.000	Dlr
0030	HMA, 5EL	5012036	1,962.000	Ton
0035	Pavt Mrkg, Waterborne, 4 inch, White	8110231	15,101.000	Ft
0040	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	10,014.000	Ft
0045	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0050	Recessing Pavt Mrkg, Longit	8110450	25,115.000	Ft
0055	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	15,101.000	Ft
0060	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	10,014.000	Ft
0065	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	3.000	Ea
0070	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	3.000	Ea
0075	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	400.000	Ea
0080	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	400.000	Ea
0085	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0090	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0095	Minor Traf Devices	8120170	1.000	LSUM
0100	Mobile Attenuator	8120180	2.000	Ea
0105	Sign Cover	8120310	3.000	Ea
0110	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0115	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0120	Sign, Type B, Temp, Prismatic, Furn	8120350	400.000	Sft
0125	Sign, Type B, Temp, Prismatic, Oper	8120351	400.000	Sft
0130	Traf Regulator Control	8120370	1.000	LSUM

0135	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	9,500.000	Ft
0140	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0145	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0150	Protect Corners	8210020	6.000	Ea
0155	Centerline Corrugations, Milled, HMA	8220013	7,550.000	Ft
0160	Contractor Staking	8240001	1.000	LSUM
0165	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 015

**Letting Date:** October 3, 2025

**Contract ID:** 77000-219863

**Description:** 0.2 mi of compact roundabout construction, concrete curb and gutter, drainage improvements, permanent signing and pavement markings on Shea Road at the intersection of Starville Road, St Clair County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219863A	25A0875	N/A	HRRR 77000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$43,000.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	5.000	Ea
0015	Exploratory Investigation, Vertical	2040080	30.000	Ft
0020	_ Pavt, Rem, Modified	2047011	424.000	Syd
0025	Excavation, Earth	2050016	760.000	Cyd
0030	_ Embankment, CIP, Modified	2057021	600.000	Cyd
0035	_ Subgrade Undercutting, Modified	2057021	150.000	Cyd
0040	Erosion Control, Check Dam, Stone	2080012	40.000	Ft
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	1.000	Ea
0050	Project Cleanup	2090001	1.000	LSUM
0055	_ Aggregate Base, Modified	3027031	939.000	Ton
0060	HMA Base Crushing and Shaping	3050002	2,608.000	Syd
0065	Maintenance Gravel	3060020	100.000	Ton
0070	_ Approach, CI II, Modified	3077031	45.000	Ton
0075	_ Shld, CI II, Modified	3077031	72.000	Ton
0080	Culv, CI E, Conc, 18 inch	4010575	58.000	Ft
0085	Culv, CI F, 15 inch	4010608	184.000	Ft
0090	Culv, Reinf Conc Ellip, HE CI IV, 14 inch by 23 inch	4010901	31.000	Ft
0095	Sewer, CI IV, 12 inch, Tr Det B	4020987	25.000	Ft
0100	Sewer, Reinf Conc Ellip, HE CI IV, 14 inch by 23 inch, Tr Det B	4021450	134.000	Ft
0105	Dr Structure Cover, Type J	4030045	1.000	Ea
0110	Dr Structure, 48 inch dia	4030210	1.000	Ea
0115	HMA, 4EL, High Stress	5012072	927.000	Ton
0120	Conc Pavt, Nonreinf, 6 inch	6020100	152.000	Syd
0125	Conc Pavt, Nonreinf, 9 inch	6020106	168.000	Syd
0130	Joint, Expansion, E2	6020207	40.000	Ft
0135	Joint, Plane-of-Weakness, W	6020211	80.000	Ft

0140	Curb and Gutter, Conc, Det B2	8020016	814.000	Ft
0145	Shld Gutter, Conc, Det 2	8020056	7.000	Ea
0150	Shld Gutter, Conc, Det 3	8020057	1.000	Ea
0155	_ Curb and Gutter, Conc, Det D2, Modified, Central	8027001	139.000	Ft
0160	_ Curb and Gutter, Conc, Det D2, Modified, Splitter	8027001	782.000	Ft
0165	Post, Mailbox	8070095	2.000	Ea
0170	Pavt Mrkg, Polyurea, 6 inch, White	8110094	739.000	Ft
0175	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	922.000	Ft
0180	Pavt Mrkg, Polyurea, Yield	8110103	4.000	Ea
0185	Pavt Mrkg, Polyurea, 12 inch, White	8110111	243.000	Ft
0190	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	42.000	Ft
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	34.000	Ea
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	34.000	Ea
0205	Minor Traf Devices	8120170	1.000	LSUM
0210	Sign, Type B, Temp, Prismatic, Furn	8120350	409.000	Sft
0215	Sign, Type B, Temp, Prismatic, Oper	8120351	409.000	Sft
0220	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	219.000	Sft
0225	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	219.000	Sft
0230	Riprap, Plain	8130010	62.000	Syd
0235	Slope Restoration, Non-Freeway, Type F	8162006	1,652.000	Syd
0240	Slope Restoration, Non-Freeway, Type G	8162007	600.000	Syd
0245	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	1,600.000	Ft
0250	Water Shutoff, Adj, Case 2	8230422	2.000	Ea
0255	Gate Box, Adj, Case 2	8230432	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 016

**Letting Date:** October 3, 2025

**Contract ID:** 52000-220591

**Description:** 0.20 mi of hot mix asphalt road repair, aggregate shoulder, slope restoration, and pavement markings on County Road 571 from south of County Road PJ northerly and on County Road 581 from south of County Road PG northerly, Marquette County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220591A	25A0769	N/A	ER 52000
220592A	25A0770	N/A	ER 52000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$3,800.00	1100001	1.000	LSUM
0010	Embankment, CIP	2050010	2.000	Cyd
0015	Excavation, Earth	2050016	65.000	Cyd
0020	Project Cleanup	2090001	1.000	LSUM
0025	Aggregate Base, Conditioning	3020050	177.000	Syd
0030	Shld, CI II	3070121	39.000	Ton
0035	HMA Surface, Rem	5010005	164.000	Syd
0040	HMA, 4EML	5012025	19.000	Ton
0045	HMA, 5EML	5012037	15.000	Ton
0050	Post, Mailbox	8070095	2.000	Ea
0055	Pavt Mrkg, Waterborne, 4 inch, White	8110231	111.000	Ft
0060	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	136.000	Ft
0065	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0070	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0075	Minor Traf Devices	8120170	1.000	LSUM
0080	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0085	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0090	Sign, Type B, Temp, Prismatic, Furn	8120350	576.000	Sft
0095	Sign, Type B, Temp, Prismatic, Oper	8120351	576.000	Sft
0100	Traf Regulator Control	8120370	1.000	LSUM
0105	Riprap, Plain	8130010	33.000	Syd
0110	Slope Restoration, Non-Freeway, Type B	8162002	320.000	Syd
0115	Slope Restoration, Non-Freeway, Type D	8162004	298.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 017

**Letting Date:** October 3, 2025

**Contract ID:** 43000-214552

**Description:** 3.01 mi of hot mix asphalt paving, base crush and shape, culvert replacement, guardrail replacement, and permanent pavement markings in Lake County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
214552A	25A0832	N/A	STL 43000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$149,000.00	1100001	1.000	LSUM
0010	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0015	Guardrail, Rem	2040035	180.000	Ft
0020	Embankment, CIP	2050010	700.000	Cyd
0025	Excavation, Earth	2050016	440.000	Cyd
0030	_ Erosion Control, Silt Fence, Spec	2087001	4,000.000	Ft
0035	Aggregate Base	3020001	6,200.000	Ton
0040	HMA Base Crushing and Shaping	3050002	52,940.000	Syd
0045	Maintenance Gravel	3060020	100.000	Ton
0050	Approach, CI I, 6 inch	3070008	785.000	Syd
0055	Approach, CI II	3070021	90.000	Ton
0060	Shld, CI II	3070121	980.000	Ton
0065	Trenching	3070200	316.000	Sta
0070	Culv, CSP Arch, CI A, 35 inch by 24 inch	4010747	56.000	Ft
0075	HMA Approach	5010061	130.000	Ton
0080	HMA, 4EL	5012024	8,750.000	Ton
0085	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0090	Guardrail Reflector	8070080	12.000	Ea
0095	Post, Mailbox	8070095	22.000	Ea
0100	Guardrail, Type MGS-8, 72 inch Post	8072179	75.000	Ft
0105	Pavt Mrkg, Waterborne, 4 inch, White	8110231	28,150.000	Ft
0110	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	14,670.000	Ft
0115	Pavt Mrkg, Waterborne, 6 inch, White	8110233	3,650.000	Ft
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	22.000	Ea
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	22.000	Ea
0130	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0135	Lighted Arrow, Type C, Oper	8120141	2.000	Ea

0140	Minor Traf Devices	8120170	1.000	LSUM
0145	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,100.000	Ft
0150	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0155	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0160	Sign, Type B, Temp, Prismatic, Furn	8120350	460.000	Sft
0165	Sign, Type B, Temp, Prismatic, Oper	8120351	460.000	Sft
0170	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	121.000	Sft
0175	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	121.000	Sft
0180	Traf Regulator Control	8120370	1.000	LSUM
0185	Slope Restoration, Non-Freeway, Type F	8162006	21,000.000	Syd
0190	Slope Restoration, Non-Freeway, Type G	8162007	200.000	Syd
0195	Monument Box	8210001	5.000	Ea
0200	Monument Box, Adj	8210005	1.000	Ea
0205	Monument Preservation	8210010	6.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 018

**Letting Date:** October 3, 2025

**Contract ID:** 31000-214489

**Description:** 0.28 mi of hot mix asphalt base crushing, shaping and resurfacing, drainage structure adjustments, concrete sidewalks and ramps, and pavement markings in the city of Houghton, Houghton County.  
This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
214489A	25A0749	N/A	STUL 31000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$25,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	25.000	Ft
0015	Sidewalk, Rem	2040055	215.000	Syd
0020	Excavation, Earth	2050016	125.000	Cyd
0025	Subbase, CIP	3010002	100.000	Cyd
0030	Aggregate Base	3020001	125.000	Ton
0035	HMA Base Crushing and Shaping	3050002	6,350.000	Syd
0040	Material, Surplus and Unsuitable, Rem, LM	3050010	150.000	Cyd
0045	Sewer, CI A, 8 inch, Tr Det B	4020031	12.000	Ft
0050	Dr Structure Cover, Adj, Case 1, Modified	4030004	28.000	Ea
0055	Dr Structure Cover, Adj, Case 1	4030005	6.000	Ea
0060	Dr Structure Cover, Type B	4030010	2.000	Ea
0065	Dr Structure Cover, Type D	4030025	2.000	Ea
0070	Dr Structure, 24 inch dia	4030200	2.000	Ea
0075	Dr Structure, Tap, 8 inch	4030308	2.000	Ea
0080	_ Accessible Dr Structure Cover	4037050	3.000	Ea
0085	Hand Patching	5010025	5.000	Ton
0090	HMA Approach	5010061	175.000	Ton
0095	HMA, 4EML	5012025	465.000	Ton
0100	HMA, 5EML	5012037	465.000	Ton
0105	Curb and Gutter, Conc, Det F2	8020036	25.000	Ft
0110	Curb Ramp Opening, Conc	8030030	25.000	Ft
0115	_ Detectable Warning Surface, Modified	8037001	50.000	Ft
0120	_ Sidewalk, Conc, 6 inch, Modified	8037010	2,650.000	Sft
0125	Curb Slp, HMA	8050010	1,350.000	Ft
0130	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	650.000	Ft
0135	Pavt Mrkg, Polyurea, Bike, Large Sym	8110104	5.000	Ea

0140	Pavt Mrkg, Polyurea, 18 inch, Stop Bar	8110113	50.000	Ft
0145	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,100.000	Ft
0150	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	2,100.000	Ft
0155	Pavt Mrkg, Polyurea, School	8110414	1.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0165	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0170	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0175	Minor Traf Devices	8120170	1.000	LSUM
0180	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0185	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0190	Sign, Type B, Temp, Prismatic, Furn	8120350	205.000	Sft
0195	Sign, Type B, Temp, Prismatic, Oper	8120351	205.000	Sft
0200	_ Slope Restoration, Modified	8167011	100.000	Syd
0205	Water Shutoff, Adj, Case 1	8230421	10.000	Ea
0210	Contractor Staking	8240001	1.000	LSUM
0215	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 019

**Letting Date:** October 3, 2025

**Contract ID:** 63000-132535

**Description:** 1.20 mi of concrete road reconstruction, widening, water main, sewer main, drainage improvements, concrete sidewalk and ramps, permanent signing, traffic signals, and pavement markings in the city of Troy, Oakland County. This is a Local Agency and an OJT VIP Pilot Project. Please see Special Provision for Preparation and Consideration of Bids on On-the-Job-Training Voluntary Incentive Program Projects. This project includes a 5 year Local Agency pavement warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
132535A	25A0894	N/A	EDC 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	47,500.000	Dlr
0010	Mobilization, Max \$2,130,800.0	1100001	1.000	LSUM
0015	Clearing	2010001	0.230	Acre
0020	Tree, Rem, 19 inch to 36 inch	2020002	12.000	Ea
0025	Tree, Rem, 6 inch to 18 inch	2020004	37.000	Ea
0030	Stump, Rem, 19 inch to 36 inch	2020006	16.000	Ea
0035	Stump, Rem, 37 inch or Larger	2020007	2.000	Ea
0040	Stump, Rem, 6 inch to 18 inch	2020008	139.000	Ea
0045	Culv, End, Rem, Less than 24 inch	2030005	1.000	Ea
0050	Dr Structure, Rem	2030011	66.000	Ea
0055	Sewer, Rem, Less than 24 inch	2030015	6,313.000	Ft
0060	Sewer, Rem, 24 inch to 48 inch	2030016	218.000	Ft
0065	Curb and Gutter, Rem	2040020	485.000	Ft
0070	Pavt, Rem	2040050	60,527.000	Syd
0075	Sidewalk, Rem	2040055	7,375.000	Syd
0080	Exploratory Investigation, Vertical	2040080	100.000	Ft
0085	Embankment, CIP	2050010	14,200.000	Cyd
0090	Excavation, Earth	2050016	47,300.000	Cyd
0095	Non Haz Contaminated Material Handling and Disposal, LM	2050031	1,000.000	Cyd
0100	_ Subgrade Undercutting, Type II, Modified	2057021	12,000.000	Cyd
0105	Erosion Control, Check Dam, Stone	2080012	15.000	Ft
0110	Erosion Control, Inlet Protection, Fabric Drop	2080020	191.000	Ea
0115	Erosion Control, Maintenance, Sediment Rem	2080026	2.000	Cyd
0120	Erosion Control, Sediment Trap	2080034	1.000	Ea
0125	Erosion Control, Silt Fence	2080036	2,853.000	Ft

0130	Project Cleanup	2090001	1.000	LSUM
0135	_ Aggregate Base, 12 inch, Modified	3027011	72,804.000	Syd
0140	_ Aggregate Base, 4 inch, Modified	3027011	8,912.000	Syd
0145	_ Aggregate Base, 6 inch, Modified	3027011	8,724.000	Syd
0150	_ Aggregate Base, 8 inch, Modified	3027011	4,171.000	Syd
0155	Maintenance Gravel	3060020	2,000.000	Ton
0160	Approach, CI II, 6 inch	3070028	227.000	Syd
0165	Sewer, CI IV, 12 inch, Tr Det B	4020987	5,708.000	Ft
0170	Sewer, CI IV, 15 inch, Tr Det B	4020988	399.000	Ft
0175	Sewer, CI IV, 18 inch, Tr Det B	4020989	538.000	Ft
0180	Sewer, CI IV, 24 inch, Tr Det B	4020993	626.000	Ft
0185	Sewer, CI IV, 30 inch, Tr Det B	4020994	197.000	Ft
0190	Sewer, CI IV, 36 inch, Tr Det B	4020995	394.000	Ft
0195	Sewer Tap, 12 inch	4021204	4.000	Ea
0200	Sewer Tap, 36 inch	4021209	1.000	Ea
0205	Video Taping Sewer and Culv Pipe	4021275	7,862.000	Ft
0210	Dr Structure Cover, Adj, Case 1	4030005	34.000	Ea
0215	Dr Structure Cover, Adj, Case 2	4030006	7.000	Ea
0220	Dr Structure Cover, Type D	4030025	5.000	Ea
0225	Dr Structure Cover, Type G	4030040	9.000	Ea
0230	Dr Structure Cover, Type J	4030045	11.000	Ea
0235	Dr Structure Cover, Type K	4030050	112.000	Ea
0240	Dr Structure, 24 inch dia	4030200	62.000	Ea
0245	Dr Structure, 48 inch dia	4030210	60.000	Ea
0250	Dr Structure, 60 inch dia	4030220	10.000	Ea
0255	Dr Structure, Tap, 12 inch	4030312	21.000	Ea
0260	Dr Structure, Tap, 15 inch	4030315	1.000	Ea
0265	Dr Structure, Tap, 18 inch	4030318	3.000	Ea
0270	Dr Structure, Tap, 24 inch	4030324	2.000	Ea
0275	Dr Structure, Tap, 30 inch	4030330	1.000	Ea
0280	_ DPW Structure Cover, Adj, Add Depth	4037001	25.000	Ft
0285	_ DPW Structure Cover	4037050	132.000	Ea
0290	_ DPW Structure Cover, Adj	4037050	56.000	Ea
0295	_ Stormwater Hydrodynamic Separator No. 01	4037051	1.000	LSUM
0300	_ Stormwater Hydrodynamic Separator No. 02	4037051	1.000	LSUM
0305	Underdrain, Subgrade, Open-Graded, 6 inch	4040083	20,645.000	Ft
0310	Pavt, Cleaning	5010001	1.000	LSUM
0315	Bump Grinding	5010004	400.000	Syd
0320	HMA Surface, Rem	5010005	2,294.000	Syd
0325	HMA Approach	5010061	149.000	Ton
0330	HMA, 4EML	5012025	579.000	Ton
0335	_ Ride Incentive	5017060	23,144.000	Dir
0340	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	389.000	Syd
0345	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	702.000	Syd
0350	Joint, Contraction, Cp	6020200	31,750.000	Ft

0355	Joint, Expansion, E3	6020208	2,638.000	Ft
0360	Conc Pavt, Nonreinf, 10 inch, High Performance	6020504	48,166.000	Syd
0365	Conc Pavt, Misc, Nonreinf, 10 inch, High Performance	6020516	9,026.000	Syd
0370	_ Conc Pavt, Decorative, Nonreinf, 10 inch	6027011	232.000	Syd
0375	Lane Tie, Epoxy Anchored	6030030	13,952.000	Ea
0380	Driveway, Nonreinf Conc, 6 inch	8010005	987.000	Syd
0385	Driveway, Nonreinf Conc, 8 inch	8010007	3,031.000	Syd
0390	_ Remove and Replace Driveway, Spec	8017011	37.000	Syd
0395	Curb, Conc, Det E2	8020002	184.000	Ft
0400	Curb and Gutter, Conc, Det B1	8020015	1,170.000	Ft
0405	Curb and Gutter, Conc, Det D2	8020031	12.000	Ft
0410	Curb and Gutter, Conc, Det F4	8020038	75.000	Ft
0415	Curb and Gutter, Conc, Det F5	8020039	19,268.000	Ft
0420	Curb and Gutter, Conc, Det F6	8020040	16.000	Ft
0425	Driveway Opening, Conc, Det M	8020050	3,653.000	Ft
0430	Detectable Warning Surface	8030010	423.000	Ft
0435	Curb Ramp Opening, Conc	8030030	644.000	Ft
0440	Sidewalk, Conc, 4 inch	8030044	54,868.000	Sft
0445	Sidewalk, Conc, 6 inch	8030046	7,250.000	Sft
0450	Sidewalk, Conc, 8 inch	8030048	16,667.000	Sft
0455	Curb Ramp, Conc, 4 inch	8032001	1,876.000	Sft
0460	Curb Ramp, Conc, 6 inch	8032002	7,530.000	Sft
0465	Shared use Path, HMA	8060040	539.000	Ton
0470	Perforated Steel Square Tube Breakaway System	8100330	22.000	Ea
0475	Post, Steel, 3 pound	8100371	4,388.000	Ft
0480	Post, Wood, 4 inch by 6 inch	8100380	412.000	Ft
0485	Post, Wood, 6 inch by 8 inch	8100382	128.000	Ft
0490	Sign, Type II, Rem	8100397	10.000	Ea
0495	Sign, Type IIA	8100398	295.000	Sft
0500	Sign, Type IIB	8100399	184.000	Sft
0505	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0510	Sign, Type III, Rem	8100403	157.000	Ea
0515	Sign, Type IIIA	8100404	720.000	Sft
0520	Sign, Type IIIB	8100405	454.000	Sft
0525	Sign, Type VA	8100424	230.000	Sft
0530	Sign, Type VB	8100425	334.000	Sft
0535	Sign, Type III, Rem, Salv	8102003	1.000	Ea
0540	Ground Mtd Sign Support, Rem	8102010	113.000	Ea
0545	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	28.000	Ea
0550	Pavt Mrkg, Polyurea, 6 inch, White	8110094	10,228.000	Ft
0555	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	2,000.000	Ft
0560	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	530.000	Ft
0565	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	365.000	Ft
0570	Pavt Mrkg, Polyurea, Merge	8110407	2.000	Ea
0575	Recessing Pavt Mrkg, Longit	8110450	12,228.000	Ft

0580	Recessing Pavt Mrkg, Transv	8110451	1,886.000	Sft
0585	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	100.000	Ea
0590	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	100.000	Ea
0595	Pedestrian Type II Barricade, Temp	8120026	18.000	Ea
0600	Pedestrian Type II Channelizer, Temp	8120027	715.000	Ft
0605	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,030.000	Ea
0610	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,030.000	Ea
0615	Conc Barrier Ending, Temp, Det 2, Furn	8120041	22.000	Ea
0620	Conc Barrier Ending, Temp, Det 2, Oper	8120042	22.000	Ea
0625	Conc Barrier, Temp, Furn	8120081	715.000	Ft
0630	Conc Barrier, Temp, Oper	8120082	715.000	Ft
0635	Lighted Arrow, Type C, Furn	8120140	3.000	Ea
0640	Lighted Arrow, Type C, Oper	8120141	3.000	Ea
0645	Minor Traf Devices	8120170	1.000	LSUM
0650	Pavt Mrkg, Wet Reflective, Type NR, Paint, 4 inch, White, Temp	8120235	14,460.000	Ft
0655	Pavt Mrkg, Wet Reflective, Type NR, Paint, 4 inch, Yellow, Temp	8120236	18,800.000	Ft
0660	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	18,785.000	Ft
0665	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	28,100.000	Ft
0670	Pavt Mrkg, Wet Reflective, Type R, Tape, Lt Turn Arrow	8120257	8.000	Ea
0675	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt Turn Arrow	8120258	10.000	Ea
0680	Pavt Mrkg, Wet Reflective, Type NR, Tape, 4 inch, White, Temp	8120263	700.000	Ft
0685	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	6.000	Ea
0690	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	6.000	Ea
0695	Sign, Type A, Temp, Prismatic, Furn	8120340	225.000	Sft
0700	Sign, Type A, Temp, Prismatic, Oper	8120341	225.000	Sft
0705	Sign, Type B, Temp, Prismatic, Furn	8120350	3,015.000	Sft
0710	Sign, Type B, Temp, Prismatic, Oper	8120351	3,015.000	Sft
0715	Traf Regulator Control	8120370	1.000	LSUM
0720	Pavt Mrkg, Wet Reflective, Type R, Tape, Only	8122111	16.000	Ea
0725	Pedestrian Path, Temp	8122250	1,040.000	Ft
0730	Pedestrian Ramp, Temp	8122251	6.000	Ea
0735	Carpinus caroliniana, #10 cont.	8150735	366.000	Ea
0740	Nyssa sylvatica, 2 inch	8152513	44.000	Ea
0745	Fertilizer, Chemical Nutrient, Cl A	8160020	1,120.000	Lb
0750	Mulch	8160025	30,713.000	Syd
0755	Sodding	8160055	5,004.000	Syd
0760	Topsoil Surface, Furn, 3 inch	8160061	35,714.000	Syd
0765	Water, Sodding/Seeding	8160090	2,091.000	Unit

0770	Weed Control	8160095	4.000	Acre
0775	_ Mulch Anchoring, Modified	8167011	30,713.000	Syd
0780	_ Sod Replacement	8167011	1,000.000	Syd
0785	_ Seeding, Mixture THM, Modified	8167030	1,395.000	Lb
0790	Conduit, Rem	8182000	235.000	Ft
0795	Conduit, Directional Bore, 2, 3 inch	8182037	120.000	Ft
0800	Conduit, DB, 1, 1 1/4 inch	8182047	710.000	Ft
0805	Conduit, DB, 1, 3 inch	8182050	166.000	Ft
0810	Conduit, DB, 2, 3 inch	8182053	85.000	Ft
0815	Conduit, DB, 2, 4 inch	8182054	5.000	Ft
0820	Conduit, DB, 3, 3 inch	8182056	165.000	Ft
0825	Conduit, DB, 3, 4 inch	8182057	21.000	Ft
0830	Conduit, Schedule 80, 1 1/2 inch	8182145	40.000	Ft
0835	Conduit, Schedule 80, 2 inch	8182146	6,480.000	Ft
0840	DB Cable, in Conduit, Rem	8182197	665.000	Ft
0845	Cable, Sec, 600V, 1, 3/C#6	8182238	135.000	Ft
0850	Cable, Sec, 600V, 3, 1/C#6	8182246	700.000	Ft
0855	Hh, Round, 3 foot dia	8182319	2.000	Ea
0860	Hh, Rem	8182330	7.000	Ea
0865	Wood Pole, Cl 4, 30 foot	8182349	2.000	Ea
0870	Wood Pole, Cl 4, 40 foot	8182351	5.000	Ea
0875	Wood Pole, Rem	8182363	13.000	Ea
0880	Serv Disconnect	8182366	5.000	Ea
0885	Serv Disconnect, Rem	8182367	2.000	Ea
0890	Wood Pole, Fit Up, Sec Cable Pole	8182381	2.000	Ea
0895	Wood Pole, Fit Up, Sec Serv Pole	8182382	2.000	Ea
0900	Wood Pole, Fit Up, TS and Sec Cable Pole	8182386	3.000	Ea
0905	_ 2-#2 + 1-#2 Grd	8187001	3,140.000	Ft
0910	_ 4-#2 + 2-#2 Grd	8187001	3,130.000	Ft
0915	_ 4-#2 + 2-#6 Grd	8187001	295.000	Ft
0920	_ Conduit, Directional Bore, 2, 3 inch, RCOC	8187001	360.000	Ft
0925	_ Conduit, Directional Bore, 2, 4 inch, RCOC	8187001	150.000	Ft
0930	_ Conduit, Schedule 80, 1-6 inch and 2-4 inch Sleeve	8187001	995.000	Ft
0935	_ Hh, Round, 2 foot Dia, RCOC	8187050	13.000	Ea
0940	_ Hh, Round, 3 foot Dia, RCOC	8187050	4.000	Ea
0945	Light Std Arm, 15 foot	8190269	8.000	Ea
0950	Light Std Arm, Install Salv	8190276	4.000	Ea
0955	Light Std Arm, Rem	8190277	4.000	Ea
0960	Light Std Arm, Rem and Salv	8190278	4.000	Ea
0965	Light Std Fdn, Rem	8190280	2.000	Ea
0970	Light Std Shaft, Install Salv	8190301	2.000	Ea
0975	Light Std Shaft, Rem and Salv	8190306	2.000	Ea
0980	Luminaire, Install Salv	8190350	8.000	Ea
0985	Luminaire, Rem and Salv	8190365	8.000	Ea
0990	_ Lighting Control Enclosure	8197050	2.000	Ea

0995	_ Lighting Control Enclosure Concrete Base	8197050	2.000	Ea
1000	_ Type "OA" Light Std	8197050	32.000	Ea
1005	_ Type "OA" Light Std Fdn	8197050	34.000	Ea
1010	_ Type "OB" Luminaire	8197050	4.000	Ea
1015	_ Utility, Elec	8197060	2,000.000	Dlr
1020	Case Sign Panel	8200003	2.000	Ea
1025	Case Sign Panel, Rem	8200004	2.000	Ea
1030	Case Sign, Rem	8200020	5.000	Ea
1035	Controller and Cabinet, Rem	8200030	2.000	Ea
1040	Case Sign, Salv	8200039	1.000	Ea
1045	Controller Fdn, Base Mtd	8200045	3.000	Ea
1050	Controller Fdn, Rem	8200046	1.000	Ea
1055	Global Positioning System Module	8200050	1.000	Ea
1060	Digital Loop Detector	8200055	7.000	Ea
1065	Fdn, Rem	8200065	2.000	Ea
1070	Pedestal, Fdn	8200105	6.000	Ea
1075	Pedestal Fdn, Rem	8200106	3.000	Ea
1080	Pedestal, Rem	8200110	3.000	Ea
1085	Pushbutton and Sign	8200121	16.000	Ea
1090	Pushbutton, Rem	8200122	14.000	Ea
1095	Span Wire	8200140	13.000	Ea
1100	Span Wire, Rem	8200141	11.000	Ea
1105	Span Wire Tether	8200142	4.000	Ea
1110	Steel Pole, Rem	8200145	2.000	Ea
1115	Strut Guy	8200168	1.000	Ea
1120	TS, Bracket Arm Mtd, Rem	8200175	1.000	Ea
1125	TS, Pedestal Mtd, Rem	8200179	1.000	Ea
1130	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	11.000	Ea
1135	TS, Pedestrian, Pedestal Mtd, Rem	8200181	3.000	Ea
1140	TS, Span Wire Mtd, Rem	8200182	8.000	Ea
1145	TS, Pedestrian, Two Way Bracket Arm Mtd, Salv	8200228	2.000	Ea
1150	TS, One Way Span Wire Mtd (LED)	8200313	8.000	Ea
1155	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	2.000	Ea
1160	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	3.000	Ea
1165	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	4.000	Ea
1170	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	2.000	Ea
1175	TS, One Way Mast Arm Mtd (LED)	8200359	16.000	Ea
1180	Bracket, Truss, with 12 foot Arm	8200376	3.000	Ea
1185	Video Traf Detection Camera, Rem	8200384	4.000	Ea
1190	Bracket, Truss, Rem	8200388	4.000	Ea
1195	Emergency Pre-emption, Rem	8200415	3.000	Ea
1200	TS Head, Adj	8200452	19.000	Ea

1205	TS Head, Temp	8200453	16.000	Ea
1210	TS Face, Bag	8200458	31.000	Ea
1215	TS Face, Bag, Rem	8200459	31.000	Ea
1220	Strain Pole, Steel, 6 bolt, Size 1B	8200464	4.000	Ea
1225	Strain Pole, Steel, 6 bolt, Size 3	8200467	2.000	Ea
1230	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	65.000	Ft
1235	Casing, 42 inch	8200485	71.000	Ft
1240	Casing, 48 inch	8200486	44.000	Ft
1245	Mast Arm Pole, Cat III	8202012	8.000	Ea
1250	Mast Arm, 40 foot, Cat III	8202031	3.000	Ea
1255	Mast Arm, 45 foot, Cat III	8202032	2.000	Ea
1260	Mast Arm, 50 foot, Cat III	8202033	1.000	Ea
1265	Mast Arm Pole Fdn, 6 Bolt	8202034	99.000	Ft
1270	Mast Arm, 55 foot, Cat III	8202037	2.000	Ea
1275	TS, One Way Bracket Arm Mtd (LED), Long Life	8202200	2.000	Ea
1280	_ Antenna, Delivered, RCOC	8207050	3.000	Ea
1285	_ Backplate, TS, RCOC	8207050	24.000	Ea
1290	_ Cabinet, ITS Type, Delivered, RCOC	8207050	3.000	Ea
1295	_ Cabinet, ITS Type, RCOC	8207050	3.000	Ea
1300	_ Camera, Traf Monitoring, RCOC	8207050	3.000	Ea
1305	_ Camera, Traf Monitoring, Sytem Integration Support, RCOC	8207050	3.000	Ea
1310	_ Case Sign, One Way, 24 inch by 30 inch, Non-Illuminated, RCOC	8207050	18.000	Ea
1315	_ Case Sign, Two Way, 24 inch by 30 inch, Non-Illuminated, RCOC	8207050	3.000	Ea
1320	_ Cellular Router, 4/5G, Delivered, RCOC	8207050	3.000	Ea
1325	_ Controller, Digital Type, Delivered, SCATS, RCOC	8207050	3.000	Ea
1330	_ GPS Priority Control System, RCOC	8207050	3.000	Ea
1335	_ Ground Rod, RCOC	8207050	5.000	Ea
1340	_ Pedestal, Alum, RCOC	8207050	6.000	Ea
1345	_ Pushbutton Support Post, RCOC	8207050	12.000	Ea
1350	_ St Name Sign, Illuminated, Bracket Arm, RCOC	8207050	2.000	Ea
1355	_ St Name Sign, Illuminated, One Way, 8 foot, RCOC	8207050	6.000	Ea
1360	_ Traf Loop, Presence (Preformed), RCOC	8207050	22.000	Ea
1365	Gate Valve, 4 inch	8230060	1.000	Ea
1370	Gate Valve, 8 inch	8230062	7.000	Ea
1375	Gate Valve, 12 inch	8230064	25.000	Ea
1380	Gate Well, Abandon	8230075	1.000	Ea
1385	Gate Well, Rem	8230076	22.000	Ea
1390	Hydrant, Rem	8230091	31.000	Ea
1395	Water Main, DI, 6 inch, Tr Det F	8230150	22.000	Ft
1400	Water Main, DI, 6 inch, Tr Det G	8230151	168.000	Ft
1405	Water Main, DI, 8 inch, Tr Det F	8230155	121.000	Ft
1410	Water Main, DI, 8 inch, Tr Det G	8230156	110.000	Ft
1415	Water Main, DI, 12 inch, Tr Det F	8230165	4,989.000	Ft

1420	Water Main, DI, 12 inch, Tr Det G	8230166	3,055.000	Ft
1425	Gate Well, 60 inch dia	8230360	8.000	Ea
1430	Gate Well, 72 inch dia	8230372	25.000	Ea
1435	_ 20 inch O.D. Steel Casing (0.375 inch Min. Wall)	8237001	90.000	Ft
1440	_ Boring for Casing	8237001	90.000	Ft
1445	_ Copper Tubing, 1.5 inch	8237001	1,050.000	Ft
1450	_ Remove and Dispose of Existing Water Main (A/C) (Bag and Deliver)	8237001	100.000	Ft
1455	_ Water Main, DI, 4 inch, Tr Det F	8237001	24.000	Ft
1460	_ Curb Stop, Curb Box, and Stem (1.5 inch), Complete	8237050	35.000	Ea
1465	_ Fire Hydrant, Modified	8237050	32.000	Ea
1470	_ Nitrile Gasket	8237050	10.000	Ea
1475	_ Water Main Blow Off, 2 inch	8237050	14.000	Ea
1480	_ Water Main Connection, 12 inch	8237050	10.000	Ea
1485	_ Water Main Connection, 4 inch	8237050	1.000	Ea
1490	_ Water Main Connection, 8 inch	8237050	10.000	Ea
1495	_ Water Serv Reconnection, Saddle Tap, 1.5 inch	8237050	35.000	Ea
1500	Contractor Staking	8240001	1.000	LSUM
1505	Staking Plan Errors and Extras, Max \$180/hour	8240002	232.000	Hr
1510	Sanitary Structure, 60 inch dia	8252073	12.000	Ea
1515	Sanitary Structure, Rem	8252105	11.000	Ea
1520	Sanitary Structure, Tap, 8 inch	8252111	1.000	Ea
1525	_ Sanitary Sewer Rehab, CIPP Lining, 12 inch	8257001	119.000	Ft
1530	_ Sanitary Sewer, Conc, 21 inch, Tr Det B1	8257001	2,317.000	Ft
1535	_ Sanitary Sewer, PVC, Truss, 8 inch	8257001	32.000	Ft
1540	_ Sanitary Structure, Tap, 21 inch	8257050	1.000	Ea
1545	_ Sprinkler Line	8507001	1,000.000	Ft
1550	_ Irrigation Control Box, Relocate	8507050	5.000	Ea
1555	_ Irrigation Control Box, Replace	8507050	5.000	Ea
1560	_ Sprinkler Head, Relocate	8507050	50.000	Ea
1565	_ Sprinkler Head, Replace	8507050	50.000	Ea



9/4/2025 3:05 PM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 020

**Letting Date:** October 3, 2025

**Contract ID:** 77000-221964

**Description:** 24.98 mi of centerline rumble strips and pavement markings on various routes in St. Clair County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221964A	25A0896	N/A	HSIP 77000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$9,700.00	1100001	1.000	LSUM
0010	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	76,144.000	Ft
0015	Minor Traf Devices	8120170	1.000	LSUM
0020	_ Sinusoidal Corrugations, Milled, HMA Centerline	8227001	124,099.000	Ft



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 021

**Letting Date:** October 3, 2025

**Contract ID:** 25000-220864

**Description:** 0.31 mi of hot mix asphalt cold milling, resurfacing and widening for center left turn lane, concrete curb and gutter, drainage improvements, signing and pavement markings on Irish Road at Court Street, Genesee County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220864A	25A0874	N/A	HSIP 25000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$56,800.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	3.000	Ea
0015	Sewer, Rem, Less than 24 inch	2030015	32.000	Ft
0020	Curb and Gutter, Rem	2040020	2,080.000	Ft
0025	Pavt, Rem	2040050	1,395.000	Syd
0030	Embankment, CIP	2050010	150.000	Cyd
0035	Excavation, Earth	2050016	1,042.000	Cyd
0040	_ Subgrade Undercutting, Type IV, Modified	2057021	195.000	Cyd
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	10.000	Ea
0050	_ Erosion Control, Silt Fence, Spec	2087001	1,350.000	Ft
0055	_ Aggregate Base, 12 inch, Modified	3027011	1,525.000	Syd
0060	_ Aggregate Base, 4 inch, Modified	3027011	294.000	Syd
0065	_ Maintenance Gravel, Modified	3067031	150.000	Ton
0070	Sewer, CI IV, 12 inch, Tr Det B	4020987	23.000	Ft
0075	Sewer Tap, 12 inch	4021204	1.000	Ea
0080	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0085	Dr Structure Cover, Type B	4030010	1.000	Ea
0090	Dr Structure Cover, Type K	4030050	4.000	Ea
0095	Dr Structure, 24 inch dia	4030200	1.000	Ea
0100	Dr Structure, 48 inch dia	4030210	3.000	Ea
0105	Dr Structure, Tap, 6 inch	4030306	3.000	Ea
0110	Dr Structure, Tap, 12 inch	4030312	2.000	Ea
0115	Dr Structure, Temp Lowering	4030390	1.000	Ea
0120	_ Adjusting Sanitary Sewer Manhole Cover, Case 1, Special	4037050	4.000	Ea
0125	Underdrain, Subgrade, 6 inch	4040073	1,846.000	Ft
0130	Cold Milling HMA Surface	5010002	11,670.000	Syd
0135	Hand Patching	5010025	105.000	Ton

0140	HMA, 3EMH	5012014	625.000	Ton
0145	HMA, 4EMH	5012026	470.000	Ton
0150	HMA, 5EMH	5012038	1,355.000	Ton
0155	_ HMA Driveway, Spec	5017031	9.000	Ton
0160	_ Driveway, Nonreinf Conc, 8 inch, Modified	8017011	294.000	Syd
0165	Curb and Gutter, Conc, Det F4	8020038	1,806.000	Ft
0170	Driveway Opening, Conc, Det M	8020050	260.000	Ft
0175	Post, Mailbox	8070095	3.000	Ea
0180	Sign, Type III, Rem	8100403	1.000	Ea
0185	Ground Mtd Sign Support, Rem	8102010	1.000	Ea
0190	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	200.000	Ft
0195	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	40.000	Ft
0200	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	1.000	Ea
0205	Pavt Mrkg, Waterborne, 4 inch, White	8110231	65.000	Ft
0210	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	3,893.000	Ft
0215	Pavt Mrkg, Waterborne, 6 inch, White	8110233	681.000	Ft
0220	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	65.000	Ft
0225	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	3,893.000	Ft
0230	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	681.000	Ft
0235	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	2.000	Ea
0240	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	2.000	Ea
0245	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	60.000	Ea
0250	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	60.000	Ea
0255	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0260	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0265	Minor Traf Devices	8120170	1.000	LSUM
0270	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	1,500.000	Ft
0275	Plastic Drum, Fluorescent, Furn	8120252	10.000	Ea
0280	Plastic Drum, Fluorescent, Oper	8120253	10.000	Ea
0285	Sign, Type B, Temp, Prismatic, Furn	8120350	300.000	Sft
0290	Sign, Type B, Temp, Prismatic, Oper	8120351	300.000	Sft
0295	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	12.000	Sft
0300	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	12.000	Sft
0305	Traf Regulator Control	8120370	1.000	LSUM
0310	_ Slope Restoration, Modified	8167011	870.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 022

**Letting Date:** October 3, 2025

**Contract ID:** 63000-220151

**Description:** Traffic signal modernizations, pedestrian hybrid beacon installation, sidewalk ramp upgrades and pavement markings on various routes in the city of Pontiac, Oakland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220151A	25A0860	N/A	HSIP 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	22,500.000	Dir
0010	Mobilization, Max \$88,900.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	367.000	Ft
0020	Pavt, Rem	2040050	55.000	Syd
0025	Sidewalk, Rem	2040055	223.000	Syd
0030	Exploratory Investigation, Vertical	2040080	150.000	Ft
0035	Embankment, CIP	2050010	20.000	Cyd
0040	Excavation, Earth	2050016	10.000	Cyd
0045	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0055	Erosion Control, Silt Fence	2080036	100.000	Ft
0060	Aggregate Base, 4 inch	3020010	328.000	Syd
0065	Dr Structure Cover, Type B	4030010	1.000	Ea
0070	_ Public Utility Structure Cover, Adj, Case 1, City of Pontiac	4037050	13.000	Ea
0075	_ Public Utility Structure Cover, Adj, Case 2, City of Pontiac	4037050	1.000	Ea
0080	HMA Surface, Rem	5010005	87.000	Syd
0085	Hand Patching	5010025	23.000	Ton
0090	Conc Base Cse, Nonreinf, 8 inch	6020019	91.000	Syd
0095	Conc Pavt, Nonreinf, 6 inch	6020100	6.000	Syd
0100	Curb and Gutter, Conc, Det F3	8020037	6.000	Ft
0105	Curb and Gutter, Conc, Det F4	8020038	235.000	Ft
0110	Detectable Warning Surface	8030010	80.000	Ft
0115	Curb Ramp Opening, Conc	8030030	128.000	Ft
0120	Sidewalk, Conc, 4 inch	8030044	676.000	Sft
0125	Curb Ramp, Conc, 6 inch	8032002	1,465.000	Sft
0130	Post, Steel, 3 pound	8100371	64.000	Ft

0135	Sign, Type III, Rem	8100403	4.000	Ea
0140	Sign, Type IIIB	8100405	54.000	Sft
0145	Reflective Panel for Permanent Sign Support, 3 foot	8100613	8.000	Ea
0150	Ground Mtd Sign Support, Rem	8102010	1.000	Ea
0155	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	618.000	Ft
0160	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	185.000	Ft
0165	Pavt Mrkg, Sprayable Thermopl, 4 inch, White	8110153	1,800.000	Ft
0170	Pavt Mrkg, Sprayable Thermopl, 4 inch, Yellow	8110154	2,600.000	Ft
0175	Rem Spec Mrkg	8110343	506.000	Sft
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	18.000	Ea
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	18.000	Ea
0190	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0195	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0205	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0210	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0215	Minor Traf Devices	8120170	1.000	LSUM
0220	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	2,400.000	Ft
0225	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0230	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	200.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	200.000	Sft
0245	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0250	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft
0255	Traf Regulator Control	8120370	1.000	LSUM
0260	_ Turf Establishment, Spec, City of Pontiac	8167011	750.000	Syd
0265	Conduit, DB, 1, 1 1/4 inch	8182047	425.000	Ft
0270	Conduit, DB, 1, 3 inch	8182050	288.000	Ft
0275	Conduit, DB, 2, 3 inch	8182053	52.000	Ft
0280	Conduit, DB, 3, 3 inch	8182056	102.000	Ft
0285	Conduit, DB, 3, 4 inch	8182057	32.000	Ft
0290	Cable Pole, TS and Sec, Disman	8182209	1.000	Ea
0295	Cable, Sec, 600V, 1, 3/C#6	8182238	760.000	Ft
0300	Hh, Adj	8182328	2.000	Ea
0305	Hh, Rem	8182330	2.000	Ea
0310	Wood Pole, Rem	8182363	2.000	Ea
0315	Serv Disconnect	8182366	3.000	Ea
0320	Serv Disconnect, Rem	8182367	1.000	Ea
0325	Wood Pole, Fit Up, TS and Sec Cable Pole	8182386	1.000	Ea
0330	_ Conduit, Directional Bore, 2, 3 inch, RCOC	8187001	438.000	Ft
0335	_ Hh, Round, 2 foot Dia, RCOC	8187050	13.000	Ea
0340	_ Hh, Round, 3 foot Dia, RCOC	8187050	3.000	Ea

0345	Controller and Cabinet, Rem	8200030	2.000	Ea
0350	Controller Fdn, Base Mtd	8200045	3.000	Ea
0355	Global Positioning System Module	8200050	2.000	Ea
0360	Digital Loop Detector	8200055	4.000	Ea
0365	Fdn, Rem	8200065	1.000	Ea
0370	Pedestal, Fdn	8200105	4.000	Ea
0375	Pushbutton and Sign	8200121	12.000	Ea
0380	Push Button Station and Sign	8200128	2.000	Ea
0385	Span Wire	8200140	11.000	Ea
0390	Span Wire, Rem	8200141	2.000	Ea
0395	Span Wire Tether	8200142	11.000	Ea
0400	Steel Pole, Rem	8200145	1.000	Ea
0405	Traf Loop	8200170	13.000	Ea
0410	TS, Span Wire Mtd, Rem	8200182	4.000	Ea
0415	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0420	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	4.000	Ea
0425	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	4.000	Ea
0430	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	2.000	Ea
0435	TS, Pedestrian, Two Way Pedestal Mtd (LED)	8200346	2.000	Ea
0440	TS Face, Bag	8200458	22.000	Ea
0445	TS Face, Bag, Rem	8200459	22.000	Ea
0450	Strain Pole, Steel, 6 bolt, Size 1A	8200463	6.000	Ea
0455	Strain Pole, Steel, 6 bolt, Size 2	8200466	2.000	Ea
0460	Strain Pole, Steel, 6 bolt, Size 4	8200468	2.000	Ea
0465	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	111.000	Ft
0470	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	76.000	Ft
0475	Casing, 42 inch	8200485	90.000	Ft
0480	Casing, 48 inch	8200486	62.000	Ft
0485	TS, One Way Span Wire Mtd (LED), Long Life	8202287	20.000	Ea
0490	TS, One Way Span Wire Mtd, FYA (LED), Long Life	8202299	2.000	Ea
0495	_ Antenna, Delivered, RCOC	8207050	3.000	Ea
0500	_ Backplate, TS, RCOC	8207050	22.000	Ea
0505	_ Cabinet, ITS Type, Delivered, RCOC	8207050	3.000	Ea
0510	_ Cabinet, ITS Type, RCOC	8207050	3.000	Ea
0515	_ Case Sign (LED), One-Way, 30 inch by 36 inch	8207050	2.000	Ea
0520	_ Cellular Router, 4/5G, Delivered, RCOC	8207050	3.000	Ea
0525	_ Controller, Digital Type, Delivered, Blue, RCOC	8207050	3.000	Ea
0530	_ Pedestal, Alum, RCOC	8207050	4.000	Ea
0535	_ Pushbutton Support Post, RCOC	8207050	12.000	Ea
0540	_ St Name Sign, Illuminated, Bracket Arm, RCOC	8207050	7.000	Ea
0545	_ St Name Sign, Illuminated, Two Way, 8 foot, RCOC	8207050	7.000	Ea
0550	_ TS. Service Rack, Metered, RCOC	8207050	1.000	Ea
0555	_ Sprinkler Line, City of Pontiac	8237001	500.000	Ft

0560	_ Sprinkler Head, Relocate, City of Pontiac	8237050	20.000	Ea
0565	_ Sprinkler Head, Replace, City of Pontiac	8237050	20.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 023

**Letting Date:** October 3, 2025

**Contract ID:** 82000-220125

**Description:** Traffic signal modernization, concrete curb and gutter, sidewalk, sidewalk ramps and pavement markings on 5 Mile Road at Levan Road and on Newburgh Road at Lyndon Street in the city of Livonia, Wayne County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220125A	25A0861	N/A	HSIP 82000
220126A	25A0862	N/A	HSIP 82000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	5,575.000	Dlr
0010	Mobilization, Max \$60,900.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	188.000	Ft
0020	Curb, Rem	2040021	68.000	Ft
0025	Sidewalk, Rem	2040055	164.000	Syd
0030	Exploratory Investigation, Vertical	2040080	50.000	Ft
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	31.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	10.000	Ea
0045	_ Misc Aggregate Base, CIP	3027021	22.000	Cyd
0050	Maintenance Gravel	3060020	9.000	Ton
0055	Lane Tie, Epoxy Anchored	6030030	147.000	Ea
0060	Curb, Conc, Det E4	8020004	68.000	Ft
0065	Curb and Gutter, Conc, Det F1	8020035	10.000	Ft
0070	Curb and Gutter, Conc, Det F3	8020037	93.000	Ft
0075	Detectable Warning Surface	8030010	73.000	Ft
0080	Curb Ramp Opening, Conc	8030030	85.000	Ft
0085	Curb Ramp, Conc, 6 inch	8032002	1,453.000	Sft
0090	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	155.000	Ft
0095	Rem Spec Mrkg	8110343	78.000	Sft
0100	_ Pavt Mrkg, Waterborne, Curb	8117001	75.000	Ft
0105	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0110	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0115	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0120	Minor Traf Devices	8120170	1.000	LSUM
0125	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0130	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea

0135	Sign, Type B, Temp, Prismatic, Furn	8120350	848.000	Sft
0140	Sign, Type B, Temp, Prismatic, Oper	8120351	848.000	Sft
0145	Traf Regulator Control	8120370	1.000	LSUM
0150	Pedestrian Path, Temp	8122250	100.000	Ft
0155	Pedestrian Ramp, Temp	8122251	4.000	Ea
0160	Mulch Blanket	8160027	384.000	Syd
0165	Topsoil Surface, Furn, 3 inch	8160061	384.000	Syd
0170	Water, Sodding/Seeding	8160090	4.000	Unit
0175	_ Seeding, Mixture THM, Modified	8167011	384.000	Syd
0180	Conduit, Directional Bore, 1, 4 inch	8182036	145.000	Ft
0185	Conduit, DB, 1, 1 1/2 inch	8182048	155.000	Ft
0190	Conduit, DB, 3, 3 inch	8182056	60.000	Ft
0195	Conduit, DB, 4, 3 inch	8182059	20.000	Ft
0200	Conduit, DB, 1, 1 inch	8182060	40.000	Ft
0205	Cable Pole, TS, Disman	8182210	3.000	Ea
0210	Cable, Sec, 600V, 1, 3/C#6	8182238	120.000	Ft
0215	Hh, Polymer Conc	8182309	4.000	Ea
0220	Hh, Round	8182310	5.000	Ea
0225	Hh, Round, 3 foot dia	8182319	2.000	Ea
0230	Hh, Rem	8182330	2.000	Ea
0235	Serv Disconnect	8182366	2.000	Ea
0240	Case Sign, Rem	8200020	2.000	Ea
0245	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	2.000	Ea
0250	Controller and Cabinet, Rem	8200030	2.000	Ea
0255	Controller Fdn, Base Mtd	8200045	2.000	Ea
0260	Global Positioning System Module	8200050	2.000	Ea
0265	Pedestal, Alum	8200100	5.000	Ea
0270	Pedestal, Fdn	8200105	5.000	Ea
0275	Pedestal Fdn, Rem	8200106	2.000	Ea
0280	Pedestal, Rem	8200110	2.000	Ea
0285	Pushbutton and Sign	8200121	4.000	Ea
0290	Span Wire	8200140	4.000	Ea
0295	Span Wire, Rem	8200141	2.000	Ea
0300	Span Wire Tether	8200142	4.000	Ea
0305	TS, Bracket Arm Mtd, Rem	8200175	3.000	Ea
0310	TS, Pedestal Mtd, Rem	8200179	1.000	Ea
0315	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	5.000	Ea
0320	TS, Pedestrian, Pedestal Mtd, Rem	8200181	1.000	Ea
0325	TS, Span Wire Mtd, Rem	8200182	4.000	Ea
0330	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0335	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	1.000	Ea
0340	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	4.000	Ea
0345	Bracket, Truss, with 12 foot Arm	8200376	2.000	Ea

0350	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
0355	Video Traf Detection System	8200380	2.000	Ea
0360	Video Traf Detection Camera	8200381	6.000	Ea
0365	Junction Box, Span Wire	8200456	4.000	Ea
0370	Junction Box, Rem	8200457	2.000	Ea
0375	Strain Pole, Steel, 6 bolt, Size 2	8200466	4.000	Ea
0380	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	66.000	Ft
0385	Casing, 42 inch	8200485	29.000	Ft
0390	Casing, 48 inch	8200486	52.000	Ft
0395	Backplate, TS	8200501	16.000	Ea
0400	Mast Arm Pole, Cat I	8202010	2.000	Ea
0405	Mast Arm, 45 foot, Cat I	8202018	2.000	Ea
0410	Mast Arm, 50 foot, Cat I	8202019	1.000	Ea
0415	Mast Arm Pole Fdn, 6 Bolt	8202034	36.000	Ft
0420	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	6.000	Ea
0425	TS, One Way Mast Arm Mtd, FYA (LED), Long Life	8202239	1.000	Ea
0430	TS, One Way Span Wire Mtd (LED), Long Life	8202287	8.000	Ea
0435	TS, One Way Span Wire Mtd, FYA (LED), Long Life	8202299	2.000	Ea
0440	_ Cabinet, NEMA Type, Modified	8207050	2.000	Ea
0445	_ Controller, NEMA, ATC Type, Modified	8207050	2.000	Ea
0450	_ St Name Sign Bracket Arm, 8 Foot	8207050	2.000	Ea
0455	_ St Name Sign, One Way, LED, 8 foot	8207050	1.000	Ea
0460	_ St Name Sign, Two Way, LED 6 foot	8207050	2.000	Ea
0465	_ St Name Sign, Two Way, LED, 6 foot	8207050	1.000	Ea
0470	Protect Corners	8210020	4.000	Ea
0475	Lightning Protection, Pole	8260021	2.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 024

**Letting Date:** October 3, 2025

**Contract ID:** 63000-221335

**Description:** 0.8 mi of hot mix asphalt shared-use path, concrete sidewalk and ramps, and surface restoration on Nine Mile Road from Evergreen Road to Southfield Road in the city of Southfield, Oakland County.  
This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221335A	25A0839	N/A	TAU 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Audio-Visual Filming	1047051	1.000	LSUM
0010	Mobilization, Max \$59,700.00	1100001	1.000	LSUM
0015	_ Clearing, Modified	2017011	41.000	Syd
0020	Tree, Rem, 19 inch to 36 inch	2020002	11.000	Ea
0025	Tree, Rem, 37 inch or Larger	2020003	1.000	Ea
0030	Tree, Rem, 6 inch to 18 inch	2020004	16.000	Ea
0035	Curb and Gutter, Rem	2040020	409.000	Ft
0040	Pavt, Rem	2040050	575.000	Syd
0045	Sidewalk, Rem	2040055	464.000	Syd
0050	_ Bench, Salv and Reinstall	2047050	1.000	Ea
0055	_ Litter Receptacle, Salv and Reinstall	2047050	1.000	Ea
0060	_ Subgrade Undercut and Refill, 21AA, Type II, Modified	2057021	250.000	Cyd
0065	_ Exploratory Excavation	2057050	5.000	Ea
0070	Erosion Control, Inlet Protection, Fabric Drop	2080020	18.000	Ea
0075	Erosion Control, Silt Fence	2080036	2,500.000	Ft
0080	_ Aggregate Base, 6 inch, Modified	3027011	5,443.000	Syd
0085	_ Aggregate Base, 8 inch, Modified	3027011	548.000	Syd
0090	Maintenance Gravel, LM	3060021	10.000	Cyd
0095	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0100	HMA Surface, Rem	5010005	1,021.000	Syd
0105	HMA Approach	5010061	207.000	Ton
0110	Conc Pavt with Integral Curb, Nonreinf, 8 inch	6020164	190.000	Syd
0115	Driveway, Nonreinf Conc, 6 inch	8010005	20.000	Syd
0120	Curb, Conc, Det E2	8020002	89.000	Ft
0125	Curb and Gutter, Conc, Det F2	8020036	35.000	Ft
0130	_ Curb and Gutter, Conc, Det F3, Modified	8027001	12.000	Ft
0135	Detectable Warning Surface	8030010	85.000	Ft

0140	Curb Ramp Opening, Conc	8030030	99.000	Ft
0145	Sidewalk, Conc, 4 inch	8030044	1,121.000	Sft
0150	Curb Ramp, Conc, 6 inch	8032002	1,221.000	Sft
0155	Shared use Path, Grading	8060030	4,300.000	Ft
0160	Shared use Path, HMA	8060040	986.000	Ton
0165	Post, Mailbox	8070095	16.000	Ea
0170	_ Relocate Mailbox	8077050	1.000	Ea
0175	Post, Steel, 3 pound	8100371	154.000	Ft
0180	Sign, Type III, Erect, Salv	8100402	12.000	Ea
0185	Sign, Type III, Rem	8100403	6.000	Ea
0190	Post, Flexible, Delineator, Ground Mtd	8100555	18.000	Ea
0195	_ School Sign, Rem	8107050	1.000	Ea
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0205	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0210	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0215	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0220	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0225	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0230	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0235	Minor Traf Devices	8120170	1.000	LSUM
0240	Sign Cover	8120310	5.000	Ea
0245	Sign, Type B, Temp, Prismatic, Furn	8120350	276.000	Sft
0250	Sign, Type B, Temp, Prismatic, Oper	8120351	276.000	Sft
0255	_ Slope Restoration, Bonded Fiber Matrix	8167011	4,795.000	Syd
0260	Conduit, DB, 1, 1 1/4 inch	8182047	35.000	Ft
0265	Hh, Adj	8182328	3.000	Ea
0270	_ Light Std Unit, Rem	8197050	2.000	Ea
0275	Pushbutton and Sign	8200121	2.000	Ea
0280	Pushbutton, Rem	8200122	1.000	Ea
0285	TS Face, Bag	8200458	10.000	Ea
0290	TS Face, Bag, Rem	8200459	10.000	Ea
0295	_ Pushbutton Support Post, RCOC	8207050	2.000	Ea
0300	_ Pushbutton Support Post, Rem, RCOC	8207050	2.000	Ea
0305	Protect Corners	8210020	10.000	Ea
0310	Water Shutoff, Adj, Case 1	8230421	2.000	Ea
0315	Water Shutoff, Adj, Case 2	8230422	1.000	Ea
0320	Gate Box, Adj, Case 2	8230432	2.000	Ea
0325	_ Gate Well Cover, Adj, Case 1	8237050	4.000	Ea
0330	_ Hydrant, Relocate, Case 1, Modified	8237050	1.000	Ea
0335	_ Hydrant, Relocate, Case 2, Modified	8237050	1.000	Ea
0340	_ Sprinkler Line	8257001	500.000	Ft
0345	_ Sanitary Sewer Mh Cover, Adj, Case 1	8257050	2.000	Ea
0350	_ Sanitary Sewer Mh Cover, Adj, Case 2	8257050	1.000	Ea

0355	_ Sprinkler Head, Relocate	8257050	20.000	Ea
0360	_ Sprinkler Head, Replace	8257050	20.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 025

**Letting Date:** October 3, 2025

**Contract ID:** 13000-218314

**Description:** 2.10 mi of hot mix asphalt cold milling and resurfacing and pavement markings on Hill Brady Road from Skyline Drive to Dickman Road in the city of Battle Creek, Calhoun County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218314A	25A0826	N/A	STUL 13000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$76,600.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	64.000	Ea
0015	Cold Milling HMA Surface	5010002	61,600.000	Syd
0020	Hand Patching	5010025	10.000	Ton
0025	HMA, 4EML	5012025	6,776.000	Ton
0030	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	120.000	Ft
0035	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	1.000	Ea
0040	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	1.000	Ea
0045	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym	8110078	1.000	Ea
0050	Pavt Mrkg, Polyurea, 6 inch, White	8110094	8,195.000	Ft
0055	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	22,655.000	Ft
0060	Recessing Pavt Mrkg, Longit	8110450	30,850.000	Ft
0065	Recessing Pavt Mrkg, Transv	8110451	392.000	Sft
0070	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0075	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0080	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	475.000	Ea
0085	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	475.000	Ea
0090	Lighted Arrow, Type C, Furn	8120140	3.000	Ea
0095	Lighted Arrow, Type C, Oper	8120141	3.000	Ea
0100	Minor Traf Devices	8120170	1.000	LSUM
0105	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	2,000.000	Ft
0110	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,000.000	Ft
0115	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	120.000	Ft
0120	Sign Cover	8120310	6.000	Ea

0125	Sign, Portable, Changeable Message, Furn	8120330	4.000	Ea
0130	Sign, Portable, Changeable Message, Oper	8120331	4.000	Ea
0135	Sign, Type B, Temp, Prismatic, Furn	8120350	400.000	Sft
0140	Sign, Type B, Temp, Prismatic, Oper	8120351	400.000	Sft
0145	Traf Regulator Control	8120370	1.000	LSUM

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 026

**Letting Date:** October 3, 2025

**Contract ID:** 82000-218966

**Description:** Install HAWK non-motorized pedestrian crossing on Beech Daly Road from Lawrence Street to North Central Drive in the city of Dearborn Heights, Wayne County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218966A	25A0794	N/A	TAU 82000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$12,700.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	44.000	Ft
0015	Pavt, Rem	2040050	4.000	Syd
0020	Sidewalk, Rem	2040055	31.000	Syd
0025	Exploratory Investigation, Vertical	2040080	14.000	Ft
0030	Excavation, Earth	2050016	9.000	Cyd
0035	Erosion Control, Silt Fence	2080036	200.000	Ft
0040	Project Cleanup	2090001	1.000	LSUM
0045	Hand Patching	5010025	1.000	Ton
0050	Coating Galvanized Support Structures	7160010	1.000	Ea
0055	Detectable Warning Surface	8030010	20.000	Ft
0060	Curb Ramp Opening, Conc	8030030	44.000	Ft
0065	Sidewalk, Conc, 4 inch	8030044	370.000	Sft
0070	Curb Ramp, Conc, 6 inch	8032002	140.000	Sft
0075	Post, Steel, 3 pound	8100371	102.000	Ft
0080	Sign, Type IIIB	8100405	98.000	Sft
0085	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	140.000	Ft
0090	Pavt Mrkg, Ovly Cold Plastic, Yield Triangle Sym	8112169	16.000	Ea
0095	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	2.000	Ea
0100	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	2.000	Ea
0105	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0110	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0115	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0120	Minor Traf Devices	8120170	1.000	LSUM
0125	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	48.000	Ft
0130	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0135	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea

0140	Sign Cover	8120310	4.000	Ea
0145	Sign, Type B, Temp, Prismatic, Furn	8120350	264.000	Sft
0150	Sign, Type B, Temp, Prismatic, Oper	8120351	264.000	Sft
0155	Pedestrian Path, Temp	8122250	80.000	Ft
0160	Pedestrian Ramp, Temp	8122251	2.000	Ea
0165	Slope Restoration, Non-Freeway, Type A	8162001	33.000	Syd
0170	Power Company (Estimated Cost to Contractor)	8180001	7,100.000	Dir
0175	Conduit, Directional Bore, 1, 3 inch	8182035	60.000	Ft
0180	Conduit, DB, 1, 1 1/2 inch	8182048	10.000	Ft
0185	Conduit, DB, 1, 3 inch	8182050	15.000	Ft
0190	Conduit, DB, 3, 3 inch	8182056	10.000	Ft
0195	Cable, Sec, 600V, 1, 3/C#6	8182238	175.000	Ft
0200	Hh, Round	8182310	2.000	Ea
0205	Metered Serv	8182338	1.000	Ea
0210	Serv Disconnect	8182366	1.000	Ea
0215	Wood Pole, Fit Up, Sec Cable Pole	8182381	1.000	Ea
0220	_ Conduit, DB, 1, 2 inch	8187001	35.000	Ft
0225	_ Bracket Arm, 24 Foot with 3 Foot Rise	8187050	1.000	Ea
0230	Luminaire	8190330	1.000	Ea
0235	Pedestal, Alum	8200100	1.000	Ea
0240	Pedestal, Fdn	8200105	2.000	Ea
0245	Pedestal, Pushbutton, Alum	8200118	1.000	Ea
0250	Pushbutton and Sign	8200121	2.000	Ea
0255	Casing, 42 inch	8200485	11.000	Ft
0260	Mast Arm Pole, Cat I	8202010	1.000	Ea
0265	Mast Arm, 50 foot, Cat I	8202019	1.000	Ea
0270	Mast Arm Pole Fdn, 6 Bolt	8202034	14.000	Ft
0275	_ Flsh Beacon, Rectangular Rapid	8207050	4.000	Ea
0280	_ Pedestal Painting	8207050	2.000	Ea
0285	_ Two-Way Crosswalk Sign, Illuminated (LED) 8 Feet W/ Downlight	8207050	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 027

**Letting Date:** October 3, 2025

**Contract ID:** 82000-215264

**Description:** Traffic signal modernization including signal retiming, wireless signal interconnect, and concrete sidewalk ramps across 18 locations in the city of Detroit, Wayne County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215264A	25A0815	N/A	CPMG 82000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Conrail	1027060	5,000.000	Dir
0010	Mobilization, Max \$196,000.00	1100001	1.000	LSUM
0015	Exploratory Investigation, Vertical	2040080	260.000	Ft
0020	_ Curb, Rem, Modified	2047001	291.000	Ft
0025	_ Sidewalk, Rem, Modified	2047011	411.000	Syd
0030	Excavation, Earth	2050016	110.000	Cyd
0035	Granular Material, CI II	2050023	110.000	Cyd
0040	Non Haz Contaminated Material Handling and Disposal, LM	2050031	130.000	Cyd
0045	Dr Structure Cover, Adj, Case 2	4030006	17.000	Ea
0050	Curb and Gutter, Conc, Det C4	8020023	53.000	Ft
0055	Detectable Warning Surface	8030010	136.000	Ft
0060	Curb Ramp Opening, Conc	8030030	230.000	Ft
0065	Curb Ramp, Conc, 6 inch	8032002	1,713.000	Sft
0070	_ Sidewalk, Conc, 4 inch, Modified	8037010	2,212.000	Sft
0075	_ Sidewalk, Conc, 6 inch, Modified	8037010	354.000	Sft
0080	Sign, Type III, Rem	8100403	1.000	Ea
0085	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	940.000	Ft
0090	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	160.000	Ft
0095	_ Recessing Pavt Mrkg, Transv, Modified	8117010	470.000	Sft
0100	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0110	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0115	Lighted Arrow, Type C, Furn	8120140	6.000	Ea
0120	Lighted Arrow, Type C, Oper	8120141	6.000	Ea
0125	Minor Traf Devices	8120170	1.000	LSUM
0130	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	840.000	Ft

0135	Plastic Drum, Fluorescent, Furn	8120252	300.000	Ea
0140	Plastic Drum, Fluorescent, Oper	8120253	300.000	Ea
0145	Sign, Type B, Temp, Prismatic, Furn	8120350	1,480.000	Sft
0150	Sign, Type B, Temp, Prismatic, Oper	8120351	1,480.000	Sft
0155	_ Horticultural Work	8157040	4.000	Hr
0160	Conduit, DB, 1, 3 inch	8182050	264.000	Ft
0165	Conduit, DB, 2, 3 inch	8182053	352.000	Ft
0170	Conduit, DB, 3, 4 inch	8182057	112.000	Ft
0175	Cable, Sec, Rem	8182199	680.000	Ft
0180	Cable Pole, TS, Disman	8182210	1.000	Ea
0185	Cable, Sec, 600V, 1, 3/C#6	8182238	1,250.000	Ft
0190	Hh, Rem	8182330	2.000	Ea
0195	Wood Pole, Cl 4, 45 foot	8182352	50.000	Ea
0200	Wood Pole, Rem	8182363	15.000	Ea
0205	Serv Disconnect	8182366	15.000	Ea
0210	Serv Disconnect, Rem	8182367	8.000	Ea
0215	Wood Pole, Fit Up, TS and Sec Cable Pole	8182386	12.000	Ea
0220	Wood Pole, Fit Up, TS Cable Pole	8182387	2.000	Ea
0225	_ Hh, Round, Detroit	8187050	17.000	Ea
0230	Pole Guy	8200002	2.000	Ea
0235	Case Sign, Disappearing Legend, 24 inch by 30 inch	8200015	2.000	Ea
0240	Case Sign, Rem	8200020	9.000	Ea
0245	Case Sign (LED), Two Way, 24 inch by 30 inch	8200022	20.000	Ea
0250	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	2.000	Ea
0255	Controller and Cabinet, Rem	8200030	14.000	Ea
0260	Controller and Cabinet, Salv	8200037	1.000	Ea
0265	Controller Fdn, Base Mtd	8200045	15.000	Ea
0270	Controller Fdn, Rem	8200046	6.000	Ea
0275	Fdn, Rem	8200065	24.000	Ea
0280	Louver	8200080	24.000	Ea
0285	Pedestal Fdn, Rem	8200106	13.000	Ea
0290	Pedestal, Rem	8200110	18.000	Ea
0295	Pushbutton and Sign	8200121	8.000	Ea
0300	Pushbutton, Rem	8200122	6.000	Ea
0305	Span Wire	8200140	53.000	Ea
0310	Span Wire, Rem	8200141	17.000	Ea
0315	Span Wire Tether	8200142	53.000	Ea
0320	Steel Pole, Rem	8200145	21.000	Ea
0325	TS, Bracket Arm Mtd, Rem	8200175	10.000	Ea
0330	TS, Mast Arm Mtd, Rem	8200177	4.000	Ea
0335	TS, Pedestal Mtd, Rem	8200179	2.000	Ea
0340	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	51.000	Ea
0345	TS, Pedestrian, Pedestal Mtd, Rem	8200181	19.000	Ea
0350	TS, Span Wire Mtd, Rem	8200182	43.000	Ea
0355	TS, Pedestrian, One Way Bracket Arm Mtd (LED)	8200336	20.000	Ea

Countdown				
0360	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	40.000	Ea
0365	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	4.000	Ea
0370	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	2.000	Ea
0375	TS, Antenna, Salv	8200369	1.000	Ea
0380	Bracket, Truss, with 18 foot Arm	8200378	3.000	Ea
0385	Emergency Pre-emption, Salv	8200416	2.000	Ea
0390	TS Face, Bag	8200458	16.000	Ea
0395	TS Face, Bag, Rem	8200459	16.000	Ea
0400	Strain Pole, Steel, 6 bolt, Size 1A	8200463	4.000	Ea
0405	Strain Pole, Steel, 6 bolt, Size 4	8200468	1.000	Ea
0410	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	76.000	Ft
0415	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	20.000	Ft
0420	Casing, 42 inch	8200485	95.000	Ft
0425	Casing, 48 inch	8200486	17.000	Ft
0430	Mast Arm, Rem	8202004	2.000	Ea
0435	Mast Arm Std, Rem	8202005	2.000	Ea
0440	Mast Arm Pole, Cat II	8202011	2.000	Ea
0445	Mast Arm, 50 foot, Cat II	8202026	2.000	Ea
0450	Mast Arm Pole Fdn, 6 Bolt	8202034	38.000	Ft
0455	TS, One Way Bracket Arm Mtd (LED), Long Life	8202200	3.000	Ea
0460	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	12.000	Ea
0465	TS, One Way Span Wire Mtd (LED), Long Life	8202287	100.000	Ea
0470	TS, Two Way Span Wire Mtd (LED), Long Life	8202290	1.000	Ea
0475	_ Antenna, Spectrum	8207050	13.000	Ea
0480	_ Backplate, TS, Detroit	8207050	106.000	Ea
0485	_ Controller and Cabinet, Digital Type, Modified	8207050	14.000	Ea
0490	_ Controller and Cabinet, Digital Type, Railroad	8207050	1.000	Ea
0495	_ Controller, Digital Type, Modified	8207050	4.000	Ea
0500	_ Controller, Rem	8207050	4.000	Ea
0505	_ Pedestal Alum, Modified	8207050	10.000	Ea
0510	_ Pedestal Fdn, Modified	8207050	4.000	Ea
0515	_ Transfer Switch, Detroit	8207050	19.000	Ea
0520	_ Video Capture and Streaming System	8207050	1.000	Ea
0525	_ Video Capture and Streaming System, Salv	8207050	2.000	Ea
0530	_ Video Detection and Analytics System	8207050	2.000	Ea
0535	_ Video Detection and Analytics System, Salv	8207050	1.000	Ea
0540	_ Wireless Data Acquisition and Alerts System, Salv	8207050	13.000	Ea
0545	_ Wireless Data Acquisition, Alerts and Analytics System	8207050	1.000	Ea
0550	Hh, Clean	8260030	9.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 028

**Letting Date:** October 3, 2025

**Contract ID:** 17000-220667

**Description:** Bridge rehabilitation including epoxy overlay, concrete patching, expansion joint work, guardrail and pavement markings on Fort Street over Power Canal, Riverside Drive over Mission Creek and West Portage Avenue over Power Canal in the city of Sault Ste. Marie, Chippewa County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220667A	25A0867	N/A	BFP 17000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$36,000.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	84.000	Ft
0015	Guardrail Anch, Bridge, Det T5	8070026	1.000	Ea
0020	Guardrail Departing Terminal, Type B	8070050	1.000	Ea
0025	Guardrail, Type B, 72 inch Post	8072171	25.000	Ft
0030	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	200.000	Ft
0035	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0040	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0045	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0050	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	110.000	Ea
0055	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	110.000	Ea
0060	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0065	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0070	Minor Traf Devices	8120170	1.000	LSUM
0075	Pavt Mrkg Cover, Type R, Black	8120200	450.000	Ft
0080	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,000.000	Ft
0085	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	24.000	Ft
0090	PTS, Temp, Furn	8120272	1.000	Ea
0095	PTS, Temp, Oper	8120273	1.000	Ea
0100	Sign, Type B, Temp, Prismatic, Furn	8120350	530.000	Sft
0105	Sign, Type B, Temp, Prismatic, Oper	8120351	530.000	Sft
0110	Traf Regulator Control	8120370	1.000	LSUM

**Section: 2**

0115	Excavation, Fdn	2060010	3.000	Cyd
0120	Crack Sealing, Conc Pavt	6030010	150.000	Ft
0125	Resealing Trans Joints with Hot-Poured Rubber	6030100	100.000	Ft
0130	Expansion Joint Device	7060050	120.000	Ft
0135	Expansion Joint Device, Cover Plate	7060051	37.000	Ft
0140	Reinforcement, Steel, Epoxy Coated	7060092	305.000	Lb
0145	Conc, Grade 4500	7062003	5.000	Cyd
0150	_ Expansion Joint Device Gland Cleanout	7067001	96.000	Ft
0155	Hand Chipping, Deep	7120004	6.000	Syd
0160	Epoxy Ovly	7120020	270.000	Syd
0165	Deck Joint, Rem	7120071	120.000	Ft
0170	Reinforcement, Mechanical Splice	7120084	4.000	Ea
0175	Patching Conc, C-L	7120112	2.000	Cyd
0180	Beam Plate, Seal Perimeter	7130010	440.000	Ft
0185	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	150.000	Lb

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 029

**Letting Date:** October 3, 2025

**Contract ID:** 47000-222323

**Description:** 1.13 mi of hot mix asphalt cold milling and resurfacing and pavement markings on Maltby Road from Whitmore Lake Road to Scranton Middle School, Livingston County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222323A	25A0851	N/A	STU 47000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$77,600.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	30.000	Ea
0015	Aggregate Base, LM	3020002	50.000	Cyd
0020	Aggregate Base, Conditioning	3020050	7,710.000	Syd
0025	Aggregate Base, Conditioning, Surplus and Unsuitable, Rem, LM	3022000	200.000	Cyd
0030	Maintenance Gravel	3060020	70.000	Ton
0035	Pavt, Cleaning	5010001	1.000	LSUM
0040	Cold Milling HMA Surface	5010002	12,672.000	Syd
0045	HMA Surface, Rem	5010005	7,868.000	Syd
0050	HMA, 4EML	5012025	2,671.000	Ton
0055	HMA, 5EML	5012037	2,327.000	Ton
0060	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	54.000	Ft
0065	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0070	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	2.000	Ea
0075	Pavt Mrkg, Waterborne, 4 inch, White	8110231	5,320.000	Ft
0080	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	10,300.000	Ft
0085	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	5,320.000	Ft
0090	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	10,300.000	Ft
0095	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0100	Pavt Mrkg, Ovly Cold Plastic, Left	8110368	2.000	Ea
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	130.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	130.000	Ea
0125	Minor Traf Devices	8120170	1.000	LSUM
0130	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch,	8120246	560.000	Ft

	Yellow, Temp			
0135	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0140	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0145	Sign, Type B, Temp, Prismatic, Furn	8120350	320.000	Sft
0150	Sign, Type B, Temp, Prismatic, Oper	8120351	320.000	Sft
0155	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	520.000	Sft
0160	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	520.000	Sft
0165	Traf Regulator Control	8120370	1.000	LSUM
0170	Monument Preservation	8210010	1.000	Ea
0175	Contractor Staking	8240001	1.000	LSUM
0180	Staking Plan Errors and Extras, Max \$180/hour	8240002	9.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 030

**Letting Date:** October 3, 2025

**Contract ID:** 38000-220301

**Description:** 1.10 mi of hot mix asphalt cold milling, resurfacing and widening, concrete curb, gutter and sidewalk ramps, traffic signal upgrades and pavement markings on Airport Road from Argyle Street to County Farm Road, Jackson County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220301A	25A0822	N/A	EAR 38000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$121,600.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	1.000	Ea
0015	Tree, Rem, 37 inch or Larger	2020003	1.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	2.000	Ea
0025	Dr Structure, Rem	2030011	5.000	Ea
0030	Sewer, Rem, Less than 24 inch	2030015	128.000	Ft
0035	Curb and Gutter, Rem	2040020	4,847.000	Ft
0040	Pavt, Rem	2040050	307.000	Syd
0045	Sidewalk, Rem	2040055	940.000	Syd
0050	Exploratory Investigation, Vertical	2040080	100.000	Ft
0055	Excavation, Earth	2050016	2,000.000	Cyd
0060	Machine Grading	2050030	18.000	Sta
0065	Subgrade Undercutting, Type II	2050041	100.000	Cyd
0070	Erosion Control, Inlet Protection, Fabric Drop	2080020	50.000	Ea
0075	Erosion Control, Silt Fence	2080036	1,000.000	Ft
0080	Subbase, CIP	3010002	349.000	Cyd
0085	Aggregate Base, 6 inch	3020016	3,614.000	Syd
0090	Aggregate Base, 8 inch	3020020	2,539.000	Syd
0095	Approach, CI I, 6 inch	3070008	791.000	Syd
0100	Geotextile, Stabilization	3080010	1,000.000	Syd
0105	Sewer, CI A, 12 inch, Tr Det A	4020004	172.000	Ft
0110	Sewer, CI A, 12 inch, Tr Det B	4020033	60.000	Ft
0115	Dr Structure Cover, Adj, Case 1, Modified	4030004	35.000	Ea
0120	Dr Structure Cover, Type B	4030010	7.000	Ea
0125	Dr Structure Cover, Type C	4030015	1.000	Ea
0130	Dr Structure Cover, Type E	4030035	2.000	Ea
0135	Dr Structure Cover, Type K	4030050	8.000	Ea

0140	Dr Structure, 48 inch dia	4030210	9.000	Ea
0145	Dr Structure, Tap, 12 inch	4030312	4.000	Ea
0150	Dr Structure, Temp Lowering	4030390	35.000	Ea
0155	_ Dr Structure, 48 inch dia, Leaching Basin	4037050	4.000	Ea
0160	_ Dr Structure, Waterproofing	4037050	44.000	Ea
0165	Cold Milling HMA Surface	5010002	35,991.000	Syd
0170	HMA Surface, Rem	5010005	929.000	Syd
0175	Hand Patching	5010025	167.000	Ton
0180	HMA Approach	5010061	323.000	Ton
0185	HMA, 4EMH	5012026	4,773.000	Ton
0190	HMA, 5EMH	5012038	3,291.000	Ton
0195	Coating Galvanized Support Structures	7160010	7.000	Ea
0200	Curb, Conc, Det E1	8020001	100.000	Ft
0205	Curb and Gutter, Conc, Det F4	8020038	5,198.000	Ft
0210	Driveway Opening, Conc, Det M	8020050	684.000	Ft
0215	Detectable Warning Surface	8030010	60.000	Ft
0220	Curb Ramp Opening, Conc	8030030	116.000	Ft
0225	Curb Ramp, Conc, 4 inch	8032001	970.000	Sft
0230	Shared use Path, Conc	8060020	1,871.000	Syd
0235	Shared use Path, Grading	8060030	1,684.000	Ft
0240	Post, Steel, 3 pound	8100371	809.000	Ft
0245	Sign, Type IIB	8100399	98.000	Sft
0250	Sign, Type III, Rem	8100403	29.000	Ea
0255	Sign, Type IIIA	8100404	42.000	Sft
0260	Sign, Type IIIB	8100405	131.000	Sft
0265	Reflective Panel for Permanent Sign Support, 6 foot	8100616	10.000	Ea
0270	Sign, Type III, Rem, Salv	8102003	1.000	Ea
0275	Ground Mtd Sign Support, Rem	8102010	26.000	Ea
0280	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,737.000	Ft
0285	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	699.000	Ft
0290	Pavt Mrkg, Waterborne, 4 inch, White	8110231	3,931.000	Ft
0295	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	10,754.000	Ft
0300	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	13.000	Ea
0305	Pavt Mrkg, Polyurea, Only	8110410	2.000	Ea
0310	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	9.000	Ea
0315	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	5.000	Ea
0320	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	12.000	Ea
0325	Recessing Pavt Mrkg, Transv	8110451	4,432.000	Sft
0330	Pavt Mrkg, Sprayable Thermopl, 4 inch, Dotted Thru Guide Line, White	8110568	90.000	Ft
0335	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0340	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0345	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0350	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea

0355	Lighted Arrow, Type B, Furn	8120130	2.000	Ea
0360	Lighted Arrow, Type B, Oper	8120131	2.000	Ea
0365	Ltg for Night Work	8120160	1.000	LSUM
0370	Minor Traf Devices	8120170	1.000	LSUM
0375	Pavt Mrkg, Wet Reflective, Type NR, Paint, 4 inch, White, Temp	8120235	3,931.000	Ft
0380	Pavt Mrkg, Wet Reflective, Type NR, Paint, 4 inch, Yellow, Temp	8120236	10,754.000	Ft
0385	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	500.000	Ft
0390	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,000.000	Ft
0395	Sign, Portable, Changeable Message, Furn	8120330	8.000	Ea
0400	Sign, Portable, Changeable Message, Oper	8120331	8.000	Ea
0405	Sign, Type B, Temp, Prismatic, Furn	8120350	800.000	Sft
0410	Sign, Type B, Temp, Prismatic, Oper	8120351	800.000	Sft
0415	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	200.000	Sft
0420	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	200.000	Sft
0425	Traf Regulator Control	8120370	1.000	LSUM
0430	Slope Restoration, Non-Freeway, Type A	8162001	3,285.000	Syd
0435	Conduit, DB, 1, 1 1/2 inch	8182048	30.000	Ft
0440	Conduit, DB, 4, 3 inch	8182059	15.000	Ft
0445	Hh, Round	8182310	3.000	Ea
0450	Hh, Round, 3 foot dia	8182319	1.000	Ea
0455	Wood Pole, Cl 4, 45 foot	8182352	2.000	Ea
0460	Wood Pole, Cl 4, 50 foot	8182353	1.000	Ea
0465	Wood Pole, Rem	8182363	2.000	Ea
0470	Serv Disconnect	8182366	2.000	Ea
0475	Serv Disconnect, Rem	8182367	2.000	Ea
0480	Pole Guy	8200002	6.000	Ea
0485	Case Sign, Rem	8200020	1.000	Ea
0490	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	2.000	Ea
0495	Controller and Cabinet, Rem	8200030	1.000	Ea
0500	Controller and Cabinet, Salv	8200037	1.000	Ea
0505	Controller Fdn, Base Mtd	8200045	1.000	Ea
0510	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	2.000	Ea
0515	Pedestal, Fdn	8200105	2.000	Ea
0520	Pedestal, Pushbutton, Alum	8200118	2.000	Ea
0525	Pushbutton and Sign	8200121	12.000	Ea
0530	Span Wire	8200140	8.000	Ea
0535	Span Wire, Rem	8200141	2.000	Ea
0540	Span Wire Tether	8200142	4.000	Ea
0545	Steel Pole, Rem	8200145	2.000	Ea
0550	Guy, Rem	8200167	3.000	Ea
0555	TS, Span Wire Mtd, Rem	8200182	7.000	Ea
0560	Cabinet, NEMA Type	8200186	1.000	Ea

0565	TS, One Way Bracket Arm Mtd	8200220	4.000	Ea
0570	TS, One Way Span Wire Mtd (LED)	8200313	16.000	Ea
0575	TS, One Way Span Wire Mtd, FYA (LED)	8200314	4.000	Ea
0580	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	3.000	Ea
0585	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0590	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	7.000	Ea
0595	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
0600	Hemispherical Video Detection Camera	8200444	2.000	Ea
0605	Hemispherical Video Detection System	8200445	2.000	Ea
0610	Strain Pole, Steel, 6 bolt, Size 1B	8200464	2.000	Ea
0615	Strain Pole, Steel, 6 bolt, Size 2	8200466	2.000	Ea
0620	Strain Pole, Steel, 6 bolt, Size 3	8200467	1.000	Ea
0625	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	93.000	Ft
0630	Casing, 48 inch	8200486	83.000	Ft
0635	Cellular Modem, TS, 4th G	8200498	2.000	Ea
0640	Backplate, TS	8200501	24.000	Ea
0645	_ Controller, NEMA, ATC Type	8207050	1.000	Ea
0650	Monument Box	8210001	1.000	Ea
0655	Monument Preservation	8210010	1.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 031

**Letting Date:** October 3, 2025

**Contract ID:** 66041-113718

**Description:** Hot mix asphalt resurfacing of a carpool lot on M-38 at M-26, Ontonagon County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
113718A	25A0949	N/A	CRL 66041

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$11,000.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	1.000	Ea
0015	Excavation, Earth	2050016	50.000	Cyd
0020	Erosion Control, Check Dam, Stone	2080012	15.000	Ft
0025	Erosion Control, Sand Bag	2080028	10.000	Ea
0030	Erosion Control, Sediment Trap	2080034	1.000	Ea
0035	Erosion Control, Silt Fence	2080036	200.000	Ft
0040	Subbase, CIP	3010002	150.000	Cyd
0045	Approach, CI I, 6 inch	3070008	875.000	Syd
0050	Approach, CI II, 3 inch	3070025	100.000	Syd
0055	Culv End Sect, 18 inch	4010018	2.000	Ea
0060	Culv, CI F, 18 inch	4010609	65.000	Ft
0065	HMA Surface, Rem	5010005	328.000	Syd
0070	HMA Approach	5010061	145.000	Ton
0075	Installing MDOT Supplied Sign, Type III	8100302	1.000	Ea
0080	Post, Steel, 3 pound	8100371	84.000	Ft
0085	Sign, Type III, Rem	8100403	3.000	Ea
0090	Sign, Type IIIA	8100404	28.000	Sft
0095	Sign, Type IIIB	8100405	4.000	Sft
0100	Reflective Panel for Permanent Sign Support, 6 foot	8100616	2.000	Ea
0105	Ground Mtd Sign Support, Rem	8102010	1.000	Ea
0110	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	1.000	Ea
0115	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	315.000	Ft
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	3.000	Ea
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	3.000	Ea
0130	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0135	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea

0140	Minor Traf Devices	8120170	1.000	LSUM
0145	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0150	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0155	Sign Cover	8120310	2.000	Ea
0160	Sign, Type B, Temp, Prismatic, Furn	8120350	500.000	Sft
0165	Sign, Type B, Temp, Prismatic, Oper	8120351	500.000	Sft
0170	Traf Regulator Control	8120370	1.000	LSUM
0175	Rumble Strip, Temp, Portable, Furn	8122188	18.000	Ea
0180	Rumble Strip, Temp, Portable, Oper	8122189	18.000	Ea
0185	Slope Restoration, Non-Freeway, Type A	8162001	485.000	Syd
0190	Contractor Staking	8240001	1.000	LSUM
0195	Staking Plan Errors and Extras, Max \$180/hour	8240002	2.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 032

**Letting Date:** October 3, 2025

**Contract ID:** 13031-223119

**Description:** 10.38 mi of micro texture pavement milling, overband crack fill, lane, single course chip seal, and fog seal on M-66 from S Drive to L Drive, D Drive to Boulevard/I-94BL and I-94 EB ramp to Helmer Road, St. Joseph and Calhoun Counties. This project includes a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
223119A	25A0957	N/A	ST 13031

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$133,100.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	15.000	Ea
0015	Hand Patching	5010025	1.000	Ton
0020	Micro Texture Pavt Milling	5010101	137,900.000	Syd
0025	Overband Crack Fill, Lane	5020003	25.490	Lnmi
0030	_ Asphalt Repr Mastic	5027001	1,000.000	Ft
0035	Seal, Fog	5050015	236,724.000	Syd
0040	Chip Seal, Single, Warranty	5050040	236,724.000	Syd
0045	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	115.000	Ft
0050	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	202.000	Ft
0055	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	8110058	43.000	Ea
0060	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	12.000	Ea
0065	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	16.000	Ea
0070	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	2.000	Ea
0075	Pavt Mrkg, Waterborne, 6 inch, White	8110233	110,774.000	Ft
0080	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	48,465.000	Ft
0085	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	110,774.000	Ft
0090	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	48,465.000	Ft
0095	Rem Spec Mrkg	8110343	1,933.000	Sft
0100	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0105	Pavt Mrkg, Ovly Cold Plastic, Bike Thru Arrow Sym	8112165	43.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	32.000	Ea
0115	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	32.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	600.000	Ea
0125	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	600.000	Ea

0130	Minor Traf Devices	8120170	1.000	LSUM
0135	Plastic Drum, Fluorescent, Furn	8120252	31.000	Ea
0140	Plastic Drum, Fluorescent, Oper	8120253	31.000	Ea
0145	Raised Pavt Marker, Temp, Type 1, White, Monodirectional	8120280	306.000	Ea
0150	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	4,902.000	Ea
0155	Sign Cover	8120310	12.000	Ea
0160	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0165	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0170	Sign, Type B, Temp, Prismatic, Furn	8120350	1,848.000	Sft
0175	Sign, Type B, Temp, Prismatic, Oper	8120351	1,848.000	Sft
0180	Traf Regulator Control	8120370	1.000	LSUM
0185	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0190	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0195	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0200	Monument Box, Adj	8210005	1.000	Ea
0205	Monument Preservation	8210010	1.000	Ea
0210	Centerline Corrugations, Milled, HMA	8220013	31,855.000	Ft
0215	Contractor Staking	8240001	1.000	LSUM
0220	Staking Plan Errors and Extras, Max \$180/hour	8240002	15.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 033

**Letting Date:** October 3, 2025

**Contract ID:** 38171-220382

**Description:** 1.18 mi of single course hot mix asphalt cold milling and resurfacing, shoulder widening and paving and pavement markings on M-50 from south of Stoney Lake Road northwesterly to west of Napoleon Road, Jackson County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220382A	25A0967	N/A	VRU 38171
221059A	25A0968	N/A	ST 38171

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	500.000	Dlr
0010	Mobilization, Max \$80,000.00	1100001	1.000	LSUM
0015	Berm Grading	2050008	22.000	Sta
0020	Non Haz Contaminated Material Handling and Disposal, LM	2050031	130.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	30.000	Ea
0030	Project Cleanup	2090001	1.000	LSUM
0035	Aggregate Base, 6 inch	3020016	3,670.000	Syd
0040	Approach, CI II	3070021	45.000	Ton
0045	Shld, CI II	3070121	152.000	Ton
0050	Trenching	3070200	65.000	Sta
0055	Dr Structure Cover, Adj, Case 2	4030006	1.000	Ea
0060	_ Dr Structure Cover, Adj, Case 1, Modified	4037050	3.000	Ea
0065	Pavt, Cleaning	5010001	1.000	LSUM
0070	Cold Milling HMA Surface	5010002	24,137.000	Syd
0075	Bump Grinding	5010004	150.000	Syd
0080	HMA Surface, Rem	5010005	357.000	Syd
0085	HMA Quality Initiative	5010007	6,740.000	Dlr
0090	Edge Trimming	5010009	6,500.000	Ft
0095	Longit Joint Density Quality Initiative	5010018	12,715.000	Dlr
0100	Pavt Joint and Crack Repr, Det 7	5010020	1,200.000	Ft
0105	Hand Patching	5010025	85.000	Ton
0110	HMA Approach	5010061	154.000	Ton
0115	HMA, 4EML	5012025	663.000	Ton
0120	HMA, 5EML	5012037	2,468.000	Ton
0125	Curb Slp, HMA	8050010	2,040.000	Ft
0130	Post, Mailbox	8070095	5.000	Ea

0135	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	4.000	Ea
0140	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0145	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0150	Pavt Mrkg, Ovly Cold Plastic, Stop	8110075	1.000	Ea
0155	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	100.000	Ft
0160	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	200.000	Ft
0165	Pavt Mrkg, Waterborne, 6 inch, White	8110233	12,750.000	Ft
0170	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	7,725.000	Ft
0175	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	12,750.000	Ft
0180	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	7,725.000	Ft
0185	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0190	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0195	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0200	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0205	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0210	Minor Traf Devices	8120170	1.000	LSUM
0215	Plastic Drum, Fluorescent, Furn	8120252	30.000	Ea
0220	Plastic Drum, Fluorescent, Oper	8120253	30.000	Ea
0225	Sign Cover	8120310	8.000	Ea
0230	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0235	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0240	Sign, Type B, Temp, Prismatic, Furn	8120350	1,200.000	Sft
0245	Sign, Type B, Temp, Prismatic, Oper	8120351	1,200.000	Sft
0250	Traf Regulator Control	8120370	1.000	LSUM
0255	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	550.000	Ft
0260	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0265	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0270	_ HMA Spillway	8147011	40.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 034

**Letting Date:** October 3, 2025

**Contract ID:** 50111-220283

**Description:** 0.97 mi of high friction surface treatment on various routes, Wayne, Oakland and Macomb Counties.  
This project includes a 5 year bridge deck performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220283A	25A0955	N/A	HSIP 50111

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$78,800.00	1100001	1.000	LSUM
0010	Project Cleanup	2090001	1.000	LSUM
0015	High Friction Surface Treatment	5060800	18,809.000	Syd
0020	_ High Friction Epoxy Ovly, Warranty	7127011	2,253.000	Syd
0025	Pavt Mrkg, Waterborne, 6 inch, White	8110233	14,235.000	Ft
0030	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	10,328.000	Ft
0035	Pavt Mrkg, Waterborne, 12 inch, White	8110237	3,268.000	Ft
0040	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0045	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0050	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0055	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0060	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0065	Minor Traf Devices	8120170	1.000	LSUM
0070	Mobile Attenuator	8120180	2.000	Ea
0075	Plastic Drum, Fluorescent, Furn	8120252	330.000	Ea
0080	Plastic Drum, Fluorescent, Oper	8120253	330.000	Ea
0085	Sign Cover	8120310	15.000	Ea
0090	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0095	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0100	Sign, Type B, Temp, Prismatic, Furn	8120350	1,200.000	Sft
0105	Sign, Type B, Temp, Prismatic, Oper	8120351	1,200.000	Sft
0110	Contractor Staking	8240001	1.000	LSUM
0115	Staking Plan Errors and Extras, Max \$180/hour	8240002	2.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 035

**Letting Date:** October 3, 2025

**Contract ID:** 27031-219858

**Description:** 1.31 mi of overband crack seal, single chip seal, micro-surface, shoulder aggregate and pavement markings on M-64 from Sawmill Lane northerly to US-2 in the village of Marenisco, Gogebic County. This project includes a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219858A	25A0969	N/A	ST 27031

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$32,100.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	9.000	Ea
0015	Shld, CI II	3070121	228.000	Ton
0020	Overband Crack Fill, Lane	5020003	2.640	Lnmi
0025	Micro-Surface, Single Cse, Warranty	5040020	27,220.000	Syd
0030	Seal, Single Chip	5050001	27,220.000	Syd
0035	Pavt Mrkg, Waterborne, 6 inch, White	8110233	12,801.000	Ft
0040	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	8,390.000	Ft
0045	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	12,801.000	Ft
0050	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	8,390.000	Ft
0055	Rem Spec Mrkg	8110343	441.000	Sft
0060	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0065	Protective Ovly, Snowmobile Trail Crossing	8110550	49.000	Syd
0070	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0075	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0090	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	816.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	816.000	Sft
0105	Traf Regulator Control	8120370	1.000	LSUM
0110	Rumble Strip, Temp, Portable, Furn	8122188	6.000	Ea
0115	Rumble Strip, Temp, Portable, Oper	8122189	6.000	Ea
0120	Monument Box, Adj	8210005	1.000	Ea



9/4/2025 3:05 PM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 036

**Letting Date:** October 3, 2025

**Contract ID:** 29011-222916

**Description:** Replacement of building heating system and geothermal abandonment at Ithaca Rest Area, Gratiot County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222916A	N/A	N/A	M 29011

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$8,400.00	1100001	1.000	LSUM
0010	Erosion Control, Silt Fence	2080036	150.000	Ft
0015	_ Rest Area Building Heat System	7097051	1.000	LSUM
0020	_ Decommission Closed-Loop Ground Source Heat Exchange System	8007051	1.000	LSUM
0025	_ Underground Propane Tank System	8007051	1.000	LSUM
0030	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0035	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0040	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0045	Minor Traf Devices	8120170	1.000	LSUM
0050	Plastic Drum, Fluorescent, Furn	8120252	40.000	Ea
0055	Plastic Drum, Fluorescent, Oper	8120253	40.000	Ea
0060	Sign Cover	8120310	3.000	Ea
0065	Sign Cover, Type I	8120320	1.000	Ea
0070	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	1.000	Ea
0075	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	1.000	Ea
0080	Sign, Type B, Temp, Prismatic, Furn	8120350	63.000	Sft
0085	Sign, Type B, Temp, Prismatic, Oper	8120351	63.000	Sft
0090	_ Turf Establishment, Performance, Modified	8167011	1,000.000	Syd
0095	Contractor Staking	8240001	1.000	LSUM
0100	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 037

**Letting Date:** October 3, 2025

**Contract ID:** 80012-223415

**Description:** 27.19 mi of overband crack fill, single course chip seal, fog seal and pavement markings on I-196 northbound from I-94 northerly to the Van Buren Trail, on I-196 southbound from I-94 to north of Coloma Road, on I-196BL from 15th Avenue to south of Alyworth Avenue and on M-63 from Blue Star Highway to Harrison Street, Berrien and Van Buren Counties. This project contains a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
223415A	25A0966	N/A	NH 80012

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$232,000.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	5.000	Ea
0015	Overband Crack Fill, Lane	5020003	44.000	Lnmi
0020	Overband Crack Fill, Ramp	5020004	5.000	Lnmi
0025	_ Overband Crack Fill, Carpool Parking Lot	5027011	1,188.000	Syd
0030	Seal, Fog	5050015	594,120.000	Syd
0035	Chip Seal, Single, Warranty	5050040	592,932.000	Syd
0040	Pavt Mrkg, Ovly Cold Plastic, Merge Arrow Sym	8110050	2.000	Ea
0045	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	8.000	Ea
0050	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0055	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0060	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0065	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	2.000	Ea
0070	Pavt Mrkg, Waterborne, 6 inch, White	8110233	177,690.000	Ft
0075	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	144,900.000	Ft
0080	Pavt Mrkg, Waterborne, 12 inch, White	8110237	6,822.000	Ft
0085	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	177,690.000	Ft
0090	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	144,900.000	Ft
0095	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	6,822.000	Ft
0100	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	80.000	Ft
0105	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	620.000	Ft
0110	Rem Spec Mrkg	8110343	816.000	Sft
0115	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0120	Pavt Mrkg, Polyurea, Merge	8110407	2.000	Ea

0125	Pavt Mrkg, Polyurea, Exit	8112186	2.000	Ea
0130	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	14.000	Ea
0135	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	14.000	Ea
0140	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	450.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	450.000	Ea
0150	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0155	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Raised Pavt Marker, Temp, Type 1, White, Monodirectional	8120280	2,340.000	Ea
0170	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	1,170.000	Ea
0175	Sign Cover	8120310	15.000	Ea
0180	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	8.000	Ea
0185	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	8.000	Ea
0190	Sign, Type A, Temp, Prismatic, Furn	8120340	36.000	Sft
0195	Sign, Type A, Temp, Prismatic, Oper	8120341	36.000	Sft
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	2,401.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	2,401.000	Sft
0210	Traf Regulator Control	8120370	1.000	LSUM
0215	Speed Radar Trailer, Temp	8122028	2.000	Ea
0220	Contractor Staking	8240001	1.000	LSUM
0225	Staking Plan Errors and Extras, Max \$180/hour	8240002	27.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 038

**Letting Date:** October 3, 2025

**Contract ID:** 23063-222458

**Description:** 0.39 mi of application of high friction surface treatment and epoxy overlay on the I-96WB ramp to I-69SB, Eaton County. This project includes a 5 year epoxy performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222458A	25A0954	N/A	HSIP 23063

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$14,700.00	1100001	1.000	LSUM
0010	High Friction Surface Treatment	5060800	3,135.000	Syd
0015	_ High Friction Epoxy Ovly, Warranty	7127011	1,000.000	Syd
0020	Pavt Mrkg, Waterborne, 6 inch, White	8110233	2,035.000	Ft
0025	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	2,115.000	Ft
0030	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0035	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0040	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0045	Connected Arrow Board, Type C, Furn	8120155	1.000	Ea
0050	Connected Arrow Board, Type C, Oper	8120156	1.000	Ea
0055	Minor Traf Devices	8120170	1.000	LSUM
0060	Mobile Attenuator	8120180	1.000	Ea
0065	Plastic Drum, Fluorescent, Furn	8120252	175.000	Ea
0070	Plastic Drum, Fluorescent, Oper	8120253	175.000	Ea
0075	Sign Cover	8120310	5.000	Ea
0080	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0085	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0090	Sign, Type A, Temp, Prismatic, Furn	8120340	230.000	Sft
0095	Sign, Type A, Temp, Prismatic, Oper	8120341	230.000	Sft
0100	Sign, Type B, Temp, Prismatic, Furn	8120350	760.000	Sft
0105	Sign, Type B, Temp, Prismatic, Oper	8120351	760.000	Sft
0110	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	380.000	Sft
0115	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	380.000	Sft



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 039

**Letting Date:** October 3, 2025

**Contract ID:** 71021-213189

**Description:** 26.55 mi of overband crack fill, single chip seal, fog seal, shoulder aggregate, micro-surfacing, centerline and edgeline corrugations, high stress hot mix asphalt, fine texture cold milling and resurfacing and pavement markings on M-30, M-65 and M-68, Ogemaw, Iosco, Alcona and Presque Isle Counties. This project includes a 3 year materials and workmanship pavement warranty and a 2 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221838A	25A0956	N/A	ST 71021

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$276,600.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	17.000	Ea
0015	Approach, CI II	3070021	80.000	Ton
0020	_ Shld CI II, Modified	3077031	3,120.000	Ton
0025	Cold Milling HMA Surface	5010002	32,790.000	Syd
0030	Bump Grinding	5010004	40.000	Syd
0035	HMA Quality Initiative	5010007	8,000.000	Dlr
0040	Longit Joint Density Quality Initiative	5010018	16,515.000	Dlr
0045	HMA Approach, High Stress	5010520	125.000	Ton
0050	HMA, 5EL, High Stress	5012084	2,665.000	Ton
0055	Overband Crack Fill, Lane	5020003	52.030	Lnmi
0060	Micro-Surface, Longit	5042005	19,467.000	Ft
0065	Seal, Fog	5050015	471,680.000	Syd
0070	Chip Seal, Single, Warranty	5050040	471,680.000	Syd
0075	Chip Seal Emulsion, Long Line Application	5050100	59,855.000	Ft
0080	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	12.000	Ft
0085	Pavt Mrkg, Waterborne, 6 inch, White	8110233	280,124.000	Ft
0090	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	98,171.000	Ft
0095	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	280,124.000	Ft
0100	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	98,171.000	Ft
0105	Rem Spec Mrkg	8110343	659.000	Sft
0110	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0115	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	1.000	Ea
0120	Pavt Mrkg, Polyurea, Only	8110410	3.000	Ea
0125	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	8.000	Ea
0130	Protective Ovly, Snowmobile Trail Crossing	8110550	68.000	Syd

0135	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,870.000	Ea
0140	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,870.000	Ea
0145	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0150	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0155	Minor Traf Devices	8120170	1.000	LSUM
0160	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	7,135.000	Ea
0165	Sign Cover	8120310	15.000	Ea
0170	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0175	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0180	Sign, Type B, Temp, Prismatic, Furn	8120350	2,332.000	Sft
0185	Sign, Type B, Temp, Prismatic, Oper	8120351	2,332.000	Sft
0190	Traf Regulator Control	8120370	1.000	LSUM
0195	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	1,092.000	Ft
0200	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	25,000.000	Ft
0205	Rumble Strip, Temp, Portable, Furn	8122188	30.000	Ea
0210	Rumble Strip, Temp, Portable, Oper	8122189	30.000	Ea
0215	_ Automated Flagger Assistance Device	8127050	5.000	Ea
0220	_ Pilot Car	8127051	1.000	LSUM
0225	Monument Box	8210001	1.000	Ea
0230	Monument Preservation	8210010	1.000	Ea
0235	Centerline Corrugations, Milled, HMA	8220013	21,228.000	Ft
0240	_ Sinusoidal Corrugations, Milled, HMA Edgeline	8227001	254,338.000	Ft



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 040

**Letting Date:** October 3, 2025

**Contract ID:** 36022-221817

**Description:** 1.64 mi of micro texture pavement milling, paver placed surface seal, 41 drainage structure repairs and permanent pavement markings from west of US-141 easterly to Urban Avenue in the city of Crystal Falls, Iron County. This project includes a 3 year pavement performance warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221817A	25A0963	N/A	NH 36022

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$56,200.00	1100001	1.000	LSUM
0010	Curb, Rem	2040021	170.000	Ft
0015	Erosion Control, Inlet Protection, Fabric Drop	2080020	63.000	Ea
0020	Shld, CI II, LM	3070123	11.000	Cyd
0025	Dr Structure Cover, Adj, Case 1	4030005	41.000	Ea
0030	Dr Structure, Adj, Add Depth	4030280	10.000	Ft
0035	Micro Texture Pavt Milling	5010101	37,334.000	Syd
0040	Overband Crack Fill, Lane	5020003	4.880	Lnmi
0045	Paver Placed Surface Seal, Type C, Warranty	5030041	37,334.000	Syd
0050	Curb and Gutter, Conc, Det F4	8020038	170.000	Ft
0055	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	216.000	Ft
0060	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	90.000	Ft
0065	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	48.000	Ft
0070	Pavt Mrkg, Waterborne, 6 inch, White	8110233	2,430.000	Ft
0075	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	25,480.000	Ft
0080	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	2,430.000	Ft
0085	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	25,480.000	Ft
0090	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0095	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	9.000	Ea
0100	Pavt Mrkg, Polyurea, Only	8110410	4.000	Ea
0105	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	3.000	Ea
0110	Pavt Mrkg, Polyurea, School	8110414	2.000	Ea
0115	Pavt Mrkg, Polyurea, Thru and Lt Turn Arrow Sym	8110416	1.000	Ea
0120	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	2.000	Ea
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	6.000	Ea
0130	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	6.000	Ea

0135	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0140	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0145	Minor Traf Devices	8120170	1.000	LSUM
0150	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0155	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0160	Sign Cover	8120310	5.000	Ea
0165	Sign, Type B, Temp, Prismatic, Furn	8120350	1,150.000	Sft
0170	Sign, Type B, Temp, Prismatic, Oper	8120351	1,150.000	Sft
0175	Traf Regulator Control	8120370	1.000	LSUM
0180	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	400.000	Ft
0185	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,700.000	Ft
0190	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	400.000	Ft
0195	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	2,700.000	Ft
0200	Rumble Strip, Temp, Portable, Furn	8122188	6.000	Ea
0205	Rumble Strip, Temp, Portable, Oper	8122189	6.000	Ea
0210	Monument Box	8210001	1.000	Ea
0215	Monument Box, Adj	8210005	2.000	Ea
0220	Monument Preservation	8210010	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 041

**Letting Date:** October 3, 2025

**Contract ID:** 11019-219292

**Description:** 0.03 mi of culvert replacement including hot mix asphalt reconstruction, drainage improvements and pavement markings on M-239 over Blood Run Creek near the Indiana/Michigan state line, Berrien County.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219292A	25A0961	N/A	ST 11019

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$64,900.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.220	Acre
0015	Culv, Rem, Over 48 inch	2030003	1.000	Ea
0020	Excavation, Earth	2050016	1,454.000	Cyd
0025	Non Haz Contaminated Material Handling and Disposal, LM	2050031	20.000	Cyd
0030	_ Embankment, CIP, Spec	2057021	458.000	Cyd
0035	_ Channel, Temp	2057051	1.000	LSUM
0040	Erosion Control, Check Dam, Stone	2080012	90.000	Ft
0045	Erosion Control, Filter Bag	2080014	2.000	Ea
0050	Erosion Control, Gravel Filter Berm	2080018	90.000	Ft
0055	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0060	Erosion Control, Sand Bag	2080028	25.000	Ea
0065	Erosion Control, Sediment Trap	2080034	8.000	Ea
0070	Erosion Control, Silt Fence	2080036	412.000	Ft
0075	Erosion Control, Turbidity Curtain, Shallow	2080044	200.000	Ft
0080	_ Liner, PVC, 30 mil, Spec	2087011	14.000	Syd
0085	Subbase, CIP	3010002	1,030.000	Cyd
0090	Aggregate Base, 6 inch	3020016	821.000	Syd
0095	Shld, CI II, 6 inch	3070128	75.000	Syd
0100	Culv, Reinf Conc Ellip, HE CI II, 63 inch by 98 inch	4010866	120.000	Ft
0105	Dr Marker Post	4011109	4.000	Ea
0110	_ Culv End Treatment, Conc, Ellip Pipe, 63 inch by 98 inch	4017050	2.000	Ea
0115	Video Taping Sewer and Culv Pipe	4021275	120.000	Ft
0120	Underdrain, Fdn, 6 inch	4040033	240.000	Ft
0125	Underdrain Outlet, 6 inch	4040093	40.000	Ft
0130	Underdrain, Outlet Ending, 6 inch	4040113	4.000	Ea

0135	Video Inspection of Underdrain	4040200	280.000	Ft
0140	HMA Surface, Rem	5010005	739.000	Syd
0145	HMA Quality Initiative	5010007	544.000	Dlr
0150	HMA Approach	5010061	272.000	Ton
0155	Water Repellent Treatment, Penetrating	7060140	21.000	Syd
0160	Delineator, Rem	8100349	2.000	Ea
0165	Pavt Mrkg, Waterborne, 6 inch, White	8110233	600.000	Ft
0170	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	600.000	Ft
0175	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	600.000	Ft
0180	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	600.000	Ft
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	14.000	Ea
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	14.000	Ea
0195	Minor Traf Devices	8120170	1.000	LSUM
0200	Plastic Drum, Fluorescent, Furn	8120252	55.000	Ea
0205	Plastic Drum, Fluorescent, Oper	8120253	55.000	Ea
0210	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0215	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0220	Sign, Type B, Temp, Prismatic, Furn	8120350	1,926.000	Sft
0225	Sign, Type B, Temp, Prismatic, Oper	8120351	1,926.000	Sft
0230	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	21.000	Sft
0235	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	21.000	Sft
0240	Traf Regulator Control	8120370	1.000	LSUM
0245	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0250	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0255	Riprap, Plain	8130010	195.000	Syd
0260	_ Arboricultural Work	8157040	10.000	Hr
0265	Slope Restoration, Non-Freeway, Type F	8162006	1,115.000	Syd
0270	Slope Restoration, Non-Freeway, Type G	8162007	425.000	Syd
0275	Contractor Staking	8240001	1.000	LSUM
0280	Staking Plan Errors and Extras, Max \$180/hour	8240002	8.000	Hr



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 042

**Letting Date:** October 3, 2025

**Contract ID:** 29042-217888

**Description:** 12.29 mi of hot mix asphalt cold milling and resurfacing, concrete sidewalk ramps and pavement markings on M-46 from Croswell Road to the west village limits of Merrill in the village of Breckenridge and Wheeler Township, Gratiot and Saginaw Counties. This project includes a 3 year materials and workmanship warranty.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
217888A	N/A	N/A	M 29042
224529A	25A0960	N/A	STRH 29042

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Mid-Michigan Railroad	1027060	15,000.000	Dlr
0010	Mobilization, Max \$398,800.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	279.000	Ft
0020	Guardrail, Rem	2040035	3,550.000	Ft
0025	Pavt, Rem	2040050	210.000	Syd
0030	Sidewalk, Rem	2040055	108.000	Syd
0035	Embankment, CIP	2050010	20.000	Cyd
0040	Excavation, Earth	2050016	513.000	Cyd
0045	Subbase, CIP	3010002	478.000	Cyd
0050	Aggregate Base, 3 inch	3020008	43.000	Syd
0055	Aggregate Base, 6 inch	3020016	830.000	Syd
0060	_ Shld, CI II, Modified	3077031	11,530.000	Ton
0065	Dr Structure Cover, Adj, Case 1, Modified	4030004	36.000	Ea
0070	Dr Structure Cover, Type K	4030050	4.000	Ea
0075	Cold Milling HMA Surface	5010002	221,500.000	Syd
0080	HMA Surface, Rem	5010005	813.000	Syd
0085	HMA Quality Initiative	5010007	38,508.000	Dlr
0090	Longit Joint Density Quality Initiative	5010018	76,949.000	Dlr
0095	Hand Patching	5010025	14.000	Ton
0100	HMA Approach	5010061	1,310.000	Ton
0105	HMA, 5EML	5012037	16,630.000	Ton
0110	HMA, 5EML, High Stress	5012085	1,300.000	Ton
0115	Conc Base Cse, Nonreinf, 6 inch	6020015	43.000	Syd
0120	Curb and Gutter, Conc, Det F4	8020038	279.000	Ft
0125	Driveway Opening, Conc, Det M	8020050	40.000	Ft

0130	Detectable Warning Surface	8030010	66.000	Ft
0135	Curb Ramp Opening, Conc	8030030	91.000	Ft
0140	Sidewalk, Conc, 6 inch	8030046	422.000	Sft
0145	Curb Ramp, Conc, 6 inch	8032002	452.000	Sft
0150	Guardrail Approach Terminal, Type 2M	8070044	14.000	Ea
0155	Guardrail Departing Terminal, Type B	8070050	2.000	Ea
0160	Guardrail Reflector	8070080	100.000	Ea
0165	Guardrail Anch, Bridge, Det M1	8070130	4.000	Ea
0170	Guardrail, Long Span, Det MGS-2	8072122	3.000	Ea
0175	Guardrail, Long Span, Det MGS-3	8072123	2.000	Ea
0180	Guardrail, Type MGS-8, 72 inch Post	8072179	1,400.000	Ft
0185	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	6.000	Ea
0190	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	2.000	Ea
0195	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0200	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0205	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	82.000	Ft
0210	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	288.000	Ft
0215	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	168.000	Ft
0220	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0225	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	240.000	Ft
0230	Recessing Pavt Mrkg, Longit	8110450	149,654.000	Ft
0235	Recessing Pavt Mrkg, Transv	8110451	1,549.000	Sft
0240	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	121,278.000	Ft
0245	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	28,376.000	Ft
0250	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	32.000	Ea
0255	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	32.000	Ea
0260	Pedestrian Type II Barricade, Temp	8120026	15.000	Ea
0265	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0270	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0275	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0280	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0285	Minor Traf Devices	8120170	1.000	LSUM
0290	Sign Cover	8120310	10.000	Ea
0295	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0300	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0305	Sign, Type B, Temp, Prismatic, Furn	8120350	1,710.000	Sft
0310	Sign, Type B, Temp, Prismatic, Oper	8120351	1,710.000	Sft
0315	Traf Regulator Control	8120370	1.000	LSUM
0320	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	600.000	Ft
0325	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	11,400.000	Ft

0330	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0335	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0340	Slope Restoration, Non-Freeway, Type A	8162001	120.000	Syd
0345	_ Turf Establishment, Performance, Modified	8167011	114.000	Syd
0350	TS Face, Bag	8200458	2.000	Ea
0355	TS Face, Bag, Rem	8200459	2.000	Ea
0360	Radar Vehicle Presence Stop-Bar Detector System	8200510	1.000	Ea
0365	Radar Vehicle Presence Stop-Bar Detector Sensor	8200513	1.000	Ea
0370	Monument Box, Adj	8210005	16.000	Ea
0375	Protect Corners	8210020	16.000	Ea
0380	Centerline Corrugations, Milled, HMA	8220013	59,800.000	Ft
0385	Water Shutoff, Adj, Case 1	8230421	6.000	Ea
0390	Contractor Staking	8240001	1.000	LSUM
0395	Staking Plan Errors and Extras, Max \$180/hour	8240002	45.000	Hr

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 043

**Letting Date:** October 3, 2025

**Contract ID:** 19000-220163

**Description:** 0.28 mi of guardrail improvements and shoulder widening on N. Shepardsville Road from Maple Rapids Road to Gratiot Road, Clinton County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
220163A	25A0905	N/A	HSIP 19000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$11,100.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	1,131.000	Ft
0015	_ Roadway Grading	2057002	15.000	Sta
0020	Erosion Control, Silt Fence	2080036	1,500.000	Ft
0025	Project Cleanup	2090001	1.000	LSUM
0030	Shld, CI II, 4 inch	3070126	1,000.000	Syd
0035	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0040	Guardrail Reflector	8070080	56.000	Ea
0045	Guardrail, Type MGS-8, 108 inch Post	8072180	1,350.000	Ft
0050	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0055	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0070	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0075	Sign, Type B, Temp, Prismatic, Furn	8120350	197.000	Sft
0080	Sign, Type B, Temp, Prismatic, Oper	8120351	197.000	Sft
0085	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	64.000	Sft
0090	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	64.000	Sft
0095	Slope Restoration, Non-Freeway, Type G	8162007	2,000.000	Syd



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 044

**Letting Date:** October 3, 2025

**Contract ID:** 38000-219895-2

**Description:** 6.89 mi of tree removal, flashing LED stop sign, sign upgrades, guardrail improvements, and pavement markings along Jackson Road from Vicary Road to Kimmel Road and Ackerson Lake Road at Hart Road, Jackson County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
219895A	25A0728	N/A	HRRR 38000
220179A	25A0729	N/A	HSIP 38000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$42,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	49.000	Ea
0015	Tree, Rem, 37 inch or Larger	2020003	20.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	23.000	Ea
0025	Stump, Rem, 19 inch to 36 inch	2020006	1.000	Ea
0030	Guardrail, Rem	2040035	1,198.000	Ft
0035	Embankment, CIP	2050010	250.000	Cyd
0040	Guardrail Approach Terminal, Type 2M	8070044	6.000	Ea
0045	Guardrail Reflector	8070080	56.000	Ea
0050	Guardrail, Type MGS-8, 108 inch Post	8072180	1,200.000	Ft
0055	Delineator Reflector, Green	8100133	6.000	Ea
0060	Post, Rigid, Delineator	8100361	6.000	Ea
0065	Post, Steel, 3 pound	8100371	1,416.000	Ft
0070	Sign, Type III, Erect, Salv	8100402	9.000	Ea
0075	Sign, Type III, Rem	8100403	66.000	Ea
0080	Sign, Type IIIA	8100404	179.000	Sft
0085	Sign, Type IIIB	8100405	264.000	Sft
0090	Sign, Type V, Rem	8100421	2.000	Ea
0095	Sign, Type VB	8100425	24.000	Sft
0100	Reflective Panel for Permanent Sign Support, 6 foot	8100616	84.000	Ea
0105	Sign, Type III, Rem, Salv	8102003	9.000	Ea
0110	Ground Mtd Sign Support, Rem	8102010	47.000	Ea
0115	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	102.000	Ft
0120	Pavt Mrkg, Waterborne, 4 inch, White	8110231	71,692.000	Ft
0125	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	70,886.000	Ft
0130	Rem Spec Mrkg	8110343	80.000	Sft

0135	Recessing Pavt Mrkg, Longit	8110450	142,578.000	Ft
0140	Recessing Pavt Mrkg, Transv	8110451	204.000	Sft
0145	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 4 inch, White	8112000	71,692.000	Ft
0150	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 4 inch, Yellow	8112003	70,886.000	Ft
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	220.000	Ea
0170	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	220.000	Ea
0175	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0180	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0185	Minor Traf Devices	8120170	1.000	LSUM
0190	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0195	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	758.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	758.000	Sft
0210	Traf Regulator Control	8120370	1.000	LSUM
0215	Slope Restoration, Non-Freeway, Type A	8162001	1,150.000	Syd
0220	_ Flsh LED Border Sign, Solar	8207050	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 045

**Letting Date:** October 3, 2025

**Contract ID:** 41000-222061

**Description:** Pedestrian hybrid beacon and median refuge island installation, signing and pavement markings on Division Avenue between Leroy Street to Elwell Street in the city of Kentwood, Kent County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
222061A	25A0879	N/A	VRU 41000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$27,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	62.000	Ft
0015	Pavt, Rem	2040050	201.000	Syd
0020	Sidewalk, Rem	2040055	51.000	Syd
0025	Excavation, Earth	2050016	10.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	4.000	Ea
0035	Aggregate Base, 6 inch	3020016	12.000	Syd
0040	Hand Patching	5010025	12.000	Ton
0045	Conc Base Cse, Nonreinf, 6 inch	6020015	223.000	Syd
0050	Curb, Conc, Det E4	8020004	300.000	Ft
0055	Curb Ramp Opening, Conc	8030030	20.000	Ft
0060	Sidewalk, Conc, 6 inch	8030046	500.000	Sft
0065	_ Detectable Warning Surface, Metal	8037001	20.000	Ft
0070	Post Hole Through Conc for Steel Post	8100340	10.000	Ea
0075	Post, Steel, 3 pound	8100371	90.000	Ft
0080	Sign, Type IIIB	8100405	200.000	Sft
0085	Reflective Panel for Permanent Sign Support, 6 foot	8100616	4.000	Ea
0090	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	60.000	Ft
0095	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	40.000	Ft
0100	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	4.000	Ea
0110	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0125	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0130	Lighted Arrow, Type C, Oper	8120141	2.000	Ea

0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Sign, Type B, Temp, Prismatic, Furn	8120350	300.000	Sft
0145	Sign, Type B, Temp, Prismatic, Oper	8120351	300.000	Sft
0150	Traf Regulator Control	8120370	1.000	LSUM
0155	Slope Restoration, Non-Freeway, Type A	8162001	12.000	Syd
0160	Power Company (Estimated Cost to Contractor)	8180001	1,000.000	Dlr
0165	Conduit, Directional Bore, 3, 3 inch	8182039	200.000	Ft
0170	Conduit, DB, 1, 1 1/2 inch	8182048	100.000	Ft
0175	Conduit, DB, 3, 3 inch	8182056	150.000	Ft
0180	Conduit, DB, 4, 3 inch	8182059	150.000	Ft
0185	Cable, Sec, 600V, 1, 3/C#6	8182238	20.000	Ft
0190	Hh, Round, 3 foot dia	8182319	3.000	Ea
0195	Serv Disconnect	8182366	1.000	Ea
0200	Light Std Arm, 17 foot	8190270	2.000	Ea
0205	Luminaire	8190330	2.000	Ea
0210	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	2.000	Ea
0215	Controller Fdn, Base Mtd	8200045	1.000	Ea
0220	Pushbutton and Sign	8200121	2.000	Ea
0225	TS, One Way Mast Arm Mtd	8200250	4.000	Ea
0230	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	2.000	Ea
0235	Casing, 42 inch	8200485	44.000	Ft
0240	Cellular Modem, TS, 4th G	8200498	1.000	Ea
0245	Mast Arm Pole, Cat I	8202010	2.000	Ea
0250	Mast Arm, 35 foot, Cat I	8202016	2.000	Ea
0255	Mast Arm Pole Fdn, 6 Bolt	8202034	50.000	Ft
0260	_ Cabinet, NEMA Type, Modified	8207050	1.000	Ea
0265	_ Controller, NEMA, ATC Type, Modified	8207050	1.000	Ea
0270	_ Managed Field Ethernet Switch, Layer 2, Modified	8207050	1.000	Ea
0275	_ Opticom GPS System	8207050	1.000	Ea



9/12/2025 7:35 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

### Schedule of Pay Items

Report v1

**Letting Call:** 251003 046

**Letting Date:** October 3, 2025

**Contract ID:** 32000-221234

**Description:** 1.01 mi of hot mix asphalt paving, cold milling, aggregate shoulder, and permanent pavement markings in the village of Kinde, Huron County. This is a Local Agency project.

#### Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221234A	25A0883	N/A	STL 32000

#### List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$33,000.00	1100001	1.000	LSUM
0010	_ Shld, CI II, Modified	3077031	85.000	Ton
0015	Pavt, Cleaning	5010001	1.000	LSUM
0020	Cold Milling HMA Surface	5010002	23,763.000	Syd
0025	HMA Approach	5010061	105.000	Ton
0030	_ HMA, 4EL, Modified	5017031	2,350.000	Ton
0035	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	564.000	Ft
0040	Pavt Mrkg, Waterborne, 4 inch, White	8110231	4,020.000	Ft
0045	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	1,338.000	Ft
0050	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0055	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	411.000	Ft
0070	Pavt Mrkg, Wet Reflective, Type NR, Tape, 4 inch, Yellow, Temp	8120264	411.000	Ft
0075	Sign, Type B, Temp, Prismatic, Furn	8120350	495.000	Sft
0080	Sign, Type B, Temp, Prismatic, Oper	8120351	495.000	Sft
0085	Traf Regulator Control	8120370	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 047

**Letting Date:** October 3, 2025

**Contract ID:** 69000-215313

**Description:** 0.99 mi of hot mix asphalt cold milling and resurfacing, sanitary sewer, concrete sidewalk and ramps and pavement markings on Center Avenue from Main Street (M-32) to Fairview Road in the city of Gaylord, Otsego County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215313A	25A0801	N/A	STUL 69000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$106,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	2,355.000	Ft
0015	Curb, Rem	2040021	114.000	Ft
0020	Pavt, Rem	2040050	79.000	Syd
0025	Sidewalk, Rem	2040055	295.000	Syd
0030	_ Trench Grading, Modified	2057002	20.000	Sta
0035	Subbase, CIP	3010002	1,236.000	Cyd
0040	Aggregate Base, 6 inch	3020016	3,240.000	Syd
0045	Sewer, Cl A, 12 inch, Tr Det A	4020004	92.000	Ft
0050	Dr Structure Cover, Adj, Case 1	4030005	35.000	Ea
0055	Dr Structure Cover, Type K	4030050	3.000	Ea
0060	Dr Structure Cover, Type R	4030070	1.000	Ea
0065	Dr Structure, 24 inch dia	4030200	4.000	Ea
0070	_ Dr Structure, Reconstruct	4037001	30.000	Ft
0075	Cold Milling HMA Surface	5010002	20,027.000	Syd
0080	HMA Surface, Rem	5010005	3,285.000	Syd
0085	Hand Patching	5010025	10.000	Ton
0090	HMA Approach	5010061	37.000	Ton
0095	HMA, 4EML	5012025	2,992.000	Ton
0100	Driveway, Nonreinf Conc, 6 inch	8010005	86.000	Syd
0105	Curb and Gutter, Conc, Det F4	8020038	2,161.000	Ft
0110	Driveway Opening, Conc, Det M	8020050	248.000	Ft
0115	Curb Ramp Opening, Conc	8030030	12.000	Ft
0120	Sidewalk, Conc, 4 inch	8030044	1,134.000	Sft
0125	Sidewalk, Conc, 6 inch	8030046	329.000	Sft
0130	Curb Ramp, Conc, 4 inch	8032001	56.000	Sft
0135	_ Dectectable Warning Surface, Cast Iron, Spec	8037001	16.000	Ft

0140	_ Sidewalk, Conc, Decorative, 4 inch	8037010	1,160.000	Sft
0145	Post, Steel, 3 pound	8100371	56.000	Ft
0150	Sign, Type III, Erect, Salv	8100402	4.000	Ea
0155	Sign, Type III, Rem	8100403	4.000	Ea
0160	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0165	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	72.000	Ft
0170	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	140.000	Ft
0175	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	24.000	Ft
0180	Pavt Mrkg, Waterborne, 4 inch, White	8110231	75.000	Ft
0185	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	12,850.000	Ft
0190	Pavt Mrkg, Ovly Cold Plastic, Left	8110368	17.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	22.000	Ea
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	22.000	Ea
0205	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0210	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	110.000	Ea
0215	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	110.000	Ea
0220	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0225	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0230	Minor Traf Devices	8120170	1.000	LSUM
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	948.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	948.000	Sft
0245	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	326.000	Sft
0250	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	326.000	Sft
0255	Traf Regulator Control	8120370	1.000	LSUM
0260	_ Slope Restoration, Type A, Modified	8167011	1,258.000	Syd
0265	Monument Box, Adj	8210005	1.000	Ea
0270	Monument Preservation	8210010	1.000	Ea
0275	Gate Box, Adj, Case 1	8230431	5.000	Ea
0280	_ Hydrant, Replace, Type I	8237050	3.000	Ea
0285	_ Hydrant, Replace, Type II	8237050	4.000	Ea
0290	Sanitary Structure Cover, Adj, Case 1	8252145	7.000	Ea
0295	_ Sanitary Sewer, PVC, 8 inch, Tr Det B2, Modified	8257001	1,872.000	Ft
0300	_ Sanitary Sewer, Serv Lead, PVC, 6 inch, Modified	8257001	492.000	Ft
0305	_ Sanitary Sewer Cleanout Assembly	8257050	20.000	Ea
0310	_ Sanitary Sewer Cleanout Casting	8257050	4.000	Ea
0315	_ Sanitary Sewer Wye, 8 inch by 6 inch	8257050	17.000	Ea
0320	_ Sanitary Structure Cover, Type Q, Modified	8257050	1.000	Ea
0325	_ Sanitary Structure, 48 inch dia, Modified	8257050	1.000	Ea
0330	_ Sanitary Structure, Rem, Modified	8257050	1.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 048

**Letting Date:** October 3, 2025

**Contract ID:** 73000-221355

**Description:** Bridge reconstruction including removal and replacement with 25-foot x 14-foot clam shell culvert and approach work on Chapin Road over the Lamb Creek, Saginaw County. This is Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221355A	N/A	N/A	EDD 73000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$100,700.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	502.000	Ft
0015	_ Machine Grading, Modified	2057002	2.000	Sta
0020	Erosion Control, Filter Bag	2080014	1.000	Ea
0025	Erosion Control, Silt Fence	2080036	344.000	Ft
0030	Subbase, CIP	3010002	187.000	Cyd
0035	_ Aggregate Base, Modified	3027031	392.000	Ton
0040	Maintenance Gravel	3060020	25.000	Ton
0045	_ Shld, CL II, 5.5 inch, Modified	3077011	194.000	Syd
0050	_ Shld, CI II, Modified	3077031	14.000	Ton
0055	HMA Surface, Rem	5010005	434.000	Syd
0060	HMA, 4EL	5012024	123.000	Ton
0065	HMA, 5EL	5012036	46.000	Ton
0070	Guardrail Approach Terminal, Type 2M	8070044	3.000	Ea
0075	Guardrail Departing Terminal, Type B	8070050	1.000	Ea
0080	Guardrail Reflector	8070080	18.000	Ea
0085	Guardrail, Curved, Type B-CRT	8072154	13.000	Ft
0090	Guardrail, Type MGS-8, 108 inch Post	8072180	385.000	Ft
0095	Sign, Type III, Rem	8100403	2.000	Ea
0100	Pavt Mrkg, Waterborne, 4 inch, White	8110231	400.000	Ft
0105	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	400.000	Ft
0110	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	400.000	Ft
0115	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	400.000	Ft
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	14.000	Ea
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	14.000	Ea
0130	Minor Traf Devices (STR 9237)	8120170	1.000	LSUM
0135	Sign, Type B, Temp, Prismatic, Furn	8120350	572.000	Sft

0140	Sign, Type B, Temp, Prismatic, Oper	8120351	572.000	Sft
0145	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	298.000	Sft
0150	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	298.000	Sft
0155	Slope Restoration, Non-Freeway, Type A	8162001	90.000	Syd

**Section: 2**

0160	Structures, Rem	2040060	1.000	LSUM
0165	Backfill, Structure, CIP	2060002	672.000	Cyd
0170	Excavation, Fdn	2060010	950.000	Cyd
0175	Underdrain, Fdn, 4 inch	4040031	116.000	Ft
0180	Underdrain Outlet, 4 inch	4040091	80.000	Ft
0185	Underdrain, Outlet Ending, 4 inch	4040111	4.000	Ea
0190	Culv Bedding, Box Culv	4060005	53.000	Cyd
0195	_ Culv, Precast Conc Box, 25 foot by 14 foot, Spec	4067001	38.000	Ft
0200	False Decking	7060060	792.000	Sft
0205	Liner, PVC, 30 mil	7060209	266.000	Syd
0210	Joint Waterproofing	7100001	443.000	Sft
0215	Guardrail Post, Culv	8070070	8.000	Ea
0220	_ Riprap, Spec, CL II	8137011	145.000	Syd



9/12/2025 7:35 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 049

**Letting Date:** October 3, 2025

**Contract ID:** 79000-224626

**Description:** 100.89 mi of longitudinal waterborne permanent pavement markings, Tuscola County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
224626A	25A0889	N/A	STL 79000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$21,600.00	1100001	1.000	LSUM
0010	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,002,917.000	Ft
0015	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	324,175.000	Ft
0020	Pavt Mrkg, Waterborne, 6 inch, White	8110233	33,270.000	Ft
0025	Minor Traf Devices	8120170	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 050

**Letting Date:** October 3, 2025

**Contract ID:** 63000-218481

**Description:** 3.00 mi of construction of boardwalk and concrete sidewalk on west side of Evergreen Road from 14 Mile Road to Embassy on the north side of 13 Mile Road from Old Stage Road to Evergreen Road and on the south side of 14 Mile Road from Long Bow Road to Lahser Road in the village of Beverly Hills, Oakland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218481A	25A0853	N/A	TAU 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Reimbursed Permit Fees	1077060	5,000.000	Dir
0010	Mobilization, Max \$298,000.00	1100001	1.000	LSUM
0015	Culv, Rem, Less than 24 inch	2030001	4.000	Ea
0020	Dr Structure, Rem	2030011	1.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	129.000	Ft
0030	Curb and Gutter, Rem	2040020	135.000	Ft
0035	Fence, Rem	2040025	397.000	Ft
0040	Masonry and Conc Structure, Rem	2040045	11.000	Cyd
0045	Pavt, Rem	2040050	22.000	Syd
0050	Sidewalk, Rem	2040055	1,360.000	Syd
0055	Exploratory Investigation, Vertical	2040080	200.000	Ft
0060	_ Sidewalk Deck, Rem, Portions	2047010	430.000	Sft
0065	_ Sidewalk, Rem, Portions	2047010	115.000	Sft
0070	Granular Material, CI II	2050023	1,008.000	Cyd
0075	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0080	Subgrade Undercutting, Type IV	2050043	300.000	Cyd
0085	_ Sidewalk Station Grading, Modified	2057002	133.000	Sta
0090	_ Subgrade Undercutting, Streambed, Modified	2057021	100.000	Cyd
0095	Backfill, Structure, CIP	2060002	40.000	Cyd
0100	Excavation, Fdn	2060010	100.000	Cyd
0105	Erosion Control, Check Dam, Stone	2080012	50.000	Ft
0110	Erosion Control, Inlet Protection, Fabric Drop	2080020	63.000	Ea
0115	Erosion Control, Maintenance, Sediment Rem	2080026	50.000	Cyd
0120	Erosion Control, Silt Fence	2080036	5,144.000	Ft
0125	_ Aggregate Base, 8 inch, 21AA, Modified	3027011	411.000	Syd
0130	Maintenance Gravel	3060020	250.000	Ton

0135	_ Crushed Limestone, Modified	3067031	100.000	Ton
0140	_ Road Grade Biaxial Geogrid, Modified	3087011	100.000	Syd
0145	_ CMP Arch Culvert, 103 inch by 71 inch, Modified	4017051	1.000	LSUM
0150	Sewer Tap, 8 inch	4021202	2.000	Ea
0155	Sewer Tap, 12 inch	4021204	4.000	Ea
0160	_ Sewer, CI A, CPE, 12 inch, Perforated	4027001	287.000	Ft
0165	_ Sewer, CI A, CPE, 12 inch, Tr Det B	4027001	516.000	Ft
0170	_ Sewer, CI A, CPE, 8 inch, Tr Det B	4027001	115.000	Ft
0175	_ Sewer, CI A, PVC, 6 inch, Tr Det B	4027001	30.000	Ft
0180	Dr Structure Cover, Adj, Case 2	4030006	18.000	Ea
0185	Dr Structure, 48 inch dia	4030210	2.000	Ea
0190	Dr Structure, Tap, 12 inch	4030312	5.000	Ea
0195	_ Dr Structure, 24 inch dia, Modified	4037050	7.000	Ea
0200	_ Dr Structure, 8 inch dia, Modified	4037050	2.000	Ea
0205	_ Dr Structure, 8 inch dia, Tapped, Modified	4037050	5.000	Ea
0210	Underdrain, Subbase, 6 inch	4040063	67.000	Ft
0215	_ Underdrain, Fdn, 4 Inch, Modified	4047001	40.000	Ft
0220	HMA Surface, Rem	5010005	934.000	Syd
0225	Hand Patching	5010025	192.000	Ton
0230	_ Joint Seal, Hot-Poured Rubber	5027001	64.000	Ft
0235	Lane Tie, Epoxy Anchored	6030030	10.000	Ea
0240	_ Boardwalk Steel Helical Pier	7057050	44.000	Ea
0245	_ Boardwalk Steel Helical Pier, Add 7 Foot Sect	7057050	11.000	Ea
0250	_ Boardwalk Steel Helical Pier, Load Testing	7057050	3.000	Ea
0255	_ Bridge Steel Helical Pier	7057050	20.000	Ea
0260	_ Bridge Steel Helical Pier, Add 7 Foot Sect	7057050	5.000	Ea
0265	_ Bridge Steel Helical Pier, Load Testing	7057050	2.000	Ea
0270	_ Diagonal Brace	7057050	6.000	Ea
0275	Elec Grounding System	7060040	1.000	Ea
0280	Reinforcement, Steel, Epoxy Coated	7060092	3,251.000	Lb
0285	Water Repellent Treatment, Penetrating	7060140	130.000	Syd
0290	Conc, Grade 4500	7062003	10.000	Cyd
0295	_ Expansion Joint Device, Sidewalk	7067001	16.000	Ft
0300	_ Prefabricated Pedestrian Bridge, Conc Deck	7067021	13.000	Cyd
0305	_ Substructure Conc, Modified	7067021	17.000	Cyd
0310	_ Expansion Joint, Sidewalk Cover Plate	7067050	2.000	Ea
0315	_ Prefabricated Pedestrian Bridge, Erect	7077051	1.000	LSUM
0320	_ Prefabricated Pedestrian Bridge, Furn and Fab	7077051	1.000	LSUM
0325	_ Approach Railing	7097001	64.000	Ft
0330	_ Boardwalk Railing	7097001	510.000	Ft
0335	_ Boardwalk	7097010	2,040.000	Sft
0340	_ Silane Treatment	7107010	820.000	Sft
0345	_ Deck Joint Seal	7127001	64.000	Ft
0350	_ Retaining Wall, Modular Block, Modified	8007010	4,544.000	Sft
0355	Driveway, Nonreinf Conc, 6 inch	8010005	20.000	Syd

0360	Curb and Gutter, Conc, Det C4	8020023	348.000	Ft
0365	Detectable Warning Surface	8030010	200.000	Ft
0370	Curb Ramp Opening, Conc	8030030	96.000	Ft
0375	Sidewalk, Conc, 4 inch	8030044	61,848.000	Sft
0380	Sidewalk, Conc, 6 inch	8030046	3,894.000	Sft
0385	Curb Ramp, Conc, 4 inch	8032001	701.000	Sft
0390	Curb Ramp, Conc, 6 inch	8032002	1,609.000	Sft
0395	Post, Mailbox	8070095	14.000	Ea
0400	Fence, Protective	8080007	829.000	Ft
0405	Fence, Chain Link, 60 inch	8080012	325.000	Ft
0410	Fence Gate, 8 foot, for 60 inch Chain Link Fence	8080042	1.000	Ea
0415	_ Fence, Wood, 2-Rail, Split, Modified	8087001	733.000	Ft
0420	_ Fence, Wood, 3-Rail, Split, Modified	8087001	512.000	Ft
0425	Post, Steel, 3 pound	8100371	230.000	Ft
0430	Sign, Type III, Erect, Salv	8100402	20.000	Ea
0435	Sign, Type III, Rem, Salv	8102003	20.000	Ea
0440	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	440.000	Ft
0445	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	30.000	Ft
0450	Rem Spec Mrkg	8110343	40.000	Sft
0455	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0460	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0465	Pedestrian Type II Barricade, Temp	8120026	30.000	Ea
0470	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	220.000	Ea
0475	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	220.000	Ea
0480	Lighted Arrow, Type C, Furn	8120140	8.000	Ea
0485	Lighted Arrow, Type C, Oper	8120141	8.000	Ea
0490	Minor Traf Devices	8120170	1.000	LSUM
0495	Plastic Drum, Fluorescent, Furn	8120252	220.000	Ea
0500	Plastic Drum, Fluorescent, Oper	8120253	220.000	Ea
0505	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0510	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0515	Sign, Type B, Temp, Prismatic, Furn	8120350	864.000	Sft
0520	Sign, Type B, Temp, Prismatic, Oper	8120351	864.000	Sft
0525	Traf Regulator Control	8120370	1.000	LSUM
0530	Pedestrian Path, Temp	8122250	20.000	Ft
0535	Pedestrian Ramp, Temp	8122251	2.000	Ea
0540	Site Preparation, Max \$13,800.00	8150001	1.000	LSUM
0545	Watering and Cultivating, First Season, Min \$6,700.00	8150002	1.000	LSUM
0550	Watering and Cultivating, 2nd Season, Min \$8,300.00	8150003	1.000	LSUM
0555	Forsythia x intermedia 'Lynwood Gold', #3 cont.	8151493	5.000	Ea
0560	Picea glauca 'Densata', 5 foot	8152755	30.000	Ea
0565	Viburnum burkwoodii, #3 cont.	8154002	5.000	Ea

0570	_ Thuja standishii x plicata, 'Green Giant', 5 foot	8157050	95.000	Ea
0575	Slope Restoration, Non-Freeway, Type E	8162005	14,603.000	Syd
0580	Slope Restoration, Non-Freeway, Type G	8162007	4,156.000	Syd
0585	Conduit, Schedule 80, 2 inch	8182146	160.000	Ft
0590	_ Utility Pole Protection	8507050	2.000	Ea
0595	_ Audio Video Route Survey	8507051	1.000	LSUM

---



9/12/2025 7:35 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

### Schedule of Pay Items

Report v1

**Letting Call:** 251003 051

**Letting Date:** October 3, 2025

**Contract ID:** 20000-211766

**Description:** 2.87 mi of hot mix asphalt resurfacing on North Down River Road from Bald Hill Road to Mcmasters Bridge Road, Crawford County. This is a Local Agency project.

#### Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211766A	25A0897	N/A	STL 20000

#### List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$65,600.00	1100001	1.000	LSUM
0010	HMA Approach	5010061	100.000	Ton
0015	HMA, 4EL	5012024	7,100.000	Ton
0020	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	175.000	Ea
0025	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	175.000	Ea
0030	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0035	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0040	Minor Traf Devices	8120170	1.000	LSUM
0045	Pavt Mrkg, Wet Reflective, Type NR, Tape, 4 inch, Yellow, Temp	8120264	1,400.000	Ft
0050	Sign, Type B, Temp, Prismatic, Furn	8120350	360.000	Sft
0055	Sign, Type B, Temp, Prismatic, Oper	8120351	360.000	Sft
0060	Traf Regulator Control	8120370	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 052

**Letting Date:** October 3, 2025

**Contract ID:** 14000-221125

**Description:** 0.90 mi of hot mix asphalt, base crushing and shaping, concrete sidewalk and ramps, concrete curb and gutter, drainage structure adjustments, and permanent pavement markings in the city of Dowagiac, Cass County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221125A	25A0837	N/A	STUL 14000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$50,000.00	1100001	1.000	LSUM
0010	Curb, Rem	2040021	3,574.000	Ft
0015	Pavt, Rem	2040050	760.000	Syd
0020	Subgrade Undercutting, Type III	2050042	75.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	33.000	Ea
0030	Aggregate Base, 6 inch	3020016	575.000	Syd
0035	HMA Base Crushing and Shaping	3050002	6,325.000	Syd
0040	Material, Surplus and Unsuitable, Rem, LM	3050010	695.000	Cyd
0045	Dr Structure Cover, Adj, Case 1, Modified	4030004	43.000	Ea
0050	Cold Milling HMA Surface	5010002	9,919.000	Syd
0055	Hand Patching	5010025	71.000	Ton
0060	HMA, 4EML	5012025	870.000	Ton
0065	HMA, 5EML	5012037	1,615.000	Ton
0070	Pavt Repr, Rem	6030080	320.000	Syd
0075	Driveway, Nonreinf Conc, 6 inch	8010005	575.000	Syd
0080	Curb and Gutter, Conc, Det F4	8020038	3,574.000	Ft
0085	Detectable Warning Surface	8030010	55.000	Ft
0090	Sidewalk, Conc, 4 inch	8030044	5,290.000	Sft
0095	Curb Ramp, Conc, 4 inch	8032001	639.000	Sft
0100	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	981.000	Ft
0105	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	280.000	Ft
0110	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0115	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0120	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	1.000	Ea
0125	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	1.000	Ea
0130	Pavt Mrkg, Waterborne, 4 inch, White	8110231	170.000	Ft
0135	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	5,090.000	Ft

---

0140	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	22.000	Ea
0145	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	22.000	Ea
0150	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0155	Minor Traf Devices	8120170	1.000	LSUM
0160	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0165	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0170	Sign, Type A, Temp, Prismatic, Furn	8120340	175.000	Sft
0175	Sign, Type A, Temp, Prismatic, Oper	8120341	175.000	Sft
0180	Traf Regulator Control	8120370	1.000	LSUM
0185	Pedestrian Ramp, Temp	8122251	6.000	Ea
0190	Slope Restoration, Non-Freeway, Type A	8162001	2,100.000	Syd
0195	Water Shutoff, Adj, Case 1	8230421	8.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 053

**Letting Date:** October 3, 2025

**Contract ID:** 63000-221329

**Description:** 1.25 mi of hot mix asphalt shared-use path and concrete sidewalk, concrete ramps, curb and gutter, timber boardwalk, and pedestrian crossing with hawk signal in the city of Troy, Oakland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
221329A	25A0871	N/A	TAU 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Audio Video Route Survey	1077051	1.000	LSUM
0010	_ Reimbursed Permit Fees	1077060	5,000.000	Dlr
0015	Mobilization, Max \$232,000.00	1100001	1.000	LSUM
0020	_ Clearing, Modified	2017002	16.000	Sta
0025	Tree, Rem, 19 inch to 36 inch	2020002	7.000	Ea
0030	Tree, Rem, 37 inch or Larger	2020003	1.000	Ea
0035	Tree, Rem, 6 inch to 18 inch	2020004	12.000	Ea
0040	Curb and Gutter, Rem	2040020	277.000	Ft
0045	Fence, Rem	2040025	18.000	Ft
0050	Sidewalk, Rem	2040055	1,756.000	Syd
0055	Exploratory Investigation, Vertical	2040080	65.000	Ft
0060	_ Pavt, Rem, Modified	2047011	1,540.000	Syd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	30.000	Cyd
0070	Subgrade Undercutting, Type IV	2050043	230.000	Cyd
0075	Erosion Control, Check Dam, Stone	2080012	100.000	Ft
0080	Erosion Control, Inlet Protection, Fabric Drop	2080020	24.000	Ea
0085	Erosion Control, Silt Fence	2080036	1,715.000	Ft
0090	Project Cleanup	2090001	1.000	LSUM
0095	_ Aggregate Base, 4 inch, Modified	3027011	1,751.000	Syd
0100	_ Aggregate Base, 6 inch, Modified	3027011	7,358.000	Syd
0105	_ Maintenance Gravel, Modified	3067031	400.000	Ton
0110	Culv End Sect, 12 inch	4010012	2.000	Ea
0115	Sewer, Cl E, 12 inch, Tr Det B	4020600	34.000	Ft
0120	Dr Structure Cover, Type B	4030010	1.000	Ea
0125	Dr Structure Cover, Type E	4030035	2.000	Ea
0130	Dr Structure Cover, Type G	4030040	1.000	Ea
0135	Dr Structure Cover, Type K	4030050	1.000	Ea

0140	Dr Structure Cover, Type Q	4030065	2.000	Ea
0145	_ Structure, Adj, Add Depth	4037001	11.000	Ft
0150	_ San Structure Cover, Adj	4037050	8.000	Ea
0155	_ Stm Structure Cover, Adj	4037050	8.000	Ea
0160	_ Utl Structure Cover, Adj	4037050	4.000	Ea
0165	_ Wtr Structure Cover, Adj	4037050	2.000	Ea
0170	Hand Patching	5010025	6.000	Ton
0175	HMA Approach	5010061	429.000	Ton
0180	Conc Pavt, Nonreinf, 9 1/2 inch	6020107	5.000	Syd
0185	Lane Tie, Epoxy Anchored	6030030	56.000	Ea
0190	_ Helical Pile, Add 7' Sect	7057050	100.000	Ea
0195	_ Helical Pile, Resistance	7057050	20.000	Ea
0200	_ Steel Helical Pile	7057050	153.000	Ea
0205	Reinforcement, Steel, Epoxy Coated	7060092	1,502.000	Lb
0210	Conc, Grade 3500	7062001	48.000	Cyd
0215	_ Pressure Treated Wood Boardwalk	7097001	990.000	Ft
0220	Driveway, Nonreinf Conc, 6 inch	8010005	142.000	Syd
0225	Driveway, Nonreinf Conc, 9 inch	8010008	284.000	Syd
0230	Curb and Gutter, Conc, Det D2	8020031	20.000	Ft
0235	Curb and Gutter, Conc, Det F3	8020037	108.000	Ft
0240	Curb and Gutter, Conc, Det F4	8020038	1,079.000	Ft
0245	_ Curb and Gutter, Conc, Det D2, Modified	8027001	94.000	Ft
0250	Detectable Warning Surface	8030010	110.000	Ft
0255	Curb Ramp Opening, Conc	8030030	244.000	Ft
0260	Sidewalk, Conc, 4 inch	8030044	31,337.000	Sft
0265	Sidewalk, Conc, 6 inch	8030046	1,511.000	Sft
0270	Curb Ramp, Conc, 6 inch	8032002	3,450.000	Sft
0275	Shared use Path, Grading	8060030	6,315.000	Ft
0280	Shared use Path, HMA	8060040	332.000	Ton
0285	_ Guardrail, Wood Back	8077001	104.000	Ft
0290	_ Post, Mailbox, Rem and Reset	8077050	2.000	Ea
0295	_ Fence, Chain Link, 48 inch, Vinyl Coated, Modified	8087001	104.000	Ft
0300	Post, Steel, 3 pound	8100371	182.000	Ft
0305	Sign, Type III, Erect, Salv	8100402	16.000	Ea
0310	Sign, Type III, Rem	8100403	8.000	Ea
0315	Sign, Type IIIA	8100404	13.000	Sft
0320	Sign, Type IIIB	8100405	24.000	Sft
0325	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	6.000	Ea
0330	Ground Mtd Sign Support, Rem	8102010	12.000	Ea
0335	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	200.000	Ft
0340	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	160.000	Ft
0345	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	220.000	Ft
0350	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	143.000	Ft
0355	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	50.000	Ft
0360	Rem Spec Mrkg	8110343	112.000	Sft

0365	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0370	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0375	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0380	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	170.000	Ea
0385	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	170.000	Ea
0390	Lighted Arrow, Type C, Furn	8120140	3.000	Ea
0395	Lighted Arrow, Type C, Oper	8120141	3.000	Ea
0400	Minor Traf Devices	8120170	1.000	LSUM
0405	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0410	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0415	Sign, Type B, Temp, Prismatic, Furn	8120350	971.000	Sft
0420	Sign, Type B, Temp, Prismatic, Oper	8120351	971.000	Sft
0425	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	20.000	Sft
0430	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	20.000	Sft
0435	Traf Regulator Control	8120370	1.000	LSUM
0440	Riprap, Plain	8130010	27.000	Syd
0445	_ Slope Restoration, Non-Freeway, Type F, Modified	8167002	63.000	Sta
0450	_ Wetland Seed Mix	8167002	10.000	Sta
0455	Power Company (Estimated Cost to Contractor)	8180001	4,000.000	Dlr
0460	Conduit, Directional Bore, 1, 3 inch	8182035	85.000	Ft
0465	Conduit, DB, 1, 1 1/4 inch	8182047	100.000	Ft
0470	Conduit, DB, 1, 3 inch	8182050	70.000	Ft
0475	Conduit, DB, 3, 3 inch	8182056	10.000	Ft
0480	Conduit, DB, 3, 4 inch	8182057	5.000	Ft
0485	DB Cable, in Conduit, 600V, 1/C#6	8182187	170.000	Ft
0490	Cable, Sec, 600V, 1, 3/C#6	8182238	60.000	Ft
0495	Cable, Equipment Grounding Wire, 1/C#6	8182291	85.000	Ft
0500	Hh, Polymer Conc	8182309	1.000	Ea
0505	Serv Disconnect	8182366	1.000	Ea
0510	_ Conduit, DB, 1, 2 inch	8187001	15.000	Ft
0515	_ Conduit, Directional Bore, 1, 3 inch, RCOC	8187001	80.000	Ft
0520	_ Conduit, Directional Bore, 1, 4 inch, RCOC	8187001	110.000	Ft
0525	_ Hh, Round, 2 foot dia, RCOC	8187050	4.000	Ea
0530	_ Hh, Round, 3 foot dia, RCOC	8187050	1.000	Ea
0535	_ Type 'PL' Lighting Unit	8187050	1.000	Ea
0540	Light Std Fdn	8190279	1.000	Ea
0545	Case Sign, Disappearing Legend, 24 inch by 30 inch	8200015	1.000	Ea
0550	Controller Fdn, Base Mtd	8200045	1.000	Ea
0555	Pedestal, Fdn	8200105	4.000	Ea
0560	Push Button Station and Sign	8200128	4.000	Ea
0565	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0570	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea

0575	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	3.000	Ea
0580	Casing, 42 inch	8200485	21.000	Ft
0585	Mast Arm Pole, Cat III	8202012	2.000	Ea
0590	Mast Arm, 45 foot, Cat III	8202032	1.000	Ea
0595	Mast Arm, 50 foot, Cat III	8202033	1.000	Ea
0600	Mast Arm Pole Fdn, 6 Bolt	8202034	28.000	Ft
0605	TS, One Way Mast Arm Mtd (LED), Long Life	8202224	5.000	Ea
0610	_ Antenna, Delivered, RCOC	8207050	1.000	Ea
0615	_ Backplate, TS, RCOC	8207050	5.000	Ea
0620	_ Cabinet, ITS Type, Delivered, RCOC	8207050	1.000	Ea
0625	_ Cabinet, ITS Type, RCOC	8207050	1.000	Ea
0630	_ Cellular Router, 4/5G, Delivered, RCOC	8207050	1.000	Ea
0635	_ Controller, Digital Type, Delivered, Blue, RCOC	8207050	1.000	Ea
0640	_ Ground Rod, RCOC	8207050	3.000	Ea
0645	_ Pedestal, Alum, RCOC	8207050	4.000	Ea
0650	_ Pushbutton Support Post, RCOC	8207050	1.000	Ea
0655	_ Sign, Mast Arm Mtd, Type IIIB, RCOC	8207050	2.000	Ea
0660	_ TS, Service Rack, Metered, RCOC	8207050	1.000	Ea
0665	Protect Corners	8210020	4.000	Ea
0670	Hydrant, Relocate, Case 2	8230096	1.000	Ea
0675	Gate Well, Cover	8232000	2.000	Ea
0680	_ Sprinkler Line	8237001	1,000.000	Ft
0685	_ Irrigation Control Box, Relocate	8237050	2.000	Ea
0690	_ Irrigation Control Box, Replace	8237050	2.000	Ea
0695	_ Sprinkler Head, Relocate	8237050	30.000	Ea
0700	_ Sprinkler Head, Replace	8237050	30.000	Ea
0705	Sanitary Structure Cover, Type Q	8252098	5.000	Ea



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 054

**Letting Date:** October 3, 2025

**Contract ID:** 12000-216406

**Description:** 6.09 mi of hot mix asphalt paving, cold milling, superelevation correction, and permanent pavement markings, Branch County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
216406A	25A0893	N/A	STL 12000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$108,000.00	1100001	1.000	LSUM
0010	Pavt, Rem	2040050	50.000	Syd
0015	Approach, CI II	3070021	90.000	Ton
0020	Shld, CI II	3070121	1,120.000	Ton
0025	HMA Approach	5010061	210.000	Ton
0030	HMA, 5EL	5012036	9,900.000	Ton
0035	_ Cold Milling HMA Surface, Modified	5017011	94,400.000	Syd
0040	Pavt Mrkg, Waterborne, 4 inch, White	8110231	64,310.000	Ft
0045	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	40,000.000	Ft
0050	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	64,310.000	Ft
0055	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	40,000.000	Ft
0060	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0065	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0070	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0075	Minor Traf Devices	8120170	1.000	LSUM
0080	Sign, Type B, Temp, Prismatic, Furn	8120350	992.000	Sft
0085	Sign, Type B, Temp, Prismatic, Oper	8120351	992.000	Sft
0090	Traf Regulator Control	8120370	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 055

**Letting Date:** October 3, 2025

**Contract ID:** 61000-215731

**Description:** 0.51 mi of hot mix asphalt cold milling, resurfacing, signing and pavement markings on Ruddiman Drive from Bear Lake Bridge Road northeasterly to East Circle Drive in the city of North Muskegon, Muskegon County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215731A	25A0865	N/A	STUL 61000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$25,200.00	1100001	1.000	LSUM
0010	Erosion Control, Inlet Protection, Fabric Drop	2080020	25.000	Ea
0015	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0020	Erosion Control, Silt Fence	2080036	500.000	Ft
0025	Maintenance Gravel, LM	3060021	100.000	Cyd
0030	Dr Structure Cover, Adj, Case 1, Modified	4030004	12.000	Ea
0035	Dr Structure, Temp Lowering	4030390	12.000	Ea
0040	Cold Milling HMA Surface	5010002	11,400.000	Syd
0045	Hand Patching	5010025	5.000	Ton
0050	HMA Approach	5010061	100.000	Ton
0055	HMA, 5EML	5012037	1,160.000	Ton
0060	_ Detectable Warning Surface, Composite, Retrofit	8037001	70.000	Ft
0065	Post, Steel, 3 pound	8100371	75.000	Ft
0070	Sign, Type III, Rem	8100403	4.000	Ea
0075	Sign, Type IIIB	8100405	25.000	Sft
0080	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0085	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	115.000	Ft
0090	Pavt Mrkg, Waterborne, 4 inch, White	8110231	4,540.000	Ft
0095	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	4,750.000	Ft
0100	_ Pavt Mrkg, Waterborne, 6 inch, Crosswalk	8117001	560.000	Ft
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	5.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	5.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	65.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	65.000	Ea
0125	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0130	Lighted Arrow, Type C, Oper	8120141	2.000	Ea

0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Sign, Type B, Temp, Prismatic, Furn	8120350	405.000	Sft
0145	Sign, Type B, Temp, Prismatic, Oper	8120351	405.000	Sft
0150	Traf Regulator Control	8120370	1.000	LSUM
0155	Slope Restoration, Non-Freeway, Type E	8162005	20.000	Syd
0160	Gate Box, Adj, Temp, Case 1	8230391	9.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 056

**Letting Date:** October 3, 2025

**Contract ID:** 33000-215549

**Description:** 2.23 mi of hot mix asphalt reconstruction, concrete curb, gutter and sidewalk and pavement markings on Pennsylvania Avenue from Mt Hope Avenue to Fayette Road, Mt Hope Avenue from Pennsylvania Avenue to Aurelius Road and Jolly Road from west of Cedar Street to east of Pennsylvania Avenue in the city of Lansing, Ingham County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215549A	25A0796	N/A	STU 33000
215992A	25A0829	N/A	STU 33000
215995A	25A0798	N/A	STU 33000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	_ Railroad Protection, at Grade Crossing, Jackson & Lansing Railroad	1027060	4,000.000	Dir
0010	_ Audio Visual Filming	1047051	1.000	LSUM
0015	Mobilization, Max \$350,000.00	1100001	1.000	LSUM
0020	Tree, Rem, 6 inch to 18 inch	2020004	7.000	Ea
0025	Stump, Rem, 6 inch to 18 inch	2020008	3.000	Ea
0030	Dr Structure, Rem	2030011	19.000	Ea
0035	Sewer, Rem, Less than 24 inch	2030015	1,310.000	Ft
0040	Sewer, Rem, 24 inch to 48 inch	2030016	468.000	Ft
0045	Curb and Gutter, Rem	2040020	8,276.000	Ft
0050	Sidewalk, Rem	2040055	1,827.000	Syd
0055	Exploratory Investigation, Vertical	2040080	60.000	Ft
0060	_ Pavt, Rem, Modified	2047011	17,925.000	Syd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	100.000	Cyd
0070	Subgrade Undercutting, Type II	2050041	300.000	Cyd
0075	_ Machine Grading, Modified, Jolly Rd	2057002	24.000	Sta
0080	_ Machine Grading, Modified, Mt Hope Ave	2057002	40.000	Sta
0085	_ Machine Grading, Modified, Pennsylvania Ave	2057002	22.000	Sta
0090	_ Erosion Control, Inlet Protection, Fabric Drop, Modified	2087050	57.000	Ea
0095	_ Street Sweeping	2087050	34.000	Ea
0100	Project Cleanup	2090001	1.000	LSUM
0105	Subbase, CIP	3010002	6,318.000	Cyd
0110	Aggregate Base, 8 inch	3020020	17,625.000	Syd
0115	_ Aggregate Base, 5.5 inch	3027011	2,375.000	Syd

0120	Video Taping Sewer and Culv Pipe	4021275	1,209.000	Ft
0125	_ Sewer Spot Repair, CI A, 30 inch	4027001	30.000	Ft
0130	_ Sewer, CI A, 10 inch, Tr Det B, Modified	4027001	5.000	Ft
0135	_ Sewer, CI A, 12 inch, Tr Det B, Modified	4027001	202.000	Ft
0140	_ Sewer, CI A, 18 inch, Tr Det B, Modified	4027001	529.000	Ft
0145	_ Sewer, CI A, 20 inch, Tr Det B, Modified	4027001	5.000	Ft
0150	_ Sewer, CI A, 30 inch, Tr Det B, Modified	4027001	428.000	Ft
0155	_ Sewer, CI A, 36 inch, Tr Det B, Modified	4027001	5.000	Ft
0160	_ Sewer, CI A, 42 inch, Tr Det B, Modified	4027001	5.000	Ft
0165	_ Sewer, CI A, 8 inch, Tr Det B, Modified	4027001	30.000	Ft
0170	_ Sewer, Spot Repair, CI A, 12 inch	4027001	43.000	Ft
0175	_ Sewer, Spot Repair, CI A, 15 inch	4027001	6.000	Ft
0180	_ Sewer, Spot Repair, CI A, 18 inch	4027001	28.000	Ft
0185	_ Sewer, Spot Repair, CI A, 20 inch	4027001	20.000	Ft
0190	_ Sewer, Spot Repair, CI A, 24 inch	4027001	22.000	Ft
0195	_ Dewatering System for Petroleum Contaminated Groundwater, Site	4027051	1.000	LSUM
0200	Dr Structure Cover, Adj, Case 1	4030005	10.000	Ea
0205	Dr Structure Cover, Adj, Case 2	4030006	7.000	Ea
0210	Dr Structure Cover, Type K	4030050	9.000	Ea
0215	Dr Structure, 48 inch dia	4030210	14.000	Ea
0220	Dr Structure, 60 inch dia	4030220	5.000	Ea
0225	Dr Structure, Cleaning	4030290	60.000	Ea
0230	_ Dr Structure Cover, Modified	4037050	72.000	Ea
0235	_ Manhole Cover, Adj	4037050	51.000	Ea
0240	Hand Patching	5010025	70.000	Ton
0245	HMA Approach	5010061	656.000	Ton
0250	HMA, 2EML	5012001	1,101.000	Ton
0255	HMA, 3EML	5012013	2,751.000	Ton
0260	HMA, 4EML	5012025	4,800.000	Ton
0265	HMA, 5EML	5012037	3,698.000	Ton
0270	_ Cold Milling, HMA Surface, 3.5 inch	5017011	12,910.000	Syd
0275	_ Cold Milling, HMA Surface, 4.5 inch	5017011	7,595.000	Syd
0280	Cold Milling Conc Pavt	6030014	500.000	Syd
0285	Conduit, 3 inch, Placed	7060031	45.000	Ft
0290	Driveway, Nonreinf Conc, 6 inch	8010005	563.000	Syd
0295	Curb and Gutter, Conc, Det F4	8020038	5,950.000	Ft
0300	_ Curb and Gutter, Conc, Modified, Inverted	8027001	2,335.000	Ft
0305	Curb Ramp Opening, Conc	8030030	453.000	Ft
0310	Sidewalk, Conc, 4 inch	8030044	10,490.000	Sft
0315	Sidewalk, Conc, 6 inch	8030046	2,350.000	Sft
0320	Curb Ramp, Conc, 6 inch	8032002	4,111.000	Sft
0325	_ Detectable Warning Surface, Modified	8037001	332.000	Ft
0330	Fence, Protective	8080007	600.000	Ft
0335	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	2,874.000	Ft

0340	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	60.000	Ft
0345	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	750.000	Ft
0350	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	8110058	19.000	Ea
0355	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	8.000	Ea
0360	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	1.000	Ea
0365	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	1.000	Ea
0370	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0375	Pavt Mrkg, Ovly Cold Plastic, Sharrow Sym	8110079	3.000	Ea
0380	Pavt Mrkg, Waterborne, 4 inch, White	8110231	16,604.000	Ft
0385	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	22,036.000	Ft
0390	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	16,604.000	Ft
0395	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	22,036.000	Ft
0400	Rem Spec Mrkg	8110343	352.000	Sft
0405	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	103.000	Ea
0410	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	103.000	Ea
0415	Pedestrian Type II Barricade, Temp	8120026	24.000	Ea
0420	Minor Traf Devices	8120170	1.000	LSUM
0425	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	5,740.000	Ft
0430	Plastic Drum, Fluorescent, Furn	8120252	400.000	Ea
0435	Plastic Drum, Fluorescent, Oper	8120253	400.000	Ea
0440	Sign, Portable, Changeable Message, Furn	8120330	6.000	Ea
0445	Sign, Portable, Changeable Message, Oper	8120331	6.000	Ea
0450	Sign, Type B, Temp, Prismatic, Furn	8120350	1,355.000	Sft
0455	Sign, Type B, Temp, Prismatic, Oper	8120351	1,355.000	Sft
0460	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	298.000	Sft
0465	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	298.000	Sft
0470	Traf Regulator Control	8120370	1.000	LSUM
0475	Site Preparation, Max \$5,000.00	8150001	1.000	LSUM
0480	Watering and Cultivating, First Season, Min \$5,000.00	8150002	1.000	LSUM
0485	_ Carpinus betulus, 2 inch B&B	8157050	2.000	Ea
0490	_ Koelreuteria paniculata, 2 inch B&B	8157050	2.000	Ea
0495	_ Liquidambar styracifua, 2 inch B&B	8157050	3.000	Ea
0500	_ Turf Establishment, Performance	8167011	7,210.000	Syd
0505	Water Shutoff, Adj, Case 1	8230421	6.000	Ea
0510	Water Shutoff, Adj, Case 2	8230422	3.000	Ea
0515	_ Gate Valve Box, Adj	8237050	12.000	Ea
0520	_ Sanitary Sewer Spot Repair, CI A, 15 inch	8257001	50.000	Ft
0525	_ Sanitary Sewer Spot Repair, CL A, 8 inch	8257001	398.000	Ft
0530	_ Sanitary Sewer, CI A, 10 inch, Tr Det B	8257001	5.000	Ft
0535	_ Sanitary Sewer, CI A, 15 inch, Tr Det B	8257001	32.000	Ft
0540	_ Sanitary Sewer, CI A, 8 inch, Tr Det B	8257001	5.000	Ft
0545	_ Sanitary Sewer, Lateral Service, CI A, 6 inch	8257001	80.000	Ft
0550	_ Sanitary Sewer, Structure, 48 inch dia	8257050	1.000	Ea

0555	_ Sanitary Sewer, Wye Branch Connector, 15 inch x 6 inch	8257050	3.000	Ea
0560	_ Sanitary Sewer, Wye Branch Connector, 8 inch x 6 inch	8257050	8.000	Ea

---



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 057

**Letting Date:** October 3, 2025

**Contract ID:** 63000-218175

**Description:** Bridge rehabilitation including hot mix asphalt wearing surface, epoxy healer sealer of deck, deck patching, railing repair, waterproofing sealer and substructure patching, guardrail work and approach work on Paddock Street over the Clinton River and Martin Luther King Bridge over the Clinton River in the city of Pontiac, Oakland County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
218175A	25A0863	N/A	BFP 63000
218176A	25A0864	N/A	BFP 63000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$35,300	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	262.000	Ft
0015	Embankment, CIP	2050010	200.000	Cyd
0020	Flowable Fill, Non-Structural	2050148	10.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0030	Erosion Control, Silt Fence	2080036	100.000	Ft
0035	Aggregate Base	3020001	70.000	Ton
0040	HMA, 4EML	5012025	22.000	Ton
0045	HMA, 5EML	5012037	22.000	Ton
0050	Crack Sealing, Conc Pavt	6030010	202.000	Ft
0055	Sidewalk, Conc, 4 inch	8030044	850.000	Sft
0060	Guardrail Anch, Bridge, Det T3	8070024	4.000	Ea
0065	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0070	Guardrail Departing Terminal, Type B	8070050	2.000	Ea
0075	Guardrail Reflector	8070080	4.000	Ea
0080	Guardrail, Curved, Type B, 96 inch Post	8072142	13.000	Ft
0085	Guardrail, Type B, 96 inch Post	8072172	75.000	Ft
0090	Pavt Mrkg, Waterborne, 6 inch, White	8110233	100.000	Ft
0095	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	700.000	Ft
0100	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	600.000	Ft
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0115	Pedestrian Type II Barricade, Temp	8120026	20.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	175.000	Ea

0125	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	175.000	Ea
0130	Minor Traf Devices	8120170	1.000	LSUM
0135	Sign, Type B, Temp, Prismatic, Furn	8120350	702.000	Sft
0140	Sign, Type B, Temp, Prismatic, Oper	8120351	702.000	Sft
0145	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	124.000	Sft
0150	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	124.000	Sft
0155	Traf Regulator Control	8120370	1.000	LSUM
0160	_ Turf Establishment, Performance	8167011	1,000.000	Syd

**Section: 2**

0165	Asbestos Materials, Rem and Disposal	2040001	10,000.000	Dlr
0170	_ Structures, Rem Portion, Modified (SN 8268)	2047051	1.000	LSUM
0175	_ HMA Ovly and Waterproofing Membrane, Rem	5017011	270.000	Syd
0180	Reinforcement, Steel, Epoxy Coated	7060092	675.000	Lb
0185	Water Repellent Treatment, Penetrating	7060140	325.000	Syd
0190	Conc, Grade 4500	7062003	15.000	Cyd
0195	Membrane, Preformed Waterproofing	7100008	2,394.000	Sft
0200	Penetrating Healer/Sealer, Bridge Deck	7100025	145.000	Syd
0205	Hand Chipping, Shallow	7120003	30.000	Syd
0210	Hand Chipping, Deep	7120004	30.000	Syd
0215	Hand Chipping, Other Than Deck	7120007	52.000	Cft
0220	Patch, Forming	7120017	435.000	Sft
0225	Reinforcement, Mechanical Splice	7120084	100.000	Ea
0230	Structural Crack, Repr	7120099	350.000	Ft
0235	Patching Conc, F-L	7120114	5.000	Cyd
0240	_ Bridge Joints, Clean and Seal	7127001	150.000	Ft
0245	_ Patching Conc, C-L, Modified	7127021	5.000	Cyd
0250	_ Bridge Railing Tube, Reconst Portions	7137050	1.000	Ea
0255	Steel Structure, Cleaning, Partial, Type 4 (SN 8265)	7150047	1.000	LSUM
0260	Steel Structure, Coating, Partial, Type 4 (SN 8265)	7150048	1.000	LSUM
0265	_ Temp Work Platform (SN 8265)	7157051	1.000	LSUM
0270	_ Temp Work Platform (SN 8268)	7157051	1.000	LSUM



**Schedule of Pay Items**

Report v1

**Letting Call:** 251003 058

**Letting Date:** October 3, 2025

**Contract ID:** 41000-215843

**Description:** 0.26 mi of hot mix asphalt paving, storm sewer, watermain, concrete sidewalk and ramps, signing, street lighting, and permanent pavement markings in the city of Grand Rapids, Kent County. This is a Local Agency project.

**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
215843A	25A0886	N/A	STU 41000

**List of Items by Section**

Line Num	Item Description	Item ID	Quantity	Units
<b>Section: 1</b>				
0005	Mobilization, Max \$270,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	1.000	Ea
0015	Tree, Rem, 6 inch to 18 inch	2020004	7.000	Ea
0020	_ Abandon and Fill Underground Utilities, 12 inch Dia	2037001	1,560.000	Ft
0025	_ Abandon and Fill Underground Utilities, 8 inch Dia	2037001	120.000	Ft
0030	_ Abandon and Fill Underground Utilities, 9 inch Dia	2037001	150.000	Ft
0035	_ Manhole, Valve Chamber, or Catch Basin, Rem	2037050	10.000	Ea
0040	Curb and Gutter, Rem	2040020	2,800.000	Ft
0045	Fence, Rem	2040025	330.000	Ft
0050	Masonry and Conc Structure, Rem	2040045	1,300.000	Cyd
0055	Sidewalk, Rem	2040055	1,900.000	Syd
0060	Track, Rem	2040065	1,340.000	Ft
0065	_ Pavt, Rem, Modified	2047011	7,460.000	Syd
0070	_ Pylon Sign, Rem	2047051	1.000	LSUM
0075	_ Roadway Grading	2057002	14.000	Sta
0080	_ Unsuitable Soil, Rem and Repl with Granular Material Class II	2067021	500.000	Cyd
0085	_ Stormwater Operator's Inspection	2087050	30.000	Ea
0090	_ Dust Control	2087051	1.000	LSUM
0095	_ Soil Eroision and Sedimentation Control Plan	2087051	1.000	LSUM
0100	_ Soil Erosion and Sedimentation Control	2087051	1.000	LSUM
0105	Subbase, CIP	3010002	2,200.000	Cyd
0110	Aggregate Base, 8 inch	3020020	6,482.000	Syd
0115	_ Temporary Gravel Pavement	3067031	50.000	Ton
0120	Video Taping Sewer and Culv Pipe	4021275	741.000	Ft
0125	_ Basin Connection, C76 CI III, 12 inch	4027001	286.000	Ft
0130	_ Storm Sewer, C76 CI III, 12 inch	4027001	250.000	Ft
0135	_ Storm Sewer, C76 CI III, 15 inch	4027001	205.000	Ft

0140	_ Catch Basin, 2 foot Dia	4037050	1.000	Ea
0145	_ Catch Basin, 4 foot Dia, per Detail S-3	4037050	3.000	Ea
0150	_ Catch Basin, 4 foot Dia, per Detail S-4	4037050	4.000	Ea
0155	_ Core and Boot 15 inch Storm Sewer into Sewer or Manhole	4037050	1.000	Ea
0160	_ Core and Seal 12 inch Storm Sewer into Sewer or Manhole	4037050	2.000	Ea
0165	_ Ditch Basin Casting, Furnish	4037050	1.000	Ea
0170	_ Ditch Basin, 2 foot Dia, Detail S-8	4037050	2.000	Ea
0175	_ Ditch Basin, 4 foot Dia, Detail S-8	4037050	1.000	Ea
0180	_ Drop Inlet, Detail per S-6A	4037050	1.000	Ea
0185	_ Infiltration / Sediment Basin, 2 foot Dia, 3 foot Sump	4037050	6.000	Ea
0190	_ Infiltration Basin, 4 foot Dia, 4 foot Sump, per Detail S-5	4037050	4.000	Ea
0195	_ Manhole Casting, Adjust	4037050	8.000	Ea
0200	_ Manhole Casting, Furnish	4037050	8.000	Ea
0205	_ Manhole or Catch Basin, Rebuild with Flattop, per Detail S-10	4037050	4.000	Ea
0210	_ Storm Manhole, 4 foot Dia, per Detail S-1	4037050	7.000	Ea
0215	Underdrain, Subbase, 6 inch	4040063	2,880.000	Ft
0220	HMA Approach	5010061	30.000	Ton
0225	HMA, 3EML	5012013	1,100.000	Ton
0230	HMA, 4EML	5012025	800.000	Ton
0235	HMA, 5EML	5012037	650.000	Ton
0240	_ Temporary HMA Pavement	5017031	10.000	Ton
0245	Driveway, Nonreinf Conc, 6 inch	8010005	300.000	Syd
0250	Driveway, Nonreinf Conc, 8 inch	8010007	260.000	Syd
0255	_ Curb and Gutter, 18 x 8 inch pan, Detail P-5	8027001	2,880.000	Ft
0260	_ Curb, 6 inch x 20 inch, Detail P-5A	8027001	28.000	Ft
0265	Sidewalk, Conc, 4 inch	8030044	14,800.000	Sft
0270	Sidewalk, Conc, 6 inch	8030046	2,600.000	Sft
0275	Sidewalk, Conc, 8 inch	8030048	980.000	Sft
0280	Curb Ramp, Conc, 4 inch	8032001	180.000	Sft
0285	Curb Ramp, Conc, 6 inch	8032002	400.000	Sft
0290	_ Detectable Warning Surface, Modified	8037001	80.000	Ft
0295	_ Curb Ramp, Conc, 6 inch, Modified	8037010	350.000	Sft
0300	_ Sidewalk, Conc, 4 inch, Modified	8037010	600.000	Sft
0305	_ Fence, Ornamental, 48 inch	8087001	189.000	Ft
0310	_ Fence Gate, 3 foot for 48 inch Ornamental Fence	8087050	6.000	Ea
0315	Sign, Type III, Rem	8100403	13.000	Ea
0320	_ Sign	8107010	188.000	Sft
0325	_ Sign Post	8107050	13.000	Ea
0330	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	140.000	Ft
0335	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	80.000	Ft
0340	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	22.000	Ft
0345	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea

0350	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	2.000	Ea
0355	Pavt Mrkg, Wet Reflective Polyurea, 4 inch, White	8112114	112.000	Ft
0360	Pavt Mrkg, Wet Reflective Polyurea, 4 inch, Yellow	8112117	2,600.000	Ft
0365	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	30.000	Ea
0370	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	30.000	Ea
0375	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0380	Pedestrian Type II Channelizer, Temp	8120027	60.000	Ft
0385	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0390	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0395	Minor Traf Devices	8120170	1.000	LSUM
0400	Plastic Drum, Fluorescent, Furn	8120252	75.000	Ea
0405	Plastic Drum, Fluorescent, Oper	8120253	75.000	Ea
0410	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0415	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0420	Sign, Type B, Temp, Prismatic, Furn	8120350	760.000	Sft
0425	Sign, Type B, Temp, Prismatic, Oper	8120351	760.000	Sft
0430	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	105.000	Sft
0435	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	105.000	Sft
0440	Traf Regulator Control	8120370	1.000	LSUM
0445	Pedestrian Path, Temp	8122250	100.000	Ft
0450	Pedestrian Ramp, Temp	8122251	6.000	Ea
0455	_ Sign, Temp Business, Oper	8127050	20.000	Ea
0460	Site Preparation, Max \$18,000.00	8150001	1.000	LSUM
0465	Amelanchier x grandifolia 'Robin Hill', 2 inch	8150335	2.000	Ea
0470	Liatris spicata 'Kobold', #1 cont.	8152104	113.000	Ea
0475	Nepeta x faassenii 'Walkers Low', #1 cont.	8152496	45.000	Ea
0480	Rudbeckia fuldiga 'Goldsturm', #1 cont.	8153279	203.000	Ea
0485	Schizachyrium scoparium 'The Blues', #1 cont.	8153406	45.000	Ea
0490	_ Steel Edging	8157001	28.000	Ft
0495	_ Sulfur Application	8157010	40.000	Sft
0500	_ Prepared Soil	8157021	120.000	Cyd
0505	_ Carpinus caroliniana, 2 1/2 inch	8157050	13.000	Ea
0510	_ Cladtrastis kentuckea, 2 inch	8157050	12.000	Ea
0515	_ Koelreuteria paniculata, 2 1/2 inch	8157050	9.000	Ea
0520	_ Pennisetum alopecuroides 'Hush Puppy', #1 Cont	8157050	36.000	Ea
0525	_ Platanus x acerifolia 'Bloodgood', 2 1/2 inch	8157050	5.000	Ea
0530	_ Protect Tree, per Detail M-2	8157050	5.000	Ea
0535	_ Tree Irrigation Bag	8157050	52.000	Ea
0540	_ Turf Watering	8157050	10.000	Ea
0545	_ Ulmus propinqua 'JFS-Bieberich', 2 1/2 inch	8157050	11.000	Ea
0550	_ Weed Control, Modified	8157050	4.000	Ea
0555	_ Root Pruning	8157051	1.000	LSUM
0560	_ Watering and Cultivating, Special	8157051	1.000	LSUM

0565	_ Mulch Blanket, Modified	8167011	200.000	Syd
0570	_ Turf Establishment	8167011	2,600.000	Syd
0575	_ Direct Buried Conduit, (1) 2-Inch, Schedule 40 PVC	8187001	1,375.000	Ft
0580	_ Direct Buried Conduit, (2) 2-Inch, Schedule 40 PVC	8187001	205.000	Ft
0585	_ Underground Secondary Conductor, 4 -#6 CU U.S.E.	8187001	1,345.000	Ft
0590	_ Conduits, Connect to Existing	8187050	2.000	Ea
0595	_ Fiberglass Light Pole, 35-Foot Mounting Height and 8-Foot Mast Arm	8187050	9.000	Ea
0600	_ Handhole, Precast Concrete 22-Inch Dia x 40-Inch Deep	8187050	7.000	Ea
0605	_ Light Pole Foundation, 24-Inch Dia	8187050	9.000	Ea
0610	_ Salvaged Light Type C	8187050	9.000	Ea
0615	_ Secondary Riser, (1) 2-Inch	8187050	3.000	Ea
0620	_ Removal of Existing Lighting System	8187051	1.000	LSUM
0625	_ Water Main, 12 inch	8237001	1,340.000	Ft
0630	_ Water Main, 4 inch	8237001	36.000	Ft
0635	_ Water Main, 6 inch	8237001	290.000	Ft
0640	_ Water Service, 1 1/2 inch	8237001	150.000	Ft
0645	_ Water Service, 1 inch	8237001	940.000	Ft
0650	_ Bend, 22 1/2 Degree, 6 inch	8237050	4.000	Ea
0655	_ Bend, 45 Degree, 6 inch	8237050	2.000	Ea
0660	_ Bend, 90 Degree, 6 inch	8237050	1.000	Ea
0665	_ Cap, 4 inch	8237050	1.000	Ea
0670	_ Curb Stop and Box on Water Service, 1 1/2 inch	8237050	6.000	Ea
0675	_ Curb Stop and Box on Water Service, 1 inch	8237050	34.000	Ea
0680	_ Fire Hydrant, Rem	8237050	3.000	Ea
0685	_ Hydrant, 5 inch	8237050	4.000	Ea
0690	_ Sleeve, 12 inch	8237050	2.000	Ea
0695	_ Sleeve, 6 inch	8237050	4.000	Ea
0700	_ Tap for Water Service, Including Corporation Stop and Collar, 1 1/2 inch	8237050	6.000	Ea
0705	_ Tap for Water Service, Including Corporation Stop, 1 inch	8237050	34.000	Ea
0710	_ Tee, 12 inch x 12 inch x 4 inch	8237050	1.000	Ea
0715	_ Tee, 12 inch x 12 inch x 6 inch	8237050	6.000	Ea
0720	_ Tee, 6 inch x 6 inch x 6 inch	8237050	2.000	Ea
0725	_ Valve and Box, 12 inch	8237050	3.000	Ea
0730	_ Valve and Box, 4 inch	8237050	1.000	Ea
0735	_ Valve and Box, 6 inch	8237050	8.000	Ea
0740	_ Valve Box, Adjust	8237050	2.000	Ea
0745	_ Valve Box, Furnish	8237050	2.000	Ea
0750	_ Water Filter	8237050	22.000	Ea
0755	_ Water Service, 1 1/2 inch, Curb Box to Meter	8237050	2.000	Ea
0760	_ Water Service, 1 inch, Curb Box to Meter	8237050	19.000	Ea
0765	_ Water Service, Exploratory Investigation	8237050	4.000	Ea
0770	_ Water Main Construction, Plumbing Allowance	8237060	15,000.000	Dir

0775	_ Preconstruction Documentation	8507051	1.000	LSUM
0780	_ Contaminated Material, Storage, Handling and Disposal	8507060	5,000.000	Dir
0785	_ Underground Sprinkling Systems, Restore	8507060	2,000.000	Dir

---