



Schedule of Pay Items

Report v1

Letting Call: 251107 001

Letting Date: November 7, 2025

Contract ID: 38131-201223

Description: 9.64 mi of hot mix asphalt cold milling and resurfacing, concrete longitudinal joint resealing, full depth concrete pavement repairs, detail 7 pavement repairs, overband crack fill, shoulder, shoulder widening and paving, shoulder chip and fog seal and pavement markings and bridge rehabilitation on three structures including structural steel repairs, partial painting, bearing replacement, diaphragm replacement, expansion joint replacement, pressure relief joint resealing, end joint resealing and substructure repair on US-127 from Parnall Road northerly to Huntoon Creek, Jackson and Ingham Counties. This project includes a 3 year materials and workmanship pavement warranty and a 2 year pavement performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
201223A	25A0998	N/A	NH 38131
213702A	N/A	N/A	M 38131
214106A	25A1002	N/A	HSIP 38131

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Reimbursed Permit Fees	1077060	500.000	Dir
0010	Mobilization, Max \$838,900.00	1100001	1.000	LSUM
0015	Pavt, Rem	2040050	200.000	Syd
0020	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	20.000	Ea
0030	Erosion Control, Silt Fence	2080036	600.000	Ft
0035	Project Cleanup	2090001	1.000	LSUM
0040	Aggregate Base, 6 inch	3020016	1,893.000	Syd
0045	Shld, CI II	3070121	2,700.000	Ton
0050	Trenching	3070200	24.000	Sta
0055	Dr Marker Post	4011109	20.000	Ea
0060	Dr Structure Lead, Cleaning, 12 inch	4030112	8,400.000	Ft
0065	Dr Structure Lead, Cleaning, 18 inch	4030118	1,280.000	Ft
0070	Dr Structure Lead, Cleaning, 24 inch	4030124	440.000	Ft
0075	Dr Structure, Cleaning	4030290	230.000	Ea
0080	_ Underdrain Outlet Cleanout	4047050	325.000	Ea
0085	Pavt, Cleaning	5010001	1.000	LSUM
0090	Cold Milling HMA Surface	5010002	245,750.000	Syd
0095	HMA Surface, Rem	5010005	853.000	Syd
0100	HMA Quality Initiative	5010007	50,250.000	Dir
0105	Longit Joint Density Quality Initiative	5010018	91,000.000	Dir

0110	Pavt Joint and Crack Repr, Det 7	5010020	14,800.000	Ft
0115	Pavt Joint and Crack Repr, Det 8	5010021	2,220.000	Ft
0120	Hand Patching	5010025	2,200.000	Ton
0125	HMA, 4EML	5012025	1,005.000	Ton
0130	HMA, 5EML	5012037	21,920.000	Ton
0135	_ Asphalt Repr Mastic	5027001	2,000.000	Ft
0140	_ Overband Crack Fill, Shld	5027001	117,650.000	Ft
0145	_ Overband Crack Fill, Carpool Parking Lot	5027011	2,230.000	Syd
0150	Seal, Fog	5050015	123,855.000	Syd
0155	Chip Seal, Shld, Warranty	5050030	123,855.000	Syd
0160	High Friction Surface Treatment	5060800	12,200.000	Syd
0165	Joint, Contraction, Cp	6020200	377.000	Ft
0170	Crack Sealing, Conc Pavt	6030010	500.000	Ft
0175	Cold Milling Conc Pavt	6030014	3,127.000	Syd
0180	Joint, Contraction, Crg	6030020	10,605.000	Ft
0185	Joint, Expansion, Erg	6030021	2,030.000	Ft
0190	Lane Tie, Epoxy Anchored	6030030	368.000	Ea
0195	Pavt Repr, Nonreinf Conc, 10 inch	6030048	1,645.000	Syd
0200	Pavt Repr, Rem	6030080	4,572.000	Syd
0205	Saw Cut, Intermediate	6030090	1,422.000	Ft
0210	Resealing Trans Joints with Hot-Poured Rubber	6030100	2,400.000	Ft
0215	Resealing Longit Joints with Hot-Poured Rubber	6030101	102,100.000	Ft
0220	_ Pavt Repr, Nonreinf Conc, 14.5 inch	6037011	3,127.000	Syd
0225	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	2.000	Ea
0230	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0235	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0240	Pavt Mrkg, Polyurea, 6 inch, White	8110094	225.000	Ft
0245	Pavt Mrkg, Polyurea, 12 inch, White	8110111	128.000	Ft
0250	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	66.000	Ft
0255	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	2.000	Ea
0260	Pavt Mrkg, Waterborne, 6 inch, White	8110233	83,000.000	Ft
0265	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	65,500.000	Ft
0270	Pavt Mrkg, Waterborne, 12 inch, White	8110237	5,500.000	Ft
0275	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	83,000.000	Ft
0280	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	65,500.000	Ft
0285	Pavt Mrkg, Waterborne, 2nd Application, 12 inch, White	8110257	5,500.000	Ft
0290	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	1,510.000	Ft
0295	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0300	Recessing Pavt Mrkg, Longit	8110450	353.000	Ft
0305	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	14.000	Ea
0310	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	14.000	Ea
0315	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	525.000	Ea

0320	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	525.000	Ea
0325	Conc Barrier Ending, Temp, Det 2, Adj	8120040	3.000	Ea
0330	Conc Barrier Ending, Temp, Det 2, Furn	8120041	3.000	Ea
0335	Conc Barrier Ending, Temp, Det 2, Oper	8120042	3.000	Ea
0340	Conc Barrier, Temp, Adj	8120080	1,410.000	Ft
0345	Conc Barrier, Temp, Furn	8120081	1,410.000	Ft
0350	Conc Barrier, Temp, Oper	8120082	1,410.000	Ft
0355	High Intensity Light, Type B, Furn	8120110	3.000	Ea
0360	High Intensity Light, Type B, Oper	8120111	3.000	Ea
0365	Connected Arrow Board, Type C, Furn	8120155	7.000	Ea
0370	Connected Arrow Board, Type C, Oper	8120156	7.000	Ea
0375	Minor Traf Devices	8120170	1.000	LSUM
0380	Mobile Attenuator	8120180	2.000	Ea
0385	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	14,250.000	Ft
0390	Plastic Drum, Fluorescent, Furn	8120252	590.000	Ea
0395	Plastic Drum, Fluorescent, Oper	8120253	590.000	Ea
0400	Sign Cover	8120310	50.000	Ea
0405	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	8.000	Ea
0410	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	8.000	Ea
0415	Sign, Type A, Temp, Prismatic, Furn	8120340	20.000	Sft
0420	Sign, Type A, Temp, Prismatic, Oper	8120341	20.000	Sft
0425	Sign, Type B, Temp, Prismatic, Furn	8120350	2,200.000	Sft
0430	Sign, Type B, Temp, Prismatic, Oper	8120351	2,200.000	Sft
0435	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	48.000	Sft
0440	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	48.000	Sft
0445	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	26,816.000	Ft
0450	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	17,316.000	Ft
0455	Speed Radar Trailer, Temp	8122028	6.000	Ea
0460	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	1,300.000	Ft
0465	Freeway Shld Corrugations, Milled, Conc	8222000	225.000	Ft
0470	Freeway Shld Corrugations, Milled, HMA	8222001	113,078.000	Ft
0475	Contractor Staking	8240001	1.000	LSUM
0480	Staking Plan Errors and Extras, Max \$180/hour	8240002	12.000	Hr

Section: 2

0485	Backfill, Structure, CIP	2060002	9.000	Cyd
0490	Excavation, Fdn	2060010	9.000	Cyd
0495	_ Joint, Pressure Relief, Replace Filler	6027001	272.000	Ft
0500	Expansion Joint Device	7060050	175.000	Ft
0505	False Decking	7060060	2,834.000	Sft
0510	Reinforcement, Steel, Epoxy Coated	7060092	8,900.000	Lb
0515	Conc, Grade 4500HP	7062004	33.000	Cyd

0520	Substructure Horizontal Surface Sealer (B01-1 of 38131)	7100030	16.000	Syd
0525	Substructure Horizontal Surface Sealer (B01-2 of 38131)	7100030	16.000	Syd
0530	Hand Chipping, Other Than Deck	7120007	40.000	Cft
0535	Patch, Forming	7120017	160.000	Sft
0540	Bolt, Adhesive Anchored, 1 inch	7120044	72.000	Ea
0545	Structures, Rehabilitation, Rem Portions (B01-1 of 38131)	7120070	1.000	LSUM
0550	Structures, Rehabilitation, Rem Portions (B01-2 of 38131)	7120070	1.000	LSUM
0555	Structures, Rehabilitation, Rem Portions (S07-2 of 38131)	7120070	1.000	LSUM
0560	Deck Joint, Rem	7120071	178.000	Ft
0565	Reinforcement, Mechanical Splice	7120084	48.000	Ea
0570	Patching Conc, C-L	7120112	2.000	Cyd
0575	Embedded Galvanic Anode	7120120	218.000	Ea
0580	_ Bridge Joints, Clean and Seal	7127001	267.000	Ft
0585	Beam Plate, Seal Perimeter	7130010	883.000	Ft
0590	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	20,110.000	Lb
0595	Structural Steel, Welded Repr, Furn, Fab, and Erect	7130072	2,333.000	Lb
0600	Support, Column, Temp	7130080	1.000	Ea
0605	Support, Diaphragm, Temp	7130081	36.000	Ea
0610	End Diaphragm, Rem and Replace	7150010	32.000	Ea
0615	Steel Structure, Cleaning, Partial, Type 4 (B01-1 of 38131)	7150047	1.000	LSUM
0620	Steel Structure, Cleaning, Partial, Type 4 (B01-2 of 38131)	7150047	1.000	LSUM
0625	Steel Structure, Coating, Partial, Type 4 (B01-1 of 38131)	7150048	1.000	LSUM
0630	Steel Structure, Coating, Partial, Type 4 (B01-2 of 38131)	7150048	1.000	LSUM
0635	Field Repr of Damaged Coating (B01-1 of 38131)	7160001	1.000	LSUM
0640	Field Repr of Damaged Coating (B01-2 of 38131)	7160001	1.000	LSUM
0645	Slope Paving, Conc	8130020	11.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 002

Letting Date: November 7, 2025

Contract ID: 61152-218329

Description: 0.17 mi of hot mix asphalt inlay of interchange ramps, concrete pavement inlay, crossovers, shoulder resurfacing, drainage improvements, concrete median barrier reconstruction, signing, guardrail, slope restoration and pavement markings and bridge rehabilitation including concrete barrier replacement, partial deck replacement, deck patching, substructure patching, steel beam repair, zone painting, temporary supports, expansion joint replacement, high friction hybrid copolymer overlay and approach work on US-31 at I-96 interchange in the city of Norton Shores, Muskegon County. This project includes a 5 year materials and workmanship pavement warranty and a 5 year bridge deck performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218329A	N/A	N/A	M 61152
223531A	25A1086	N/A	NH 61074

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Conc Quality Initiative	10000030	18,300.000	Dir
0010	Mobilization, Max \$585,000.00	1100001	1.000	LSUM
0015	Culv, End, Rem, Less than 24 inch	2030005	4.000	Ea
0020	Dr Structure, Rem	2030011	10.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	281.000	Ft
0030	Conc Barrier, Rem	2040010	733.000	Ft
0035	Guardrail, Rem	2040035	1,250.000	Ft
0040	Pavt, Rem	2040050	8,038.000	Syd
0045	Excavation, Earth	2050016	7,789.000	Cyd
0050	Subgrade Undercutting, Type II	2050041	300.000	Cyd
0055	_ Embankment, CIP, Spec	2057021	1,129.000	Cyd
0060	Erosion Control, Check Dam, Stone	2080012	132.000	Ft
0065	Erosion Control, Inlet Protection, Fabric Drop	2080020	15.000	Ea
0070	Erosion Control, Inlet Protection, Sediment Trap	2080024	3.000	Ea
0075	Erosion Control, Maintenance, Sediment Rem	2080026	12.000	Cyd
0080	Erosion Control, Sand Bag	2080028	50.000	Ea
0085	Erosion Control, Sediment Trap	2080034	7.000	Ea
0090	Erosion Control, Silt Fence	2080036	748.000	Ft
0095	Project Cleanup	2090001	1.000	LSUM
0100	Subbase, CIP	3010002	687.000	Cyd
0105	Aggregate Base, 6 inch	3020016	17,332.000	Syd
0110	Shld, CI II	3070121	37.000	Ton
0115	Shld, CI II, 4 inch	3070126	159.000	Syd

0120	Shld, CI II, 6 inch	3070128	563.000	Syd
0125	Shld, CI II, 5 inch, Temp	3070182	306.000	Syd
0130	_ Shld, CI II, 10 inch	3077011	365.000	Syd
0135	_ Shld, CI II, 6.5 inch	3077011	1,340.000	Syd
0140	Culv End Sect, 12 inch	4010012	2.000	Ea
0145	Culv End Sect, Footing	4010072	4.000	Ea
0150	Culv, Downspout, 18 inch	4010797	54.000	Ft
0155	Dr Marker Post	4011109	2.000	Ea
0160	Culv, Outlet Headwall, 18 inch	4012002	2.000	Ea
0165	Sewer, CI A, 12 inch, Tr Det B	4020033	235.000	Ft
0170	_ Slotted Drain, Galv, 12 inch, Temp	4027001	250.000	Ft
0175	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0180	Dr Structure Cover, Type B	4030010	1.000	Ea
0185	Dr Structure Cover, Type DX	4030030	4.000	Ea
0190	Dr Structure Cover, Type VG	4030090	4.000	Ea
0195	Dr Structure, 24 inch dia	4030200	2.000	Ea
0200	Dr Structure, 48 inch dia	4030210	7.000	Ea
0205	_ Dr Structure Cover, Type DX, Modified	4037050	3.000	Ea
0210	Pavt, Cleaning	5010001	1.000	LSUM
0215	Cold Milling HMA Surface	5010002	6,459.000	Syd
0220	HMA Surface, Rem	5010005	8,734.000	Syd
0225	HMA Quality Initiative	5010007	10,200.000	Dlr
0230	Longit Joint Density Quality Initiative	5010018	20,700.000	Dlr
0235	Hand Patching	5010025	10.000	Ton
0240	HMA Approach	5010061	374.000	Ton
0245	HMA, 3EML	5012013	1,529.000	Ton
0250	HMA, 4EML	5012025	1,836.000	Ton
0255	HMA, 5EML	5012037	1,350.000	Ton
0260	HMA, Temp Pavt (4EML)	5012103	607.000	Ton
0265	Joint, Contraction, Cp	6020200	1,067.000	Ft
0270	Joint, Contraction, C3p	6020201	500.000	Ft
0275	Joint, Expansion, E2	6020207	552.000	Ft
0280	Joint, Expansion, E3	6020208	222.000	Ft
0285	Joint, Expansion, E4	6020209	227.000	Ft
0290	Conc Pavt, Misc, Nonreinf, 10 inch, High Performance	6020516	2,292.000	Syd
0295	Shld, Nonreinf Conc, High Performance	6020524	873.000	Syd
0300	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	466.000	Syd
0305	Crack Sealing, Conc Pavt	6030010	336.000	Ft
0310	Joint, Contraction, Crg	6030020	396.000	Ft
0315	Lane Tie, Epoxy Anchored	6030030	525.000	Ea
0320	Pavt Repr, Nonreinf Conc, 9 inch	6030046	229.000	Syd
0325	Pavt Repr, Rem	6030080	129.000	Syd
0330	Saw Cut, Intermediate	6030090	384.000	Ft
0335	_ Curb and Gutter, Bridge Approach, Det 4A, Modified	8027001	106.000	Ft
0340	_ Valley Gutter, Conc, Modified	8027001	202.000	Ft

0345	Sidewalk, Conc, 4 inch	8030044	11.000	Sft
0350	Conc Barrier, Double Face, Type A	8040005	705.000	Ft
0355	Conc Barrier, Split, Type A	8040010	53.000	Ft
0360	Glare Screen, Conc	8040015	705.000	Ft
0365	Glare Screen, Conc, Split	8040016	28.000	Ft
0370	Conc Barrier Backfill, CIP	8040030	2.000	Cyd
0375	Guardrail Anch, Median	8070035	1.000	Ea
0380	Guardrail Approach Terminal, Type 2M	8070044	5.000	Ea
0385	Guardrail Departing Terminal, Type MGS	8070052	2.000	Ea
0390	Guardrail Reflector	8070080	30.000	Ea
0395	Guardrail Anch, Bridge, Det M1	8070130	4.000	Ea
0400	Guardrail Anch, Bridge, Det M7	8070136	2.000	Ea
0405	Cable Barrier, High Tension, Salv	8070201	1,005.000	Ft
0410	Cable Barrier, High Tension, Reconst	8070202	1,005.000	Ft
0415	Guardrail, Type MGS-8, 72 inch Post	8072179	777.000	Ft
0420	Delineator Reflector, Red	8100131	25.000	Ea
0425	Delineator Reflector, Yellow	8100132	15.000	Ea
0430	Delineator Reflector, Green	8100133	26.000	Ea
0435	Delineator Reflector, White	8100134	40.000	Ea
0440	Fdn, Wood Support, Rem	8100280	17.000	Ea
0445	Perforated Steel Square Tube Breakaway System	8100330	4.000	Ea
0450	Fdn, Perforated Steel Square Tube Sign Breakaway System, Rem	8100331	4.000	Ea
0455	Delineator, Rem	8100349	160.000	Ea
0460	Post, Rigid, Delineator	8100361	51.000	Ea
0465	Post, Steel, 3 pound	8100371	744.000	Ft
0470	Post, Wood, 4 inch by 6 inch	8100380	79.000	Ft
0475	Post, Wood, 6 inch by 8 inch	8100382	217.000	Ft
0480	Sign, Type II, Erect, Salv	8100396	15.000	Ea
0485	Sign, Type III, Erect, Salv	8100402	52.000	Ea
0490	Sign, Type IIIB	8100405	10.000	Sft
0495	Post, Flexible, Delineator, Ground Mtd	8100555	60.000	Ea
0500	Reflective Panel for Permanent Sign Support, 3 foot	8100613	2.000	Ea
0505	Reflective Panel for Permanent Sign Support, 6 foot	8100616	33.000	Ea
0510	Sign, Type II, Rem, Salv	8102002	15.000	Ea
0515	Sign, Type III, Rem, Salv	8102003	52.000	Ea
0520	Ground Mtd Sign Support, Rem	8102010	70.000	Ea
0525	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	1.000	Ea
0530	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	4,799.000	Ft
0535	Rem Curing Compound, for Longit Mrkg, 12 inch	8110310	180.000	Ft
0540	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0545	Recessing Pavt Mrkg, Longit	8110450	10,541.000	Ft
0550	Recessing Pavt Mrkg, Transv	8110451	41.000	Sft
0555	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	6,349.000	Ft
0560	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	1,399.000	Ft

0565	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	4,142.000	Ft
0570	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	50.000	Ea
0575	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	50.000	Ea
0580	Conc Barrier Ending, Temp, Det 2, Adj	8120040	1.000	Ea
0585	Conc Barrier Ending, Temp, Det 2, Furn	8120041	6.000	Ea
0590	Conc Barrier Ending, Temp, Det 2, Oper	8120042	6.000	Ea
0595	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	12.000	Ea
0600	Conc Barrier Reflector Replacement	8120070	110.000	Ea
0605	Conc Barrier, Temp, Adj	8120080	1,881.000	Ft
0610	Conc Barrier, Temp, Furn	8120081	7,870.000	Ft
0615	Conc Barrier, Temp, Oper	8120082	7,870.000	Ft
0620	Conc Barrier, Temp, Relocated	8120083	5,670.000	Ft
0625	Conc Barrier, Temp, Limited Deflection, Reflector Replacement	8120086	100.000	Ea
0630	Delineator, Flexible, Temp, Furn	8120091	10.000	Ea
0635	Delineator, Flexible, Temp, Oper	8120092	10.000	Ea
0640	Glare Screen, Temp	8120094	3,400.000	Ft
0645	Glare Screen, Temp, Complete Sect, Replaced	8120096	100.000	Ea
0650	High Intensity Light, Type B, Furn	8120110	8.000	Ea
0655	High Intensity Light, Type B, Oper	8120111	8.000	Ea
0660	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0665	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0670	Ltg for Night Work	8120160	1.000	LSUM
0675	Minor Traf Devices	8120170	1.000	LSUM
0680	Mobile Attenuator	8120180	2.000	Ea
0685	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	760.000	Ft
0690	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	100.000	Ft
0695	Pavt Mrkg, Longit, Water Blasting, 6 inch or less Width, Rem	8120212	15,130.000	Ft
0700	Pavt Mrkg, Longit, Water Blasting, Greater than 6 inch Width, Rem	8120213	1,590.000	Ft
0705	Plastic Drum, Fluorescent, Furn	8120252	780.000	Ea
0710	Plastic Drum, Fluorescent, Oper	8120253	780.000	Ea
0715	Raised Pavt Marker, Temp, Type 3, White, Monodirectional	8120300	100.000	Ea
0720	Raised Pavt Marker, Temp, Type 3, Yellow, Bidirectional	8120301	100.000	Ea
0725	Sign Cover	8120310	170.000	Ea
0730	Sign Cover, Type I	8120320	26.000	Ea
0735	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	8.000	Ea
0740	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	8.000	Ea
0745	Sign, Type A, Temp, Prismatic, Furn	8120340	1,550.000	Sft
0750	Sign, Type A, Temp, Prismatic, Oper	8120341	1,550.000	Sft
0755	Sign, Type B, Temp, Prismatic, Furn	8120350	4,850.000	Sft

0760	Sign, Type B, Temp, Prismatic, Oper	8120351	4,850.000	Sft
0765	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	2,510.000	Sft
0770	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	2,510.000	Sft
0775	Conc Barrier, Temp, Limited Deflection, Det 1, Furn	8121000	480.000	Ft
0780	Conc Barrier, Temp, Limited Deflection, Det 1, Oper	8121001	480.000	Ft
0785	Conc Barrier, Temp, Limited Deflection, Det 1, Adj	8121002	960.000	Ft
0790	Conc Barrier, Temp, Limited Deflection, Det 1, Relocated	8121003	480.000	Ft
0795	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	31,610.000	Ft
0800	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	31,610.000	Ft
0805	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	10,220.000	Ft
0810	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	5,670.000	Ft
0815	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	5,840.000	Ft
0820	Pavt Mrkg, Wet Reflective, Type NR, Paint, 12 inch, White, Temp	8122016	1,690.000	Ft
0825	Speed Radar Trailer, Temp	8122028	4.000	Ea
0830	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	2,730.000	Ft
0835	Conc Barrier-Mtd Temp Sign System, Furn	8122192	6.000	Ea
0840	Conc Barrier-Mtd Temp Sign System, Oper	8122193	6.000	Ea
0845	Riprap, Plain	8130010	45.000	Syd
0850	Mulch	8160025	2,223.000	Syd
0855	Mulch Anchoring	8160026	228.000	Syd
0860	Seeding, Mixture TSM	8160041	46.000	Lb
0865	Water, Sodding/Seeding	8160090	8.000	Unit
0870	Slope Restoration, Freeway, Type A	8162013	2,422.000	Syd
0875	Slope Restoration, Freeway, Type B	8162014	10,481.000	Syd
0880	Slope Restoration, Freeway, Type C	8162015	1,166.000	Syd
0885	Freeway Shld Corrugations, Milled, HMA	8222001	5,882.000	Ft
0890	Contractor Staking	8240001	1.000	LSUM
0895	Staking Plan Errors and Extras, Max \$180/hour	8240002	65.000	Hr

Section: 2

0900	Backfill, Structure, CIP	2060002	11.000	Cyd
0905	Excavation, Fdn	2060010	11.000	Cyd
0910	HMA Patch, Rem	5010006	3.000	Syd
0915	Bridge Ltg, Furn and Rem (S03 of 61152)	7060001	1.000	LSUM
0920	Bridge Ltg, Oper and Maintain	7060002	195.000	Cyd
0925	Expansion Joint Device	7060050	333.000	Ft
0930	False Decking	7060060	7,486.000	Sft
0935	Reinforcement, Steel, Epoxy Coated	7060092	77,135.000	Lb
0940	Superstructure Conc, Form, Finish, and Cure, Night Casting (S03 of 61152)	7060112	1.000	LSUM

0945	Superstructure Conc, Night Casting, High Performance	7060117	195.000	Cyd
0950	Conc, Grade 4500HP	7062004	39.000	Cyd
0955	Shear Developers (S03 of 61152)	7070040	1.000	LSUM
0960	Joint Waterproofing	7100001	333.000	Sft
0965	Substructure Horizontal Surface Sealer (S03 of 61152)	7100030	114.000	Syd
0970	_ Silane Treatment	7107010	4,765.000	Sft
0975	Reflective Marker, Permanent Barrier	7110003	16.000	Ea
0980	Bridge Barrier Railing, Type 6, High Performance	7110017	213.000	Ft
0985	Bridge Barrier Railing, Type 7, High Performance	7110018	422.000	Ft
0990	_ Bridge Barrier Railing, Type 6, High Performance, Modified	7117001	213.000	Ft
0995	Hand Chipping, Deep	7120004	10.000	Syd
1000	Hand Chipping, Other Than Deck	7120007	4.000	Cft
1005	Patch, Full Depth	7120010	6.000	Cyd
1010	Patch, Forming	7120017	160.000	Sft
1015	Structures, Rehabilitation, Rem Portions with Shear Developer Rem (S03 of 61152)	7120065	1.000	LSUM
1020	Deck Joint, Rem	7120071	333.000	Ft
1025	Reinforcement, Mechanical Splice	7120084	120.000	Ea
1030	Top Flanges and Beam Ends, Clean and Coat	7120100	1,187.000	Syd
1035	Patching Conc, C-L	7120112	2.000	Cyd
1040	Embedded Galvanic Anode, High Performing	7120125	960.000	Ea
1045	Hand Chipping, Full Depth	7122000	150.000	Cft
1050	_ High Friction Hybrid Copolymer Ovly, Warranty	7127011	2,386.000	Syd
1055	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	358.000	Lb
1060	Support, Column, Temp	7130080	3.000	Ea
1065	Steel Structure, Cleaning, Partial, Type 4 (S03 of 61152)	7150047	1.000	LSUM
1070	Steel Structure, Coating, Partial, Type 4 (S03 of 61152)	7150048	1.000	LSUM
1075	Field Repr of Damaged Coating (S03 of 61152)	7160001	1.000	LSUM
1080	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM
1085	Structure Survey During Construction (S03 of 61152)	8240020	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 003

Letting Date: November 7, 2025

Contract ID: 52032-208421

Description: 3.34 mi of hot mix asphalt base crushing, shaping, and resurfacing, grading, roundabout construction, drainage improvements, guardrail, lighting, traffic signal upgrades, signing and pavement markings on M-35 from County Road 480 northerly to US-41/M-28, Marquette County. This project includes two 5 year materials and workmanship pavement warranties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
208421A	25A1037	N/A	ST 52032
211767A	25A1030	N/A	HSIP 52032

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, Lake Superior & Ishpeming	1047060	20,000.000	Dir
0010	Mobilization, Max \$605,800.00	1100001	1.000	LSUM
0015	Clearing	2010001	1.830	Acre
0020	_ Clearing, Spec	2017012	0.200	Acre
0025	Tree, Rem, 19 inch to 36 inch	2020002	1.000	Ea
0030	Culv, Rem, Less than 24 inch	2030001	10.000	Ea
0035	Culv, Rem, 24 inch to 48 inch	2030002	4.000	Ea
0040	Dr Structure, Rem	2030011	3.000	Ea
0045	Sewer, Rem, Less than 24 inch	2030015	205.000	Ft
0050	Curb and Gutter, Rem	2040020	932.000	Ft
0055	Guardrail, Rem	2040035	6,710.000	Ft
0060	Pavt, Rem	2040050	191.000	Syd
0065	Sidewalk, Rem	2040055	23.000	Syd
0070	Track, Rem	2040065	375.000	Ft
0075	Backfill, Swamp	2050001	1,750.000	Cyd
0080	Ditch Cleanout	2050006	1.000	Sta
0085	Embankment, CIP	2050010	20,527.000	Cyd
0090	Embankment, LM	2050011	20.000	Cyd
0095	Excavation, Earth	2050016	14,059.000	Cyd
0100	Excavation, Peat	2050017	1,350.000	Cyd
0105	Excavation, Rock	2050018	200.000	Cyd
0110	Granular Blanket, Type 1	2050020	125.000	Cyd
0115	Non Haz Contaminated Material Handling and Disposal, LM	2050031	20.000	Cyd
0120	Erosion Control, Check Dam, Stone	2080012	190.000	Ft

0125	Erosion Control, Inlet Protection, Fabric Drop	2080020	19.000	Ea
0130	Erosion Control, Inlet Protection, Sediment Trap	2080024	1.000	Ea
0135	Erosion Control, Sediment Trap	2080034	34.000	Ea
0140	Erosion Control, Silt Fence	2080036	7,440.000	Ft
0145	Subbase, CIP	3010002	4,940.000	Cyd
0150	Aggregate Base	3020001	10,181.000	Ton
0155	Aggregate Base, 6 inch	3020016	18,949.000	Syd
0160	HMA Base Crushing and Shaping	3050002	70,121.000	Syd
0165	Material, Surplus and Unsuitable, Rem, LM	3050010	425.000	Cyd
0170	Salv Crushed Material, LM	3050015	350.000	Cyd
0175	Driveway Maintenance, Residential	3062001	98.000	Ea
0180	Intersection Maintenance	3062002	6.000	Ea
0185	Approach, CI I, 3 inch	3070005	2,910.000	Syd
0190	Approach, CI II, 6 inch	3070028	2,136.000	Syd
0195	Shld, CI II, 4 inch	3070126	6,955.000	Syd
0200	Trenching	3070200	319.000	Sta
0205	Culv End Sect, 12 inch	4010012	5.000	Ea
0210	Culv End Sect, 15 inch	4010015	1.000	Ea
0215	Culv End Sect, 24 inch	4010024	3.000	Ea
0220	Culv End Sect, 30 inch	4010030	5.000	Ea
0225	Culv End Sect, Conc, 24 inch	4010051	2.000	Ea
0230	Culv End Sect, Footing	4010072	29.000	Ea
0235	Culv, CI A, 24 inch	4010134	273.000	Ft
0240	Culv, CI A, 30 inch	4010135	364.000	Ft
0245	Culv, CI A, Conc, 24 inch	4010168	16.000	Ft
0250	Culv, CI E, 18 inch	4010541	206.000	Ft
0255	Culv, CI E, 24 inch	4010542	72.000	Ft
0260	Culv, CI F, 18 inch	4010609	436.000	Ft
0265	Culv, Slp End Sect, 1 on 4, 18 inch, Transv	4010920	12.000	Ea
0270	Culv, Slp End Sect, 1 on 4, 24 inch, Transv	4010924	4.000	Ea
0275	Culv, Slp End Sect, 1 on 4, 30 inch, Transv	4010928	3.000	Ea
0280	Culv, Slp End Sect, 1 on 6, 18 inch, Longit	4010951	29.000	Ea
0285	Culv, Slp End Sect, 1 on 6, 24 inch, Longit	4010955	4.000	Ea
0290	Dr Marker Post	4011109	39.000	Ea
0295	_ Culv Cleanout	4017001	155.000	Ft
0300	Sewer, CI A, 18 inch, Tr Det A	4020006	205.000	Ft
0305	Sewer, CI A, 12 inch, Tr Det B	4020033	304.000	Ft
0310	Sewer, CI A, 18 inch, Tr Det B	4020035	302.000	Ft
0315	Sewer, CI A, 24 inch, Tr Det B	4020036	283.000	Ft
0320	Sewer, CI E, 12 inch, Tr Det B	4020600	233.000	Ft
0325	Video Taping Sewer and Culv Pipe	4021275	2,694.000	Ft
0330	Dr Structure Cover, Type B	4030010	1.000	Ea
0335	Dr Structure Cover, Type E	4030035	5.000	Ea
0340	Dr Structure Cover, Type G	4030040	1.000	Ea
0345	Dr Structure Cover, Type J	4030045	10.000	Ea

0350	Dr Structure, 24 inch dia	4030200	2.000	Ea
0355	Dr Structure, 48 inch dia	4030210	15.000	Ea
0360	Underdrain, Bank, 6 inch	4040003	200.000	Ft
0365	Underdrain, Subbase, 6 inch	4040063	2,380.000	Ft
0370	Underdrain Outlet, 6 inch	4040093	160.000	Ft
0375	Underdrain, Outlet Ending, 6 inch	4040113	2.000	Ea
0380	Video Inspection of Underdrain	4040200	2,740.000	Ft
0385	Cold Milling HMA Surface	5010002	3,064.000	Syd
0390	Bump Grinding	5010004	100.000	Syd
0395	HMA Surface, Rem	5010005	14,670.000	Syd
0400	HMA Quality Initiative	5010007	34,670.000	Dlr
0405	Longit Joint Density Quality Initiative	5010018	35,930.000	Dlr
0410	HMA Approach	5010061	669.000	Ton
0415	HMA Approach, High Stress	5010520	509.000	Ton
0420	HMA, 3EML	5012013	427.000	Ton
0425	HMA, 4EML	5012025	14,050.000	Ton
0430	HMA, 4EML, High Stress	5012073	1,680.000	Ton
0435	HMA, Temp Pavt (4EML)	5012103	165.000	Ton
0440	_ Ride Incentive	5017060	7,822.000	Dlr
0445	_ Conc Pavt, Decorative, Nonreinf, 9 inch	6027011	465.000	Syd
0450	Driveway, Nonreinf Conc, 6 inch	8010005	191.000	Syd
0455	Curb, Conc, Det E1	8020001	206.000	Ft
0460	Curb and Gutter, Conc, Det B2	8020016	3,369.000	Ft
0465	Driveway Opening, Conc, Det M	8020050	172.000	Ft
0470	Shld Gutter, Conc, Det 1	8020055	2.000	Ea
0475	Shld Gutter, Conc, Det 2	8020056	4.000	Ea
0480	Shld Gutter, Conc, Det 3	8020057	2.000	Ea
0485	Spillway, Conc	8020075	50.000	Ft
0490	_ Curb and Gutter, Conc, Det D2, Modified	8027001	312.000	Ft
0495	_ Curb and Gutter, Conc, Det F4, Modified	8027001	1,322.000	Ft
0500	Detectable Warning Surface	8030010	80.000	Ft
0505	Curb Ramp Opening, Conc	8030030	100.000	Ft
0510	Curb Ramp, Conc, 4 inch	8032001	800.000	Sft
0515	_ Decorative Conc, Surface, 6 inch	8037010	5,826.000	Sft
0520	Shared use Path, Aggregate, LM	8060011	330.000	Cyd
0525	Shared use Path, Grading	8060030	770.000	Ft
0530	Shared use Path, HMA	8060040	85.000	Ton
0535	Guardrail Approach Terminal, Type 2M	8070044	11.000	Ea
0540	Guardrail Departing Terminal, Type B	8070050	1.000	Ea
0545	Guardrail, Salv	8070075	288.000	Ft
0550	Guardrail Reflector	8070080	160.000	Ea
0555	Post, Mailbox	8070095	70.000	Ea
0560	Guardrail, Curved, Type B-CRT	8072154	38.000	Ft
0565	Guardrail, Type MGS-8, 108 inch Post	8072180	3,836.000	Ft
0570	Delineator Reflector, Green	8100133	12.000	Ea

0575	Fdn, Wood Support, Rem	8100280	21.000	Ea
0580	Post Hole Through Conc for Wood Post	8100341	8.000	Ea
0585	Post, Rigid, Delineator	8100361	12.000	Ea
0590	Post, Steel, 3 pound	8100371	1,404.000	Ft
0595	Post, Wood, 4 inch by 6 inch	8100380	286.000	Ft
0600	Post, Wood, 6 inch by 8 inch	8100382	49.000	Ft
0605	Sign, Type II, Erect, Salv	8100396	3.000	Ea
0610	Sign, Type II, Rem	8100397	4.000	Ea
0615	Sign, Type III, Erect, Salv	8100402	62.000	Ea
0620	Sign, Type III, Rem	8100403	35.000	Ea
0625	Sign, Type IIIA	8100404	51.000	Sft
0630	Sign, Type IIIB	8100405	202.000	Sft
0635	Sign, Type V, Erect, Salv	8100422	1.000	Ea
0640	Sign, Type VB	8100425	27.000	Sft
0645	Reflective Panel for Permanent Sign Support, 6 foot	8100616	46.000	Ea
0650	Bracket, H	8100650	2.000	Ea
0655	Sign, Type II, Rem, Salv	8102002	3.000	Ea
0660	Sign, Type III, Rem, Salv	8102003	66.000	Ea
0665	Sign, Type V, Rem, Salv	8102005	1.000	Ea
0670	Ground Mtd Sign Support, Rem	8102010	96.000	Ea
0675	Pavt Mrkg, Polyurea, Yield	8110103	4.000	Ea
0680	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	180.000	Ft
0685	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	200.000	Ft
0690	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	158.000	Ft
0695	Pavt Mrkg, Waterborne, 6 inch, White	8110233	34,216.000	Ft
0700	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	31,588.000	Ft
0705	Pavt Mrkg, Waterborne, 12 inch, White	8110237	54.000	Ft
0710	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	34,216.000	Ft
0715	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	31,588.000	Ft
0720	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0725	Pavt Mrkg, Polyurea, Railroad Sym	8110411	3.000	Ea
0730	Recessing Pavt Mrkg, Longit	8110450	65,804.000	Ft
0735	Protective Ovly, Snowmobile Trail Crossing	8110550	110.000	Syd
0740	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0745	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0750	Pedestrian Type II Barricade, Temp	8120026	18.000	Ea
0755	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0760	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0765	Minor Traf Devices	8120170	1.000	LSUM
0770	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	1,170.000	Ft
0775	Plastic Drum, Fluorescent, Furn	8120252	270.000	Ea
0780	Plastic Drum, Fluorescent, Oper	8120253	270.000	Ea
0785	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	60.000	Ft

0790	PTS, Temp, Furn	8120272	2.000	Ea
0795	PTS, Temp, Oper	8120273	2.000	Ea
0800	Sign Cover	8120310	10.000	Ea
0805	Sign, Type B, Temp, Prismatic, Furn	8120350	2,192.000	Sft
0810	Sign, Type B, Temp, Prismatic, Oper	8120351	2,192.000	Sft
0815	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0820	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft
0825	Traf Regulator Control	8120370	1.000	LSUM
0830	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	325.000	Ft
0835	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	10,800.000	Ft
0840	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	1,705.000	Ft
0845	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	1,705.000	Ft
0850	Rumble Strip, Temp, Portable, Furn	8122188	48.000	Ea
0855	Riprap, Plain	8130010	1,536.000	Syd
0860	Site Preparation, Max \$10,000.00	8150001	1.000	LSUM
0865	Watering and Cultivating, First Season, Min \$5,000.00	8150002	1.000	LSUM
0870	Watering and Cultivating, 2nd Season, Min \$6,500.00	8150003	1.000	LSUM
0875	Amelanchier canadensis, tree form, 1 3/4 inch	8150319	11.000	Ea
0880	_ Steel Landscape Edging, 4 inch	8157001	110.000	Ft
0885	_ Decorative Stone, (Michigan Stone, crushed)	8157021	12.000	Cyd
0890	_ Panicum virgatum 'Totem Pole', #1 cont. - \$Ea	8157050	9.000	Ea
0895	_ Picea pungens 'Fat Albert', 6 foot - \$Ea	8157050	3.000	Ea
0900	_ Pinus mugo 'Pumilio', #2 cont. - \$Ea	8157050	14.000	Ea
0905	Slope Restoration, Non-Freeway, Type A	8162001	250.000	Syd
0910	Slope Restoration, Non-Freeway, Type B	8162002	45,253.000	Syd
0915	Slope Restoration, Non-Freeway, Type C	8162003	8,900.000	Syd
0920	Slope Restoration, Non-Freeway, Type D	8162004	1,150.000	Syd
0925	Conduit, Schedule 80, 2 inch	8182146	1,525.000	Ft
0930	DB Cable, in Conduit, 600V, 1/C#1/0	8182181	4,000.000	Ft
0935	DB Cable, in Conduit, 600V, 1/C#8	8182188	1,250.000	Ft
0940	Cable Pole, Sec, Disman	8182206	1.000	Ea
0945	Cable, Equipment Grounding Wire, 1/C#8	8182292	625.000	Ft
0950	Cable, Equipment Grounding Wire, 1/C#10	8182293	1,525.000	Ft
0955	Hh, Round	8182310	16.000	Ea
0960	Metered Serv	8182338	1.000	Ea
0965	Metered Serv, Rem	8182339	1.000	Ea
0970	Wood Pole, Cl 4, 40 foot	8182351	2.000	Ea
0975	Wood Pole, Rem	8182363	3.000	Ea
0980	Serv Disconnect	8182366	1.000	Ea
0985	Serv Disconnect, Rem	8182367	1.000	Ea
0990	Light Std Arm, 10 foot	8190267	13.000	Ea
0995	Light Std Fdn	8190279	12.000	Ea

1000	Light Std, Frangible Transformer Base	8190281	12.000	Ea
1005	Light Std Shaft, 30 foot or less	8190285	12.000	Ea
1010	_ Ltg Control Panel	8197050	1.000	Ea
1015	_ Luminaire, Round-a-bout	8197050	13.000	Ea
1020	_ Wire Grip Rodent Barrier	8197050	12.000	Ea
1025	Case Sign, Rem	8200020	1.000	Ea
1030	Case Sign (LED), Four Way, 24 inch by 30 inch	8200023	1.000	Ea
1035	Controller and Cabinet, Rem	8200030	1.000	Ea
1040	Flsh Beacon, Controller and Cabinet, Solid State	8200070	1.000	Ea
1045	Span Wire	8200140	1.000	Ea
1050	Span Wire, Rem	8200141	1.000	Ea
1055	TS, Span Wire Mtd, Rem	8200182	2.000	Ea
1060	TS, Four Way Span Wire Mtd, One Sect (LED), Long Life	8202284	2.000	Ea
1065	Monument Box	8210001	15.000	Ea
1070	Monument Box, Adj	8210005	1.000	Ea
1075	Monument Preservation	8210010	40.000	Ea
1080	Protect Corners	8210020	34.000	Ea
1085	Centerline Corrugations, Milled, HMA	8220013	16,791.000	Ft
1090	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	33,582.000	Ft
1095	Gate Box, Adj, Case 2	8230432	2.000	Ea
1100	_ Insulation Board, 2 inch	8237010	2,976.000	Sft
1105	Contractor Staking	8240001	1.000	LSUM
1110	Staking Plan Errors and Extras, Max \$180/hour	8240002	68.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 004

Letting Date: November 7, 2025

Contract ID: 77031-208692

Description: 2.18 mi of concrete patches, joint sealing and concrete sidewalk ramp upgrades on I-94BL from Range Road to M-29 in the city of Marysville, St Clair County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
208692A	25A1032	N/A	NH 77031

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$182,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	732.000	Ft
0015	Sidewalk, Rem	2040055	121.000	Syd
0020	Subgrade Undercutting, Type II	2050041	10.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	50.000	Ea
0030	Aggregate Base, 6 inch	3020016	206.000	Syd
0035	Dr Structure Cover, Adj, Case 1, Modified	4030004	10.000	Ea
0040	Dr Structure Cover, Type B	4030010	10.000	Ea
0045	Dr Structure Cover, Type K	4030050	10.000	Ea
0050	HMA Surface, Rem	5010005	78.000	Syd
0055	Joint, Contraction, Cp	6020200	5,340.000	Ft
0060	Joint, Expansion, E2	6020207	100.000	Ft
0065	Joint, Contraction, Crg	6030020	9,820.000	Ft
0070	Joint, Expansion, Erg	6030021	100.000	Ft
0075	Lane Tie, Epoxy Anchored	6030030	3,400.000	Ea
0080	Pavt Repr, Nonreinf Conc, 10 inch	6030048	10,320.000	Syd
0085	Pavt Repr, Rem	6030080	10,320.000	Syd
0090	Saw Cut, Intermediate	6030090	5,240.000	Ft
0095	Resealing Trans Joints with Hot-Poured Rubber	6030100	16,820.000	Ft
0100	Resealing Longit Joints with Hot-Poured Rubber	6030101	68,940.000	Ft
0105	_ Conc Repr, Non-Cementitious, Partial Depth	6037011	50.000	Syd
0110	Curb and Gutter, Conc, Det F5	8020039	653.000	Ft
0115	Detectable Warning Surface	8030010	79.000	Ft
0120	Curb Ramp Opening, Conc	8030030	79.000	Ft
0125	Curb Ramp, Conc, 6 inch	8032002	1,506.000	Sft
0130	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	1,000.000	Ft
0135	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	9.000	Ea

0140	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	17.000	Ea
0145	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	2.000	Ea
0150	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	8.000	Ea
0155	Pavt Mrkg, Ovly Cold Plastic, School	8110074	8.000	Ea
0160	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	2,470.000	Ft
0165	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	644.000	Ft
0170	Pavt Mrkg, Waterborne, 6 inch, White	8110233	4,000.000	Ft
0175	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	28,800.000	Ft
0180	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	4,000.000	Ft
0185	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	28,800.000	Ft
0190	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0195	Recessing Pavt Mrkg, Longit	8110450	2,478.000	Ft
0200	Recessing Pavt Mrkg, Transv	8110451	3,321.000	Sft
0205	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	30.000	Ea
0210	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	30.000	Ea
0215	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0220	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	400.000	Ea
0225	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	400.000	Ea
0230	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0235	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0240	Minor Traf Devices	8120170	1.000	LSUM
0245	Sign Cover	8120310	10.000	Ea
0250	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0255	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0260	Sign, Type B, Temp, Prismatic, Furn	8120350	685.000	Sft
0265	Sign, Type B, Temp, Prismatic, Oper	8120351	685.000	Sft
0270	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	3,200.000	Ft
0275	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	3,200.000	Ft
0280	Slope Restoration, Non-Freeway, Type A	8162001	200.000	Syd
0285	TS Head, Adj	8200452	27.000	Ea
0290	TS Face, Bag	8200458	30.000	Ea
0295	TS Face, Bag, Rem	8200459	23.000	Ea
0300	Monument Box	8210001	2.000	Ea
0305	Monument Preservation	8210010	2.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 005

Letting Date: November 7, 2025

Contract ID: 17072-220528

Description: Bridge reconstruction including removal and replacement and approach work on M-129 over Fletcher Creek, Chippewa County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220528A	24A0441	N/A	BFP 17072

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$182,700.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.050	Acre
0015	Culv, End, Rem, Less than 24 inch	2030005	2.000	Ea
0020	Curb and Gutter, Rem	2040020	132.000	Ft
0025	Guardrail, Rem	2040035	1,085.000	Ft
0030	Excavation, Earth	2050016	800.000	Cyd
0035	_ Embankment, CIP, Spec	2057021	1,328.000	Cyd
0040	Erosion Control, Silt Fence	2080036	800.000	Ft
0045	Subbase, CIP	3010002	800.000	Cyd
0050	Approach, CI I, 6 inch	3070008	1,200.000	Syd
0055	Shld, CI II	3070121	50.000	Ton
0060	HMA Surface, Rem	5010005	978.000	Syd
0065	Longit Joint Density Quality Initiative	5010018	2,160.000	Dlr
0070	HMA Approach	5010061	400.000	Ton
0075	Guardrail Approach Terminal, Type 2M	8070044	3.000	Ea
0080	Guardrail Departing Terminal, Type B	8070050	1.000	Ea
0085	Guardrail Post, Culv	8070070	8.000	Ea
0090	Guardrail Reflector	8070080	36.000	Ea
0095	Guardrail, Curved, Type B-CRT	8072154	13.000	Ft
0100	Guardrail, Type MGS-8, 108 inch Post	8072180	723.000	Ft
0105	Delineator Reflector, Green	8100133	4.000	Ea
0110	Fdn, Wood Support, Rem	8100280	1.000	Ea
0115	Post, Rigid, Delineator	8100361	4.000	Ea
0120	Post, Steel, 3 pound	8100371	30.000	Ft
0125	Sign, Type II, Rem	8100397	4.000	Ea
0130	Sign, Type III, Rem	8100403	2.000	Ea
0135	Sign, Type IIIA	8100404	8.000	Sft
0140	Ground Mtd Sign Support, Rem	8102010	5.000	Ea

0145	Pavt Mrkg, Waterborne, 6 inch, White	8110233	480.000	Ft
0150	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	60.000	Ft
0155	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	480.000	Ft
0160	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	60.000	Ft
0165	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0170	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0175	Minor Traf Devices	8120170	1.000	LSUM
0180	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0185	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0190	Sign Cover	8120310	20.000	Ea
0195	Sign, Type A, Temp, Prismatic, Furn	8120340	32.000	Sft
0200	Sign, Type A, Temp, Prismatic, Oper	8120341	32.000	Sft
0205	Sign, Type B, Temp, Prismatic, Furn	8120350	628.000	Sft
0210	Sign, Type B, Temp, Prismatic, Oper	8120351	628.000	Sft
0215	Slope Restoration, Non-Freeway, Type B	8162002	400.000	Syd
0220	Slope Restoration, Non-Freeway, Type C	8162003	600.000	Syd
0225	Contractor Staking	8240001	1.000	LSUM
0230	Staking Plan Errors and Extras, Max \$180/hour	8240002	18.000	Hr

Section: 2

0235	Asbestos Materials, Rem and Disposal	2040001	20,000.000	Dir
0240	Structures, Rem (B01 of 17072)	2040060	1.000	LSUM
0245	Backfill, Structure, CIP	2060002	513.000	Cyd
0250	Aggregate	2060005	60.000	Cyd
0255	Excavation, Fdn	2060010	2,414.000	Cyd
0260	Erosion Control, Check Dam, Stone	2080012	20.000	Ft
0265	Erosion Control, Filter Bag	2080014	4.000	Ea
0270	Erosion Control, Gravel Filter Berm	2080018	180.000	Ft
0275	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0280	Erosion Control, Sand Bag	2080028	700.000	Ea
0285	Erosion Control, Sediment Basin	2080032	5.000	Cyd
0290	Erosion Control, Sediment Trap	2080034	1.000	Ea
0295	Geotextile, Separator, Non-Woven	3082000	1,742.000	Syd
0300	Road Grade Biaxial Geogrid	3082002	2,247.000	Syd
0305	Underdrain, Fdn, 4 inch	4040031	70.000	Ft
0310	Underdrain, Fdn, 6 inch	4040033	94.000	Ft
0315	Underdrain Outlet, 6 inch	4040093	96.000	Ft
0320	Underdrain, Outlet Ending, 6 inch	4040113	4.000	Ea
0325	Video Inspection of Underdrain	4040200	262.000	Ft
0330	Culv Bedding, Box Culv	4060005	273.000	Cyd
0335	_ Culv, Precast Conc Box, 24 foot by 9 foot	4067001	52.000	Ft
0340	_ Steel Sheet Piling, Temp, Spec	7047010	490.000	Sft
0345	_ Cofferdam, Left in Place, Spec (C06 of 17072)	7047051	1.000	LSUM

0350	False Decking	7060060	802.000	Sft
0355	Liner, PVC, 30 mil	7060209	807.000	Syd
0360	Joint Waterproofing	7100001	234.000	Sft
0365	Conc Barrier, Temp, Furn	8120081	154.000	Ft
0370	Conc Barrier, Temp, Oper	8120082	154.000	Ft
0375	_ Riprap, Spec, CI II	8137031	320.000	Ton



Schedule of Pay Items

Report v1

Letting Call: 251107 006

Letting Date: November 7, 2025

Contract ID: 14011-221627

Description: 4.90 mi of hot mix asphalt shoulder widening, curve warning signs, center rumble strips and guardrail upgrades on M-51 from White Street to Crystal Springs Street, Cass County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221627A	25A1026	N/A	CRL 14011
222348A	25A1027	N/A	VRU 14011

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$278,700.00	1100001	1.000	LSUM
0010	Pavt, Rem	2040050	319.000	Syd
0015	Berm Grading	2050008	46.000	Sta
0020	Embankment, LM	2050011	702.000	Cyd
0025	Excavation, Earth	2050016	993.000	Cyd
0030	Erosion Control, Silt Fence	2080036	925.000	Ft
0035	Aggregate Base, 6 inch	3020016	50,469.000	Syd
0040	Maintenance Gravel, LM	3060021	100.000	Cyd
0045	Approach, CI I, 6 inch	3070008	1,902.000	Syd
0050	Approach, CI II, 6 inch	3070028	100.000	Syd
0055	Shld, CI II, 6 inch	3070128	10,082.000	Syd
0060	_ Trenching, Spec	3077002	456.000	Sta
0065	HMA Surface, Rem	5010005	100.000	Syd
0070	HMA Quality Initiative	5010007	31,620.000	Dlr
0075	Pavt for Butt Joints, Rem	5010008	776.000	Syd
0080	HMA Approach	5010061	694.000	Ton
0085	HMA, 3EL	5012012	9,619.000	Ton
0090	HMA, 4EL	5012024	5,497.000	Ton
0095	Seal, Fog	5050015	433.000	Syd
0100	Post, Mailbox	8070095	113.000	Ea
0105	Guardrail, Reconst, Type B	8070105	388.000	Ft
0110	Delineator Reflector, Green	8100133	6.000	Ea
0115	Fdn, Wood Support, Rem	8100280	6.000	Ea
0120	Post, Rigid, Delineator	8100361	6.000	Ea
0125	Post, Steel, 3 pound	8100371	1,302.000	Ft
0130	Post, Wood, 4 inch by 6 inch	8100380	96.000	Ft
0135	Sign, Type II, Erect, Salv	8100396	3.000	Ea

0140	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0145	Sign, Type III, Rem	8100403	9.000	Ea
0150	Sign, Type IIIB	8100405	300.000	Sft
0155	Sign, Type V, Rem	8100421	1.000	Ea
0160	Sign, Type VB	8100425	80.000	Sft
0165	Post, Flexible, Delineator, Ground Mtd	8100555	74.000	Ea
0170	Reflective Panel for Permanent Sign Support, 6 foot	8100616	82.000	Ea
0175	Sign, Type II, Rem, Salv	8102002	3.000	Ea
0180	Sign, Type III, Rem, Salv	8102003	1.000	Ea
0185	Ground Mtd Sign Support, Rem	8102010	28.000	Ea
0190	Pavt Mrkg, Waterborne, 6 inch, White	8110233	50,989.000	Ft
0195	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	26,399.000	Ft
0200	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	50,989.000	Ft
0205	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	26,399.000	Ft
0210	Witness, Log, \$1,250.00 \$1,250.00	8110351	1,250.000	Dlr
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	24.000	Ea
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	24.000	Ea
0225	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	540.000	Ea
0230	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	540.000	Ea
0235	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0240	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0245	Minor Traf Devices	8120170	1.000	LSUM
0250	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	1,000.000	Ft
0255	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	200.000	Ft
0260	Sign Cover	8120310	9.000	Ea
0265	Sign, Type B, Temp, Prismatic, Furn	8120350	636.000	Sft
0270	Sign, Type B, Temp, Prismatic, Oper	8120351	636.000	Sft
0275	Traf Regulator Control	8120370	1.000	LSUM
0280	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0285	Slope Restoration, Non-Freeway, Type F	8162006	10,095.000	Syd
0290	Centerline Corrugations, Milled, HMA	8220013	1,948.000	Ft
0295	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	36,104.000	Ft
0300	Contractor Staking	8240001	1.000	LSUM
0305	Staking Plan Errors and Extras, Max \$180/hour	8240002	34.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 007

Letting Date: November 7, 2025

Contract ID: 78061-221564

Description: 4.99 mi of hot mix asphalt overlay, shoulder widening, crack seal treatment, chip seal, guardrail upgrades, edgeline corrugations and pavement markings on M-86 from Shimmel Road easterly to M-66, St. Joseph County. This project includes a 3 year materials and workmanship warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221564A	25A1029	N/A	CRL 78061
223436A	25A1028	N/A	ST 78061

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$436,200.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	1,084.000	Ft
0015	Pavt, Rem	2040050	172.000	Syd
0020	Embankment, CIP	2050010	1,162.000	Cyd
0025	Excavation, Earth	2050016	13,259.000	Cyd
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	250.000	Cyd
0035	_ Subgrade Undercutting, Modified	2057021	100.000	Cyd
0040	Erosion Control, Silt Fence	2080036	7,498.000	Ft
0045	Subbase, CIP	3010002	6,165.000	Cyd
0050	Aggregate Base, 6 inch	3020016	44,589.000	Syd
0055	Maintenance Gravel	3060020	50.000	Ton
0060	Approach, CI II	3070021	189.000	Ton
0065	Shld, CI II, 6 inch	3070128	9,421.000	Syd
0070	_ Shld, CI II, 2 inch	3077011	906.000	Syd
0075	Cold Milling HMA Surface	5010002	67.000	Syd
0080	Bump Grinding	5010004	200.000	Syd
0085	HMA Surface, Rem	5010005	14,732.000	Syd
0090	HMA Quality Initiative	5010007	46,278.000	Dlr
0095	Pavt for Butt Joints, Rem	5010008	3,244.000	Syd
0100	Longit Joint Density Quality Initiative	5010018	78,110.000	Dlr
0105	HMA Approach	5010061	1,268.000	Ton
0110	HMA, 4EML	5012025	21,871.000	Ton
0115	Overband Crack Fill, Lane	5020003	9.860	Lnmi
0120	_ Asphalt Repr Mastic	5027001	1,000.000	Ft
0125	Seal, Single Chip	5050001	69,819.000	Syd
0130	Seal, Shld Chip	5050010	3,816.000	Syd

0135	Driveway, Nonreinf Conc, 6 inch	8010005	299.000	Syd
0140	Guardrail Anch, Bridge, Det T1	8070022	4.000	Ea
0145	Guardrail Approach Terminal, Type 2M	8070044	6.000	Ea
0150	Guardrail Reflector	8070080	72.000	Ea
0155	Post, Mailbox	8070095	77.000	Ea
0160	Guardrail, Type MGS-8, 108 inch Post	8072180	1,328.000	Ft
0165	Delineator Reflector, Green	8100133	11.000	Ea
0170	Delineator Reflector, White	8100134	3.000	Ea
0175	Delineator, Rem	8100349	10.000	Ea
0180	Post, Rigid, Delineator	8100361	14.000	Ea
0185	Post, Steel, 3 pound	8100371	96.000	Ft
0190	Sign, Type III, Erect, Salv	8100402	6.000	Ea
0195	Sign, Type III, Rem, Salv	8102003	6.000	Ea
0200	Ground Mtd Sign Support, Rem	8102010	6.000	Ea
0205	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	120.000	Ft
0210	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	64.000	Ft
0215	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0220	Pavt Mrkg, Ovly Cold Plastic, School	8110074	4.000	Ea
0225	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	2.000	Ea
0230	Pavt Mrkg, Waterborne, 6 inch, White	8110233	51,160.000	Ft
0235	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	12,614.000	Ft
0240	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	51,160.000	Ft
0245	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	12,614.000	Ft
0250	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0255	Recessing Pavt Mrkg, Transv	8110451	184.000	Sft
0260	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0265	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0270	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	550.000	Ea
0275	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	550.000	Ea
0280	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0285	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0290	Minor Traf Devices	8120170	1.000	LSUM
0295	Sign Cover	8120310	10.000	Ea
0300	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0305	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0310	Sign, Type B, Temp, Prismatic, Furn	8120350	544.000	Sft
0315	Sign, Type B, Temp, Prismatic, Oper	8120351	544.000	Sft
0320	Traf Regulator Control	8120370	1.000	LSUM
0325	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	10,000.000	Ft
0330	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	6,000.000	Ft

0335	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	6,000.000	Ft
0340	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0345	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0350	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0355	Slope Restoration, Non-Freeway, Type F	8162006	19,014.000	Syd
0360	Monument Box, Adj	8210005	9.000	Ea
0365	Protect Corners	8210020	10.000	Ea
0370	Centerline Corrugations, Milled, HMA	8220013	24,543.000	Ft
0375	Contractor Staking	8240001	1.000	LSUM
0380	Staking Plan Errors and Extras, Max \$180/hour	8240002	48.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 008

Letting Date: November 7, 2025

Contract ID: 25084-215603

Description: 1.47 mi of construction of noise barrier wall, concrete barrier and guardrail work along westbound I-69, ramp from westbound I-69 to northbound I-475, and ramp from northbound I-475 to eastbound I-69 in the city of Flint, Genesee County. This project includes a 2 year concrete surface coating warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215603A	N/A	N/A	M 25084

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$1,303,600.00	1100001	1.000	LSUM
0010	Clearing	2010001	1.460	Acre
0015	Tree, Rem, 19 inch to 36 inch	2020002	6.000	Ea
0020	Tree, Rem, 6 inch to 18 inch	2020004	43.000	Ea
0025	_ Tree Trimming	2027050	29.000	Ea
0030	Conc Barrier, Rem	2040010	8.000	Ft
0035	Curb and Gutter, Rem	2040020	100.000	Ft
0040	Guardrail, Rem	2040035	3,873.000	Ft
0045	Exploratory Investigation, Vertical	2040080	100.000	Ft
0050	Embankment, CIP	2050010	1,440.000	Cyd
0055	Excavation, Earth	2050016	2,392.000	Cyd
0060	Backfill, Structure, CIP	2060002	256.000	Cyd
0065	Excavation, Fdn	2060010	42.000	Cyd
0070	_ PVC Liner for Expanded Polystyrene Block	2067011	15.000	Syd
0075	_ Fill, Lightweight, Expanded Polystyrene Block	2067021	5.000	Cyd
0080	Erosion Control, Gravel Access Approach	2080016	1.000	Ea
0085	Erosion Control, Inlet Protection, Fabric Drop	2080020	41.000	Ea
0090	Erosion Control, Silt Fence	2080036	3,912.000	Ft
0095	Project Cleanup	2090001	1.000	LSUM
0100	Aggregate Base, 9 inch	3020022	2,247.000	Syd
0105	Dr Marker Post	4011109	6.000	Ea
0110	Dr Structure, Adj, Add Depth	4030280	5.000	Ft
0115	Dr Structure, Tap, 6 inch	4030306	2.000	Ea
0120	Underdrain, Fdn, 6 inch	4040033	653.000	Ft
0125	Underdrain Outlet, 6 inch	4040093	60.000	Ft
0130	Underdrain, Outlet Ending, 6 inch	4040113	6.000	Ea
0135	Video Inspection of Underdrain	4040200	725.000	Ft

0140	Lane Tie, Epoxy Anchored	6030030	40.000	Ea
0145	Reinforcement, Steel, Epoxy Coated	7060092	518,167.000	Lb
0150	Substructure Conc, High Performance	7060101	18.000	Cyd
0155	Aesthetic Texturing	7062005	70.000	Syd
0160	_ Noise Barrier Wall, Precast Conc, Erect	7067010	113,233.000	Sft
0165	_ Noise Barrier Wall, Precast Conc, Furn	7067010	113,233.000	Sft
0170	Conc Surface Coating, Warranty (NW-000374)	7100009	1.000	LSUM
0175	Conc Surface Coating, Warranty (NW-000375)	7100009	1.000	LSUM
0180	Conc Surface Coating, Warranty (NW-000376)	7100009	1.000	LSUM
0185	Conc Surface Coating, Warranty (NW-000377)	7100009	1.000	LSUM
0190	Reflective Marker, Permanent Barrier	7110003	81.000	Ea
0195	Drilled Shaft Equipment, Furn (NW-000374)	7180010	1.000	LSUM
0200	Drilled Shaft Equipment, Furn (NW-000375)	7180010	1.000	LSUM
0205	Drilled Shaft Equipment, Furn (NW-000376)	7180010	1.000	LSUM
0210	Drilled Shaft Equipment, Furn (NW-000377)	7180010	1.000	LSUM
0215	Drilled Shaft, 36 inch	7180036	8,216.000	Ft
0220	Obstruction Rem	7180100	7,620.000	Dir
0225	Temp Casing-Left in Place	7180121	400.000	Ft
0230	Curb, Conc, Det G1	8020005	50.000	Ft
0235	Curb and Gutter, Conc, Det D1	8020030	50.000	Ft
0240	Conc Barrier, Single Face, Type A	8040001	132.000	Ft
0245	Conc Barrier, Single Face, Type C	8040003	316.000	Ft
0250	Glare Screen, Conc	8040015	300.000	Ft
0255	_ Conc Barrier, Crash Wall	8047001	4,043.000	Ft
0260	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0265	Guardrail Reflector	8070080	10.000	Ea
0270	Guardrail Anch, Bridge, Det M1	8070130	3.000	Ea
0275	Guardrail Anch, Bridge, Det M2	8070131	2.000	Ea
0280	Delineator Reflector, Green	8100133	1.000	Ea
0285	Delineator Reflector, White	8100134	21.000	Ea
0290	Delineator, Rem	8100349	59.000	Ea
0295	Post, Rigid, Delineator	8100361	22.000	Ea
0300	Post, Wood, 4 inch by 6 inch	8100380	76.000	Ft
0305	Sign, Type II, Erect, Salv	8100396	2.000	Ea
0310	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0315	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0320	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0325	Pedestrian Type II Barricade, Temp	8120026	4.000	Ea
0330	Conc Barrier Ending, Temp, Det 2, Furn	8120041	1.000	Ea
0335	Conc Barrier Ending, Temp, Det 2, Oper	8120042	1.000	Ea
0340	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	1.000	Ea
0345	Conc Barrier, Temp, Adj	8120080	1,000.000	Ft
0350	Conc Barrier, Temp, Furn	8120081	5,200.000	Ft

0355	Conc Barrier, Temp, Oper	8120082	5,200.000	Ft
0360	Conc Barrier, Temp, Relocated	8120083	1,000.000	Ft
0365	High Intensity Light, Type B, Furn	8120110	6.000	Ea
0370	High Intensity Light, Type B, Oper	8120111	6.000	Ea
0375	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0380	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0385	Minor Traf Devices	8120170	1.000	LSUM
0390	Mobile Attenuator	8120180	2.000	Ea
0395	Pavt Mrkg, Longit, Water Blasting, Greater than 6 inch Width, Rem	8120213	1,860.000	Ft
0400	Plastic Drum, Fluorescent, Furn	8120252	420.000	Ea
0405	Plastic Drum, Fluorescent, Oper	8120253	420.000	Ea
0410	Sign Cover	8120310	70.000	Ea
0415	Sign Cover, Type I	8120320	12.000	Ea
0420	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0425	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0430	Sign, Type A, Temp, Prismatic, Furn	8120340	755.000	Sft
0435	Sign, Type A, Temp, Prismatic, Oper	8120341	755.000	Sft
0440	Sign, Type B, Temp, Prismatic, Furn	8120350	1,256.000	Sft
0445	Sign, Type B, Temp, Prismatic, Oper	8120351	1,256.000	Sft
0450	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	287.000	Sft
0455	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	287.000	Sft
0460	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	7,870.000	Ft
0465	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	1,680.000	Ft
0470	Pavt Mrkg, Wet Reflective, Type NR, Paint, 12 inch, White, Temp	8122016	1,860.000	Ft
0475	Speed Radar Trailer, Temp	8122028	1.000	Ea
0480	Riprap, Plain	8130010	16.000	Syd
0485	_ Turf Establishment, Performance	8167011	29,292.000	Syd
0490	Contractor Staking	8240001	1.000	LSUM
0495	Staking Plan Errors and Extras, Max \$180/hour	8240002	142.000	Hr



9/26/2025 7:28 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 251107 009

Letting Date: November 7, 2025

Contract ID: 14051-221812

Description: 35.90 mi of installation of edgeline corrugations and pavement markings on various routes, Branch, Calhoun, Cass, St. Joseph and Van Buren Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211812A	25A0999	N/A	HSIP 14051

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$50,800.00	1100001	1.000	LSUM
0010	Seal, Fog	5050015	84,249.000	Syd
0015	Pavt Mrkg, Waterborne, 6 inch, White	8110233	379,110.000	Ft
0020	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	160,200.000	Ft
0025	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	379,110.000	Ft
0030	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	160,200.000	Ft
0035	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0040	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0045	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Mobile Attenuator	8120180	1.000	Ea
0060	Sign, Type B, Temp, Prismatic, Furn	8120350	828.000	Sft
0065	Sign, Type B, Temp, Prismatic, Oper	8120351	828.000	Sft
0070	Traf Regulator Control	8120370	1.000	LSUM
0075	_ Sinusoidal Corrugations, Milled, HMA Edgeline	8227001	379,110.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 010

Letting Date: November 7, 2025

Contract ID: 67022-24892

Description: 1.40 mi of hot mix asphalt reconstruction, concrete sidewalk and ramps, water main work, drainage, traffic signal upgrades, signing, lighting, bridge cold milling and resurfacing and pavement markings on US-10 from west of 95th Avenue east to the Muskegon River in the city of Ewart, Osceola County. This project includes a 5 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
214892A	25A1025	N/A	NH 67022

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$1,213,300.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.010	Acre
0015	Tree, Rem, 6 inch to 18 inch	2020004	1.000	Ea
0020	Culv, Rem, Less than 24 inch	2030001	18.000	Ea
0025	Culv, End, Rem, Less than 24 inch	2030005	6.000	Ea
0030	Dr Structure, Rem	2030011	65.000	Ea
0035	Sewer, Rem, Less than 24 inch	2030015	4,708.000	Ft
0040	Sewer, Rem, 24 inch to 48 inch	2030016	599.000	Ft
0045	Curb and Gutter, Rem	2040020	14,208.000	Ft
0050	Fence, Rem	2040025	32.000	Ft
0055	Guardrail, Rem	2040035	691.000	Ft
0060	Masonry and Conc Structure, Rem	2040045	25.000	Cyd
0065	Pavt, Rem	2040050	5,403.000	Syd
0070	Sidewalk, Rem	2040055	5,399.000	Syd
0075	Exploratory Investigation, Vertical	2040080	300.000	Ft
0080	Embankment, CIP	2050010	1,751.000	Cyd
0085	Excavation, Earth	2050016	45,793.000	Cyd
0090	Non Haz Contaminated Material Handling and Disposal, LM	2050031	150.000	Cyd
0095	Subgrade Undercutting, Type II	2050041	1,000.000	Cyd
0100	Flowable Fill, Non-Structural	2050148	53.000	Cyd
0105	Erosion Control, Check Dam, Stone	2080012	60.000	Ft
0110	Erosion Control, Gravel Access Approach	2080016	4.000	Ea
0115	Erosion Control, Inlet Protection, Fabric Drop	2080020	113.000	Ea
0120	Erosion Control, Inlet Protection, Sediment Trap	2080024	55.000	Ea
0125	Erosion Control, Maintenance, Sediment Rem	2080026	25.000	Cyd
0130	Erosion Control, Sand Bag	2080028	100.000	Ea

0135	Erosion Control, Sediment Trap	2080034	4.000	Ea
0140	Erosion Control, Silt Fence	2080036	2,490.000	Ft
0145	Erosion Control, Turbidity Curtain, Shallow	2080044	40.000	Ft
0150	Subbase, CIP	3010002	22,419.000	Cyd
0155	Aggregate Base, 6 inch	3020016	58,322.000	Syd
0160	Maintenance Gravel	3060020	150.000	Ton
0165	Driveway Maintenance, Commercial	3062000	56.000	Ea
0170	Driveway Maintenance, Residential	3062001	5.000	Ea
0175	Intersection Maintenance	3062002	16.000	Ea
0180	Shld, CI II	3070121	269.000	Ton
0185	Culv End Sect, 12 inch	4010012	1.000	Ea
0190	Culv End Sect, 15 inch	4010015	18.000	Ea
0195	Culv End Sect, 18 inch	4010018	1.000	Ea
0200	Culv End Sect, Footing	4010072	19.000	Ea
0205	Culv, CI E, 24 inch	4010542	78.000	Ft
0210	Culv, CI F, 15 inch	4010608	473.000	Ft
0215	Culv, CI F, 24 inch	4010610	70.000	Ft
0220	Culv, Slp End Sect, 1 on 4, 24 inch, Transv	4010924	2.000	Ea
0225	Culv, Slp End Sect, 1 on 6, 24 inch, Longit	4010955	2.000	Ea
0230	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 24 inch by 38 inch, Transv	4011056	2.000	Ea
0235	Dr Marker Post	4011109	25.000	Ea
0240	Sewer, CI A, 12 inch, Tr Det B	4020033	1,684.000	Ft
0245	Sewer, CI A, 15 inch, Tr Det B	4020034	471.000	Ft
0250	Sewer, CI A, 18 inch, Tr Det B	4020035	163.000	Ft
0255	Sewer, CI A, 24 inch, Tr Det B	4020036	1,929.000	Ft
0260	Sewer, CI A, 30 inch, Tr Det B	4020037	292.000	Ft
0265	Sewer, CI E, 12 inch, Tr Det B	4020600	510.000	Ft
0270	Sewer, CI E, 15 inch, Tr Det B	4020601	146.000	Ft
0275	Sewer, CI E, 24 inch, Tr Det B	4020603	291.000	Ft
0280	Sewer Tap, 6 inch	4021201	5.000	Ea
0285	Sewer Tap, 15 inch	4021205	1.000	Ea
0290	Trench Undercut and Backfill	4021260	50.000	Cyd
0295	Sewer, Reinf Conc Ellip, HE CI IV, 24 inch by 38 inch, Tr Det B	4021453	779.000	Ft
0300	_ Slotted Drain, Galv, 12 Inch	4027001	24.000	Ft
0305	_ Sewer Pipe Coupling Device	4027050	8.000	Ea
0310	Dr Structure Cover, Adj, Case 1, Modified	4030004	32.000	Ea
0315	Dr Structure Cover, Adj, Case 1	4030005	10.000	Ea
0320	Dr Structure Cover, Adj, Case 2	4030006	9.000	Ea
0325	Dr Structure Cover, Type B	4030010	37.000	Ea
0330	Dr Structure Cover, Type D	4030025	3.000	Ea
0335	Dr Structure Cover, Type G	4030040	2.000	Ea
0340	Dr Structure Cover, Type K	4030050	73.000	Ea
0345	Dr Structure Cover, Type Q	4030065	32.000	Ea

0350	Dr Structure, 24 inch dia	4030200	47.000	Ea
0355	Dr Structure, 48 inch dia	4030210	20.000	Ea
0360	Dr Structure, 60 inch dia	4030220	25.000	Ea
0365	Dr Structure, 72 inch dia	4030230	1.000	Ea
0370	Dr Structure, 84 inch dia	4030231	1.000	Ea
0375	Dr Structure, Tap, 6 inch	4030306	37.000	Ea
0380	Dr Structure, Tap, 10 inch	4030310	2.000	Ea
0385	Dr Structure, Tap, 12 inch	4030312	12.000	Ea
0390	Dr Structure, Tap, 15 inch	4030315	3.000	Ea
0395	Underdrain, Subbase, 6 inch	4040063	9,623.000	Ft
0400	Underdrain, Subgrade, 6 inch	4040073	1,000.000	Ft
0405	Underdrain Outlet, 6 inch	4040093	292.000	Ft
0410	Underdrain, Outlet Ending, 6 inch	4040113	20.000	Ea
0415	Video Inspection of Underdrain	4040200	9,623.000	Ft
0420	_ Underdrain Outlet, 6 inch, Modified	4047001	300.000	Ft
0425	Cold Milling HMA Surface	5010002	458.000	Syd
0430	Bump Grinding	5010004	100.000	Syd
0435	HMA Surface, Rem	5010005	54,178.000	Syd
0440	HMA Quality Initiative	5010007	45,572.000	Dlr
0445	Longit Joint Density Quality Initiative	5010018	91,423.000	Dlr
0450	HMA Approach	5010061	1,233.000	Ton
0455	HMA Approach, High Stress	5010520	2,363.000	Ton
0460	HMA, 3EMH	5012014	8,895.000	Ton
0465	HMA, 4EMH	5012026	248.000	Ton
0470	HMA, 5EMH	5012038	101.000	Ton
0475	HMA, 4EMH, High Stress	5012074	9,946.000	Ton
0480	_ Vibration Monitoring	8007051	1.000	LSUM
0485	Driveway, Reinf Conc, 8 inch	8010003	122.000	Syd
0490	Driveway, Nonreinf Conc, 6 inch	8010005	54.000	Syd
0495	Driveway, Nonreinf Conc, 8 inch	8010007	878.000	Syd
0500	Curb, Conc, Det E2	8020002	275.000	Ft
0505	Curb and Gutter, Conc, Det B2	8020016	704.000	Ft
0510	Curb and Gutter, Conc, Det C2	8020021	628.000	Ft
0515	Curb and Gutter, Conc, Det C6	8020025	2,629.000	Ft
0520	Curb and Gutter, Conc, Det F6	8020040	6,231.000	Ft
0525	Driveway Opening, Conc, Det M	8020050	3,061.000	Ft
0530	Valley Gutter, Conc	8020060	69.000	Ft
0535	Curb and Gutter, Bridge Approach, Det 1	8022010	27.000	Ft
0540	Curb and Gutter, Bridge Approach, Det 2	8022011	22.000	Ft
0545	_ Curb and Gutter, Conc, Det B2, Modified	8027001	97.000	Ft
0550	_ Curb and Gutter, Conc, Det C2, Modified	8027001	34.000	Ft
0555	_ Valley Gutter, Conc, Modified	8027001	359.000	Ft
0560	Detectable Warning Surface	8030010	311.000	Ft
0565	Railing for Steps	8030020	14.000	Ft
0570	Curb Ramp Opening, Conc	8030030	959.000	Ft

0575	Sidewalk, Conc, 4 inch	8030044	51,161.000	Sft
0580	Sidewalk, Conc, 6 inch	8030046	1,071.000	Sft
0585	Sidewalk, Conc, 8 inch	8030048	12,534.000	Sft
0590	Steps, Conc	8030100	1.000	Cyd
0595	Curb Ramp, Conc, 6 inch	8032002	8,297.000	Sft
0600	Guardrail Anch, Bridge, Det T1	8070022	3.000	Ea
0605	Guardrail Anch, Bridge, Det T2	8070023	1.000	Ea
0610	Guardrail Anch, Bridge, Det T3	8070024	2.000	Ea
0615	Guardrail Anch, Bridge, Det T4	8070025	2.000	Ea
0620	Guardrail Approach Terminal, Type 2M	8070044	2.000	Ea
0625	Guardrail Departing Terminal, Type B	8070050	3.000	Ea
0630	Guardrail Departing Terminal, Type T	8070051	3.000	Ea
0635	Guardrail Reflector	8070080	46.000	Ea
0640	Post, Mailbox	8070095	12.000	Ea
0645	Guardrail, Curved, Type B-CRT	8072154	154.000	Ft
0650	Guardrail, Type B, 72 inch Post	8072171	13.000	Ft
0655	Guardrail, Type MGS-8, 72 inch Post	8072179	129.000	Ft
0660	Guardrail, Type MGS-8, 108 inch Post	8072180	179.000	Ft
0665	Fence, Chain Link, 48 inch	8080011	32.000	Ft
0670	Fence Post	8080130	3.000	Ea
0675	Delineator Reflector, Yellow	8100132	4.000	Ea
0680	Delineator Reflector, Green	8100133	33.000	Ea
0685	Fdn, Wood Support, Rem	8100280	4.000	Ea
0690	Delineator, Rem	8100349	10.000	Ea
0695	Post, Rigid, Delineator	8100361	8.000	Ea
0700	Post, Steel, 3 pound	8100371	906.000	Ft
0705	Post, Wood, 4 inch by 6 inch	8100380	75.000	Ft
0710	Sign, Type II, Rem	8100397	4.000	Ea
0715	Sign, Type IIA	8100398	39.000	Sft
0720	Sign, Type III, Rem	8100403	48.000	Ea
0725	Sign, Type IIIA	8100404	12.000	Sft
0730	Sign, Type IIIB	8100405	340.000	Sft
0735	Sign, Type V, Rem	8100421	1.000	Ea
0740	Sign, Type VA	8100424	12.000	Sft
0745	Post, Flexible, Delineator, Surface Mtd, 48 inch	8100552	4.000	Ea
0750	Ground Mtd Sign Support, Rem	8102010	58.000	Ea
0755	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	252.000	Ft
0760	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	3.000	Ea
0765	Pavt Mrkg, Ovly Cold Plastic, School	8110074	8.000	Ea
0770	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	475.000	Ft
0775	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	822.000	Ft
0780	Pavt Mrkg, Polyurea, 12 inch, White	8110111	524.000	Ft
0785	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	354.000	Ft
0790	Pavt Mrkg, Waterborne, 6 inch, White	8110233	7,332.000	Ft

0795	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	14,864.000	Ft
0800	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	7,332.000	Ft
0805	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	14,864.000	Ft
0810	Rem Spec Mrkg	8110343	933.000	Sft
0815	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	18.000	Ea
0820	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	4.000	Ea
0825	Recessing Pavt Mrkg, Longit	8110450	45,926.000	Ft
0830	Recessing Pavt Mrkg, Transv	8110451	2,618.000	Sft
0835	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	7,391.000	Ft
0840	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	17,967.000	Ft
0845	_ Pavt Mrkg, Polyurea, 6 inch, Yellow, Curb Painting	8117001	100.000	Ft
0850	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	60.000	Ea
0855	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	60.000	Ea
0860	Pedestrian Type II Barricade, Temp	8120026	22.000	Ea
0865	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0870	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0875	Minor Traf Devices	8120170	1.000	LSUM
0880	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	22,196.000	Ft
0885	Plastic Drum, Fluorescent, Furn	8120252	341.000	Ea
0890	Plastic Drum, Fluorescent, Oper	8120253	341.000	Ea
0895	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	72.000	Ft
0900	PTS, Temp, Furn	8120272	1.000	Ea
0905	PTS, Temp, Oper	8120273	1.000	Ea
0910	Sign Cover	8120310	10.000	Ea
0915	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0920	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0925	Sign, Type A, Temp, Prismatic, Furn	8120340	12.000	Sft
0930	Sign, Type A, Temp, Prismatic, Oper	8120341	12.000	Sft
0935	Sign, Type B, Temp, Prismatic, Furn	8120350	1,063.000	Sft
0940	Sign, Type B, Temp, Prismatic, Oper	8120351	1,063.000	Sft
0945	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	28.000	Sft
0950	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	28.000	Sft
0955	Traf Regulator Control	8120370	1.000	LSUM
0960	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	6,577.000	Ft
0965	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	5,668.000	Ft
0970	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	11,300.000	Ft
0975	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	22,599.000	Ft
0980	Pedestrian Path, Temp	8122250	300.000	Ft
0985	Pedestrian Ramp, Temp	8122251	5.000	Ea

0990	_ Residential Driveway Signal, Portable, Temp	8127050	7.000	Ea
0995	Riprap, Plain	8130010	219.000	Syd
1000	_ HMA Spillway	8147011	52.000	Syd
1005	Site Preparation, Max \$3,000.00	8150001	1.000	LSUM
1010	Watering and Cultivating, First Season, Min \$1,400.00	8150002	1.000	LSUM
1015	Watering and Cultivating, 2nd Season, Min \$1,800.00	8150003	1.000	LSUM
1020	Tilia cordata 'Greenspire', 1 1/2 inch	8153860	8.000	Ea
1025	Zelkova serrata, 1 1/2 inch	8154211	9.000	Ea
1030	_ Porous Pour-In-Place Tree Grate	8157010	68.000	Sft
1035	Slope Restoration, Non-Freeway, Type F	8162006	2,519.000	Syd
1040	_ Turf Establishment, Performance	8167011	18,886.000	Syd
1045	Conduit, Rem	8182000	7,045.000	Ft
1050	Conduit, Schedule 80, 3 inch	8182148	10,210.000	Ft
1055	DB Cable, in Conduit, 600V, 1/C#6	8182187	40,295.000	Ft
1060	DB Cable, in Conduit, 600V, 1/C#10	8182189	4,900.000	Ft
1065	Cable, Equipment Grounding Wire, 1/C#6	8182291	13,860.000	Ft
1070	Cable, Equipment Grounding Wire, 1/C#10	8182293	2,450.000	Ft
1075	Hh, Round	8182310	51.000	Ea
1080	Hh, Rem	8182330	76.000	Ea
1085	_ Cable, Rem and Salv	8187001	7,225.000	Ft
1090	Light Std Fdn	8190279	51.000	Ea
1095	Light Std Fdn, Rem	8190280	78.000	Ea
1100	Light Std, Frangible Transformer Base	8190281	51.000	Ea
1105	Light Std Shaft, 31 foot to 40 foot	8190286	51.000	Ea
1110	Light Std Shaft, Rem and Salv	8190306	78.000	Ea
1115	Luminaire, Rem and Salv	8190365	78.000	Ea
1120	_ Elec Service Panel	8197050	2.000	Ea
1125	_ Elec Service, Rem and Salv	8197050	8.000	Ea
1130	_ Ltg Control Panel	8197050	2.000	Ea
1135	_ Luminaire, Walkway	8197050	51.000	Ea
1140	_ Outdoor Outlet	8197050	51.000	Ea
1145	_ Wire Grip Rodent Barrier	8197050	51.000	Ea
1150	TS Head, Adj	8200452	8.000	Ea
1155	TS Face, Bag	8200458	13.000	Ea
1160	TS Face, Bag, Rem	8200459	13.000	Ea
1165	Monument Box	8210001	3.000	Ea
1170	Monument Box, Adj	8210005	2.000	Ea
1175	Monument Preservation	8210010	4.000	Ea
1180	Protect Corners	8210020	32.000	Ea
1185	Fire Hydrant	8230040	5.000	Ea
1190	Gate Valve and Box, 6 inch	8230051	5.000	Ea
1195	Gate Valve and Box, 8 inch	8230052	1.000	Ea
1200	Gate Valve and Box, 12 inch	8230054	8.000	Ea
1205	Hydrant, Rem	8230091	3.000	Ea
1210	Hydrant, Relocate, Case 1	8230095	8.000	Ea

1215	Water Main, 4 inch, Cut and Plug	8230130	1.000	Ea
1220	Water Main, 10 inch, Cut and Plug	8230133	4.000	Ea
1225	Water Main, 12 inch, Cut and Plug	8230134	2.000	Ea
1230	Water Main, DI, 6 inch, Tr Det G	8230151	114.000	Ft
1235	Water Main, DI, 8 inch, Tr Det G	8230156	19.000	Ft
1240	Water Main, DI, 12 inch, Tr Det G	8230166	2,203.000	Ft
1245	Water Serv, Long	8230245	22.000	Ea
1250	Water Serv, Conflict	8230250	4.000	Ea
1255	Gate Box, Adj, Case 2	8230432	25.000	Ea
1260	Water Main Conflict, 10 inch	8232025	2.000	Ea
1265	Water Main Conflict, 12 inch	8232026	6.000	Ea
1270	_ Gate Box, Adj, Case 1, Modified	8237050	21.000	Ea
1275	_ Gate Box, Rem	8237050	6.000	Ea
1280	_ Valve Box, Collar	8237050	7.000	Ea
1285	Contractor Staking	8240001	1.000	LSUM
1290	Staking Plan Errors and Extras, Max \$180/hour	8240002	128.000	Hr

Section: 2

1295	_ Spray Applied Waterproofing Membrane	7107011	960.000	Syd
1300	Embedded Galvanic Anode, High Performing	7120125	120.000	Ea
1305	_ Bridge Joints, Clean and Seal	7127001	218.000	Ft
1310	_ HMA Ovly and Waterproofing Membrane, Rem	7127011	960.000	Syd
1315	_ Rapid-Setting Polymer Conc	7127020	150.000	Cft



Schedule of Pay Items

Report v1

Letting Call: 251107 011

Letting Date: November 7, 2025

Contract ID: 82023-221451

Description: ITS devices modernization on various routes at 9 sites involving construction of ITS sites including full site modernization, power meter modernizations and ITS structures in the cities of Warren, Harper Woods, Dearborn, Detroit and Rochester Hills, Macomb, Wayne and Oakland Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221451A	25A1008	N/A	ST 82023

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$176,100.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.100	Acre
0015	Fence, Rem	2040025	300.000	Ft
0020	Masonry and Conc Structure, Rem	2040045	10.000	Cyd
0025	Exploratory Investigation, Vertical	2040080	60.000	Ft
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	60.000	Cyd
0035	Erosion Control, Silt Fence	2080036	2,400.000	Ft
0040	Project Cleanup	2090001	1.000	LSUM
0045	Obstruction Rem	7180100	1,500.000	Dlr
0050	_ Fiber Optic, Cable, Reinstall	8007001	270.000	Ft
0055	_ Fiber Optic, Cable, Rem	8007001	530.000	Ft
0060	_ Cabinet Equipment, Cabinet Monitoring System, Rem	8007050	7.000	Ea
0065	_ Cabinet Equipment, Power Distribution Unit, Rem	8007050	7.000	Ea
0070	_ Closed Circuit Television Camera, Rem	8007050	1.000	Ea
0075	_ Digital Video Encoder, Rem	8007050	6.000	Ea
0080	_ Dynamic Message Sign Controller, Install Salv	8007050	1.000	Ea
0085	_ Dynamic Message Sign Controller, Rem and Salv	8007050	1.000	Ea
0090	_ Fiber Optic, Hardware Assembly, Rem	8007050	8.000	Ea
0095	_ Power Distribution Unit	8007050	7.000	Ea
0100	_ Rack-Mtd Step-Up Transformer, 7.5kV AMP	8007050	2.000	Ea
0105	_ Radio, Install Salv, Unlicensed	8007050	1.000	Ea
0110	_ Radio, Realignment	8007050	2.000	Ea
0115	_ Radio, Rem and Salv, Unlicensed	8007050	1.000	Ea
0120	_ Roadside Unit, Rem and Salv	8007050	5.000	Ea
0125	_ Surveillance System, Remote Site, Type A, Rem	8007050	5.000	Ea
0130	_ Underground Splice Enclosure	8007050	2.000	Ea

0135	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
0140	_ System Testing	8007051	1.000	LSUM
0145	Fence, Woven Wire with Steel Post	8080002	200.000	Ft
0150	Fence, Chain Link, 48 inch	8080011	100.000	Ft
0155	Fence Gate, 6 foot, for 48 inch Chain Link Fence	8080031	1.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0165	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0170	Connected Arrow Board, Type C, Furn	8120155	3.000	Ea
0175	Connected Arrow Board, Type C, Oper	8120156	3.000	Ea
0180	Minor Traf Devices	8120170	1.000	LSUM
0185	Mobile Attenuator	8120180	3.000	Ea
0190	Plastic Drum, Fluorescent, Furn	8120252	160.000	Ea
0195	Plastic Drum, Fluorescent, Oper	8120253	160.000	Ea
0200	Sign Cover	8120310	10.000	Ea
0205	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0210	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	1,000.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	1,000.000	Sft
0225	_ Turf Establishment, Performance	8167011	1,610.000	Syd
0230	Power Company (Estimated Cost to Contractor)	8180001	600.000	Dlr
0235	Conduit, Rem	8182000	350.000	Ft
0240	Conduit, Directional Bore, 1, 3 inch	8182035	100.000	Ft
0245	Conduit, Directional Bore, 3, 3 inch	8182039	1,110.000	Ft
0250	Conduit, DB, 1, 3 inch	8182050	405.000	Ft
0255	Conduit, DB, 2, 3 inch	8182053	380.000	Ft
0260	Conduit, DB, 4, 3 inch	8182059	140.000	Ft
0265	DB Cable, in Conduit, 600V, 1/C#4	8182185	1,350.000	Ft
0270	DB Cable, in Conduit, 600V, 1/C#6	8182187	6,180.000	Ft
0275	DB Cable, in Conduit, 600V, 1/C#10	8182189	960.000	Ft
0280	DB Cable, in Conduit, Rem	8182197	1,930.000	Ft
0285	Cable, Equipment Grounding Wire, 1/C#4	8182290	450.000	Ft
0290	Cable, Equipment Grounding Wire, 1/C#6	8182291	350.000	Ft
0295	Cable, Equipment Grounding Wire, 1/C#10	8182293	130.000	Ft
0300	Hh, Round	8182310	1.000	Ea
0305	Hh, Round, 3 foot dia	8182319	2.000	Ea
0310	Serv Disconnect, Rem	8182367	4.000	Ea
0315	Wood Pole, Fit Up, Sec Cable Pole	8182381	1.000	Ea
0320	_ DB Cable, in Conduit, 600V, 1/C#6, Install Salv	8187001	95.000	Ft
0325	_ Hh Entry, Conc Plug	8187050	4.000	Ea
0330	_ Hh, Round, Elec	8187050	5.000	Ea
0335	Light Std Fdn	8190279	1.000	Ea
0340	Light Std Shaft, 30 foot or less	8190285	1.000	Ea

0345	_ Cable, Rem and Salv	8197001	100.000	Ft
0350	Fdn, Rem	8200065	7.000	Ea
0355	Steel Pole, Rem	8200145	3.000	Ea
0360	Cabinet, Rem	8200184	7.000	Ea
0365	Conc Pole, Rem	8200412	3.000	Ea
0370	Strain Pole, Steel, 6 bolt, Size 3	8200467	1.000	Ea
0375	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	13.000	Ft
0380	Casing, 48 inch	8200486	13.000	Ft
0385	Contractor Staking	8240001	1.000	LSUM
0390	Staking Plan Errors and Extras, Max \$180/hour	8240002	18.000	Hr
0395	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0400	Lightning Protection, Pole	8260021	8.000	Ea
0405	Hh, Clean	8260030	16.000	Ea
0410	Conduit, Clean and Test	8260031	800.000	Ft
0415	Microwave Vehicle Detection System	8260040	5.000	Ea
0420	Microwave Vehicle Detection System, Rem	8260043	3.000	Ea
0425	Fiber Optic, Cable, Single Mode Fiber, 12 Strand	8260047	1,200.000	Ft
0430	Fiber Optic, Hardware Assembly, Small	8260065	7.000	Ea
0435	Tracer Wire	8260070	1,450.000	Ft
0440	Fiber Optic, Pigtail	8260071	56.000	Ea
0445	Fiber Optic, Jumper	8260072	42.000	Ea
0450	Managed Field Ethernet Switch, Layer 2, Gigabit	8260081	7.000	Ea
0455	Managed Field Ethernet Switch, Rem	8260087	7.000	Ea
0460	Power Serv, Underground, 30AMP, 120/240V	8260100	2.000	Ea
0465	Safety Switch, Non-Fusible	8260108	3.000	Ea
0470	Safety Switch, Fusible	8260109	2.000	Ea
0475	Elec Rack	8260110	5.000	Ea
0480	Power Serv, Refurbish, 30AMP, 120/240V	8260111	1.000	Ea
0485	Power Serv, Refurbish, 60AMP, 120/240V	8260112	1.000	Ea
0490	ITS Cabinet, Ground Mtd	8260130	7.000	Ea
0495	Uninterruptible Power Supply, Rem	8260146	7.000	Ea
0500	Flowable Fill, Spun Pole Fdn	8260149	54.000	Cyd
0505	Spun Conc Pole, Type A	8260152	6.000	Ea
0510	Drilled Shaft and Conc Skirt, Cased	8260155	6.000	Ea
0515	Surveillance System, Remote Site, Type A	8260157	7.000	Ea
0520	System Integration and Testing	8260160	1.000	LSUM
0525	Camera Lowering Device	8260161	7.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 012

Letting Date: November 7, 2025

Contract ID: 20022-220326

Description: 123.73 mi of delineation removal and replacement on I-75 Business Loop, M-18, M-32, M-55, M-72, M-93, M-157 and Old 55 in the village of Roscommon and cities of Grayling and Gaylord, Charlevoix, Antrim, Otsego, Crawford and Roscommon Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220326A	25A1053	N/A	HSIP 20022

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$41,700.00	1100001	1.000	LSUM
0010	Delineator Reflector, Green	8100133	552.000	Ea
0015	Delineator Reflector, White	8100134	6,360.000	Ea
0020	Delineator, Reflective Sheeting, 3 inch by 12 inch, White	8100145	2,040.000	Ea
0025	Delineator, Rem	8100349	4,490.000	Ea
0030	Post, Rigid, Delineator	8100361	3,720.000	Ea
0035	_ Enhanced Delineation, Bidirectional, Guardrail, Channel Mtd	8107001	1,910.000	Ft
0040	_ Enhanced Delineation, Bidirectional, Guardrail, Post Mtd	8107001	33,370.000	Ft
0045	_ Post, Flexible, Delineator, Replaceable	8107050	1,050.000	Ea
0050	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0055	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Mobile Attenuator	8120180	2.000	Ea
0070	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0075	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0080	Sign Cover	8120310	6.000	Ea
0085	Sign, Type B, Temp, Prismatic, Furn	8120350	400.000	Sft
0090	Sign, Type B, Temp, Prismatic, Oper	8120351	400.000	Sft
0095	Contractor Staking	8240001	1.000	LSUM
0100	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 013

Letting Date: November 7, 2025

Contract ID: 03112-217333

Description: 0.33 mi of hot mix asphalt shoulder reconstruction, retaining wall, guardrail, signing and pavement markings on US-131 north of M-222, Allegan. County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217333A	25A1070	N/A	NH 03112

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$163,900.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.050	Acre
0015	Guardrail, Rem	2040035	936.000	Ft
0020	Subgrade Undercutting, Type II	2050041	300.000	Cyd
0025	Subgrade Undercutting, Type IV	2050043	25.000	Cyd
0030	_ Embankment, CIP, Spec	2057021	140.000	Cyd
0035	Backfill, Structure, CIP	2060002	252.000	Cyd
0040	Erosion Control, Check Dam, Stone	2080012	16.000	Ft
0045	Erosion Control, Gravel Access Approach	2080016	1.000	Ea
0050	Erosion Control, Maintenance, Sediment Rem	2080026	10.000	Cyd
0055	Erosion Control, Sand Bag	2080028	100.000	Ea
0060	Erosion Control, Sediment Trap	2080034	2.000	Ea
0065	Erosion Control, Silt Fence	2080036	3,137.000	Ft
0070	Erosion Control, Temp Plastic Sheet/Geotextile Cover	2080040	800.000	Syd
0075	_ Straw Wattle	2087001	530.000	Ft
0080	Aggregate Base, 6 inch	3020016	949.000	Syd
0085	Aggregate Base, Conditioning	3020050	554.000	Syd
0090	Shld, CI II, 6 inch	3070128	552.000	Syd
0095	Trenching	3070200	25.000	Sta
0100	Underdrain, Pipe, Open-Graded, 4 inch	4040041	560.000	Ft
0105	Underdrain, Subbase, 6 inch	4040063	300.000	Ft
0110	Underdrain Outlet, 6 inch	4040093	40.000	Ft
0115	Underdrain, Outlet Ending, 4 inch	4040111	1.000	Ea
0120	Underdrain, Outlet Ending, 6 inch	4040113	4.000	Ea
0125	Video Inspection of Underdrain	4040200	600.000	Ft
0130	Cold Milling HMA Surface	5010002	959.000	Syd
0135	HMA Surface, Rem	5010005	670.000	Syd
0140	HMA Quality Initiative	5010007	1,070.000	Dlr

0145	HMA, 5EML	5012037	535.000	Ton
0150	Steel Sheet Piling, Permanent	7040001	18,670.000	Sft
0155	Structural Steel, Mixed, Erect	7070050	1,282.000	Lb
0160	Structural Steel, Mixed, Furn and Fab	7070051	1,282.000	Lb
0165	Structural Steel, Plate, Erect	7070060	8,999.000	Lb
0170	Structural Steel, Plate, Furn and Fab	7070061	8,999.000	Lb
0175	Structural Steel, Rolled Shape, Erect	7070070	31,170.000	Lb
0180	Structural Steel, Rolled Shape, Furn and Fab	7070071	31,170.000	Lb
0185	_ Ground Anchor Test, Performance	8007050	3.000	Ea
0190	_ Ground Anchor Test, Proof	8007050	40.000	Ea
0195	_ Ground Anchor, Permanent	8007050	40.000	Ea
0200	_ Ground Anchor Equipment, Furn (Retaining Wall)	8007051	1.000	LSUM
0205	_ Temp Haul Road	8007051	1.000	LSUM
0210	Curb and Gutter, Conc, Det D2	8020031	593.000	Ft
0215	Shld Gutter, Conc, Det 2	8020056	1.000	Ea
0220	Spillway, Conc	8020075	4.000	Ft
0225	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0230	Guardrail Departing Terminal, Type MGS	8070052	1.000	Ea
0235	Guardrail Reflector	8070080	27.000	Ea
0240	Guardrail, Type MGS-8, 72 inch Post	8072179	1,275.000	Ft
0245	Delineator Reflector, Green	8100133	2.000	Ea
0250	Post, Rigid, Delineator	8100361	2.000	Ea
0255	Post, Wood, 4 inch by 6 inch	8100380	14.000	Ft
0260	Post, Wood, 6 inch by 8 inch	8100382	40.000	Ft
0265	Sign, Type IA	8100392	40.000	Sft
0270	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0275	Sign, Type IIIA	8100404	7.000	Sft
0280	Sign, Type III, Rem, Salv	8102003	1.000	Ea
0285	Pavt Mrkg, Waterborne, 6 inch, White	8110233	4,826.000	Ft
0290	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	4,812.000	Ft
0295	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	4,826.000	Ft
0300	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	4,812.000	Ft
0305	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0310	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	7.000	Ea
0315	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	7.000	Ea
0320	Conc Barrier Ending, Temp, Det 2, Adj	8120040	1.000	Ea
0325	Conc Barrier Ending, Temp, Det 2, Furn	8120041	1.000	Ea
0330	Conc Barrier Ending, Temp, Det 2, Oper	8120042	1.000	Ea
0335	Conc Barrier, Temp, Adj	8120080	750.000	Ft
0340	Conc Barrier, Temp, Furn	8120081	1,825.000	Ft
0345	Conc Barrier, Temp, Oper	8120082	1,825.000	Ft
0350	Conc Barrier, Temp, Relocated	8120083	350.000	Ft
0355	High Intensity Light, Type B, Furn	8120110	1.000	Ea

0360	High Intensity Light, Type B, Oper	8120111	1.000	Ea
0365	Connected Arrow Board, Type C, Furn	8120155	1.000	Ea
0370	Connected Arrow Board, Type C, Oper	8120156	1.000	Ea
0375	Minor Traf Devices	8120170	1.000	LSUM
0380	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	2,773.000	Ft
0385	Plastic Drum, Fluorescent, Furn	8120252	76.000	Ea
0390	Plastic Drum, Fluorescent, Oper	8120253	76.000	Ea
0395	Sign Cover	8120310	2.000	Ea
0400	Sign, Type B, Temp, Prismatic, Furn	8120350	440.000	Sft
0405	Sign, Type B, Temp, Prismatic, Oper	8120351	440.000	Sft
0410	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	2,232.000	Ft
0415	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	9,784.000	Ft
0420	Speed Radar Trailer, Temp	8122028	1.000	Ea
0425	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	648.000	Ft
0430	Riprap, Plain	8130010	8.000	Syd
0435	Water, Sodding/Seeding	8160090	3.000	Unit
0440	Slope Restoration, Freeway, Type E	8162017	1,300.000	Syd
0445	Freeway Shld Corrugations, Milled, HMA	8222001	2,328.000	Ft
0450	Contractor Staking	8240001	1.000	LSUM
0455	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 014

Letting Date: November 7, 2025

Contract ID: 11111-224747

Description: Bridge rehabilitation including substructure patching at abutment with temporary supports on Barney Road over US-131BR and I-196 under Schmuhl Road, Berrien and Kalamazoo Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224747A	N/A	N/A	M 11111

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$32,000.00	1100001	1.000	LSUM
0010	Erosion Control, Silt Fence	2080036	120.000	Ft
0015	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	24.000	Ea
0020	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	24.000	Ea
0025	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0030	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0035	Minor Traf Devices	8120170	1.000	LSUM
0040	Pavt Mrkg Cover, Type R, Black	8120200	2,000.000	Ft
0045	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	16,000.000	Ft
0050	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	16,000.000	Ft
0055	Plastic Drum, Fluorescent, Furn	8120252	360.000	Ea
0060	Plastic Drum, Fluorescent, Oper	8120253	360.000	Ea
0065	Sign Cover	8120310	40.000	Ea
0070	Sign, Type B, Temp, Prismatic, Furn	8120350	2,052.000	Sft
0075	Sign, Type B, Temp, Prismatic, Oper	8120351	2,052.000	Sft
0080	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	292.000	Sft
0085	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	292.000	Sft
0090	Slope Restoration, Freeway, Type C	8162015	254.000	Syd

Section: 2

0095	Backfill, Structure, CIP	2060002	95.000	Cyd
0100	Excavation, Fdn	2060010	95.000	Cyd
0105	Reinforcement, Steel, Epoxy Coated	7060092	548.000	Lb
0110	Hand Chipping, Other Than Deck	7120007	98.000	Cft
0115	Patch, Forming	7120017	146.000	Sft
0120	Adhesive Anchoring of Horizontal Bar, 3/4 inch	7120028	44.000	Ea

0125	Patching Conc, C-L	7120112	5.000	Cyd
0130	_ Embedded Galvanic Anode, High Performing	7127050	26.000	Ea
0135	Support, Column, Temp	7130080	4.000	Ea
0140	Slope Paving Header	8130015	38.000	Ft
0145	Slope Paving, Conc	8130020	60.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 015

Letting Date: November 7, 2025

Contract ID: 41025-221449

Description: ITS Modernization of 19 devices on I-96, I-196, US-131 and US-31, Kent and Muskegon Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221449A	25A1109	N/A	ST 41025

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$144,700.00	1100001	1.000	LSUM
0010	Exploratory Investigation, Vertical	2040080	120.000	Ft
0015	Non Haz Contaminated Material Handling and Disposal, LM	2050031	100.000	Cyd
0020	Erosion Control, Silt Fence	2080036	3,900.000	Ft
0025	_ Fiber Optic, Cable, Reinstall	8007001	335.000	Ft
0030	_ Fiber Optic, Cable, Rem	8007001	365.000	Ft
0035	_ Cabinet Equipment, Direct Current Power Supply, Rem	8007050	1.000	Ea
0040	_ Cabinet Equipment, Power Distribution Unit, Rem and Salv	8007050	5.000	Ea
0045	_ Cabinet Equipment, Rem and Salv, Cabinet Monitoring System	8007050	4.000	Ea
0050	_ Cellular Modem, Rem and Salv	8007050	1.000	Ea
0055	_ Closed Circuit Television Camera, Rem and Salv	8007050	1.000	Ea
0060	_ Digital Video Encoder, Rem and Salv	8007050	1.000	Ea
0065	_ Drilled Shaft and Conc Skirt, Into Rock, Cased	8007050	1.000	Ea
0070	_ Fiber Optic, Hardware Assembly, Rem	8007050	7.000	Ea
0075	_ ITS Cabinet, Backup Power System	8007050	3.000	Ea
0080	_ Managed Field Ethernet Switch, Layer 2, Modified	8007050	10.000	Ea
0085	_ Media Converter	8007050	1.000	Ea
0090	_ Power Distribution Unit	8007050	15.000	Ea
0095	_ Power Source, Solar, Rem	8007050	1.000	Ea
0100	_ Underground Splice Enclosure	8007050	2.000	Ea
0105	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
0110	_ System Testing	8007051	1.000	LSUM
0115	_ Obstruction Rem, Spun Conc Fdn, Into Rock	8007060	5,000.000	Dlr
0120	Fence, Protective	8080007	100.000	Ft
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	5.000	Ea

0130	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	5.000	Ea
0135	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0140	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0145	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0150	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0155	Minor Traf Devices	8120170	1.000	LSUM
0160	Mobile Attenuator	8120180	2.000	Ea
0165	Sign Cover	8120310	10.000	Ea
0170	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0175	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0180	Sign, Type B, Temp, Prismatic, Furn	8120350	1,200.000	Sft
0185	Sign, Type B, Temp, Prismatic, Oper	8120351	1,200.000	Sft
0190	Slope Restoration, Freeway, Type A	8162013	250.000	Syd
0195	Slope Restoration, Freeway, Type B	8162014	70.000	Syd
0200	Slope Restoration, Freeway, Type C	8162015	70.000	Syd
0205	Power Company (Estimated Cost to Contractor)	8180001	1,880.000	Dlr
0210	Conduit, Rem	8182000	650.000	Ft
0215	Conduit, DB, 1, 3 inch	8182050	1,135.000	Ft
0220	Conduit, DB, 2, 3 inch	8182053	395.000	Ft
0225	Conduit, DB, 4, 3 inch	8182059	10.000	Ft
0230	Conduit, DB, 1, 1 inch	8182060	15.000	Ft
0235	DB Cable, in Conduit, 600V, 1/C#4	8182185	9,210.000	Ft
0240	DB Cable, in Conduit, 600V, 1/C#6	8182187	2,250.000	Ft
0245	DB Cable, in Conduit, Rem	8182197	3,585.000	Ft
0250	Cable Pole, Sec, Disman	8182206	1.000	Ea
0255	Cable, Equipment Grounding Wire, 1/C#4	8182290	3,070.000	Ft
0260	Cable, Equipment Grounding Wire, 1/C#6	8182291	750.000	Ft
0265	Hh, Round, 3 foot dia	8182319	1.000	Ea
0270	Hh, Rem	8182330	1.000	Ea
0275	Wood Pole, Rem	8182363	11.000	Ea
0280	Serv Disconnect	8182366	1.000	Ea
0285	Serv Disconnect, Rem	8182367	5.000	Ea
0290	Wood Pole, Fit Up, Sec Cable Pole	8182381	1.000	Ea
0295	_ Cable, Install Salv	8187001	80.000	Ft
0300	_ Cable, Rem and Salv	8187001	105.000	Ft
0305	_ Hh, Round, Elec	8187050	9.000	Ea
0310	Light Std Fdn	8190279	10.000	Ea
0315	Light Std Fdn, Rem	8190280	2.000	Ea
0320	Light Std, Frangible Transformer Base	8190281	10.000	Ea
0325	Light Std Shaft, 31 foot to 40 foot	8190286	7.000	Ea
0330	Light Std Shaft, 41 foot to 50 foot	8190287	3.000	Ea
0335	Controller Fdn, Base Mtd	8200045	3.000	Ea
0340	Cabinet, Rem	8200184	8.000	Ea

0345	Strain Pole, Steel, 6 bolt, Size 3	8200467	1.000	Ea
0350	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	15.000	Ft
0355	Casing, 48 inch	8200486	10.000	Ft
0360	Contractor Staking	8240001	1.000	LSUM
0365	Staking Plan Errors and Extras, Max \$180/hour	8240002	16.000	Hr
0370	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0375	Lightning Protection, Pole	8260021	11.000	Ea
0380	Hh, Clean	8260030	31.000	Ea
0385	Conduit, Clean and Test	8260031	2,580.000	Ft
0390	Microwave Vehicle Detection System	8260040	16.000	Ea
0395	Microwave Vehicle Detection System, Rem and Salv	8260041	1.000	Ea
0400	Microwave Vehicle Detection System, Install Salv	8260042	1.000	Ea
0405	Microwave Vehicle Detection System, Rem	8260043	14.000	Ea
0410	Fiber Optic, Cable, Single Mode Fiber, 12 Strand	8260047	770.000	Ft
0415	Fiber Optic, Hardware Assembly, Small	8260065	10.000	Ea
0420	Fiber Optic, Marker, Above Ground	8260069	24.000	Ea
0425	Tracer Wire	8260070	110.000	Ft
0430	Fiber Optic, Pigtail	8260071	138.000	Ea
0435	Fiber Optic, Jumper	8260072	86.000	Ea
0440	Managed Field Ethernet Switch, Rem and Salv	8260084	7.000	Ea
0445	Power Serv, Underground, 30AMP, 120/240V	8260100	2.000	Ea
0450	Safety Switch, Non-Fusible	8260108	2.000	Ea
0455	Elec Rack	8260110	2.000	Ea
0460	Power Serv, Refurbish, 30AMP, 120/240V	8260111	1.000	Ea
0465	ITS Cabinet, Ground Mtd	8260130	1.000	Ea
0470	ITS Cabinet, Pole Mtd	8260134	9.000	Ea
0475	Cabinet Modification	8260138	3.000	Ea
0480	Uninterruptible Power Supply, Rem and Salv	8260143	3.000	Ea
0485	Uninterruptible Power Supply, Rem	8260146	1.000	Ea
0490	Flowable Fill, Spun Pole Fdn	8260149	2.000	Cyd
0495	Spun Conc Pole, Type A	8260152	1.000	Ea
0500	Surveillance System, Remote Site, Type A	8260157	2.000	Ea
0505	System Integration and Testing	8260160	1.000	LSUM



10/6/2025 7:21 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 251107 016

Letting Date: November 7, 2025

Contract ID: 40023-224988

Description: Installation of solar powered carpool lot lights at three locations, M-72 at Kalkaska Road, M-72 at Maple City Road and US-31 at First Street, Kalkaska, Antrim and Leelanau Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224988A	25A1013	N/A	ST 40023

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$15,800.00	1100001	1.000	LSUM
0010	Minor Traf Devices	8120170	1.000	LSUM
0015	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0020	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0025	Sign, Type B, Temp, Prismatic, Furn	8120350	112.000	Sft
0030	Sign, Type B, Temp, Prismatic, Oper	8120351	112.000	Sft
0035	Slope Restoration, Non-Freeway, Type A	8162001	24.000	Syd
0040	_ Light Std Fdn, Solar	8197050	18.000	Ea
0045	_ Park and Ride Solar Lighting System	8197050	18.000	Ea

**Schedule of Pay Items**

Report v1

Letting Call: 251107 017**Letting Date:** November 7, 2025**Contract ID:** 64015-224343**Description:** Bridge rehabilitation including pin and hanger replacement, joint replacement, steel diaphragm replacement and zone painting on US-31 over the south branch of the Pentwater River, Oceana County.**Project Information**

Project Number	Federal Project Number	Federal Item Number	Control Section
224343A	N/A	N/A	M 64015

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$116,000.00	1100001	1.000	LSUM
0010	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0015	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, White	8112130	5,160.000	Ft
0020	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, Yellow	8112133	1,960.000	Ft
0025	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	2.000	Ea
0030	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	2.000	Ea
0035	Conc Barrier Ending, Temp, Det 2, Adj	8120040	2.000	Ea
0040	Conc Barrier Ending, Temp, Det 2, Furn	8120041	2.000	Ea
0045	Conc Barrier Ending, Temp, Det 2, Oper	8120042	2.000	Ea
0050	Conc Barrier, Temp, Adj	8120080	803.000	Ft
0055	Conc Barrier, Temp, Furn	8120081	803.000	Ft
0060	Conc Barrier, Temp, Oper	8120082	803.000	Ft
0065	Delineator, Flexible, Temp, Furn	8120091	19.000	Ea
0070	Delineator, Flexible, Temp, Oper	8120092	19.000	Ea
0075	High Intensity Light, Type B, Furn	8120110	2.000	Ea
0080	High Intensity Light, Type B, Oper	8120111	2.000	Ea
0085	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0090	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0095	Minor Traf Devices	8120170	1.000	LSUM
0100	Mobile Attenuator	8120180	4.000	Ea
0105	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	7,120.000	Ft
0110	Plastic Drum, Fluorescent, Furn	8120252	165.000	Ea
0115	Plastic Drum, Fluorescent, Oper	8120253	165.000	Ea
0120	Sign Cover	8120310	1.000	Ea
0125	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea

0130	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0135	Sign, Type B, Temp, Prismatic, Furn	8120350	980.000	Sft
0140	Sign, Type B, Temp, Prismatic, Oper	8120351	980.000	Sft
0145	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	7,530.000	Ft
0150	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	9,330.000	Ft
0155	Speed Radar Trailer, Temp	8122028	2.000	Ea
0160	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	2,736.000	Ft
0165	_ Filling Shld Corrugations with Micro-Surface	8127001	1,250.000	Ft

Section: 2

0170	Expansion Joint Device	7060050	92.000	Ft
0175	False Decking	7060060	1,840.000	Sft
0180	Reinforcement, Steel, Epoxy Coated	7060092	4,424.000	Lb
0185	Conc, Grade 4500HP	7062004	31.000	Cyd
0190	Structural Steel, Mixed, Erect	7070050	11,420.000	Lb
0195	Structural Steel, Mixed, Furn and Fab	7070051	11,420.000	Lb
0200	Structures, Rehabilitation, Rem Portions (B01 of 64015)	7120070	1.000	LSUM
0205	Structures, Rehabilitation, Rem Portions (B02 of 64015)	7120070	1.000	LSUM
0210	Deck Joint, Rem	7120071	184.000	Ft
0215	Reinforcement, Mechanical Splice	7120084	48.000	Ea
0220	Embedded Galvanic Anode, High Performing	7120125	265.000	Ea
0225	Beam Plate, Seal Perimeter	7130010	780.000	Ft
0230	Hanger Assembly, Field Measurement	7130030	24.000	Ea
0235	Hanger Assembly, Rem and Erect	7130031	24.000	Ea
0240	Structural Steel, Furn and Fab, Pin and Hanger	7130070	4,500.000	Lb
0245	Support, Suspension, Temp	7130082	24.000	Ea
0250	Field Repr of Damaged Coating (B01 of 64015)	7160001	1.000	LSUM
0255	Field Repr of Damaged Coating (B02 of 64015)	7160001	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 018

Letting Date: November 7, 2025

Contract ID: 43011-224535

Description: 0.72 mi of install concrete sidewalk and ramps, signing and pavement markings on M-37 from Third Street northerly to Prospect Street in the village of Baldwin, Lake County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224535A	25A0675	N/A	VRU 43011

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$33,300.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	767.000	Ft
0015	Pavt, Rem	2040050	4.000	Syd
0020	Embankment, LM	2050011	81.000	Cyd
0025	Excavation, Earth	2050016	1,081.000	Cyd
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0035	Subgrade Undercutting, Type II	2050041	50.000	Cyd
0040	Subgrade Undercutting, Type IV	2050043	25.000	Cyd
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	20.000	Ea
0050	Erosion Control, Maintenance, Sediment Rem	2080026	15.000	Cyd
0055	Erosion Control, Sand Bag	2080028	20.000	Ea
0060	Erosion Control, Silt Fence	2080036	500.000	Ft
0065	Subbase, CIP	3010002	169.000	Cyd
0070	Aggregate Base, 6 inch	3020016	396.000	Syd
0075	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0080	HMA Surface, Rem	5010005	668.000	Syd
0085	Hand Patching	5010025	45.000	Ton
0090	Driveway, Nonreinf Conc, 6 inch	8010005	186.000	Syd
0095	Curb and Gutter, Conc, Det C6	8020025	326.000	Ft
0100	Driveway Opening, Conc, Det M	8020050	100.000	Ft
0105	Curb Ramp Opening, Conc	8030030	345.000	Ft
0110	Sidewalk, Conc, 6 inch	8030046	10,834.000	Sft
0115	Curb Ramp, Conc, 6 inch	8032002	3,290.000	Sft
0120	_ Detectable Warning Surface, Cast Iron, Spec	8037001	202.000	Ft
0125	Post, Steel, 3 pound	8100371	384.000	Ft
0130	Sign, Type IIIB	8100405	152.000	Sft
0135	Reflective Panel for Permanent Sign Support, 6 foot	8100616	56.000	Ea

0140	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, Yellow	8110109	85.000	Ft
0145	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	1,086.000	Ft
0150	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	3.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	3.000	Ea
0165	Pedestrian Type II Barricade, Temp	8120026	63.000	Ea
0170	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	60.000	Ea
0175	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	60.000	Ea
0180	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0185	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0190	Minor Traf Devices	8120170	1.000	LSUM
0195	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	1,260.000	Ft
0200	Plastic Drum, Fluorescent, Furn	8120252	6.000	Ea
0205	Plastic Drum, Fluorescent, Oper	8120253	6.000	Ea
0210	Sign Cover	8120310	10.000	Ea
0215	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0220	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0225	Sign, Type B, Temp, Prismatic, Furn	8120350	329.000	Sft
0230	Sign, Type B, Temp, Prismatic, Oper	8120351	329.000	Sft
0235	Pedestrian Path, Temp	8122250	45.000	Ft
0240	Slope Restoration, Non-Freeway, Type A	8162001	1,205.000	Syd
0245	Contractor Staking	8240001	1.000	LSUM
0250	Staking Plan Errors and Extras, Max \$180/hour	8240002	4.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 019

Letting Date: November 7, 2025

Contract ID: 82121-222091

Description: 0.10 mi of installing pedestrian crosswalk improvements including rectangular rapid flashing beacon crosswalk, concrete sidewalk ramps, median island and delineator work on M-5 (Grand River Avenue) from Warren Avenue to 14th Street in the city of Detroit, Wayne County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
222091A	25A1046	N/A	VRU 82121

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$15,700.00	1100001	1.000	LSUM
0010	Curb, Rem	2040021	50.000	Ft
0015	Masonry and Conc Structure, Rem	2040045	3.000	Cyd
0020	Sidewalk, Rem	2040055	92.000	Syd
0025	Exploratory Investigation, Vertical	2040080	20.000	Ft
0030	Excavation, Earth	2050016	67.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0045	Project Cleanup	2090001	1.000	LSUM
0050	Subbase, CIP	3010002	42.000	Cyd
0055	Aggregate Base, 6 inch	3020016	38.000	Syd
0060	Aggregate Base, 10 inch	3020026	64.000	Syd
0065	HMA Surface, Rem	5010005	76.000	Syd
0070	Conc Pavt, Misc, Nonreinf, 9 inch	6020056	58.000	Syd
0075	Joint, Contraction, Crg	6030020	182.000	Ft
0080	Lane Tie, Epoxy Anchored	6030030	36.000	Ea
0085	Pavt Repr, Rem	6030080	76.000	Syd
0090	Curb, Conc, Det E1	8020001	94.000	Ft
0095	Detectable Warning Surface	8030010	20.000	Ft
0100	Curb Ramp Opening, Conc	8030030	22.000	Ft
0105	Sidewalk, Conc, 6 inch	8030046	545.000	Sft
0110	Curb Ramp, Conc, 6 inch	8032002	485.000	Sft
0115	Fence, Protective	8080007	100.000	Ft
0120	Perforated Steel Square Tube Breakaway System	8100330	2.000	Ea
0125	Post Hole Through Conc for Steel Post	8100340	14.000	Ea
0130	Post, Steel, 3 pound	8100371	110.000	Ft
0135	Sign, Type IIIB	8100405	104.000	Sft

0140	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	6.000	Ea
0145	Reflective Panel for Permanent Sign Support, 6 foot	8100616	2.000	Ea
0150	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	168.000	Ft
0155	Rem Spec Mrkg	8110343	68.000	Sft
0160	Pavt Mrkg, Polyurea, Yield Triangle Sym	8112173	16.000	Ea
0165	_ Pavt Mrkg, Waterborne, 12 inch, Yellow, Curb Painting	8117001	48.000	Ft
0170	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	14.000	Ea
0175	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	14.000	Ea
0180	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0185	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0190	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0195	Minor Traf Devices	8120170	1.000	LSUM
0200	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	430.000	Ft
0205	Plastic Drum, Fluorescent, Furn	8120252	80.000	Ea
0210	Plastic Drum, Fluorescent, Oper	8120253	80.000	Ea
0215	Sign Cover	8120310	5.000	Ea
0220	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0225	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0230	Sign, Type B, Temp, Prismatic, Furn	8120350	450.000	Sft
0235	Sign, Type B, Temp, Prismatic, Oper	8120351	450.000	Sft
0240	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	100.000	Ft
0245	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	100.000	Ft
0250	Conduit, DB, 1, 1/2 inch	8182046	60.000	Ft
0255	Conduit, DB, 1, 3 inch	8182050	85.000	Ft
0260	Cable, Sec, 600V, 1, 3/C#6	8182238	225.000	Ft
0265	Hh, Round	8182310	2.000	Ea
0270	Serv Disconnect	8182366	1.000	Ea
0275	Wood Pole, Fit Up, Sec Serv Pole	8182382	1.000	Ea
0280	Pedestal, Alum	8200100	2.000	Ea
0285	Pedestal Fdn, Flush	8200103	1.000	Ea
0290	Pedestal, Fdn	8200105	1.000	Ea
0295	Pushbutton and Sign	8200121	2.000	Ea
0300	_ Flsh Beacon, Rectangular Rapid	8207050	2.000	Ea
0305	Contractor Staking	8240001	1.000	LSUM
0310	Staking Plan Errors and Extras, Max \$180/hour	8240002	1.000	Hr
0315	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 020

Letting Date: November 7, 2025

Contract ID: 82052-212635

Description: Bridge rehabilitation including full depth concrete pavement repairs, epoxy overlay, concrete barrier patching, reseal bridge joints, steel repairs, diaphragm replacement, substructure patching, substructure horizontal surface sealer, concrete surface coating and approach work on US-24 from Oxford Street to Fordson Drive and US-12 westbound over US-24 in the city of Dearborn, Wayne County. This project includes a 5 year performance warranty for the thin epoxy polymer bridge deck overlay and a 2 year performance warranty for the concrete surface coating.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
212635A	25A1000	N/A	NH 82052
219831A	25A1019	N/A	BFP 82061

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Conc Quality Initiative	10000030	1,753.000	Dir
0010	Mobilization, Max \$258,200.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	33.000	Ft
0020	Pavt, Rem	2040050	181.000	Syd
0025	Sidewalk, Rem	2040055	25.000	Syd
0030	Excavation, Earth	2050016	2.000	Cyd
0035	Subgrade Undercutting, Type II	2050041	10.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	120.000	Ea
0045	Project Cleanup	2090001	1.000	LSUM
0050	Aggregate Base, Conditioning	3020050	181.000	Syd
0055	Dr Structure Cover, Adj, Case 1, Modified	4030004	10.000	Ea
0060	Dr Structure Lead, Cleaning, 12 inch	4030112	500.000	Ft
0065	Dr Structure Lead, Cleaning, 24 inch	4030124	250.000	Ft
0070	Dr Structure, Cleaning	4030290	50.000	Ea
0075	Pavt, Cleaning	5010001	1.000	LSUM
0080	HMA Surface, Rem	5010005	79.000	Syd
0085	Joint, Contraction, Cp	6020200	1,799.000	Ft
0090	Joint, Expansion, E2	6020207	53.000	Ft
0095	Joint, Expansion, E3	6020208	55.000	Ft
0100	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	101.000	Syd
0105	_ Conc Pavt, Reinf, 9 inch, High Performance	6027011	80.000	Syd
0110	Joint, Contraction, Crg	6030020	4,020.000	Ft
0115	Lane Tie, Epoxy Anchored	6030030	325.000	Ea
0120	Pavt Repr, Nonreinf Conc, 10 inch	6030048	3,000.000	Syd

0125	Pavt Repr, Rem	6030080	3,000.000	Syd
0130	Saw Cut, Intermediate	6030090	2,010.000	Ft
0135	Resealing Trans Joints with Hot-Poured Rubber	6030100	23,123.000	Ft
0140	Resealing Longit Joints with Hot-Poured Rubber	6030101	17,984.000	Ft
0145	_ Joint, Tied, 2.5 foot	6037001	20,500.000	Ft
0150	_ Pav Repr, 2.5 foot, Rem	6037011	3,250.000	Syd
0155	_ Pavt Repr, 2.5 foot, Nonreinf, 10 inch	6037011	3,250.000	Syd
0160	_ Curb and Gutter, Conc, Det C5, Modified	8027001	33.000	Ft
0165	Sidewalk, Conc, 4 inch	8030044	220.000	Sft
0170	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	427.000	Ft
0175	Pavt Mrkg, Polyurea, 6 inch, White	8110094	25,445.000	Ft
0180	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	4,988.000	Ft
0185	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	125.000	Ft
0190	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	25,445.000	Ft
0195	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0200	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea
0205	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	60.000	Ea
0210	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	60.000	Ea
0215	Pedestrian Type II Barricade, Temp	8120026	18.000	Ea
0220	Conc Barrier Ending, Temp, Det 2, Furn	8120041	2.000	Ea
0225	Conc Barrier Ending, Temp, Det 2, Oper	8120042	2.000	Ea
0230	Conc Barrier Reflector Replacement	8120070	10.000	Ea
0235	Conc Barrier, Temp, Furn	8120081	300.000	Ft
0240	Conc Barrier, Temp, Oper	8120082	300.000	Ft
0245	High Intensity Light, Type B, Furn	8120110	2.000	Ea
0250	High Intensity Light, Type B, Oper	8120111	2.000	Ea
0255	Connected Arrow Board, Type C, Furn	8120155	11.000	Ea
0260	Connected Arrow Board, Type C, Oper	8120156	11.000	Ea
0265	Minor Traf Devices	8120170	1.000	LSUM
0270	Mobile Attenuator	8120180	2.000	Ea
0275	Pavt Mrkg Cover, Type R, Black	8120200	70.000	Ft
0280	Plastic Drum, Fluorescent, Furn	8120252	360.000	Ea
0285	Plastic Drum, Fluorescent, Oper	8120253	360.000	Ea
0290	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt Turn Arrow	8120258	2.000	Ea
0295	Pavt Mrkg, Wet Reflective, Type R, Tape, Thru Arrow	8120259	2.000	Ea
0300	Sign Cover	8120310	3.000	Ea
0305	Sign Cover, Type I	8120320	2.000	Ea
0310	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0315	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0320	Sign, Type B, Temp, Prismatic, Furn	8120350	2,072.000	Sft
0325	Sign, Type B, Temp, Prismatic, Oper	8120351	2,072.000	Sft
0330	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	21.000	Sft

0335	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	21.000	Sft
0340	Traf Regulator Control	8120370	1.000	LSUM
0345	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	25,881.000	Ft
0350	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	3,240.000	Ft
0355	Wireless Vehicle Sensor Node	8200425	9.000	Ea
0360	Wireless Vehicle Sensor Node, Rem	8200426	9.000	Ea
0365	TS Face, Bag	8200458	13.000	Ea
0370	TS Face, Bag, Rem	8200459	13.000	Ea
0375	Contractor Staking	8240001	1.000	LSUM
0380	Staking Plan Errors and Extras, Max \$180/hour	8240002	28.000	Hr

Section: 2

0385	Erosion Control, Sand Bag	2080028	40.000	Ea
0390	HMA Patch, Rem	5010006	1.000	Syd
0395	False Decking	7060060	5,453.000	Sft
0400	Reinforcement, Steel, Epoxy Coated	7060092	500.000	Lb
0405	Metal Mesh Panels	7070120	5,434.000	Sft
0410	Conc Surface Coating, Warranty (S01-4 of 82062)	7100009	1.000	LSUM
0415	Substructure Horizontal Surface Sealer (S01-4 of 82062)	7100030	22.000	Syd
0420	_ Silane Treatment	7107010	718.000	Sft
0425	Hand Chipping, Deep	7120004	23.000	Syd
0430	Hand Chipping, Other Than Deck	7120007	191.000	Cft
0435	Patch, Full Depth	7120010	30.000	Cyd
0440	Patch, Forming	7120017	388.000	Sft
0445	Epoxy Ovly, Rem	7120021	574.000	Syd
0450	Epoxy Ovly, Warranty	7120022	695.000	Syd
0455	Structures, Rehabilitation, Rem Portions (S01-4 of 82062)	7120070	1.000	LSUM
0460	Patching Conc, C-L	7120112	10.000	Cyd
0465	Embedded Galvanic Anode, High Performing	7120125	634.000	Ea
0470	Hand Chipping, Full Depth	7122000	788.000	Cft
0475	_ Bridge Joints, Clean and Seal	7127001	129.000	Ft
0480	_ Deck, Scaling	7127010	1,000.000	Sft
0485	Beam Plate, Seal Perimeter	7130010	508.000	Ft
0490	Heat Straightening Type 1 (S01-4 of 82062)	7130041	1.000	LSUM
0495	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	3,524.000	Lb
0500	Support, Column, Temp	7130080	2.000	Ea
0505	Steel Structure, Cleaning, Partial, Type 4 (S01-4 of 82062)	7150047	1.000	LSUM
0510	Steel Structure, Coating, Partial, Type 4 (S01-4 of 82062)	7150048	1.000	LSUM
0515	Field Repr of Damaged Coating (S01-4 of 82062)	7160001	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 021

Letting Date: November 7, 2025

Contract ID: 58032-220353

Description: 0.01 mi of installation of a pedestrian island and rectangular flashing beacon on M-50 from Mechanic Street and Rawson Street in the city of Dundee, Monroe County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220353A	25A1006	N/A	VRU 58032

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$11,500.00	1100001	1.000	LSUM
0010	Pavt, Rem	2040050	53.000	Syd
0015	Exploratory Investigation, Vertical	2040080	20.000	Ft
0020	Excavation, Earth	2050016	11.000	Cyd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	3.000	Ea
0030	Subbase, CIP	3010002	20.000	Cyd
0035	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0040	Dr Structure Cover, Type Q	4030065	1.000	Ea
0045	Dr Structure, Adj, Add Depth	4030280	1.000	Ft
0050	HMA Surface, Rem	5010005	53.000	Syd
0055	_ Curb and Gutter, Conc, Det F3, Modified	8027001	62.000	Ft
0060	Detectable Warning Surface	8030010	16.000	Ft
0065	Curb Ramp Opening, Conc	8030030	18.000	Ft
0070	Curb Ramp, Conc, 6 inch	8032002	71.000	Sft
0075	_ Decorative Conc, Surface, 6 inch	8037010	177.000	Sft
0080	Band, Sign	8100010	8.000	Ea
0085	Perforated Steel Square Tube Breakaway System	8100330	2.000	Ea
0090	Post, Steel, 3 pound	8100371	60.000	Ft
0095	Sign, Type III, Rem	8100403	4.000	Ea
0100	Sign, Type IIIB	8100405	55.000	Sft
0105	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	8.000	Ea
0110	Reflective Panel for Permanent Sign Support, 6 foot	8100616	6.000	Ea
0115	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0120	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	64.000	Ft
0125	Rem Spec Mrkg	8110343	88.000	Sft
0130	Recessing Pavt Mrkg, Longit	8110450	64.000	Ft
0135	Recessing Pavt Mrkg, Transv	8110451	24.000	Sft
0140	Pavt Mrkg, Polyurea, Yield Triangle Sym	8112173	8.000	Ea

0145	_ Pavt Mrkg, Waterborne, 12 inch, Yellow, Curb Painting	8117001	62.000	Ft
0150	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0155	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0160	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0165	Minor Traf Devices	8120170	1.000	LSUM
0170	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	80.000	Ft
0175	Plastic Drum, Fluorescent, Furn	8120252	96.000	Ea
0180	Plastic Drum, Fluorescent, Oper	8120253	96.000	Ea
0185	Sign Cover	8120310	6.000	Ea
0190	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0195	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	320.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	320.000	Sft
0210	Traf Regulator Control	8120370	1.000	LSUM
0215	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0220	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0225	Conduit, Directional Bore, 1, 1 1/2 inch	8182034	390.000	Ft
0230	Conduit, DB, 1, 1 1/2 inch	8182048	400.000	Ft
0235	Cable, Sec, 600V, 1, 3/C#6	8182238	450.000	Ft
0240	Hh, Round	8182310	5.000	Ea
0245	Pedestal, Alum	8200100	2.000	Ea
0250	Pedestal, Fdn	8200105	3.000	Ea
0255	Pedestal, Underground Serv, Unmetered	8200112	1.000	Ea
0260	Push Button Station and Sign	8200128	2.000	Ea
0265	Pedestrian Signal System, Accessible	8200240	2.000	Ea
0270	_ Flsh Beacon, Rectangular Rapid	8207050	2.000	Ea
0275	Contractor Staking	8240001	1.000	LSUM
0280	Staking Plan Errors and Extras, Max \$180/hour	8240002	8.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 022

Letting Date: November 7, 2025

Contract ID: 28013-210774

Description: 0.28 mi of hot mix asphalt cold milling and resurfacing, widening for center left turn lane, concrete curb and gutter, sidewalk, signal work, guardrail improvements and pavement markings on US-31 at Three Mile Road in the city of Traverse City, Grand Traverse County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
210774A	25A0215	N/A	ST 28013

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$140,500.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	2.000	Ea
0015	Tree, Rem, 6 inch to 18 inch	2020004	11.000	Ea
0020	Dr Structure, Rem	2030011	5.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	40.000	Ft
0030	_ Monitoring Well, Abandon	2037050	2.000	Ea
0035	Curb and Gutter, Rem	2040020	1,359.000	Ft
0040	Pavt, Rem	2040050	269.000	Syd
0045	Sidewalk, Rem	2040055	289.000	Syd
0050	Exploratory Investigation, Vertical	2040080	100.000	Ft
0055	Embankment, CIP	2050010	748.000	Cyd
0060	Excavation, Earth	2050016	1,360.000	Cyd
0065	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0070	Subgrade Undercutting, Type II	2050041	200.000	Cyd
0075	Erosion Control, Inlet Protection, Fabric Drop	2080020	22.000	Ea
0080	Erosion Control, Sediment Trap	2080034	3.000	Ea
0085	Erosion Control, Silt Fence	2080036	1,137.000	Ft
0090	Subbase, CIP	3010002	50.000	Cyd
0095	Aggregate Base, 6 inch	3020016	2,757.000	Syd
0100	Sewer, CI E, 12 inch, Tr Det B	4020600	353.000	Ft
0105	Video Taping Sewer and Culv Pipe	4021275	353.000	Ft
0110	Dr Structure Cover, Adj, Case 1	4030005	9.000	Ea
0115	Dr Structure Cover, Type B	4030010	1.000	Ea
0120	Dr Structure Cover, Type G	4030040	3.000	Ea
0125	Dr Structure Cover, Type K	4030050	10.000	Ea
0130	Dr Structure Cover, Type Q	4030065	6.000	Ea
0135	Dr Structure, 24 inch dia	4030200	5.000	Ea

0140	Dr Structure, 48 inch dia	4030210	6.000	Ea
0145	Dr Structure, Tap, 12 inch	4030312	5.000	Ea
0150	Pavt, Cleaning	5010001	1.000	LSUM
0155	Bump Grinding	5010004	28.000	Syd
0160	HMA Surface, Rem	5010005	661.000	Syd
0165	HMA Quality Initiative	5010007	3,252.000	Dlr
0170	Hand Patching	5010025	22.000	Ton
0175	HMA Approach	5010061	468.000	Ton
0180	Fine Texture Pavt Milling	5010102	9,520.000	Syd
0185	HMA Approach, High Stress	5010520	77.000	Ton
0190	HMA, 4EML, High Stress	5012073	175.000	Ton
0195	HMA, 5EML, High Stress	5012085	884.000	Ton
0200	_ Gemini Unit, Install Salv	8007050	1.000	Ea
0205	_ Gemini Unit, Rem and Salv	8007050	1.000	Ea
0210	_ Surveillance System, Remote Site, Type A, Rem	8007050	1.000	Ea
0215	_ Wi-Fi Sensor, Field, Install Salv	8007050	1.000	Ea
0220	_ Wi-Fi Sensor, Field, Rem and Salv	8007050	1.000	Ea
0225	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
0230	Driveway, Nonreinf Conc, 6 inch	8010005	9.000	Syd
0235	Curb, Conc, Det E2	8020002	272.000	Ft
0240	Curb and Gutter, Conc, Det F4	8020038	1,735.000	Ft
0245	Driveway Opening, Conc, Det M	8020050	264.000	Ft
0250	Curb Ramp Opening, Conc	8030030	69.000	Ft
0255	Sidewalk, Conc, 4 inch	8030044	8,798.000	Sft
0260	Curb Ramp, Conc, 4 inch	8032001	1,122.000	Sft
0265	_ Detectable Warning Surface, Cast Iron, Spec	8037001	52.000	Ft
0270	Fence, Temp	8080004	1,800.000	Ft
0275	Fdn, Wood Support, Rem	8100280	12.000	Ea
0280	Perforated Steel Square Tube Breakaway System	8100330	3.000	Ea
0285	Fdn, Perforated Steel Square Tube Sign Breakaway System, Rem	8100331	2.000	Ea
0290	Post, Steel, 3 pound	8100371	144.000	Ft
0295	Post, Wood, 4 inch by 6 inch	8100380	226.000	Ft
0300	Post, Wood, 6 inch by 8 inch	8100382	36.000	Ft
0305	Sign, Type II, Rem	8100397	6.000	Ea
0310	Sign, Type IIA	8100398	101.000	Sft
0315	Sign, Type IIB	8100399	10.000	Sft
0320	Sign, Type III, Erect, Salv	8100402	6.000	Ea
0325	Sign, Type III, Rem	8100403	18.000	Ea
0330	Sign, Type IIIA	8100404	19.000	Sft
0335	Sign, Type IIIB	8100405	69.000	Sft
0340	Sign, Type V, Rem	8100421	1.000	Ea
0345	Sign, Type VB	8100425	12.000	Sft
0350	Reflective Panel for Permanent Sign Support, 6 foot	8100616	2.000	Ea

0355	Bracket, H	8100650	2.000	Ea
0360	Sign, Type III, Rem, Salv	8102003	9.000	Ea
0365	Ground Mtd Sign Support, Rem	8102010	27.000	Ea
0370	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	7.000	Ea
0375	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	2.000	Ea
0380	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0385	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	1.000	Ea
0390	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, White	8110108	69.000	Ft
0395	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	486.000	Ft
0400	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	167.000	Ft
0405	Recessing Pavt Mrkg, Longit	8110450	6,490.000	Ft
0410	Recessing Pavt Mrkg, Transv	8110451	69.000	Sft
0415	Recessing Pavt Mrkg, Guide Line	8110453	115.000	Ft
0420	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Dotted Turning Guide Line, White	8110562	115.000	Ft
0425	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	2,719.000	Ft
0430	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	3,604.000	Ft
0435	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0440	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0445	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0450	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0455	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0460	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0465	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0470	Minor Traf Devices	8120170	1.000	LSUM
0475	Pavt Mrkg Cover, Type R, Black	8120200	2,750.000	Ft
0480	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	5,500.000	Ft
0485	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0490	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0495	Sign Cover	8120310	15.000	Ea
0500	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	3.000	Ea
0505	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	3.000	Ea
0510	Sign, Type B, Temp, Prismatic, Furn	8120350	937.000	Sft
0515	Sign, Type B, Temp, Prismatic, Oper	8120351	937.000	Sft
0520	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	80.000	Sft
0525	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	80.000	Sft
0530	Traf Regulator Control	8120370	1.000	LSUM
0535	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	4,250.000	Ft
0540	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	3,200.000	Ft
0545	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	3,000.000	Ft

0550	Speed Radar Trailer, Temp	8122028	3.000	Ea
0555	Pedestrian Path, Temp	8122250	100.000	Ft
0560	Pedestrian Ramp, Temp	8122251	4.000	Ea
0565	_ Arboricultural Work	8157040	8.000	Hr
0570	Slope Restoration, Non-Freeway, Type A	8162001	1,107.000	Syd
0575	Slope Restoration, Non-Freeway, Type B	8162002	1,786.000	Syd
0580	Power Company (Estimated Cost to Contractor)	8180001	10,236.000	Dir
0585	Conduit, Rem	8182000	215.000	Ft
0590	Conduit, Directional Bore, 2, 3 inch	8182037	120.000	Ft
0595	Conduit, DB, 1, 1 1/2 inch	8182048	200.000	Ft
0600	Conduit, DB, 2, 3 inch	8182053	130.000	Ft
0605	Conduit, DB, 3, 3 inch	8182056	50.000	Ft
0610	Conduit, DB, 4, 3 inch	8182059	10.000	Ft
0615	Conduit, DB, 1, 1 inch	8182060	20.000	Ft
0620	Cable, Sec, Rem	8182199	80.000	Ft
0625	Cable Pole, TS and Sec, Disman	8182209	1.000	Ea
0630	Cable, Sec, 600V, 1, 3/C#6	8182238	60.000	Ft
0635	Hh, Polymer Conc	8182309	2.000	Ea
0640	Hh, Round	8182310	3.000	Ea
0645	Hh, Round, 3 foot dia	8182319	1.000	Ea
0650	Hh, Rem	8182330	4.000	Ea
0655	Metered Serv, Rem	8182339	1.000	Ea
0660	Serv Disconnect, Rem	8182367	1.000	Ea
0665	Case Sign, Disappearing Legend, 24 inch by 30 inch	8200015	1.000	Ea
0670	Case Sign (LED), One Way, 12 inch by 27 inch	8200019	5.000	Ea
0675	Case Sign, Rem	8200020	2.000	Ea
0680	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	1.000	Ea
0685	Controller and Cabinet, Rem	8200030	1.000	Ea
0690	Case Sign, Salv	8200039	1.000	Ea
0695	Controller Fdn, Base Mtd	8200045	1.000	Ea
0700	Controller Fdn, Rem	8200046	1.000	Ea
0705	Fdn, Rem	8200065	1.000	Ea
0710	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	1.000	Ea
0715	Pedestal, Alum	8200100	3.000	Ea
0720	Pedestal, Fdn	8200105	7.000	Ea
0725	Pedestal Fdn, Rem	8200106	3.000	Ea
0730	Pedestal, Rem	8200110	2.000	Ea
0735	Pedestal, Underground Serv, Metered	8200111	1.000	Ea
0740	Pedestal, Pushbutton, Alum	8200118	3.000	Ea
0745	Pedestal, Pushbutton, Rem	8200119	1.000	Ea
0750	Pushbutton, Rem	8200122	2.000	Ea
0755	Push Button Station and Sign	8200128	6.000	Ea
0760	Span Wire	8200140	4.000	Ea
0765	Span Wire, Rem	8200141	1.000	Ea
0770	Span Wire Tether	8200142	4.000	Ea

0775	Steel Pole, Rem	8200145	1.000	Ea
0780	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	1.000	Ea
0785	TS, Pedestrian, Pedestal Mtd, Rem	8200181	2.000	Ea
0790	TS, Span Wire Mtd, Rem	8200182	5.000	Ea
0795	Cabinet, NEMA Type	8200186	1.000	Ea
0800	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0805	TS, Wireless Link, Rem	8200280	1.000	Ea
0810	TS, Wireless Link, Salv	8200281	1.000	Ea
0815	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	1.000	Ea
0820	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0825	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	3.000	Ea
0830	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
0835	Bracket, Truss, Rem	8200388	2.000	Ea
0840	Wireless Repeater, Rem	8200418	3.000	Ea
0845	Wireless Repeater	8200421	4.000	Ea
0850	Wireless Vehicle Detection System	8200422	1.000	Ea
0855	Wireless Vehicle Sensor Node	8200425	8.000	Ea
0860	Hemispherical Video Detection Camera	8200444	2.000	Ea
0865	Hemispherical Video Detection System	8200445	1.000	Ea
0870	Hemispherical Video Detection Camera, Rem	8200446	1.000	Ea
0875	TS Head, Temp	8200453	1.000	Ea
0880	TS Face, Bag	8200458	5.000	Ea
0885	TS Face, Bag, Rem	8200459	5.000	Ea
0890	Strain Pole, Steel, 6 bolt, Size 2	8200466	4.000	Ea
0895	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	70.000	Ft
0900	Casing, 48 inch	8200486	56.000	Ft
0905	Backplate, TS	8200501	13.000	Ea
0910	TS, One Way Span Wire Mtd (LED), Long Life	8202287	13.000	Ea
0915	_ Controller, NEMA, ATC Type	8207050	1.000	Ea
0920	Protect Corners	8210020	10.000	Ea
0925	Fire Hydrant	8230040	2.000	Ea
0930	Gate Valve and Box, 6 inch	8230051	1.000	Ea
0935	Hydrant, Rem	8230091	2.000	Ea
0940	Water Main, DI, 6 inch, Tr Det F	8230150	16.000	Ft
0945	Gate Box, Adj, Case 1	8230431	1.000	Ea
0950	_ Live Tap, 16 inch by 6 inch	8237050	1.000	Ea
0955	Contractor Staking	8240001	1.000	LSUM
0960	Staking Plan Errors and Extras, Max \$180/hour	8240002	17.000	Hr
0965	Sanitary Structure Cover, Adj, Case 1	8252145	2.000	Ea
0970	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
0975	Lightning Protection, Pole	8260021	1.000	Ea
0980	Managed Field Ethernet Switch, Layer 2	8260080	1.000	Ea
0985	Surveillance System, Remote Site, Type A	8260157	1.000	Ea

0990	System Integration and Testing	8260160	1.000	LSUM
------	--------------------------------	---------	-------	------



Schedule of Pay Items

Report v1

Letting Call: 251107 023

Letting Date: November 7, 2025

Contract ID: 82071-219372

Description: 1.41 mi of full-depth concrete pavement repairs, minor spall repairs, longitudinal and transverse joint resealing and pavement markings on M-85 (Fort Street) from Clark Street northeasterly to Rosa Parks Boulevard in the city of Detroit, Wayne County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219372A	25A1004	N/A	NH 82071

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$177,900.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	185.000	Ft
0015	Pavt, Rem	2040050	3,055.000	Syd
0020	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0025	Project Cleanup	2090001	1.000	LSUM
0030	Geotextile, Separator, Non-Woven	3082000	12,675.000	Syd
0035	Dr Structure Cover, Adj, Case 1, Modified	4030004	58.000	Ea
0040	Dr Structure Cover, Type B	4030010	32.000	Ea
0045	Dr Structure Cover, Type K	4030050	16.000	Ea
0050	Dr Structure Lead, Cleaning, 12 inch	4030112	1,880.000	Ft
0055	Dr Structure, Adj, Add Depth	4030280	3.000	Ft
0060	Dr Structure, Cleaning	4030290	48.000	Ea
0065	_ Asphalt Repr Mastic	5027001	400.000	Ft
0070	Conc Pavt, Misc, Nonreinf, 7 inch	6020052	3,055.000	Syd
0075	Joint, Contraction, Cp	6020200	5,444.000	Ft
0080	Joint, Contraction, Crg	6030020	7,561.000	Ft
0085	Joint, Expansion, Erg	6030021	490.000	Ft
0090	Lane Tie, Epoxy Anchored	6030030	5,911.000	Ea
0095	Pavt Repr, Nonreinf Conc, 7 inch	6030042	9,665.000	Syd
0100	Pavt Repr, Nonreinf Conc, 10 1/2 inch	6030049	230.000	Syd
0105	Pavt Repr, Rem	6030080	9,895.000	Syd
0110	Saw Cut, Intermediate	6030090	9,034.000	Ft
0115	Resealing Trans Joints with Hot-Poured Rubber	6030100	8,000.000	Ft
0120	Resealing Longit Joints with Hot-Poured Rubber	6030101	9,000.000	Ft
0125	Curb and Gutter, Conc, Det C1	8020020	33.000	Ft
0130	Driveway Opening, Conc, Det M	8020050	152.000	Ft
0135	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	10.000	Ea

0140	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0145	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	617.000	Ft
0150	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	300.000	Ft
0155	Pavt Mrkg, Sprayable Thermopl, 6 inch, White	8110155	5,943.000	Ft
0160	Pavt Mrkg, Sprayable Thermopl, 6 inch, Yellow	8110156	17,076.000	Ft
0165	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	12,595.000	Ft
0170	Rem Curing Compound, for Spec Mrkg	8110321	475.000	Sft
0175	Rem Spec Mrkg	8110343	111.000	Sft
0180	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	30.000	Ea
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	30.000	Ea
0195	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0210	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0215	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0220	Ltg for Night Work	8120160	1.000	LSUM
0225	Minor Traf Devices	8120170	1.000	LSUM
0230	Plastic Drum, Fluorescent, Furn	8120252	300.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	300.000	Ea
0240	Sign, Type B, Temp, Prismatic, Furn	8120350	1,100.000	Sft
0245	Sign, Type B, Temp, Prismatic, Oper	8120351	1,100.000	Sft
0250	_ Heavy Duty Wrecker	8127050	1.000	Ea
0255	_ Light Duty Wrecker	8127050	5.000	Ea
0260	_ Medium Duty Wrecker	8127050	1.000	Ea
0265	Contractor Staking	8240001	1.000	LSUM
0270	Staking Plan Errors and Extras, Max \$180/hour	8240002	20.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 024

Letting Date: November 7, 2025

Contract ID: 29021-211327

Description: 47.57 mi of non-freeway sign replacement on M-46 and M-57 in the city of St. Louis, villages of Breckenridge, Gratiot County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
211327A	25A1069	N/A	STG 29021

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$59,500.00	1100001	1.000	LSUM
0010	Sidewalk, Rem	2040055	50.000	Syd
0015	Sidewalk, Conc, 4 inch	8030044	450.000	Sft
0020	Band, Sign	8100010	45.000	Ea
0025	Fdn, Wood Support, Rem	8100280	136.000	Ea
0030	Installing MDOT Supplied Sign, Type III	8100302	43.000	Ea
0035	Fdn, Perforated Steel Square Tube Sign Breakaway System, Rem	8100331	2.000	Ea
0040	Post Hole Through Conc for Steel Post	8100340	6.000	Ea
0045	Post Hole Through Conc for Wood Post	8100341	7.000	Ea
0050	Post, Steel, 3 pound	8100371	18,676.000	Ft
0055	Post, Wood, 4 inch by 6 inch	8100380	3,636.000	Ft
0060	Post, Wood, 6 inch by 8 inch	8100382	108.000	Ft
0065	Sign, Type II, Erect, Salv	8100396	2.000	Ea
0070	Sign, Type II, Rem	8100397	153.000	Ea
0075	Sign, Type IIA	8100398	2,403.000	Sft
0080	Sign, Type IIB	8100399	11.000	Sft
0085	Sign, Type III, Erect, Salv	8100402	171.000	Ea
0090	Sign, Type III, Rem	8100403	895.000	Ea
0095	Sign, Type IIIA	8100404	1,705.000	Sft
0100	Sign, Type IIIB	8100405	3,517.000	Sft
0105	Sign, Type V, Rem	8100421	13.000	Ea
0110	Sign, Type VB	8100425	406.000	Sft
0115	Reflective Panel for Permanent Sign Support, 3 foot	8100613	42.000	Ea
0120	Reflective Panel for Permanent Sign Support, 6 foot	8100616	526.000	Ea
0125	Bracket, H	8100650	8.000	Ea
0130	Sign, Type II, Rem, Salv	8102002	2.000	Ea
0135	Sign, Type III, Rem, Salv	8102003	173.000	Ea

0140	Ground Mtd Sign Support, Rem	8102010	1,269.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0150	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0155	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0160	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0165	Minor Traf Devices	8120170	1.000	LSUM
0170	Mobile Attenuator	8120180	1.000	Ea
0175	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0180	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0185	Sign Cover	8120310	20.000	Ea
0190	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0195	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	700.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	700.000	Sft
0210	Traf Regulator Control	8120370	1.000	LSUM
0215	Contractor Staking	8240001	1.000	LSUM
0220	Staking Plan Errors and Extras, Max \$180/hour	8240002	7.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 025

Letting Date: November 7, 2025

Contract ID: 56032-219502

Description: 57.50 mi of non-freeway signing replacements on M-30 from M-46 to the north Gladwin County line, Gratiot, Saginaw, Midland, and Gladwin Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219502A	25A1038	N/A	STG 56032

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$60,400.00	1100001	1.000	LSUM
0010	Band, Sign	8100010	8.000	Ea
0015	Fdn, Wood Support, Rem	8100280	96.000	Ea
0020	Installing MDOT Supplied Sign, Type III	8100302	30.000	Ea
0025	Post Hole Through Conc for Steel Post	8100340	10.000	Ea
0030	Post, Steel, 3 pound	8100371	21,021.000	Ft
0035	Post, Wood, 4 inch by 6 inch	8100380	2,120.000	Ft
0040	Post, Wood, 6 inch by 8 inch	8100382	1,128.000	Ft
0045	Sign, Type II, Rem	8100397	214.000	Ea
0050	Sign, Type IIA	8100398	2,449.000	Sft
0055	Sign, Type IIB	8100399	10.000	Sft
0060	Sign, Type III, Erect, Salv	8100402	119.000	Ea
0065	Sign, Type III, Rem	8100403	996.000	Ea
0070	Sign, Type IIIA	8100404	1,671.000	Sft
0075	Sign, Type IIIB	8100405	3,276.000	Sft
0080	Sign, Type V, Rem	8100421	1.000	Ea
0085	Sign, Type VA	8100424	24.000	Sft
0090	Sign, Type VB	8100425	1,102.000	Sft
0095	Reflective Panel for Permanent Sign Support, 3 foot	8100613	38.000	Ea
0100	Reflective Panel for Permanent Sign Support, 6 foot	8100616	717.000	Ea
0105	Bracket, H	8100650	3.000	Ea
0110	Sign, Type III, Rem, Salv	8102003	119.000	Ea
0115	Ground Mtd Sign Support, Rem	8102010	1,507.000	Ea
0120	_ Hand Digging Sign Post	8107050	20.000	Ea
0125	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0130	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Plastic Drum, Fluorescent, Furn	8120252	200.000	Ea

0145	Plastic Drum, Fluorescent, Oper	8120253	200.000	Ea
0150	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	24.000	Ft
0155	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0160	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0165	Sign, Type B, Temp, Prismatic, Furn	8120350	750.000	Sft
0170	Sign, Type B, Temp, Prismatic, Oper	8120351	750.000	Sft
0175	Traf Regulator Control	8120370	1.000	LSUM
0180	Contractor Staking	8240001	1.000	LSUM
0185	Staking Plan Errors and Extras, Max \$180/hour	8240002	7.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 026

Letting Date: November 7, 2025

Contract ID: 21000-224784

Description: 9.79 mi of hot mix asphalt overlay and wedging, aggregate shoulders, guardrail and pavement markings on County Road 511 from US-2 to south of the Holquist Gravel Pit, Delta County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224784A	25A0746	N/A	STL 21000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$172,000.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	312.000	Ft
0015	Machine Grading	2050030	93.000	Sta
0020	Approach, CI II	3070021	510.000	Ton
0025	Shld, CI II	3070121	4,142.000	Ton
0030	Cold Milling HMA Surface	5010002	1,694.000	Syd
0035	HMA Approach	5010061	244.000	Ton
0040	HMA, 4EL	5012024	15,878.000	Ton
0045	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0050	Guardrail Reflector	8070080	18.000	Ea
0055	Guardrail, Type MGS-8, 108 inch Post	8072180	313.000	Ft
0060	Pavt Mrkg, Waterborne, 4 inch, White	8110231	103,412.000	Ft
0065	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	77,600.000	Ft
0070	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0075	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0080	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0085	Minor Traf Devices	8120170	1.000	LSUM
0090	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	4,135.000	Ft
0095	Plastic Drum, Fluorescent, Furn	8120252	8.000	Ea
0100	Plastic Drum, Fluorescent, Oper	8120253	8.000	Ea
0105	Sign, Type B, Temp, Prismatic, Furn	8120350	624.000	Sft
0110	Sign, Type B, Temp, Prismatic, Oper	8120351	624.000	Sft
0115	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	10.000	Sft
0120	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	10.000	Sft
0125	Traf Regulator Control	8120370	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 027

Letting Date: November 7, 2025

Contract ID: 74000-221853

Description: Bridge rehabilitation including deck patching, replace hot mix asphalt wearing surface and approach work on Sanborn Avenue over the Black River in the city of Croswell, Sanilac County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221853A	25A0919	N/A	EMRP 74000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$72,000.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	1.000	Ea
0015	Curb and Gutter, Rem	2040020	141.000	Ft
0020	Guardrail, Rem	2040035	235.000	Ft
0025	Sidewalk, Rem	2040055	100.000	Syd
0030	Embankment, CIP	2050010	20.000	Cyd
0035	Excavation, Earth	2050016	180.000	Cyd
0040	Subbase, CIP	3010002	175.000	Cyd
0045	Aggregate Base	3020001	120.000	Ton
0050	Aggregate Base, Conditioning	3020050	150.000	Syd
0055	Sewer, CI A, 6 inch, Tr Det A	4020001	15.000	Ft
0060	Sewer Tap, 6 inch	4021201	1.000	Ea
0065	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0070	Dr Structure Cover, Type G	4030040	1.000	Ea
0075	Dr Structure, 24 inch dia	4030200	1.000	Ea
0080	HMA Surface, Rem	5010005	400.000	Syd
0085	HMA, 4EL	5012024	190.000	Ton
0090	Curb and Gutter, Conc, Det F4	8020038	131.000	Ft
0095	Guardrail Anch, Bridge, Det T2	8070023	2.000	Ea
0100	Guardrail Departing Terminal, Type B	8070050	2.000	Ea
0105	Post, Steel, 3 pound	8100371	15.000	Ft
0110	Sign, Type III, Rem	8100403	1.000	Ea
0115	Sign, Type IIIA	8100404	15.000	Sft
0120	Pavt Mrkg, Waterborne, 4 inch, White	8110231	240.000	Ft
0125	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	700.000	Ft
0130	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	240.000	Ft
0135	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	700.000	Ft

0140	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0145	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0150	Minor Traf Devices	8120170	1.000	LSUM
0155	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0160	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0165	Sign Cover	8120310	10.000	Ea
0170	Sign, Type B, Temp, Prismatic, Furn	8120350	350.000	Sft
0175	Sign, Type B, Temp, Prismatic, Oper	8120351	350.000	Sft
0180	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	110.000	Sft
0185	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	110.000	Sft
0190	Traf Regulator Control	8120370	1.000	LSUM
0195	Mulch Blanket	8160027	100.000	Syd
0200	_ Turf Restoration	8167011	100.000	Syd

Section: 2

0205	Backfill, Structure, CIP	2060002	90.000	Cyd
0210	Excavation, Fdn	2060010	180.000	Cyd
0215	Underdrain, Fdn, 4 inch	4040031	70.000	Ft
0220	Underdrain Outlet, 4 inch	4040091	10.000	Ft
0225	Underdrain, Outlet Ending, 4 inch	4040111	2.000	Ea
0230	_ HMA Surface Rem, Mod	5017011	510.000	Syd
0235	Expansion Joint Device	7060050	70.000	Ft
0240	Expansion Joint Device, Cover Plate	7060051	14.000	Ft
0245	False Decking	7060060	7,070.000	Sft
0250	Reinforcement, Steel, Epoxy Coated	7060092	12,400.000	Lb
0255	Substructure Conc	7060100	86.000	Cyd
0260	Superstructure Conc	7060110	32.000	Cyd
0265	Superstructure Conc, Form, Finish, and Cure (SN 9670)	7060111	1.000	LSUM
0270	Conc, Grade 4500	7062003	6.000	Cyd
0275	_ Fiber Reinf Polymer System for Prest Conc Beam Repr	7067010	100.000	Sft
0280	_ Structure Name Plate, Rem, Salvage and Reinstall	7067050	1.000	Ea
0285	Membrane, Preformed Waterproofing	7100008	4,420.000	Sft
0290	Conc Surface Coating	7100011	770.000	Syd
0295	_ Penetrating Healer/Sealer, Sidewalk	7107011	135.000	Syd
0300	_ Decorative Pedestrian Railing	7117001	210.000	Ft
0305	Hand Chipping, Other Than Deck	7120007	225.000	Cft
0310	Patch, Forming	7120017	1,050.000	Sft
0315	Adhesive Anchoring of Horizontal Bar, 3/4 inch	7120028	40.000	Ea
0320	Adhesive Anchoring of Horizontal Bar, 1/2 inch	7120030	166.000	Ea
0325	Adhesive Anchoring of Vertical Bar, 1/2 inch	7120032	8.000	Ea
0330	Adhesive Anchoring of Vertical Bar, 3/4 inch	7120034	20.000	Ea
0335	Structures, Rehabilitation, Rem Portions (SN 9670)	7120070	1.000	LSUM

0340	Deck Joint, Rem	7120071	70.000	Ft
0345	Structural Crack, Repr	7120099	300.000	Ft
0350	_ Patching Conc, M, Mod	7127020	145.000	Cft
0355	_ Vertical and Overhead Structure Repr, Shotcrete	7127020	80.000	Cft
0360	Sidewalk, Conc, 6 inch	8030046	900.000	Sft



Schedule of Pay Items

Report v1

Letting Call: 251107 028

Letting Date: November 7, 2025

Contract ID: 82000-220159

Description: Traffic signal modernization and concrete sidewalk ramp upgrades on Wayne Road at Hunter Avenue in the city of Westland, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220159A	25A0971	N/A	HSIP 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Reimbursed Permit Fees	1077060	3,000.000	Dir
0010	Mobilization, Max \$31,900.00	1100001	1.000	LSUM
0015	Sidewalk, Rem	2040055	27.000	Syd
0020	Exploratory Investigation, Vertical	2040080	30.000	Ft
0025	Non Haz Contaminated Material Handling and Disposal, LM	2050031	22.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	6.000	Ea
0035	_ Misc Aggregate Base, CIP	3027021	3.000	Cyd
0040	Maintenance Gravel	3060020	8.000	Ton
0045	Detectable Warning Surface	8030010	5.000	Ft
0050	Curb Ramp, Conc, 4 inch	8032001	242.000	Sft
0055	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0060	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0070	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0075	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Plastic Drum, Fluorescent, Furn	8120252	60.000	Ea
0090	Plastic Drum, Fluorescent, Oper	8120253	60.000	Ea
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	600.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	600.000	Sft
0105	Traf Regulator Control	8120370	1.000	LSUM
0110	Pedestrian Path, Temp	8122250	100.000	Ft
0115	Pedestrian Ramp, Temp	8122251	4.000	Ea
0120	Mulch Blanket	8160027	315.000	Syd
0125	Topsoil Surface, Furn, 3 inch	8160061	155.000	Syd
0130	Water, Sodding/Seeding	8160090	2.000	Unit
0135	_ Seeding, Mixture THM, Modified	8167011	315.000	Syd

0140	Conduit, DB, 1, 1 1/2 inch	8182048	125.000	Ft
0145	Conduit, DB, 3, 3 inch	8182056	45.000	Ft
0150	Conduit, DB, 4, 3 inch	8182059	10.000	Ft
0155	Conduit, DB, 1, 1 inch	8182060	20.000	Ft
0160	Cable Pole, TS, Disman	8182210	1.000	Ea
0165	Cable, Sec, 600V, 1, 3/C#6	8182238	75.000	Ft
0170	Hh, Polymer Conc	8182309	2.000	Ea
0175	Hh, Round	8182310	3.000	Ea
0180	Hh, Round, 3 foot dia	8182319	1.000	Ea
0185	Hh, Rem	8182330	2.000	Ea
0190	Wood Pole, Rem	8182363	1.000	Ea
0195	Serv Disconnect	8182366	1.000	Ea
0200	Case Sign, Rem	8200020	1.000	Ea
0205	Controller and Cabinet, Rem	8200030	1.000	Ea
0210	Controller Fdn, Base Mtd	8200045	1.000	Ea
0215	Global Positioning System Module	8200050	1.000	Ea
0220	Pedestal, Alum	8200100	3.000	Ea
0225	Pedestal, Fdn	8200105	4.000	Ea
0230	Pedestal Fdn, Rem	8200106	2.000	Ea
0235	Pedestal, Rem	8200110	2.000	Ea
0240	Pedestal, Pushbutton, Alum	8200118	1.000	Ea
0245	Pushbutton and Sign	8200121	4.000	Ea
0250	Span Wire	8200140	4.000	Ea
0255	Span Wire, Rem	8200141	1.000	Ea
0260	Span Wire Tether	8200142	4.000	Ea
0265	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	2.000	Ea
0270	TS, Pedestrian, Pedestal Mtd, Rem	8200181	2.000	Ea
0275	TS, Span Wire Mtd, Rem	8200182	2.000	Ea
0280	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	3.000	Ea
0285	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0290	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	3.000	Ea
0295	Bracket, Truss, with 6 foot Arm	8200374	2.000	Ea
0300	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
0305	Video Traf Detection System	8200380	1.000	Ea
0310	Video Traf Detection Camera	8200381	4.000	Ea
0315	Junction Box, Span Wire	8200456	4.000	Ea
0320	Junction Box, Rem	8200457	1.000	Ea
0325	Strain Pole, Steel, 6 bolt, Size 1B	8200464	3.000	Ea
0330	Strain Pole, Steel, 6 bolt, Size 2	8200466	1.000	Ea
0335	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	66.000	Ft
0340	Casing, 48 inch	8200486	52.000	Ft
0345	Backplate, TS	8200501	10.000	Ea
0350	TS, One Way Span Wire Mtd (LED), Long Life	8202287	8.000	Ea

0355	TS, One Way Span Wire Mtd, FYA (LED), Long Life	8202299	2.000	Ea
0360	_ Cabinet, NEMA Type, Modified	8207050	1.000	Ea
0365	_ Controller, NEMA, ATC Type, Modified	8207050	1.000	Ea
0370	_ St Name Sign Bracket Arm, 6 Foot	8207050	2.000	Ea
0375	_ St Name Sign, Two Way, LED, 6 foot	8207050	2.000	Ea
0380	Lightning Protection, Pole	8260021	1.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 029

Letting Date: November 7, 2025

Contract ID: 76000-221195

Description: 0.32 mi of Safe Routes to School pedestrian improvements including concrete sidewalk and ramp upgrades, pedestrian crossing signage, pedestrian lighting and pavement markings, on various routes in the village of New Lothrop, Shiawassee County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221195A	25A0942	N/A	TAL 76000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$60,000.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	5.000	Ea
0015	Sewer, Rem, Less than 24 inch	2030015	108.000	Ft
0020	Sidewalk, Rem	2040055	650.000	Syd
0025	_ Pavt, Rem, Modified	2047011	1,500.000	Syd
0030	Excavation, Earth	2050016	1,600.000	Cyd
0035	Erosion Control, Inlet Protection, Fabric Drop	2080020	14.000	Ea
0040	Subbase, CIP	3010002	750.000	Cyd
0045	Aggregate Base, 6 inch	3020016	1,200.000	Syd
0050	Sewer, CI IV, 12 inch, Tr Det B	4020987	101.000	Ft
0055	Dr Structure Cover, Adj, Case 1	4030005	4.000	Ea
0060	Dr Structure Cover, Adj, Case 2	4030006	5.000	Ea
0065	Dr Structure Cover, Type B	4030010	1.000	Ea
0070	Dr Structure Cover, Type G	4030040	1.000	Ea
0075	Dr Structure Cover, Type K	4030050	6.000	Ea
0080	Dr Structure Cover, Type Q	4030065	1.000	Ea
0085	Dr Structure, 24 inch dia	4030200	1.000	Ea
0090	Dr Structure, 48 inch dia	4030210	4.000	Ea
0095	Dr Structure, 60 inch dia	4030220	1.000	Ea
0100	Dr Structure, Tap, 8 inch	4030308	1.000	Ea
0105	Dr Structure, Tap, 12 inch	4030312	1.000	Ea
0110	Dr Structure, Tap, 15 inch	4030315	1.000	Ea
0115	Hand Patching	5010025	200.000	Ton
0120	HMA Approach	5010061	150.000	Ton
0125	Driveway, Nonreinf Conc, 6 inch	8010005	35.000	Syd
0130	Curb and Gutter, Conc, Det F4	8020038	1,500.000	Ft
0135	Detectable Warning Surface	8030010	120.000	Ft

0140	Curb Ramp Opening, Conc	8030030	150.000	Ft
0145	Sidewalk, Conc, 4 inch	8030044	12,500.000	Sft
0150	Sidewalk, Conc, 6 inch	8030046	1,450.000	Sft
0155	Curb Ramp, Conc, 6 inch	8032002	1,300.000	Sft
0160	Post, Steel, 3 pound	8100371	162.000	Ft
0165	Sign, Type II, Erect, Salv	8100396	2.000	Ea
0170	Sign, Type IIIB	8100405	186.000	Sft
0175	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	675.000	Ft
0180	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	250.000	Ft
0185	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	75.000	Ft
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	30.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	30.000	Ea
0210	Lighted Arrow, Type B, Furn	8120130	2.000	Ea
0215	Lighted Arrow, Type B, Oper	8120131	2.000	Ea
0220	Minor Traf Devices	8120170	1.000	LSUM
0225	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0230	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	750.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	750.000	Sft
0245	Traf Regulator Control	8120370	1.000	LSUM
0250	Slope Restoration, Non-Freeway, Type A	8162001	3,200.000	Syd
0255	Conduit, Directional Bore, 1, 1 1/2 inch	8182034	360.000	Ft
0260	Conduit, DB, 1, 1 1/2 inch	8182048	1,650.000	Ft
0265	Hh, Polymer Conc	8182309	6.000	Ea
0270	_ Decorative Ltg Controller Cabinet, Wall Mtd	8197050	1.000	Ea
0275	_ Decorative Pole and Light	8197050	12.000	Ea
0280	_ Decorative Pole, Fdn	8197050	12.000	Ea
0285	Pedestal, Alum	8200100	8.000	Ea
0290	Pedestal, Fdn	8200105	8.000	Ea
0295	Pushbutton and Sign	8200121	8.000	Ea
0300	_ Flsh Beacon, Rectangular Rapid, Solar Power	8207050	8.000	Ea
0305	_ Site Elec, Wiring	8207051	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 030

Letting Date: November 7, 2025

Contract ID: 58071-219344

Description: 0.10 mi of streetscape and pedestrian improvements including reconstruction of concrete sidewalk and ramps, curb, and lighting work along South Dixie Highway from Manhattan Street to Erie Road, Monroe County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219344A	25A0917	N/A	TAU 58071

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$30,300.00	1100001	1.000	LSUM
0010	Stump, Rem, 6 inch to 18 inch	2020008	5.000	Ea
0015	Curb, Rem	2040021	822.000	Ft
0020	Pavt, Rem	2040050	205.000	Syd
0025	Sidewalk, Rem	2040055	919.000	Syd
0030	Utility Pole, Rem	2040070	1.000	Ea
0035	Embankment, CIP	2050010	179.000	Cyd
0040	Excavation, Earth	2050016	62.000	Cyd
0045	Erosion Control, Inlet Protection, Fabric Drop	2080020	9.000	Ea
0050	Project Cleanup	2090001	1.000	LSUM
0055	Aggregate Base	3020001	303.000	Ton
0060	Driveway Maintenance, Commercial	3062000	5.000	Ea
0065	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0070	Dr Structure, Temp Lowering	4030390	4.000	Ea
0075	HMA Surface, Rem	5010005	300.000	Syd
0080	Hand Patching	5010025	45.000	Ton
0085	Conduit, 3 inch	7060030	1,020.000	Ft
0090	Conc, Grade 3500	7062001	8.000	Cyd
0095	_ Joint Sealant	8007001	81.000	Ft
0100	Driveway, Nonreinf Conc, 6 inch	8010005	295.000	Syd
0105	Curb, Conc, Det E1	8020001	951.000	Ft
0110	Detectable Warning Surface	8030010	63.000	Ft
0115	Curb Ramp Opening, Conc	8030030	88.000	Ft
0120	Sidewalk, Conc, 4 inch	8030044	6,798.000	Sft
0125	Sidewalk, Conc, 6 inch	8030046	640.000	Sft
0130	Curb Ramp, Conc, 4 inch	8032001	259.000	Sft
0135	Curb Ramp, Conc, 6 inch	8032002	415.000	Sft

0140	_ Handrail	8087001	42.000	Ft
0145	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	292.000	Ft
0150	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	163.000	Ft
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0160	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0165	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0170	Pedestrian Type II Channelizer, Temp	8120027	1,000.000	Ft
0175	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	55.000	Ea
0180	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	55.000	Ea
0185	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0190	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0195	Minor Traf Devices	8120170	1.000	LSUM
0200	Sign Cover	8120310	5.000	Ea
0205	Sign, Type B, Temp, Prismatic, Furn	8120350	232.000	Sft
0210	Sign, Type B, Temp, Prismatic, Oper	8120351	232.000	Sft
0215	Traf Regulator Control	8120370	1.000	LSUM
0220	Pedestrian Path, Temp	8122250	1,000.000	Ft
0225	Pedestrian Ramp, Temp	8122251	8.000	Ea
0230	Slope Restoration, Non-Freeway, Type A	8162001	131.000	Syd
0235	Hh, Polymer Conc	8182309	10.000	Ea
0240	TS Face, Bag	8200458	8.000	Ea
0245	TS Face, Bag, Rem	8200459	8.000	Ea
0250	Water Shutoff, Adj, Temp, Case 1	8230381	1.000	Ea
0255	Gate Box, Adj, Temp, Case 1	8230391	1.000	Ea
0260	Water Shutoff, Adj, Case 1	8230421	1.000	Ea
0265	Gate Box, Adj, Case 1	8230431	1.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 031

Letting Date: November 7, 2025

Contract ID: 82000-220113

Description: Traffic signal modernization on various routes at multiple locations in the city of Detroit, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220113A	25A0950	N/A	HSIP 82000
220114A	25A0952	N/A	HSIP 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$118,600.00	1100001	1.000	LSUM
0010	Exploratory Investigation, Vertical	2040080	200.000	Ft
0015	_ Sidewalk, Rem, Modified	2047011	200.000	Syd
0020	Excavation, Earth	2050016	300.000	Cyd
0025	Granular Material, CI II	2050023	500.000	Cyd
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	500.000	Cyd
0035	_ Sidewalk, Conc, 4 inch, Modified	8027010	1,000.000	Sft
0040	_ Sidewalk, Conc, 6 inch, Modified	8027010	600.000	Sft
0045	Sign, Type IIIA	8100404	760.000	Sft
0050	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	26.000	Ea
0055	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	26.000	Ea
0060	Pedestrian Type II Barricade, Temp	8120026	10.000	Ea
0065	Lighted Arrow, Type C, Furn	8120140	6.000	Ea
0070	Lighted Arrow, Type C, Oper	8120141	6.000	Ea
0075	Minor Traf Devices	8120170	1.000	LSUM
0080	Plastic Drum, Fluorescent, Furn	8120252	200.000	Ea
0085	Plastic Drum, Fluorescent, Oper	8120253	200.000	Ea
0090	Sign, Type B, Temp, Prismatic, Furn	8120350	1,400.000	Sft
0095	Sign, Type B, Temp, Prismatic, Oper	8120351	1,400.000	Sft
0100	_ Horticulture Work	8157040	10.000	Hr
0105	Conduit, Rem	8182000	15.000	Ft
0110	Cable, Rem	8182196	1,400.000	Ft
0115	Cable, Sec, Rem	8182199	1,600.000	Ft
0120	Cable Pole, TS and Sec, Disman	8182209	1.000	Ea
0125	Cable Pole, TS, Disman	8182210	3.000	Ea

0130	Cable, Sec, 600V, 1, 3/C#6	8182238	2,050.000	Ft
0135	Wood Pole, Cl 4, 45 foot	8182352	17.000	Ea
0140	Wood Pole, Rem	8182363	14.000	Ea
0145	Serv Disconnect	8182366	10.000	Ea
0150	Serv Disconnect, Rem	8182367	6.000	Ea
0155	Wood Pole, Fit Up, TS and Sec Cable Pole	8182386	6.000	Ea
0160	_ Conduit, Encased, 2, 3 inch, Modified	8187001	117.000	Ft
0165	_ Conduit, Encased, 3, 4 inch, Modified	8187001	95.000	Ft
0170	_ Hh, Round, Detroit	8187050	9.000	Ea
0175	Case Sign, Rem	8200020	3.000	Ea
0180	Case Sign (LED), Two Way, 24 inch by 30 inch	8200022	9.000	Ea
0185	Conduit Repr, Under Pavt	8200027	50.000	Ft
0190	Conduit Repr, Under Sidewalk or Earth	8200028	50.000	Ft
0195	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	4.000	Ea
0200	Controller and Cabinet, Rem	8200030	10.000	Ea
0205	Controller Fdn, Base Mtd	8200045	10.000	Ea
0210	Controller Fdn, Rem	8200046	5.000	Ea
0215	Fdn, Rem	8200065	17.000	Ea
0220	Pedestal Fdn, Rem	8200106	9.000	Ea
0225	Pedestal, Rem	8200110	10.000	Ea
0230	Pushbutton, Rem	8200122	8.000	Ea
0235	Span Wire	8200140	41.000	Ea
0240	Span Wire, Rem	8200141	15.000	Ea
0245	Span Wire Tether	8200142	38.000	Ea
0250	Steel Pole, Rem	8200145	16.000	Ea
0255	Guy, Rem	8200167	1.000	Ea
0260	TS, Bracket Arm Mtd, Rem	8200175	6.000	Ea
0265	TS, Pedestal Mtd, Rem	8200179	2.000	Ea
0270	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	36.000	Ea
0275	TS, Pedestrian, Pedestal Mtd, Rem	8200181	10.000	Ea
0280	TS, Span Wire Mtd, Rem	8200182	28.000	Ea
0285	TS, Pedestrian, Two Way Bracket Arm Mtd, Salv	8200228	1.000	Ea
0290	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	4.000	Ea
0295	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	39.000	Ea
0300	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	1.000	Ea
0305	Bracket, Truss, with 18 foot Arm	8200378	5.000	Ea
0310	Bracket, Truss, Salv	8200385	1.000	Ea
0315	Bracket, Truss, Rem	8200388	4.000	Ea
0320	Junction Box, Span Wire	8200456	2.000	Ea
0325	Strain Pole, Steel, 6 bolt, Size 1A	8200463	18.000	Ea
0330	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	342.000	Ft
0335	Casing, 42 inch	8200485	270.000	Ft
0340	Backplate, TS, Rem	8200502	8.000	Ea

0345	TS, One Way Span Wire Mtd (LED), Long Life	8202287	80.000	Ea
0350	_ Antenna, Spectrum	8207050	10.000	Ea
0355	_ Backplate, TS, Detroit	8207050	86.000	Ea
0360	_ Controller and Cabinet, Digital Type, ITS	8207050	10.000	Ea
0365	_ Pedestal Alum, Modified	8207050	1.000	Ea
0370	_ St Name Sign Bracket Arm, 4 Foot	8207050	20.000	Ea
0375	_ St Name Sign Bracket Arm, 5 Foot	8207050	20.000	Ea
0380	_ Transfer Switch, Detroit	8207050	11.000	Ea
0385	_ Video Capture and Streaming System, Salv	8207050	6.000	Ea
0390	_ Video Detection and Analytics System, Salv	8207050	6.000	Ea
0395	_ Wireless Data Acquisition and Alerts System, Salv	8207050	9.000	Ea
0400	_ Wireless Data Acquisition, Alerts and Analytics System	8207050	1.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 032

Letting Date: November 7, 2025

Contract ID: 41000-209987

Description: 0.30 mi of concrete sidewalk and ramps, concrete curb and gutter, pedestrian refuge, hot mix asphalt hand patching, and permanent pavement markings on Argo Avenue SE from Hall Street to Cascade Road and Forest Hill Drive SE from Hall Street to Orchard Creek Drive in the city of Kentwood, Kent County. This is a Local Agency project. This is a Small Business Program project. Only those approved by MDOT as a Small Business may be eligible to bid as a prime contractor.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
209987A	25A0943	N/A	TA 41000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$40,000.00	1100001	1.000	LSUM
0010	Stump, Rem, 6 inch to 18 inch	2020008	7.000	Ea
0015	Culv, Rem, Less than 24 inch	2030001	9.000	Ea
0020	Culv, End, Rem, Less than 24 inch	2030005	1.000	Ea
0025	Curb and Gutter, Rem	2040020	610.000	Ft
0030	Pavt, Rem	2040050	282.000	Syd
0035	Sidewalk, Rem	2040055	53.000	Syd
0040	Embankment, CIP	2050010	720.000	Cyd
0045	Excavation, Earth	2050016	1,150.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	3.000	Ea
0055	Erosion Control, Silt Fence	2080036	500.000	Ft
0060	_ Project Cleanup, Modified	2097051	1.000	LSUM
0065	Subbase, CIP	3010002	492.000	Cyd
0070	Aggregate Base	3020001	40.000	Ton
0075	Approach, CI I, 6 inch	3070008	548.000	Syd
0080	Culv End Sect, Conc, 12 inch	4010047	18.000	Ea
0085	Culv End Sect, Conc, 15 inch	4010048	1.000	Ea
0090	Culv, CI E, Conc, 12 inch	4010573	274.000	Ft
0095	Culv, CI E, Conc, 15 inch	4010574	16.000	Ft
0100	_ Sewer, CI A, Perforated SLCPP W\Sock, 12 inch, Tr Det B, Modified	4027001	250.000	Ft
0105	_ Sewer, CI A, Perforated SLCPP W\Sock, 15 inch, Tr Det B, Modified	4027001	7.000	Ft
0110	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0115	Dr Structure Cover, Adj, Case 2	4030006	1.000	Ea
0120	Dr Structure Cover, Type B	4030010	1.000	Ea
0125	_ Dr Structure, 48 inch dia, leaching with 2 ft sump	4037050	1.000	Ea

0130	Underdrain, Subbase, 4 inch	4040061	195.000	Ft
0135	Underdrain, Subbase, 6 inch	4040063	26.000	Ft
0140	HMA Surface, Rem	5010005	1,135.000	Syd
0145	Hand Patching	5010025	68.000	Ton
0150	HMA Approach	5010061	113.000	Ton
0155	HMA, 4EML	5012025	15.000	Ton
0160	_ HMA Spillway	5017001	5.000	Ft
0165	Saw Cut, Intermediate	6030090	145.000	Ft
0170	Driveway, Nonreinf Conc, 6 inch	8010005	126.000	Syd
0175	Curb and Gutter, Conc, Det B2	8020016	289.000	Ft
0180	Curb and Gutter, Conc, Det F4	8020038	604.000	Ft
0185	Spillway, Conc	8020075	8.000	Ft
0190	_ Curb, Conc, Det E4, Modified	8027001	138.000	Ft
0195	_ Driveway Opening, Conc, Det M, Modified	8027001	19.000	Ft
0200	Detectable Warning Surface	8030010	135.000	Ft
0205	Curb Ramp Opening, Conc	8030030	144.000	Ft
0210	Sidewalk, Conc, 4 inch	8030044	3,550.000	Sft
0215	Sidewalk, Conc, 6 inch	8030046	14,070.000	Sft
0220	Curb Ramp, Conc, 6 inch	8032002	746.000	Sft
0225	Pavt Mrkg, Ovly Cold Plastic, 4 inch, Yellow	8110023	280.000	Ft
0230	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	60.000	Ft
0235	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0240	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0245	Pedestrian Type II Barricade, Temp	8120026	9.000	Ea
0250	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	75.000	Ea
0255	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	75.000	Ea
0260	Minor Traf Devices	8120170	1.000	LSUM
0265	Plastic Drum, Fluorescent, Furn	8120252	24.000	Ea
0270	Plastic Drum, Fluorescent, Oper	8120253	24.000	Ea
0275	Sign, Type B, Temp, Prismatic, Furn	8120350	287.000	Sft
0280	Sign, Type B, Temp, Prismatic, Oper	8120351	287.000	Sft
0285	Traf Regulator Control	8120370	1.000	LSUM
0290	Riprap, Plain	8130010	35.000	Syd
0295	Mulch Blanket	8160027	975.000	Syd
0300	Mulch Blanket, High Velocity	8160028	525.000	Syd
0305	_ Roadside Seeding	8167011	1,500.000	Syd
0310	Water Shutoff, Adj, Case 2	8230422	1.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 033

Letting Date: November 7, 2025

Contract ID: 50000-220186

Description: Traffic signal improvements, vehicle and pedestrian detection and sidewalk ramp upgrades on various routes in the city of Fraser, Macomb County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220186A	25A0964	N/A	HSIP 50000
220187A	25A0972	N/A	HSIP 50000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$140,000.00	1100001	1.000	LSUM
0010	Curb, Rem	2040021	280.000	Ft
0015	Sidewalk, Rem	2040055	114.000	Syd
0020	Exploratory Investigation, Vertical	2040080	72.000	Ft
0025	Excavation, Earth	2050016	5.000	Cyd
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0035	Coating Galvanized Support Structures	7160010	23.000	Ea
0040	Curb and Gutter, Conc, Det F4	8020038	296.000	Ft
0045	Detectable Warning Surface	8030010	112.000	Ft
0050	Curb Ramp Opening, Conc	8030030	132.000	Ft
0055	Curb Ramp, Conc, 6 inch	8032002	1,224.000	Sft
0060	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0070	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0075	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Sign Cover	8120310	20.000	Ea
0090	Sign, Type B, Temp, Prismatic, Furn	8120350	200.000	Sft
0095	Sign, Type B, Temp, Prismatic, Oper	8120351	200.000	Sft
0100	Traf Regulator Control	8120370	1.000	LSUM
0105	_ Turf Estabilshment	8167011	4,400.000	Syd
0110	Conduit, Rem	8182000	351.000	Ft
0115	Conduit, DB, 1, 1 1/2 inch	8182048	923.000	Ft
0120	Conduit, DB, 1, 3 inch	8182050	564.000	Ft
0125	Conduit, DB, 3, 3 inch	8182056	282.000	Ft
0130	Conduit, DB, 4, 3 inch	8182059	135.000	Ft

0135	Cable Pole, TS, Disman	8182210	13.000	Ea
0140	Cable, Sec, 600V, 1, 3/C#6	8182238	1,170.000	Ft
0145	Hh, Round	8182310	18.000	Ea
0150	Hh, Round, 3 foot dia	8182319	6.000	Ea
0155	Hh, Rem	8182330	4.000	Ea
0160	Wood Pole, Rem	8182363	7.000	Ea
0165	Serv Disconnect	8182366	7.000	Ea
0170	Serv Disconnect, Rem	8182367	7.000	Ea
0175	Wood Pole, Fit Up, TS Cable Pole	8182387	8.000	Ea
0180	Steel Pole, Fit Up, TS Cable Pole	8182397	4.000	Ea
0185	_ Recable Intersection	8187051	1.000	LSUM
0190	Anchor Guy	8200001	2.000	Ea
0195	Case Sign, Rem	8200020	2.000	Ea
0200	Controller and Cabinet, Rem	8200030	6.000	Ea
0205	Fdn, Rem	8200065	3.000	Ea
0210	Splice Box, Rem	8200086	1.000	Ea
0215	Pedestal, Fdn	8200105	22.000	Ea
0220	Pedestal Fdn, Rem	8200106	4.000	Ea
0225	Pedestal, Rem	8200110	4.000	Ea
0230	Pushbutton, Rem	8200122	11.000	Ea
0235	Span Wire	8200140	24.000	Ea
0240	Span Wire, Rem	8200141	16.000	Ea
0245	Steel Pole, Rem	8200145	7.000	Ea
0250	Guy, Rem	8200167	5.000	Ea
0255	Strut Guy	8200168	2.000	Ea
0260	TS, Bracket Arm Mtd, Rem	8200175	13.000	Ea
0265	TS, Pedestal Mtd, Rem	8200179	4.000	Ea
0270	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	13.000	Ea
0275	TS, Pedestrian, Pedestal Mtd, Rem	8200181	7.000	Ea
0280	TS, Span Wire Mtd, Rem	8200182	16.000	Ea
0285	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	18.000	Ea
0290	Video Traf Detection Camera, Rem	8200384	16.000	Ea
0295	Bracket, Truss, Salv	8200385	2.000	Ea
0300	Bracket, Truss, Rem	8200388	18.000	Ea
0305	Strain Pole, Steel, 6 bolt, Size 1A	8200463	14.000	Ea
0310	Strain Pole, Steel, 6 bolt, Size 2	8200466	2.000	Ea
0315	Strain Pole, Steel, 6 bolt, Size 4	8200468	8.000	Ea
0320	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	123.000	Ft
0325	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	174.000	Ft
0330	Casing, 42 inch	8200485	96.000	Ft
0335	Casing, 48 inch	8200486	96.000	Ft
0340	_ ATC Cabinet Fdn, 340	8207050	6.000	Ea
0345	_ ATC Cabinet Operational Test Certification	8207050	6.000	Ea
0350	_ ATC Cabinet, 340, 32 Output, Black	8207050	6.000	Ea

0355	_ ATC Controller	8207050	6.000	Ea
0360	_ Case Sign (LED), One Way, 24 inch by 30 inch, Black	8207050	2.000	Ea
0365	_ Fiber Optic, Pigtail, Modified	8207050	4.000	Ea
0370	_ Fiber Optic, Splice	8207050	8.000	Ea
0375	_ Hemispherical Video Detection Camera, Modified	8207050	22.000	Ea
0380	_ Hemispherical Video Detection System, Modified	8207050	11.000	Ea
0385	_ Pedestal, Black	8207050	22.000	Ea
0390	_ Pushbutton and Sign, Black	8207050	9.000	Ea
0395	_ Radar Detection, Dilemma Zone	8207050	29.000	Ea
0400	_ Radar Detection, Rem	8207050	20.000	Ea
0405	_ RSU, Rem and Relocate	8207050	6.000	Ea
0410	_ Span Wire Tether, Modified	8207050	25.000	Ea
0415	_ St Name Sign, Two Way (LED) Illuminated, 8 foot, Black	8207050	11.000	Ea
0420	_ St Name Sign, Two Way, (LED) Illuminated, 10 foot, Black	8207050	9.000	Ea
0425	_ Steel Truss Arm, Adj	8207050	2.000	Ea
0430	_ Steel Truss Arm, Steel Pole Mtd, 18 Foot, Black	8207050	14.000	Ea
0435	_ Steel Truss Arm, Steel Pole Mtd, 6 Foot, Black	8207050	7.000	Ea
0440	_ Steel Truss Arm, Wood Pole Mtd, 18 Foot, Black	8207050	1.000	Ea
0445	_ TS, One Way Span Wire Mtd, Safety	8207050	44.000	Ea
0450	_ TS, One Way Span Wire Mtd, Safety, Five Sect	8207050	8.000	Ea
0455	_ TS, One Way Span Wire Mtd, Safety, FYA	8207050	16.000	Ea
0460	_ Video Surveillance, Camera, Rem	8207050	5.000	Ea
0465	_ Video Surveillance, Camera, Salv	8207050	1.000	Ea
0470	_ Wireless Interconnect, Access Point, Rem	8207050	1.000	Ea
0475	_ Wireless Interconnect, Dual Radio, Rem	8207050	4.000	Ea
0480	_ Wireless Interconnect, Integrated Radio	8207050	15.000	Ea
0485	_ Wireless Interconnect, Integrated Radio, Rem	8207050	7.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 034

Letting Date: November 7, 2025

Contract ID: 77000-218189

Description: Bridge reconstruction including replacement with 18-foot steel tub girders, concrete curb and gutter, guardrail and approach work on Frith Road at Smiths Creek, St Clair County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218189A	25A0947	N/A	BFPO 77000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$100,000.00	1100001	1.000	LSUM
0010	_ Clearing, Modified	2017002	10.000	Sta
0015	Guardrail, Rem	2040035	131.000	Ft
0020	Excavation, Earth	2050016	395.000	Cyd
0025	_ Embankment, CIP, Modified	2057021	505.000	Cyd
0030	Erosion Control, Silt Fence	2080036	918.000	Ft
0035	Project Cleanup	2090001	1.000	LSUM
0040	Subbase, CIP	3010002	186.000	Cyd
0045	_ Aggregate Base, Modified	3027031	505.000	Ton
0050	_ Aggregate Surface Cse, Modified	3067031	187.000	Ton
0055	_ Shoulder, CI II, Modified	3077031	14.000	Ton
0060	_ Shoulder, Cobble	3077031	73.000	Ton
0065	_ Geotextile Base Reinforcement	3087011	956.000	Syd
0070	_ Geotextile Stabilization, Modified	3087011	956.000	Syd
0075	HMA, 4EL	5012024	244.000	Ton
0080	Curb and Gutter, Bridge Approach, Det 5	8022016	74.000	Ft
0085	Curb and Gutter, Bridge Approach, Det 6	8022017	72.000	Ft
0090	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0095	Guardrail Anch, Bridge, Det M1	8070130	4.000	Ea
0100	Guardrail, Type MGS-8, 108 inch Post	8072180	228.000	Ft
0105	Post, Steel, 3 pound	8100371	64.000	Ft
0110	Sign, Type IIIB	8100405	26.000	Sft
0115	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0125	Minor Traf Devices	8120170	1.000	LSUM
0130	Sign, Type B, Temp, Prismatic, Furn	8120350	185.000	Sft

0135	Sign, Type B, Temp, Prismatic, Oper	8120351	185.000	Sft
0140	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	28.000	Sft
0145	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	28.000	Sft
0150	Slope Restoration, Non-Freeway, Type F	8162006	265.000	Syd
0155	Slope Restoration, Non-Freeway, Type G	8162007	635.000	Syd

Section: 2

0160	Structures, Rem (SN 10224)	2040060	1.000	LSUM
0165	Excavation, Channel	2050015	30.000	Cyd
0170	Backfill, Structure, CIP	2060002	106.000	Cyd
0175	Excavation, Fdn	2060010	1,410.000	Cyd
0180	_ Backfill, Structure, Modified	2067021	160.000	Cyd
0185	Erosion Control, Filter Bag	2080014	2.000	Ea
0190	Underdrain, Fdn, 6 inch	4040033	193.000	Ft
0195	Underdrain Outlet, 6 inch	4040093	30.000	Ft
0200	Underdrain, Outlet Ending, 6 inch	4040113	3.000	Ea
0205	Steel Sheet Piling, Temp	7040002	335.000	Sft
0210	Cofferdams, Left in Place	7040009	1.000	LSUM
0215	Pile Driving Equipment, Furn	7050002	1.000	LSUM
0220	Pile, Steel, Furn and Driven, 12 inch	7050030	2,521.000	Ft
0225	Test Pile, Steel, 12 inch	7050031	2.000	Ea
0230	Pile, Steel, Splice	7050050	33.000	Ea
0235	Bridge Ltg, Furn and Rem	7060001	1.000	LSUM
0240	Bridge Ltg, Oper and Maintain	7060002	59.000	Cyd
0245	Expansion Joint Device	7060050	33.000	Ft
0250	Expansion Joint Device, Cover Plate	7060051	3.000	Ft
0255	False Decking	7060060	475.000	Sft
0260	Reinforcement, Steel, Epoxy Coated	7060092	28,519.000	Lb
0265	Superstructure Conc, Form, Finish, and Cure	7060111	1.000	LSUM
0270	Superstructure Conc, Form, Finish, and Cure, Night Casting	7060112	1.000	LSUM
0275	Sealing Localized Cracks (SN 10224)	7060220	1.000	LSUM
0280	Conc, Grade 3500, Subfooting	7062000	96.000	Cyd
0285	_ Substructure Conc, Modified	7067021	186.000	Cyd
0290	_ Superstructure Conc, Modified	7067021	24.000	Cyd
0295	_ Superstructure Conc, Night Casting, Modified	7067021	59.000	Cyd
0300	_ Structure Name Plate	7067050	1.000	Ea
0305	Bearing, Elastomeric, 2 inch	7070016	2,592.000	Sin
0310	_ Structural Steel, Erect, Spec	7077051	1.000	LSUM
0315	_ Structural Steel, Furn and Fab, Spec	7077051	1.000	LSUM
0320	Joint Waterproofing	7100001	273.000	Sft
0325	Joint Waterproofing, Expansion	7100003	68.000	Sft
0330	Bridge Railing, 2 Tube	7110008	79.000	Ft
0335	Riprap, Plain	8130010	323.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 035

Letting Date: November 7, 2025

Contract ID: 39000-219328

Description: 1.17 mi of concrete sidewalk and ramps, storm sewer, ditch grading, hot mix asphalt hand patching, and drainage structure adjustments on S. 9th Street from Stadium Drive to Quail Run in the city of Kalamazoo, Kalamazoo County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219328A	25A0959	N/A	TAU 39000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$90,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	5.000	Ea
0015	Tree, Rem, 6 inch to 18 inch	2020004	6.000	Ea
0020	Stump, Rem, 6 inch to 18 inch	2020008	1.000	Ea
0025	Culv, Rem, Less than 24 inch	2030001	20.000	Ea
0030	Curb and Gutter, Rem	2040020	450.000	Ft
0035	Fence, Rem	2040025	60.000	Ft
0040	Masonry and Conc Structure, Rem	2040045	60.000	Cyd
0045	Sidewalk, Rem	2040055	55.000	Syd
0050	_ Pavt, Rem, Modified	2047011	190.000	Syd
0055	_ Billboard, Rem	2047050	1.000	Ea
0060	Ditch Cleanout	2050006	25.000	Sta
0065	Excavation, Earth	2050016	5.000	Cyd
0070	Subgrade Undercutting, Type II	2050041	1,165.000	Cyd
0075	_ Sidewalk, Grading	2057001	5,870.000	Ft
0080	Erosion Control, Inlet Protection, Fabric Drop	2080020	15.000	Ea
0085	Erosion Control, Silt Fence	2080036	200.000	Ft
0090	Subbase, CIP	3010002	465.000	Cyd
0095	Aggregate Base, 6 inch	3020016	1,690.000	Syd
0100	Approach, CI II	3070021	20.000	Ton
0105	Shld, CI II, 6 inch	3070128	60.000	Syd
0110	Culv End Sect, 12 inch	4010012	34.000	Ea
0115	Culv End Sect, Conc, 12 inch	4010047	2.000	Ea
0120	Culv, CI F, 12 inch	4010607	975.000	Ft
0125	Sewer, CI E, 12 inch, Tr Det B	4020600	296.000	Ft
0130	Dr Structure Cover, Adj, Case 1	4030005	3.000	Ea
0135	Dr Structure Cover, Adj, Case 2	4030006	2.000	Ea

0140	Dr Structure Cover, Type E	4030035	4.000	Ea
0145	Dr Structure, 48 inch dia	4030210	2.000	Ea
0150	HMA Surface, Rem	5010005	2,055.000	Syd
0155	Hand Patching	5010025	50.000	Ton
0160	HMA Approach	5010061	295.000	Ton
0165	Conc Base Cse, Nonreinf, 6 inch	6020015	60.000	Syd
0170	Driveway, Nonreinf Conc, 6 inch	8010005	490.000	Syd
0175	Curb, Conc, Det E2	8020002	820.000	Ft
0180	Curb and Gutter, Conc, Det C4	8020023	290.000	Ft
0185	Driveway Opening, Conc, Det M	8020050	30.000	Ft
0190	Curb Ramp Opening, Conc	8030030	160.000	Ft
0195	Sidewalk, Conc, 4 inch	8030044	28,900.000	Sft
0200	Sidewalk, Conc, 6 inch	8030046	5,375.000	Sft
0205	Curb Ramp, Conc, 6 inch	8032002	1,260.000	Sft
0210	_ Detectable Warning Surface, Cast Iron, Modified	8037001	40.000	Ft
0215	_ Sidewalk, Conc, 4 inch, Modified	8037010	460.000	Sft
0220	Post, Mailbox	8070095	24.000	Ea
0225	Post, Steel, 3 pound	8100371	180.000	Ft
0230	Sign, Type III, Erect, Salv	8100402	16.000	Ea
0235	Ground Mtd Sign Support, Rem	8102010	13.000	Ea
0240	Rem Spec Mrkg	8110343	100.000	Sft
0245	_ Pavt Mrkg, Waterborne, 12 inch, Crosswalk	8117001	100.000	Ft
0250	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	6.000	Ea
0255	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	6.000	Ea
0260	Pedestrian Type II Barricade, Temp	8120026	4.000	Ea
0265	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	300.000	Ea
0270	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	300.000	Ea
0275	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0280	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0285	Minor Traf Devices	8120170	1.000	LSUM
0290	Sign, Type B, Temp, Prismatic, Furn	8120350	360.000	Sft
0295	Sign, Type B, Temp, Prismatic, Oper	8120351	360.000	Sft
0300	Traf Regulator Control	8120370	1.000	LSUM
0305	Riprap, Plain	8130010	10.000	Syd
0310	Slope Restoration, Non-Freeway, Type E	8162005	5,445.000	Syd
0315	Slope Restoration, Non-Freeway, Type F	8162006	2,875.000	Syd
0320	Slope Restoration, Non-Freeway, Type G	8162007	710.000	Syd
0325	Hh, Adj	8182328	1.000	Ea
0330	Push Button Station, Rem	8200129	4.000	Ea
0335	_ Pedestrian Signal System, Accessible, Modified	8207050	1.000	Ea
0340	_ Push Button Station and Sign, Modified	8207050	4.000	Ea
0345	Water Shutoff, Adj, Case 1	8230421	1.000	Ea
0350	Water Shutoff, Adj, Case 2	8230422	5.000	Ea

0355

Gate Box, Adj, Case 2

8230432

3.000

Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 036

Letting Date: November 7, 2025

Contract ID: 38000-218245

Description: Bridge preventive maintenance and rehabilitation including replacement of hot mix asphalt surface, waterproofing membrane, saline treatment, deck joint replacement, concrete surface coating and approach guardrail on King Road over the north branch of the Kalamazoo River and Tompkins Road over the Grand River, Parnall Road over the Grand River, Rives Eaton Road over the Grand River and Hague Road over the Grand River, Jackson County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218245A	25A0932	N/A	BFPO 38000
218246A	25A0933	N/A	BFP 38000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$73,400.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	305.000	Ft
0015	Erosion Control, Silt Fence	2080036	350.000	Ft
0020	Cold Milling HMA Surface	5010002	836.000	Syd
0025	Guardrail Anch, Bridge, Det T4	8070025	4.000	Ea
0030	Guardrail Approach Terminal, Type 2M	8070044	4.000	Ea
0035	Guardrail Reflector	8070080	12.000	Ea
0040	Pavt Mrkg, Waterborne, 4 inch, White	8110231	1,240.000	Ft
0045	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	1,240.000	Ft
0050	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0055	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0060	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0070	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0075	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Sign, Portable, Changeable Message, Furn	8120330	10.000	Ea
0090	Sign, Portable, Changeable Message, Oper	8120331	10.000	Ea
0095	Sign, Type B, Temp, Prismatic, Furn	8120350	1,250.000	Sft
0100	Sign, Type B, Temp, Prismatic, Oper	8120351	1,250.000	Sft
0105	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0110	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft

Section: 2

0115	HMA Surface, Rem	5010005	644.000	Syd
0120	HMA, 5EML	5012037	202.000	Ton
0125	Expansion Joint Device	7060050	86.000	Ft
0130	False Decking	7060060	3,428.000	Sft
0135	Reinforcement, Steel, Epoxy Coated	7060092	59.000	Lb
0140	Conc, Grade 4500HP	7062004	1.000	Cyd
0145	_ Silane Treatment	7067010	7,560.000	Sft
0150	Membrane, Preformed Waterproofing	7100008	5,789.000	Sft
0155	Hand Chipping, Shallow	7120003	25.000	Syd
0160	Hand Chipping, Other Than Deck	7120007	50.000	Cft
0165	Patching Mortar or Conc	7120015	5.000	Cyd
0170	Patch, Forming	7120017	100.000	Sft
0175	Epoxy Ovly	7120020	1,331.000	Syd
0180	Deck Joint, Rem	7120071	86.000	Ft
0185	Patching Conc, C-L	7120112	20.000	Cyd
0190	_ Bridge Joints, Clean and Seal	7127001	80.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 037

Letting Date: November 7, 2025

Contract ID: 81000-219166

Description: 0.93 mi of hot mix asphalt shared-use path including tree removal, culvert removal and replacement, storm sewer and landscaping on Bennet Street in Mill Pond Park in the city of Saline, Washtenaw County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219166A	25A0891	N/A	CRU 81000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$101,700.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	1.000	Ea
0015	Tree, Rem, 6 inch to 18 inch	2020004	1.000	Ea
0020	Culv, Rem, Less than 24 inch	2030001	2.000	Ea
0025	Culv, Rem, 24 inch to 48 inch	2030002	2.000	Ea
0030	_ Bench, Rem, Modified	2047050	5.000	Ea
0035	_ Bench, Salv and Reinstall, Modified	2047050	1.000	Ea
0040	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0045	Subgrade Undercutting, Type II	2050041	135.000	Cyd
0050	Subgrade Undercutting, Type III	2050042	135.000	Cyd
0055	Erosion Control, Inlet Protection, Fabric Drop	2080020	1.000	Ea
0060	Erosion Control, Silt Fence	2080036	10,522.000	Ft
0065	_ Segmental Permeable Paver System, Modified	3067011	820.000	Syd
0070	_ Road Grade Biaxial Geogrid, Modified	3087011	8,085.000	Syd
0075	Culv End Sect, Conc, 12 inch	4010047	8.000	Ea
0080	Culv End Sect, Conc, 18 inch	4010049	2.000	Ea
0085	Culv End Sect, Conc, 24 inch	4010051	4.000	Ea
0090	Culv, CI E, Conc, 12 inch	4010573	264.000	Ft
0095	Culv, CI E, Conc, 18 inch	4010575	25.000	Ft
0100	Culv, CI E, Conc, 24 inch	4010576	168.000	Ft
0105	_ Sewer, Conc, 12 inch, Tr Det B, Modified	4027001	91.000	Ft
0110	_ Sewer, PVC, 8 inch, Tr Det B, Modified	4027001	16.000	Ft
0115	Dr Structure Cover, Type Q	4030065	1.000	Ea
0120	Dr Structure, 48 inch dia	4030210	1.000	Ea
0125	_ Combined Sewer Manhole, Cover, Adj, Case 2, Modified	4037050	1.000	Ea
0130	Underdrain, Subgrade, 6 inch	4040073	50.000	Ft

0135	Underdrain Outlet, 6 inch	4040093	10.000	Ft
0140	Underdrain, Outlet Ending, 6 inch	4040113	1.000	Ea
0145	_ Bench Pad, Conc, 4 inch, Modified	8037011	66.000	Syd
0150	Shared use Path, Grading	8060030	5,195.000	Ft
0155	Shared use Path, HMA	8060040	1,235.000	Ton
0160	_ Shared use Path, Aggregate, 8 inch, Modified	8067011	6,284.000	Syd
0165	Fence, Protective	8080007	480.000	Ft
0170	Post, Steel, 3 pound	8100371	48.000	Ft
0175	Sign, Type IIIB	8100405	9.000	Sft
0180	Minor Traf Devices	8120170	1.000	LSUM
0185	Plastic Drum, Fluorescent, Furn	8120252	76.000	Ea
0190	Plastic Drum, Fluorescent, Oper	8120253	76.000	Ea
0195	Sign Cover	8120310	2.000	Ea
0200	Sign, Type B, Temp, Prismatic, Furn	8120350	276.000	Sft
0205	Sign, Type B, Temp, Prismatic, Oper	8120351	276.000	Sft
0210	Traf Regulator Control	8120370	1.000	LSUM
0215	Watering and Cultivating, First Season, Min \$10,000.00	8150002	1.000	LSUM
0220	Watering and Cultivating, 2nd Season, Min \$12,500.00	8150003	1.000	LSUM
0225	_ Landscaping, Native Plantings, Modified	8167011	6,050.000	Syd
0230	_ Slope Restoration, Modified	8167011	4,170.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 038

Letting Date: November 7, 2025

Contract ID: 82000-219908

Description: Pedestrian signal upgrades on various routes in the city of Westland, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219908A	25A0962	N/A	VRU 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Reimbursed Permit Fees	1077060	10,000.000	Dir
0010	Mobilization, Max \$44,600.00	1100001	1.000	LSUM
0015	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0020	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0025	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0030	Minor Traf Devices	8120170	1.000	LSUM
0035	Sign, Type B, Temp, Prismatic, Furn	8120350	600.000	Sft
0040	Sign, Type B, Temp, Prismatic, Oper	8120351	600.000	Sft
0045	Traf Regulator Control	8120370	1.000	LSUM
0050	Wood Pole, Cl 4, 35 foot	8182350	2.000	Ea
0055	Case Sign (LED), One Way, 12 inch by 27 inch	8200019	5.000	Ea
0060	Case Sign, Rem	8200020	5.000	Ea
0065	Pedestal, Alum	8200100	36.000	Ea
0070	Pedestal, Rem	8200110	36.000	Ea
0075	Pushbutton and Sign	8200121	1.000	Ea
0080	Pushbutton, Rem	8200122	1.000	Ea
0085	Pushbutton and Sign, Salv	8200126	1.000	Ea
0090	TS, Bracket Arm Mtd, Rem	8200175	9.000	Ea
0095	TS, Pedestal Mtd, Rem	8200179	7.000	Ea
0100	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	99.000	Ea
0105	TS, Pedestrian, Pedestal Mtd, Rem	8200181	59.000	Ea
0110	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	16.000	Ea
0115	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	100.000	Ea
0120	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	4.000	Ea
0125	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	47.000	Ea
0130	TS, One Way Bracket Arm Mtd (LED), Long Life	8202200	5.000	Ea

0135	TS, One Way Pedestal Mtd (LED), Long Life	8202251	7.000	Ea
------	---	---------	-------	----



Schedule of Pay Items

Report v1

Letting Call: 251107 039

Letting Date: November 7, 2025

Contract ID: 79000-215495

Description: 6.97 mi of hot mix asphalt paving, micro cold milling and overlay, aggregate shoulders, permanent signing, and permanent pavement markings on Bray Road from Willard Road to Ormes Road in Tuscola County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215495A	25A0928	N/A	STL 79000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$137,600.00	1100001	1.000	LSUM
0010	Erosion Control, Silt Fence	2080036	100.000	Ft
0015	Approach, CI II	3070021	595.000	Ton
0020	Shld, CI II	3070121	3,654.000	Ton
0025	_ Approach, CI II, Modified	3077031	140.000	Ton
0030	Pavt for Butt Joints, Rem	5010008	3,599.000	Syd
0035	HMA Approach	5010061	339.000	Ton
0040	HMA, 4EL	5012024	9,300.000	Ton
0045	_ Micro Texture Pavt Milling, Modified	5017011	98,657.000	Syd
0050	Post, Mailbox	8070095	10.000	Ea
0055	Post, Steel, 3 pound	8100371	2,637.000	Ft
0060	Post, Wood, 6 inch by 8 inch	8100382	108.000	Ft
0065	Sign, Type II, Rem	8100397	5.000	Ea
0070	Sign, Type IIA	8100398	123.000	Sft
0075	Sign, Type IIB	8100399	12.000	Sft
0080	Sign, Type III, Rem	8100403	117.000	Ea
0085	Sign, Type IIIA	8100404	314.000	Sft
0090	Sign, Type IIIB	8100405	399.000	Sft
0095	Reflective Panel for Permanent Sign Support, 3 foot	8100613	40.000	Ea
0100	Reflective Panel for Permanent Sign Support, 6 foot	8100616	48.000	Ea
0105	Ground Mtd Sign Support, Rem	8102010	139.000	Ea
0110	_ Sign, Type IA, Modified	8107010	24.000	Sft
0115	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	132.000	Ft
0120	Pavt Mrkg, Waterborne, 4 inch, White	8110231	73,737.000	Ft
0125	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	24,316.000	Ft
0130	Recessing Pavt Mrkg, Transv	8110451	145.000	Sft
0135	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	106.000	Ea

0140	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	106.000	Ea
0145	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0150	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0155	Minor Traf Devices	8120170	1.000	LSUM
0160	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0165	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0170	Pavt Mrkg, Wet Reflective, Type NR, Tape, 4 inch, Yellow, Temp	8120264	3,988.000	Ft
0175	Sign, Type B, Temp, Prismatic, Furn	8120350	1,022.000	Sft
0180	Sign, Type B, Temp, Prismatic, Oper	8120351	1,022.000	Sft
0185	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	50.000	Sft
0190	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	50.000	Sft
0195	Traf Regulator Control	8120370	1.000	LSUM
0200	_ Slope Restoration, Modified	8167011	8,200.000	Syd
0205	Monument Box	8210001	14.000	Ea
0210	Monument Preservation	8210010	14.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 040

Letting Date: November 7, 2025

Contract ID: 86000-M00240

Description: Installation of 12 dynamic message signs on toll canopy of the Mackinac Bridge Toll Bridge Plaza on I-75, Mackinac County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
M00240	N/A	N/A	M 86000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$69,600.00	1100001	1.000	LSUM
0010	_ Dynamic Message Sign, Full Color, 10 mm, 108 by 252	8007050	12.000	Ea
0015	_ Dynamic Message Sign, Small, Rem	8007050	12.000	Ea
0020	_ Integration, Mackinac Bridge Tolling System Software	8007051	1.000	LSUM
0025	_ System Integration and Testing	8007051	1.000	LSUM
0030	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0035	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0040	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0045	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0050	Sign, Type B, Temp, Prismatic, Furn	8120350	100.000	Sft
0055	Sign, Type B, Temp, Prismatic, Oper	8120351	100.000	Sft
0060	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM



Schedule of Pay Items

Report v1

Letting Call: 251107 041

Letting Date: November 7, 2025

Contract ID: 30071-221311

Description: 0.06 mi of hot mix asphalt reconstruction, culvert replacement, signing and pavement markings on US-127 south of Beecher Road at Bean Creek Tributary, Hillsdale County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221311A	25A0996	N/A	NH 30071

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$109,500.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.500	Acre
0015	Tree, Rem, 6 inch to 18 inch	2020004	3.000	Ea
0020	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0025	Pavt, Rem	2040050	151.000	Syd
0030	Embankment, CIP	2050010	1,509.000	Cyd
0035	Excavation, Earth	2050016	2,021.000	Cyd
0040	Granular Material, CI III	2050024	21.000	Cyd
0045	Flowable Fill, Non-Structural	2050148	25.000	Cyd
0050	Backfill, Structure, CIP	2060002	1,331.000	Cyd
0055	Erosion Control, Check Dam, Stone	2080012	40.000	Ft
0060	Erosion Control, Filter Bag	2080014	4.000	Ea
0065	Erosion Control, Gravel Filter Berm	2080018	180.000	Ft
0070	Erosion Control, Inlet Protection, Sediment Trap	2080024	2.000	Ea
0075	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0080	Erosion Control, Sediment Basin	2080032	5.000	Cyd
0085	Erosion Control, Silt Fence	2080036	556.000	Ft
0090	Erosion Control, Turbidity Curtain, Shallow	2080044	26.000	Ft
0095	Project Cleanup	2090001	1.000	LSUM
0100	Subbase, CIP	3010002	238.000	Cyd
0105	Aggregate Base, 6 inch	3020016	952.000	Syd
0110	Maintenance Gravel, LM	3060021	10.000	Cyd
0115	Shld, CI II, 8 inch	3070130	209.000	Syd
0120	Shld, CI II, 4 inch, Temp	3070181	143.000	Syd
0125	Trenching	3070200	4.000	Sta
0130	Culv, CI A, Conc, 84 inch	4010178	91.000	Ft
0135	_ Bypass Pumping	4017051	1.000	LSUM
0140	Pavt, Cleaning	5010001	1.000	LSUM

0145	Cold Milling HMA Surface	5010002	54.000	Syd
0150	HMA Surface, Rem	5010005	504.000	Syd
0155	Edge Trimming	5010009	370.000	Ft
0160	Longit Joint Density Quality Initiative	5010018	185.000	Dlr
0165	HMA Approach	5010061	274.000	Ton
0170	HMA, Temp Pavt (4EML)	5012103	70.000	Ton
0175	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	17.000	Syd
0180	Steel Sheet Piling, Temp	7040002	935.000	Sft
0185	Cofferdams	7040007	1.000	LSUM
0190	Reinforcement, Steel, Culv and Headwall	7060091	12,649.000	Lb
0195	Conc, Grade 3500HP	7062002	67.000	Cyd
0200	_ Geotextile Retaining Wall	8007011	25.000	Syd
0205	Post, Steel, 3 pound	8100371	42.000	Ft
0210	Sign, Type III, Rem	8100403	1.000	Ea
0215	Sign, Type IIIB	8100405	5.000	Sft
0220	Sign, Type V, Rem	8100421	1.000	Ea
0225	Sign, Type VB	8100425	6.000	Sft
0230	Ground Mtd Sign Support, Rem	8102010	3.000	Ea
0235	Pavt Mrkg, Waterborne, 6 inch, White	8110233	2,950.000	Ft
0240	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	1,140.000	Ft
0245	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	4.000	Ea
0250	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	4.000	Ea
0255	Conc Barrier Ending, Temp, Det 5, Adj	8120060	6.000	Ea
0260	Conc Barrier Ending, Temp, Det 5, Furn	8120061	2.000	Ea
0265	Conc Barrier Ending, Temp, Det 5, Oper	8120062	2.000	Ea
0270	Conc Barrier, Temp, Limited Deflection, Reflector Replacement	8120086	7.000	Ea
0275	Culv, Temp	8120090	2.000	Ea
0280	Delineator, Flexible, Temp, Furn	8120091	10.000	Ea
0285	Delineator, Flexible, Temp, Oper	8120092	10.000	Ea
0290	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0295	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0300	Minor Traf Devices	8120170	1.000	LSUM
0305	Mobile Attenuator	8120180	1.000	Ea
0310	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	1,200.000	Ft
0315	Plastic Drum, Fluorescent, Furn	8120252	30.000	Ea
0320	Plastic Drum, Fluorescent, Oper	8120253	30.000	Ea
0325	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	96.000	Ft
0330	PTS, Temp, Furn	8120272	3.000	Ea
0335	PTS, Temp, Oper	8120273	3.000	Ea
0340	Sign Cover	8120310	4.000	Ea
0345	Sign, Type B, Temp, Prismatic, Furn	8120350	406.000	Sft
0350	Sign, Type B, Temp, Prismatic, Oper	8120351	406.000	Sft

0355	Traf Regulator Control	8120370	1.000	LSUM
0360	Conc Barrier, Temp, Limited Deflection, Det 2, Furn	8121100	234.000	Ft
0365	Conc Barrier, Temp, Limited Deflection, Det 2, Oper	8121101	234.000	Ft
0370	Conc Barrier, Temp, Limited Deflection, Det 2, Adj	8121102	440.000	Ft
0375	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	660.000	Ft
0380	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,160.000	Ft
0385	Temp Rumble Strips (Orange), Stop Condition	8122186	960.000	Ft
0390	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0395	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0400	Riprap, Plain	8130010	280.000	Syd
0405	Slope Restoration, Non-Freeway, Type A	8162001	536.000	Syd
0410	Slope Restoration, Non-Freeway, Type F	8162006	374.000	Syd
0415	Centerline Corrugations, Milled, HMA	8220013	75.000	Ft
0420	Contractor Staking	8240001	1.000	LSUM
0425	Staking Plan Errors and Extras, Max \$180/hour	8240002	14.000	Hr



10/10/2025 8:52 AM

AASHTOWare Project™ Version 5.02.04 Revision 045

Schedule of Pay Items

Report v1

Letting Call: 251107 042

Letting Date: November 7, 2025

Contract ID: 11015-222028

Description: 0.10 mi of installation of guardrail on I-94 westbound at Exit 116 north of Red Arrow Highway in the city of Bridgman, Berrien County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
222028A	25A0986	N/A	HSIP 11015

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$4,500.00	1100001	1.000	LSUM
0010	Guardrail, Rem	2040035	60.000	Ft
0015	Shld, CI II, 6 inch	3070128	15.000	Syd
0020	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0025	Guardrail Reflector	8070080	10.000	Ea
0030	Guardrail, Type MGS-8, 108 inch Post	8072180	441.000	Ft
0035	Fence, Protective	8080007	635.000	Ft
0040	Delineator Reflector, Green	8100133	1.000	Ea
0045	Post, Rigid, Delineator	8100361	1.000	Ea
0050	Connected Arrow Board, Type C, Furn	8120155	1.000	Ea
0055	Connected Arrow Board, Type C, Oper	8120156	1.000	Ea
0060	Minor Traf Devices	8120170	1.000	LSUM
0065	Mobile Attenuator	8120180	1.000	Ea
0070	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0075	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0080	Sign, Type B, Temp, Prismatic, Furn	8120350	192.000	Sft
0085	Sign, Type B, Temp, Prismatic, Oper	8120351	192.000	Sft
0090	Slope Restoration, Freeway, Type F	8162018	45.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 043

Letting Date: November 7, 2025

Contract ID: 17032-215225

Description: 0.58 mi of concrete pavement repair, concrete joint repair and concrete joint resealing on I-75BS from 10th Avenue northerly to Easterday Avenue in the city of Sault Ste Marie, Chippewa County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215225A	25A1075	N/A	ST 17032

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$78,700.00	1100001	1.000	LSUM
0010	Pavt, Rem	2040050	1,477.000	Syd
0015	Erosion Control, Inlet Protection, Fabric Drop	2080020	10.000	Ea
0020	_ Open-Graded Dr Cse, Conditioning	3037011	1,477.000	Syd
0025	Dr Structure Cover, Adj, Case 1	4030005	17.000	Ea
0030	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	1,477.000	Syd
0035	Joint, Contraction, Cp	6020200	972.000	Ft
0040	Joint, Expansion, E2	6020207	560.000	Ft
0045	Joint, Contraction, Crg	6030020	2,582.000	Ft
0050	Joint, Expansion, Erg	6030021	106.000	Ft
0055	Lane Tie, Epoxy Anchored	6030030	2,324.000	Ea
0060	Non-Chloride Accelerator	6030035	1,505.000	Gal
0065	Pavt Repr, Nonreinf Conc, 9 inch	6030046	1,843.000	Syd
0070	Pavt Repr, Rem	6030080	1,843.000	Syd
0075	Saw Cut, Intermediate	6030090	1,807.000	Ft
0080	Resealing Trans Joints with Hot-Poured Rubber	6030100	6,475.000	Ft
0085	Resealing Longit Joints with Hot-Poured Rubber	6030101	1,875.000	Ft
0090	Pavt Mrkg, Waterborne, 6 inch, White	8110233	1,564.000	Ft
0095	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	6,490.000	Ft
0100	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	1.000	Ea
0105	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	1.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0115	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	180.000	Ea
0125	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	180.000	Ea
0130	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0135	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea

0140	Minor Traf Devices	8120170	1.000	LSUM
0145	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	1,200.000	Ft
0150	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,200.000	Ft
0155	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt Turn Arrow	8120258	1.000	Ea
0160	Sign Cover	8120310	6.000	Ea
0165	Sign, Type B, Temp, Prismatic, Furn	8120350	594.000	Sft
0170	Sign, Type B, Temp, Prismatic, Oper	8120351	594.000	Sft
0175	Water Shutoff, Adj, Case 1	8230421	1.000	Ea
0180	Contractor Staking	8240001	1.000	LSUM
0185	Staking Plan Errors and Extras, Max \$180/hour	8240002	9.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 044

Letting Date: November 7, 2025

Contract ID: 44063-220383

Description: Hot mix asphalt overlay, pavement cleaning and pavement markings on M-90 Burnside Carpool Lot located east of M-53, M-90 North Branch Carpool Lot located between Brush Street and Baldwin Avenue in the village of North Branch and M-24 Fostoria Carpool Lot located in the southeast quadrant of M-24 and Millington Road, Lapeer County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220383A	25A1052	N/A	ST 44063

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$10,800.00	1100001	1.000	LSUM
0010	_ Shld, CI II, Modified	3077031	38.000	Ton
0015	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0020	Pavt, Cleaning	5010001	1.000	LSUM
0025	Cold Milling HMA Surface	5010002	144.000	Syd
0030	Pavt for Butt Joints, Rem	5010008	190.000	Syd
0035	Joint and Crack, Cleanout	5010015	630.000	Ft
0040	HMA Approach	5010061	302.000	Ton
0045	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	7.000	Ea
0050	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	253.000	Ft
0055	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	1,721.000	Ft
0060	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	45.000	Ea
0070	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	45.000	Ea
0075	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0080	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0085	Minor Traf Devices	8120170	1.000	LSUM
0090	Plastic Drum, Fluorescent, Furn	8120252	10.000	Ea
0095	Plastic Drum, Fluorescent, Oper	8120253	10.000	Ea
0100	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0105	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0110	Sign, Type B, Temp, Prismatic, Furn	8120350	413.000	Sft
0115	Sign, Type B, Temp, Prismatic, Oper	8120351	413.000	Sft
0120	Slope Restoration, Non-Freeway, Type A	8162001	135.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 045

Letting Date: November 7, 2025

Contract ID: 79042-202142

Description: Bridge reconstruction including culvert replacement and approach work on M-46 over White Creek #2, Tuscola County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
202142A	25A1116	N/A	BFP 79042

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$336,700.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	2.000	Ea
0015	Guardrail, Rem	2040035	902.000	Ft
0020	Pavt, Rem	2040050	411.000	Syd
0025	Embankment, CIP	2050010	1,280.000	Cyd
0030	Excavation, Earth	2050016	1,333.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0040	Subbase, CIP	3010002	370.000	Cyd
0045	Aggregate Base, 6 inch	3020016	704.000	Syd
0050	_ Shld, CI II, Modified	3077031	15,380.000	Ton
0055	Culv End Sect, 18 inch	4010018	2.000	Ea
0060	Culv End Sect, Footing	4010072	2.000	Ea
0065	Culv, CI A, 18 inch	4010133	40.000	Ft
0070	Dr Marker Post	4011109	4.000	Ea
0075	Video Taping Sewer and Culv Pipe	4021275	40.000	Ft
0080	Underdrain, Fdn, 6 inch	4040033	251.000	Ft
0085	Underdrain, Subbase, 6 inch	4040063	360.000	Ft
0090	Underdrain Outlet, 6 inch	4040093	171.000	Ft
0095	Underdrain, Outlet Ending, 6 inch	4040113	8.000	Ea
0100	Video Inspection of Underdrain	4040200	389.000	Ft
0105	HMA Surface, Rem	5010005	669.000	Syd
0110	HMA Quality Initiative	5010007	494.000	Dlr
0115	Longit Joint Density Quality Initiative	5010018	1,395.000	Dlr
0120	HMA Approach	5010061	247.000	Ton
0125	Post, Steel, 3 pound	8100371	28.000	Ft
0130	Sign, Type IV, Rem	8100409	2.000	Ea
0135	Sign, Type IVA	8100410	14.000	Sft

0140	Ground Mtd Sign Support, Rem	8102010	2.000	Ea
0145	Pavt Mrkg, Regular Dry, 4 inch, White	8110125	273,650.000	Ft
0150	Pavt Mrkg, Regular Dry, 4 inch, Yellow	8110126	152,800.000	Ft
0155	Pavt Mrkg, Waterborne, 6 inch, White	8110233	1,240.000	Ft
0160	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	620.000	Ft
0165	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	1,240.000	Ft
0170	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	620.000	Ft
0175	Recessing Pavt Mrkg, Longit	8110450	1,860.000	Ft
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0190	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0195	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0200	Minor Traf Devices	8120170	1.000	LSUM
0205	Plastic Drum, Fluorescent, Furn	8120252	25.000	Ea
0210	Plastic Drum, Fluorescent, Oper	8120253	25.000	Ea
0215	Sign Cover	8120310	2.000	Ea
0220	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0225	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0230	Sign, Type B, Temp, Prismatic, Furn	8120350	821.000	Sft
0235	Sign, Type B, Temp, Prismatic, Oper	8120351	821.000	Sft
0240	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	125.000	Sft
0245	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	125.000	Sft
0250	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	620.000	Ft
0255	Riprap, Plain	8130010	463.000	Syd
0260	Slope Restoration, Non-Freeway, Type A	8162001	100.000	Syd
0265	Slope Restoration, Non-Freeway, Type B	8162002	5,425.000	Syd
0270	Slope Restoration, Non-Freeway, Type C	8162003	100.000	Syd
0275	Centerline Corrugations, Milled, HMA	8220013	155.000	Ft
0280	Contractor Staking	8240001	1.000	LSUM
0285	Staking Plan Errors and Extras, Max \$180/hour	8240002	36.000	Hr

Section: 2

0290	Culv, Rem, Over 48 inch	2030003	3.000	Ea
0295	Backfill, Structure, CIP	2060002	1,940.000	Cyd
0300	Excavation, Fdn	2060010	3,690.000	Cyd
0305	Erosion Control, Check Dam, Stone	2080012	25.000	Ft
0310	Erosion Control, Filter Bag	2080014	4.000	Ea
0315	Erosion Control, Gravel Filter Berm	2080018	180.000	Ft
0320	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0325	Erosion Control, Sand Bag	2080028	400.000	Ea
0330	Erosion Control, Sediment Basin	2080032	5.000	Cyd
0335	Erosion Control, Silt Fence	2080036	400.000	Ft

0340	Erosion Control, Temp Plastic Sheet/Geotextile Cover	2080040	1,700.000	Syd
0345	Geotextile, Separator, Non-Woven	3082000	1,130.000	Syd
0350	Culv Bedding, Box Culv	4060005	198.000	Cyd
0355	_ Culv, Segmental Precast Conc Box, 36 foot by 14 foot, Spec	4067001	100.000	Ft
0360	_ Cofferdam, Left in Place, Spec (C02 of 79042)	7047051	1.000	LSUM
0365	Reinforcement, Steel, Epoxy Coated	7060092	7,415.000	Lb
0370	Substructure Conc, High Performance	7060101	65.000	Cyd
0375	Water Repellent Treatment, Penetrating	7060140	95.000	Syd
0380	Liner, PVC, 30 mil	7060209	3,125.000	Syd
0385	Joint Waterproofing	7100001	309.000	Sft



Schedule of Pay Items

Report v1

Letting Call: 251107 046

Letting Date: November 7, 2025

Contract ID: 05021-220349

Description: 41.00 mi of installation of curve warning signs on M-18, M-32, M-33, M-65, M-72 and M-75, Alpena, Antrim, Charlevoix, Clare, Crawford, Gladwin, Oscoda, Otsego and Roscommon Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220349A	25A1071	N/A	HSIP 05021

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$15,900.00	1100001	1.000	LSUM
0010	Fdn, Wood Support, Rem	8100280	14.000	Ea
0015	Post Hole Through Conc for Steel Post	8100340	4.000	Ea
0020	Post, Steel, 3 pound	8100371	4,126.000	Ft
0025	Post, Wood, 4 inch by 6 inch	8100380	1,568.000	Ft
0030	Post, Wood, 6 inch by 8 inch	8100382	47.000	Ft
0035	Sign, Type II, Erect, Salv	8100396	1.000	Ea
0040	Sign, Type II, Rem	8100397	11.000	Ea
0045	Sign, Type IIA	8100398	23.000	Sft
0050	Sign, Type III, Erect, Salv	8100402	3.000	Ea
0055	Sign, Type III, Rem	8100403	121.000	Ea
0060	Sign, Type IIIB	8100405	1,588.000	Sft
0065	Sign, Type V, Rem	8100421	62.000	Ea
0070	Sign, Type VB	8100425	747.000	Sft
0075	Sign, Type II, Rem, Salv	8102002	1.000	Ea
0080	Sign, Type III, Rem, Salv	8102003	4.000	Ea
0085	Ground Mtd Sign Support, Rem	8102010	235.000	Ea
0090	_ Reflective Panel for Permanent Sign Support, 3 foot, Modified	8107050	207.000	Ea
0095	_ Reflective Panel for Permanent Sign Support, 6 foot, Modified	8107050	146.000	Ea
0100	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0105	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0110	Minor Traf Devices	8120170	1.000	LSUM
0115	Sign, Type B, Temp, Prismatic, Furn	8120350	350.000	Sft
0120	Sign, Type B, Temp, Prismatic, Oper	8120351	350.000	Sft
0125	Contractor Staking	8240001	1.000	LSUM
0130	Staking Plan Errors and Extras, Max \$180/hour	8240002	2.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 047

Letting Date: November 7, 2025

Contract ID: 73031-221999

Description: 9.28 mi of single course chip seal with fog seal on M-52 from the south village limits of St. Charles to M-46, Saginaw County. This project includes a 2 year pavement performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221999A	25A1068	N/A	ST 73031

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, Mid-Michigan Railroad	1027060	5,000.000	Dir
0010	Mobilization, Max \$123,300.00	1100001	1.000	LSUM
0015	Erosion Control, Inlet Protection, Fabric Drop	2080020	25.000	Ea
0020	_ Shld, CI II, Modified	3027031	100.000	Ton
0025	Overband Crack Fill, Lane	5020003	19.000	Lnmi
0030	Seal, Fog	5050015	238,000.000	Syd
0035	Chip Seal, Single, Warranty	5050040	238,000.000	Syd
0040	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	575.000	Ft
0045	Pavt Mrkg, Polyurea, 6 inch, White	8110094	80,000.000	Ft
0050	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	25,000.000	Ft
0055	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	48.000	Ft
0060	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	224.000	Ft
0065	Rem Spec Mrkg	8110343	3,500.000	Sft
0070	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	25.000	Ea
0075	Pavt Mrkg, Polyurea, Railroad Sym	8110411	2.000	Ea
0080	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	8.000	Ea
0085	Pavt Mrkg, Polyurea, School	8110414	2.000	Ea
0090	Pavt Mrkg, Polyurea, Thru and Lt Turn Arrow Sym	8110416	1.000	Ea
0095	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	4.000	Ea
0100	Pavt Mrkg, Polyurea, For On-Street Parking, 4 inch, White	8110420	200.000	Ft
0105	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0110	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0115	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	350.000	Ea
0120	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	350.000	Ea
0125	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0130	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea

0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	105,000.000	Ft
0145	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0150	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0155	Raised Pavt Marker, Temp, Type 1, White, Monodirectional	8120280	850.000	Ea
0160	Raised Pavt Marker, Temp, Type 1, Yellow, Bidirectional	8120281	450.000	Ea
0165	Sign Cover	8120310	6.000	Ea
0170	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0175	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0180	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	800.000	Sft
0185	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	800.000	Sft
0190	Traf Regulator Control	8120370	1.000	LSUM
0195	Rumble Strip, Temp, Portable, Furn	8122188	3.000	Ea
0200	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 048

Letting Date: November 7, 2025

Contract ID: 22042-217329

Description: 9.01 mi of hot mix asphalt overlay, shoulder aggregate, centerline and shoulder corrugations and pavement markings on M-69 from west of the Felch Community Center entrance to east of Oakes Road, Dickinson County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217329A	N/A	N/A	M 22042

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$175,800.00	1100001	1.000	LSUM
0010	Berm Grading	2050008	5.000	Sta
0015	Approach, CI II, LM	3070023	15.000	Cyd
0020	Shld, CI II	3070121	3,110.000	Ton
0025	Cold Milling HMA Surface	5010002	2,034.000	Syd
0030	HMA Quality Initiative	5010007	25,624.000	Dlr
0035	Longit Joint Density Quality Initiative	5010018	17,557.000	Dlr
0040	HMA Approach	5010061	364.000	Ton
0045	HMA, 5EML	5012037	12,448.000	Ton
0050	Guardrail Reflector	8070080	244.000	Ea
0055	Guardrail, Reconst, Type B	8070105	4,826.000	Ft
0060	Pavt Mrkg, Waterborne, 6 inch, White	8110233	95,093.000	Ft
0065	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	70,700.000	Ft
0070	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	95,093.000	Ft
0075	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	70,700.000	Ft
0080	Rem Spec Mrkg	8110343	76.000	Sft
0085	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0090	Protective Ovly, Snowmobile Trail Crossing	8110550	146.000	Syd
0095	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0100	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0105	Minor Traf Devices	8120170	1.000	LSUM
0110	Plastic Drum, Fluorescent, Furn	8120252	40.000	Ea
0115	Plastic Drum, Fluorescent, Oper	8120253	40.000	Ea
0120	Sign Cover	8120310	5.000	Ea
0125	Sign, Type B, Temp, Prismatic, Furn	8120350	1,250.000	Sft
0130	Sign, Type B, Temp, Prismatic, Oper	8120351	1,250.000	Sft
0135	Traf Regulator Control	8120370	1.000	LSUM

0140	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	7,150.000	Ft
0145	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0150	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0155	Monument Box, Adj	8210005	4.000	Ea
0160	Centerline Corrugations, Milled, HMA	8220013	46,641.000	Ft
0165	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	87,323.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 049

Letting Date: November 7, 2025

Contract ID: 46081-224822

Description: 4.74 mi of hot mix asphalt cold milling and resurfacing, shoulder and centerline corrugations and pavement markings on M-50 from Hand Highway north to M-124, Jackson and Lenawee Counties. This project includes a 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224822A	25A1062	N/A	ST 46081

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Reimbursed Permit Fees	1077060	500.000	Dlr
0010	Mobilization, Max \$201,000.00	1100001	1.000	LSUM
0015	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0020	Shld, CI I	3070101	350.000	Ton
0025	Pavt, Cleaning	5010001	1.000	LSUM
0030	Cold Milling HMA Surface	5010002	112,974.000	Syd
0035	Bump Grinding	5010004	300.000	Syd
0040	HMA Quality Initiative	5010007	22,092.000	Dlr
0045	Longit Joint Density Quality Initiative	5010018	75,167.000	Dlr
0050	Pavt Joint and Crack Repr, Det 7	5010020	3,500.000	Ft
0055	Pavt Joint and Crack Repr, Det 8	5010021	1,200.000	Ft
0060	Hand Patching	5010025	424.000	Ton
0065	HMA Approach	5010061	575.000	Ton
0070	HMA Approach, High Stress	5010520	125.000	Ton
0075	HMA, 5EML	5012037	8,497.000	Ton
0080	HMA, 5EML, High Stress	5012085	1,425.000	Ton
0085	Curb Slp, HMA	8050010	390.000	Ft
0090	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	3.000	Ea
0095	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	4.000	Ea
0100	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym	8110078	3.000	Ea
0105	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	566.000	Ft
0110	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	74.000	Ft
0115	Pavt Mrkg, Waterborne, 6 inch, White	8110233	48,251.000	Ft
0120	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	40,669.000	Ft
0125	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	48,251.000	Ft
0130	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	40,669.000	Ft
0135	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr

0140	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	350.000	Ea
0145	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	350.000	Ea
0150	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0155	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0160	Minor Traf Devices	8120170	1.000	LSUM
0165	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0170	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0175	Sign Cover	8120310	20.000	Ea
0180	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	5.000	Ea
0185	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	5.000	Ea
0190	Sign, Type B, Temp, Prismatic, Furn	8120350	1,200.000	Sft
0195	Sign, Type B, Temp, Prismatic, Oper	8120351	1,200.000	Sft
0200	Traf Regulator Control	8120370	1.000	LSUM
0205	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	1,268.000	Ft
0210	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	8,700.000	Ft
0215	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0220	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0225	Monument Box, Adj	8210005	4.000	Ea
0230	Centerline Corrugations, Milled, HMA	8220013	21,613.000	Ft
0235	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	44,712.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 050

Letting Date: November 7, 2025

Contract ID: 33045-224588

Description: Bridge preventive maintenance on various routes at 12 structures including installing pressure relief joints and resealing bridge joints in the cities of Charlotte and Lansing, Clinton, Eaton, Ingham Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
224588A	N/A	N/A	M 33045

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$27,300.00	1100001	1.000	LSUM
0010	Joint, Pressure Relief	6020213	1,297.000	Ft
0015	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0020	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0025	Connected Arrow Board, Type C, Furn	8120155	1.000	Ea
0030	Connected Arrow Board, Type C, Oper	8120156	1.000	Ea
0035	Minor Traf Devices	8120170	1.000	LSUM
0040	Mobile Attenuator	8120180	2.000	Ea
0045	Plastic Drum, Fluorescent, Furn	8120252	200.000	Ea
0050	Plastic Drum, Fluorescent, Oper	8120253	200.000	Ea
0055	Sign Cover	8120310	8.000	Ea
0060	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0065	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0070	Sign, Type B, Temp, Prismatic, Furn	8120350	700.000	Sft
0075	Sign, Type B, Temp, Prismatic, Oper	8120351	700.000	Sft
0080	Traf Regulator Control	8120370	1.000	LSUM
0085	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0090	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
Section: 2				
0095	_ Bridge Joints, Clean and Seal	7127001	1,529.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 051

Letting Date: November 7, 2025

Contract ID: 58000-204204

Description: 7.73 mi of hot mix asphalt cold milling and resurfacing, signing and pavement markings on I-275 at Carleton-Rockwood Road carpool lot and I-275 from 1-75 to Carleton Road, Monroe County. This project includes a 5 year materials and workmanship pavement warranty, and a 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
204204A	25A1072	N/A	NH 58000
224591A	25A1073	N/A	IM 58171

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$913,600.00	1100001	1.000	LSUM
0010	Project Cleanup	2090001	1.000	LSUM
0015	Shld, CI II	3070121	3,376.000	Ton
0020	_ Cured-In-Place Pipe Lining, 18 inch	4027001	95.000	Ft
0025	Pavt, Cleaning	5010001	1.000	LSUM
0030	Cold Milling HMA Surface	5010002	499,046.000	Syd
0035	Bump Grinding	5010004	1,900.000	Syd
0040	HMA Quality Initiative	5010007	90,420.000	Dlr
0045	Pavt for Butt Joints, Rem	5010008	6,736.000	Syd
0050	Longit Joint Density Quality Initiative	5010018	347,243.000	Dlr
0055	Pavt Joint and Crack Repr, Det 7	5010020	9,240.000	Ft
0060	Hand Patching	5010025	749.000	Ton
0065	HMA Approach	5010061	1,153.000	Ton
0070	HMA, 4EML	5012025	1,310.000	Ton
0075	HMA, 5EML	5012037	14,263.000	Ton
0080	HMA, 5EMH	5012038	27,735.000	Ton
0085	Pavt Repr, Rem	6030080	330.000	Syd
0090	Saw Cut, Intermediate	6030090	254.000	Ft
0095	Installing MDOT Supplied Sign, Type III	8100302	1.000	Ea
0100	Post, Steel, 3 pound	8100371	62.000	Ft
0105	Sign, Type III, Rem	8100403	6.000	Ea
0110	Sign, Type IIIA	8100404	19.000	Sft
0115	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0120	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	4.000	Ea
0125	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	6.000	Ea
0130	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	6.000	Ea

0135	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	80.000	Ft
0140	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	4.000	Ea
0145	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	5,220.000	Ft
0150	Recessing Pavt Mrkg, Longit	8110450	252,380.000	Ft
0155	Recessing Pavt Mrkg, Transv	8110451	591.000	Sft
0160	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	137,250.000	Ft
0165	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	12,985.000	Ft
0170	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	102,145.000	Ft
0175	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	47.000	Ea
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	42.000	Ea
0185	Connected Arrow Board, Type C, Furn	8120155	6.000	Ea
0190	Connected Arrow Board, Type C, Oper	8120156	6.000	Ea
0195	Minor Traf Devices	8120170	1.000	LSUM
0200	Mobile Attenuator	8120180	1.000	Ea
0205	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	24,000.000	Ft
0210	Plastic Drum, Fluorescent, Furn	8120252	1,715.000	Ea
0215	Plastic Drum, Fluorescent, Oper	8120253	1,715.000	Ea
0220	Sign Cover	8120310	10.000	Ea
0225	Sign Cover, Type I	8120320	4.000	Ea
0230	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	8.000	Ea
0235	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	8.000	Ea
0240	Sign, Type A, Temp, Prismatic, Furn	8120340	1,434.000	Sft
0245	Sign, Type A, Temp, Prismatic, Oper	8120341	1,434.000	Sft
0250	Sign, Type B, Temp, Prismatic, Furn	8120350	3,665.000	Sft
0255	Sign, Type B, Temp, Prismatic, Oper	8120351	3,665.000	Sft
0260	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	346.000	Sft
0265	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	346.000	Sft
0270	Traf Regulator Control	8120370	1.000	LSUM
0275	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	115,200.000	Ft
0280	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	24,000.000	Ft
0285	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	24,000.000	Ft
0290	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	24,000.000	Ft
0295	Speed Radar Trailer, Temp	8122028	1.000	Ea
0300	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	1,000.000	Ft
0305	Protect Corners	8210020	10.000	Ea
0310	Freeway Shld Corrugations, Milled, HMA	8222001	152,038.000	Ft
0315	Contractor Staking	8240001	1.000	LSUM
0320	Staking Plan Errors and Extras, Max \$180/hour	8240002	101.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 052

Letting Date: November 7, 2025

Contract ID: 82052-213479

Description: 2.39 mi of hot mix asphalt cold milling and resurfacing, curb ramp upgrades, detail 7 joint and crack repair and pavement markings on US-24 from north of Pennsylvania Road northerly to I-75 connector ramps and Conn 24 from north of Carter Road northerly to south of Julie Lane, Wayne County. This project includes a 2 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
213479A	25A1084	N/A	NH 82052
221851A	25A1076	N/A	NH 82371

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$217,500.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	159.000	Ft
0015	Sidewalk, Rem	2040055	84.000	Syd
0020	Erosion Control, Inlet Protection, Fabric Drop	2080020	16.000	Ea
0025	Project Cleanup	2090001	1.000	LSUM
0030	Aggregate Base, 4 inch	3020010	9.000	Syd
0035	Dr Structure Cover, Adj, Case 1, Modified	4030004	3.000	Ea
0040	Cold Milling HMA Surface	5010002	82,665.000	Syd
0045	Bump Grinding	5010004	1,181.000	Syd
0050	HMA Quality Initiative	5010007	18,450.000	Dir
0055	Longit Joint Density Quality Initiative	5010018	56,849.000	Dir
0060	Pavt Joint and Crack Repr, Det 7	5010020	31,297.000	Ft
0065	Hand Patching	5010025	1,722.000	Ton
0070	HMA Approach, High Stress	5010520	392.000	Ton
0075	HMA, 5EML, High Stress	5012085	7,111.000	Ton
0080	_ Vibration Monitoring, Utility	8007051	1.000	LSUM
0085	Curb and Gutter, Conc, Det F6	8020040	46.000	Ft
0090	Driveway Opening, Conc, Det M	8020050	41.000	Ft
0095	Detectable Warning Surface	8030010	46.000	Ft
0100	Curb Ramp Opening, Conc	8030030	114.000	Ft
0105	Sidewalk, Conc, 4 inch	8030044	46.000	Sft
0110	Curb Ramp, Conc, 4 inch	8032001	582.000	Sft
0115	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	6.000	Ea
0120	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	364.000	Ft
0125	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	203.000	Ft
0130	Witness, Log, \$1,250.00	8110351	1,250.000	Dir

0135	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, White	8112130	22,357.000	Ft
0140	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 12 inch, White	8112131	898.000	Ft
0145	Pavt Mrkg, Wet Reflective Sprayable Thermopl, 6 inch, Yellow	8112133	21,977.000	Ft
0150	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0155	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0160	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0165	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	580.000	Ea
0170	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	580.000	Ea
0175	Connected Arrow Board, Type C, Furn	8120155	10.000	Ea
0180	Connected Arrow Board, Type C, Oper	8120156	10.000	Ea
0185	Minor Traf Devices	8120170	1.000	LSUM
0190	Mobile Attenuator	8120180	4.000	Ea
0195	Pavt Mrkg Cover, Type R, Black	8120200	3,048.000	Ft
0200	Pavt Mrkg, Type NR, Paint, 6 inch, Crosswalk	8120215	360.000	Ft
0205	Pavt Mrkg, Type NR, Paint, 24 inch, Stop Bar	8120216	228.000	Ft
0210	Sign Cover	8120310	16.000	Ea
0215	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	5.000	Ea
0220	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	5.000	Ea
0225	Sign, Type B, Temp, Prismatic, Furn	8120350	1,856.000	Sft
0230	Sign, Type B, Temp, Prismatic, Oper	8120351	1,856.000	Sft
0235	Traf Regulator Control	8120370	1.000	LSUM
0240	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	79,898.000	Ft
0245	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	70,482.000	Ft
0250	Speed Radar Trailer, Temp	8122028	2.000	Ea
0255	_ Turf Establishment, Performance	8167011	97.000	Syd
0260	Contractor Staking	8240001	1.000	LSUM
0265	Staking Plan Errors and Extras, Max \$180/hour	8240002	23.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 053

Letting Date: November 7, 2025

Contract ID: 13031-210857

Description: 3.20 mi of hot mix asphalt cold milling and resurfacing, concrete sidewalk ramp upgrades and pavement markings on M-66 from M-60 to South Drive S in the Village of Athens, Branch and Calhoun Counties.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
210857A	N/A	N/A	M 13031

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$95,600.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	106.000	Ft
0015	Pavt, Rem	2040050	112.000	Syd
0020	Sidewalk, Rem	2040055	158.000	Syd
0025	Embankment, CIP	2050010	24.000	Cyd
0030	Excavation, Earth	2050016	60.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	26.000	Ea
0045	Aggregate Base, 3 inch	3020008	64.000	Syd
0050	Aggregate Base, 4 inch	3020010	222.000	Syd
0055	Aggregate Base, 6 inch	3020016	45.000	Syd
0060	Approach, CI II, CIP	3070022	4.000	Cyd
0065	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0070	Dr Structure Cover, Type D	4030025	1.000	Ea
0075	Dr Structure, Adj, Add Depth	4030280	3.000	Ft
0080	Cold Milling HMA Surface	5010002	55,145.000	Syd
0085	HMA Surface, Rem	5010005	130.000	Syd
0090	HMA Quality Initiative	5010007	10,406.000	Dlr
0095	Longit Joint Density Quality Initiative	5010018	20,700.000	Dlr
0100	Pavt Joint and Crack Repr, Det 7	5010020	962.000	Ft
0105	Pavt Joint and Crack Repr, Det 8	5010021	240.000	Ft
0110	Hand Patching	5010025	201.000	Ton
0115	HMA Approach	5010061	157.000	Ton
0120	HMA, 5EML	5012037	4,845.000	Ton
0125	Conc Base Cse, Nonreinf, 7 1/2 inch	6020018	24.000	Syd
0130	Conc Pavt, Nonreinf, 6 inch	6020100	7.000	Syd
0135	Driveway, Nonreinf Conc, 6 inch	8010005	9.000	Syd

0140	_ Curb and Gutter, Conc, Det B2, Modified	8027001	14.000	Ft
0145	_ Curb and Gutter, Conc, Det F6, Modified	8027001	66.000	Ft
0150	Detectable Warning Surface	8030010	165.000	Ft
0155	Curb Ramp Opening, Conc	8030030	45.000	Ft
0160	Sidewalk, Conc, 4 inch	8030044	123.000	Sft
0165	Sidewalk, Conc, 6 inch	8030046	80.000	Sft
0170	Curb Ramp, Conc, 4 inch	8032001	902.000	Sft
0175	Curb Ramp, Conc, 6 inch	8032002	868.000	Sft
0180	Fence, Protective	8080007	500.000	Ft
0185	_ Fence, Protective, Temp Base	8087050	176.000	Ea
0190	Delineator Reflector, Green	8100133	25.000	Ea
0195	Post Hole Through Conc for Steel Post	8100340	1.000	Ea
0200	Post, Rigid, Delineator	8100361	25.000	Ea
0205	Post, Steel, 3 pound	8100371	13.000	Ft
0210	Sign, Type IIIA	8100404	2.000	Sft
0215	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	660.000	Ft
0220	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	96.000	Ft
0225	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	56.000	Ft
0230	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	4.000	Ea
0235	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0240	Pavt Mrkg, Ovly Cold Plastic, School	8110074	2.000	Ea
0245	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	2.000	Ea
0250	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	1.000	Ea
0255	Pavt Mrkg, Waterborne, 6 inch, White	8110233	32,800.000	Ft
0260	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	16,550.000	Ft
0265	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	32,800.000	Ft
0270	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	16,550.000	Ft
0275	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	44.000	Ft
0280	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0285	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	538.000	Ft
0290	Recessing Pavt Mrkg, Transv	8110451	1,084.000	Sft
0295	_ Pavt Mrkg, Waterborne, 8 inch, Yellow, Curb Painting	8117001	440.000	Ft
0300	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	5.000	Ea
0305	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	5.000	Ea
0310	Pedestrian Type II Barricade, Temp	8120026	32.000	Ea
0315	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	540.000	Ea
0320	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	540.000	Ea
0325	Connected Arrow Board, Type C, Furn	8120155	4.000	Ea
0330	Connected Arrow Board, Type C, Oper	8120156	4.000	Ea
0335	Minor Traf Devices	8120170	1.000	LSUM
0340	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	660.000	Ft

0345	Pavt Mrkg, Wet Reflective, Type R, Tape, Lt Turn Arrow	8120257	4.000	Ea
0350	Pavt Mrkg, Wet Reflective, Type R, Tape, Rt Turn Arrow	8120258	2.000	Ea
0355	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	56.000	Ft
0360	Sign Cover	8120310	10.000	Ea
0365	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0370	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0375	Sign, Type B, Temp, Prismatic, Furn	8120350	1,170.000	Sft
0380	Sign, Type B, Temp, Prismatic, Oper	8120351	1,170.000	Sft
0385	Traf Regulator Control	8120370	1.000	LSUM
0390	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	68.000	Ft
0395	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	2,148.000	Ft
0400	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	96.000	Ft
0405	Pavt Mrkg, Wet Reflective, Type R, Tape, Thru and Lt Turn Arrow Sym	8122147	2.000	Ea
0410	Rumble Strip, Temp, Portable, Furn	8122188	24.000	Ea
0415	Rumble Strip, Temp, Portable, Oper	8122189	24.000	Ea
0420	Site Preparation, Max \$700.00	8150001	1.000	LSUM
0425	Fertilizer, Chemical Nutrient, CI B	8160021	1.000	Lb
0430	Mulch Blanket	8160027	111.000	Syd
0435	Seeding, Mixture TUF	8160042	5.000	Lb
0440	Topsoil Surface, Furn, 4 inch	8160062	111.000	Syd
0445	Monument Box	8210001	4.000	Ea
0450	Monument Box, Adj	8210005	6.000	Ea
0455	Monument Preservation	8210010	4.000	Ea
0460	Centerline Corrugations, Milled, HMA	8220013	10,350.000	Ft
0465	Gate Box, Adj, Case 1	8230431	1.000	Ea
0470	Contractor Staking	8240001	1.000	LSUM
0475	Staking Plan Errors and Extras, Max \$180/hour	8240002	11.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 054

Letting Date: November 7, 2025

Contract ID: 23812-209416

Description: 3.96 mi of construction of directional crossovers with turning loons, a single course chip seal, and concrete pavement repairs on Lansing Road from Creyts Road and I-496 ramps, Eaton and Ingham Counties. This project includes a 2 year pavement performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
209416A	25A1097	N/A	HSIP 23812
219775A	25A1092	N/A	NH 23812

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, Grand Trunk Western Railroad	1027060	1,000.000	Dir
0010	Mobilization, Max \$221,600.00	1100001	1.000	LSUM
0015	Clearing	2010001	0.210	Acre
0020	Tree, Rem, 6 inch to 18 inch	2020004	2.000	Ea
0025	Dr Structure, Rem	2030011	2.000	Ea
0030	Sewer, Rem, Less than 24 inch	2030015	40.000	Ft
0035	Curb and Gutter, Rem	2040020	251.000	Ft
0040	Pavt, Rem	2040050	3,110.000	Syd
0045	Embankment, CIP	2050010	1,666.000	Cyd
0050	Excavation, Earth	2050016	4,330.000	Cyd
0055	Non Haz Contaminated Material Handling and Disposal, LM	2050031	200.000	Cyd
0060	_ Ditch Cleanout, Special	2057001	11,700.000	Ft
0065	Erosion Control, Check Dam, Stone	2080012	150.000	Ft
0070	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0075	Erosion Control, Maintenance, Sediment Rem	2080026	30.000	Cyd
0080	Erosion Control, Sediment Trap	2080034	20.000	Ea
0085	Erosion Control, Silt Fence	2080036	2,607.000	Ft
0090	Aggregate Base, 9 inch	3020022	650.000	Syd
0095	Aggregate Base, Conditioning	3020050	285.000	Syd
0100	_ Aggregate Base, 24 inch, Spec	3027011	6,180.000	Syd
0105	Shld, CI II, 8 inch	3070130	435.000	Syd
0110	Sewer, CI II, 12 inch, Tr Det B	4020748	12.000	Ft
0115	Sewer, CI II, 18 inch, Tr Det B	4020751	24.000	Ft
0120	Sewer Tap, 12 inch	4021204	1.000	Ea
0125	Sewer Tap, 18 inch	4021206	2.000	Ea

0130	Dr Structure Cover, Adj, Case 1	4030005	1.000	Ea
0135	Dr Structure Cover, Type G	4030040	2.000	Ea
0140	Dr Structure, 24 inch dia	4030200	1.000	Ea
0145	Dr Structure, 48 inch dia	4030210	1.000	Ea
0150	HMA Surface, Rem	5010005	4,590.000	Syd
0155	Hand Patching	5010025	280.000	Ton
0160	Overband Crack Fill, Lane	5020003	17.670	Lnmi
0165	Seal, Fog	5050015	207,138.000	Syd
0170	Chip Seal, Single, Warranty	5050040	207,138.000	Syd
0175	Conc Base Cse, Nonreinf, 10 inch	6020023	49.000	Syd
0180	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	188.000	Syd
0185	Conc Pavt, Nonreinf, 8 inch	6020104	4,195.000	Syd
0190	Joint, Contraction, Cp	6020200	2,512.000	Ft
0195	Joint, Expansion, E2	6020207	2,706.000	Ft
0200	Lane Tie, Epoxy Anchored	6030030	960.000	Ea
0205	Curb and Gutter, Conc, Det B1	8020015	667.000	Ft
0210	Shld Gutter, Conc, Det 1	8020055	1.000	Ea
0215	Spillway, Conc	8020075	95.000	Ft
0220	Delineator Reflector, Yellow	8100132	70.000	Ea
0225	Post Hole Through Conc for Steel Post	8100340	2.000	Ea
0230	Post, Rigid, Delineator	8100361	70.000	Ea
0235	Post, Steel, 3 pound	8100371	654.000	Ft
0240	Sign, Type III, Rem	8100403	18.000	Ea
0245	Sign, Type IIIA	8100404	101.000	Sft
0250	Sign, Type IIIB	8100405	87.000	Sft
0255	Sign, Type VB	8100425	27.000	Sft
0260	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	3.000	Ea
0265	Reflective Panel for Permanent Sign Support, 3 foot	8100613	12.000	Ea
0270	Reflective Panel for Permanent Sign Support, 6 foot	8100616	10.000	Ea
0275	Ground Mtd Sign Support, Rem	8102010	14.000	Ea
0280	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	12.000	Ea
0285	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	1.000	Ea
0290	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	5.000	Ea
0295	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	235.000	Ft
0300	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	389.000	Ft
0305	Pavt Mrkg, Waterborne, 6 inch, White	8110233	57,840.000	Ft
0310	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	45,882.000	Ft
0315	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	57,840.000	Ft
0320	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	45,882.000	Ft
0325	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	3,140.000	Ft
0330	Rem Curing Compound, for Spec Mrkg	8110321	119.000	Sft
0335	Rem Spec Mrkg	8110343	1,600.000	Sft
0340	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0345	Pavt Mrkg, Waterborne, 12 inch, White, Curb Painting	8117001	63.000	Ft

0350	_ Pavt Mrkg, Waterborne, 12 inch, Yellow, Curb Painting	8117001	120.000	Ft
0355	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0360	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0365	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	1,300.000	Ea
0370	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	1,300.000	Ea
0375	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0380	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0385	Minor Traf Devices	8120170	1.000	LSUM
0390	Mobile Attenuator	8120180	1.000	Ea
0395	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	92,658.000	Ft
0400	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0405	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0410	Raised Pavt Marker, Temp, Type 1, White, Monodirectional	8120280	2,000.000	Ea
0415	Sign Cover	8120310	15.000	Ea
0420	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0425	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0430	Sign, Type B, Temp, Prismatic, Furn	8120350	400.000	Sft
0435	Sign, Type B, Temp, Prismatic, Oper	8120351	400.000	Sft
0440	Riprap, Plain	8130010	25.000	Syd
0445	_ Turf Establishment, Performance	8167011	16,768.000	Syd
0450	Contractor Staking	8240001	1.000	LSUM
0455	Staking Plan Errors and Extras, Max \$180/hour	8240002	9.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 055

Letting Date: November 7, 2025

Contract ID: 51012-219881

Description: 5.39 mi of hot mix asphalt cold milling and overlay, sidewalk and drainage upgrades, signing and pavement markings on US-31 from south of Maidens Road to north of Norconk Road in the Village of Bear Lake, Manistee County. This project includes a 3 year materials and workmanship pavement warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219881A	25A1095	N/A	ST 51012

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$388,900.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	4.000	Ea
0015	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0020	Culv, End, Rem, 24 inch to 48 inch	2030006	1.000	Ea
0025	Dr Structure, Rem	2030011	3.000	Ea
0030	Sewer, Rem, Less than 24 inch	2030015	65.000	Ft
0035	Sewer, Rem, 24 inch to 48 inch	2030016	41.000	Ft
0040	Curb and Gutter, Rem	2040020	1,481.000	Ft
0045	Pavt, Rem	2040050	200.000	Syd
0050	Sidewalk, Rem	2040055	1,549.000	Syd
0055	Berm Grading	2050008	25.000	Sta
0060	Embankment, CIP	2050010	1,121.000	Cyd
0065	Excavation, Earth	2050016	3,322.000	Cyd
0070	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0075	Subgrade Undercutting, Type II	2050041	50.000	Cyd
0080	Erosion Control, Check Dam, Stone	2080012	128.000	Ft
0085	Erosion Control, Inlet Protection, Fabric Drop	2080020	47.000	Ea
0090	Erosion Control, Inlet Protection, Sediment Trap	2080024	11.000	Ea
0095	Erosion Control, Maintenance, Sediment Rem	2080026	5.000	Cyd
0100	Erosion Control, Sand Bag	2080028	60.000	Ea
0105	Erosion Control, Sediment Trap	2080034	11.000	Ea
0110	Erosion Control, Silt Fence	2080036	1,216.000	Ft
0115	_ Stormwater Treatment, Check Dam, Stone	2087050	3.000	Ea
0120	Subbase, CIP	3010002	4,780.000	Cyd
0125	Aggregate Base	3020001	937.000	Ton
0130	Aggregate Base, Conditioning	3020050	9,805.000	Syd

0135	Approach, CI I	3070001	1,281.000	Ton
0140	Approach, CI II	3070021	170.000	Ton
0145	Shld, CI II	3070121	668.000	Ton
0150	Culv End Sect, 12 inch	4010012	1.000	Ea
0155	Culv End Sect, 18 inch	4010018	4.000	Ea
0160	Culv, Slp End Sect, 1 on 6, 24 inch, Longit	4010955	4.000	Ea
0165	Dr Marker Post	4011109	16.000	Ea
0170	Sewer, CI A, 12 inch, Tr Det B	4020033	9.000	Ft
0175	Sewer, CI A, 36 inch, Tr Det B	4020038	45.000	Ft
0180	Sewer, CI E, 12 inch, Tr Det B	4020600	346.000	Ft
0185	Sewer, CI E, 18 inch, Tr Det B	4020602	931.000	Ft
0190	Sewer, CI E, 24 inch, Tr Det B	4020603	230.000	Ft
0195	Sewer Tap, 12 inch	4021204	6.000	Ea
0200	Sewer Tap, 18 inch	4021206	1.000	Ea
0205	Sewer Tap, 24 inch	4021207	4.000	Ea
0210	Dr Structure Cover, Adj, Case 1	4030005	14.000	Ea
0215	Dr Structure Cover, Adj, Case 2	4030006	1.000	Ea
0220	Dr Structure Cover, Type B	4030010	6.000	Ea
0225	Dr Structure Cover, Type D	4030025	7.000	Ea
0230	Dr Structure Cover, Type G	4030040	2.000	Ea
0235	Dr Structure Cover, Type J	4030045	9.000	Ea
0240	Dr Structure Cover, Type K	4030050	12.000	Ea
0245	Dr Structure, 24 inch dia	4030200	8.000	Ea
0250	Dr Structure, 48 inch dia	4030210	10.000	Ea
0255	Dr Structure, 60 inch dia	4030220	5.000	Ea
0260	Dr Structure, Add Depth of 60 inch dia, 8 foot to 15 foot	4030260	7.000	Ft
0265	Dr Structure, Adj, Add Depth	4030280	20.000	Ft
0270	Dr Structure, Tap, 6 inch	4030306	6.000	Ea
0275	Dr Structure, Tap, 12 inch	4030312	3.000	Ea
0280	_ Accessible Dr Structure Cover	4037050	2.000	Ea
0285	Underdrain, Subbase, 6 inch	4040063	3,509.000	Ft
0290	Underdrain, Subgrade, 6 inch	4040073	600.000	Ft
0295	Underdrain Outlet, 6 inch	4040093	185.000	Ft
0300	Underdrain, Outlet Ending, 6 inch	4040113	8.000	Ea
0305	Video Inspection of Underdrain	4040200	4,294.000	Ft
0310	_ Underdrain, Rem	4047001	1,016.000	Ft
0315	Cold Milling HMA Surface	5010002	133,111.000	Syd
0320	Bump Grinding	5010004	100.000	Syd
0325	HMA Surface, Rem	5010005	15,615.000	Syd
0330	HMA Quality Initiative	5010007	28,668.000	Dir
0335	Longit Joint Density Quality Initiative	5010018	85,350.000	Dir
0340	Pavt Joint and Crack Repr, Det 7	5010020	1,200.000	Ft
0345	Pavt Joint and Crack Repr, Det 8	5010021	2,100.000	Ft
0350	Hand Patching	5010025	835.000	Ton

0355	HMA Approach	5010061	1,086.000	Ton
0360	HMA, 4EL	5012024	185.000	Ton
0365	HMA, 5EL	5012036	12,228.000	Ton
0370	_ Vibration Monitoring	8007051	1.000	LSUM
0375	Driveway, Nonreinf Conc, 6 inch	8010005	231.000	Syd
0380	Curb and Gutter, Conc, Det B2	8020016	1,898.000	Ft
0385	Curb and Gutter, Conc, Det C4	8020023	225.000	Ft
0390	Curb and Gutter, Conc, Det F5	8020039	42.000	Ft
0395	Curb and Gutter, Conc, Det F6	8020040	1,078.000	Ft
0400	Driveway Opening, Conc, Det M	8020050	519.000	Ft
0405	Shld Gutter, Conc, Det 2	8020056	2.000	Ea
0410	Shld Gutter, Conc, Det 3	8020057	3.000	Ea
0415	Spillway, Conc	8020075	7.000	Ft
0420	_ Curb and Gutter, Conc, Det C4, Modified	8027001	625.000	Ft
0425	Curb Ramp Opening, Conc	8030030	606.000	Ft
0430	Sidewalk, Conc, 4 inch	8030044	16,249.000	Sft
0435	Sidewalk, Conc, 6 inch	8030046	15,916.000	Sft
0440	Curb Ramp, Conc, 4 inch	8032001	1,602.000	Sft
0445	Curb Ramp, Conc, 6 inch	8032002	1,974.000	Sft
0450	_ Detectable Warning Surface, Cast Iron, Spec	8037001	242.000	Ft
0455	Curb Slp, HMA	8050010	1,793.000	Ft
0460	Post, Mailbox	8070095	30.000	Ea
0465	Delineator Reflector, White	8100134	10.000	Ea
0470	Fdn, Wood Support, Rem	8100280	6.000	Ea
0475	Perforated Steel Square Tube Breakaway System	8100330	1.000	Ea
0480	Delineator, Rem	8100349	18.000	Ea
0485	Post, Rigid, Delineator	8100361	10.000	Ea
0490	Post, Steel, 3 pound	8100371	728.000	Ft
0495	Post, Wood, 4 inch by 6 inch	8100380	96.000	Ft
0500	Sign, Type II, Rem	8100397	6.000	Ea
0505	Sign, Type IIA	8100398	76.000	Sft
0510	Sign, Type III, Erect, Salv	8100402	8.000	Ea
0515	Sign, Type III, Rem	8100403	32.000	Ea
0520	Sign, Type IIIA	8100404	93.000	Sft
0525	Sign, Type IIIB	8100405	124.000	Sft
0530	Sign, Type VA	8100424	12.000	Sft
0535	Reflective Panel for Permanent Sign Support, 6 foot	8100616	17.000	Ea
0540	Sign, Type II, Rem, Salv	8102002	2.000	Ea
0545	Sign, Type III, Rem, Salv	8102003	8.000	Ea
0550	Ground Mtd Sign Support, Rem	8102010	38.000	Ea
0555	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	1,290.000	Ft
0560	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	298.000	Ft
0565	Pavt Mrkg, Waterborne, 6 inch, White	8110233	54,571.000	Ft
0570	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	33,968.000	Ft
0575	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	54,571.000	Ft

0580	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	33,968.000	Ft
0585	Rem Spec Mrkg	8110343	121.000	Sft
0590	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0595	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	512.000	Ft
0600	Recessing Pavt Mrkg, Longit	8110450	88,905.000	Ft
0605	Recessing Pavt Mrkg, Transv	8110451	1,634.000	Sft
0610	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	44.000	Ea
0615	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	44.000	Ea
0620	Pedestrian Type II Barricade, Temp	8120026	25.000	Ea
0625	Pedestrian Type II Channelizer, Temp	8120027	1,900.000	Ft
0630	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	880.000	Ea
0635	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	880.000	Ea
0640	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0645	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0650	Minor Traf Devices	8120170	1.000	LSUM
0655	Mobile Attenuator	8120180	2.000	Ea
0660	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	4,455.000	Ft
0665	Plastic Drum, Fluorescent, Furn	8120252	407.000	Ea
0670	Plastic Drum, Fluorescent, Oper	8120253	407.000	Ea
0675	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	275.000	Ft
0680	Sign Cover	8120310	30.000	Ea
0685	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0690	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0695	Sign, Type B, Temp, Prismatic, Furn	8120350	1,709.000	Sft
0700	Sign, Type B, Temp, Prismatic, Oper	8120351	1,709.000	Sft
0705	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	66.000	Sft
0710	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	66.000	Sft
0715	Traf Regulator Control	8120370	1.000	LSUM
0720	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	2,750.000	Ft
0725	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	5,489.000	Ft
0730	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	5,016.000	Ft
0735	Rumble Strip, Temp, Portable, Furn	8122188	12.000	Ea
0740	Rumble Strip, Temp, Portable, Oper	8122189	12.000	Ea
0745	Pedestrian Path, Temp	8122250	100.000	Ft
0750	Pedestrian Ramp, Temp	8122251	9.000	Ea
0755	_ Automated Flagger Assistance Device	8127050	2.000	Ea
0760	Riprap, Plain	8130010	20.000	Syd
0765	Slope Restoration, Non-Freeway, Type E	8162005	6,356.000	Syd
0770	Slope Restoration, Non-Freeway, Type F	8162006	19,657.000	Syd

0775	Slope Restoration, Non-Freeway, Type G	8162007	170.000	Syd
0780	Conduit, DB, 1, 1 1/2 inch	8182048	668.000	Ft
0785	_ Hh, Round, Ltg	8187050	8.000	Ea
0790	Monument Box, Adj	8210005	1.000	Ea
0795	Monument Preservation	8210010	4.000	Ea
0800	Protect Corners	8210020	24.000	Ea
0805	Centerline Corrugations, Milled, HMA	8220013	18,689.000	Ft
0810	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	27,788.000	Ft
0815	Water Serv, Conflict	8230250	2.000	Ea
0820	Water Shutoff, Adj, Case 1	8230421	4.000	Ea
0825	Water Shutoff, Adj, Case 2	8230422	2.000	Ea
0830	Gate Box, Adj, Case 1	8230431	17.000	Ea
0835	Gate Box, Adj, Case 2	8230432	4.000	Ea
0840	Contractor Staking	8240001	1.000	LSUM
0845	Staking Plan Errors and Extras, Max \$180/hour	8240002	42.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 056

Letting Date: November 7, 2025

Contract ID: 22021-221818

Description: 1.77 mi of hot mix asphalt cold milling and resurfacing, drainage structure cover adjusts, concrete curb, gutter and sidewalk repairs and pavement markings on US-2 from Kent Street northerly to Traders Mine Road in the city of Iron Mountain, Dickinson County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221818A	25A1079	N/A	NH 22021

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$145,600.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	2,420.000	Ft
0015	Sidewalk, Rem	2040055	82.000	Syd
0020	Erosion Control, Inlet Protection, Fabric Drop	2080020	39.000	Ea
0025	Shld, CI II, LM	3070123	10.000	Cyd
0030	Dr Structure Cover, Adj, Case 1	4030005	71.000	Ea
0035	Dr Structure, Adj, Add Depth	4030280	25.000	Ft
0040	Cold Milling HMA Surface	5010002	76,359.000	Syd
0045	HMA Surface, Rem	5010005	226.000	Syd
0050	HMA Quality Initiative	5010007	12,867.000	Dlr
0055	Joint and Crack, Cleanout	5010015	150.000	Ft
0060	Longit Joint Density Quality Initiative	5010018	42,520.000	Dlr
0065	Hand Patching	5010025	127.000	Ton
0070	HMA Approach, High Stress	5010520	529.000	Ton
0075	HMA, 5EML, High Stress	5012085	5,777.000	Ton
0080	Curb and Gutter, Conc, Det C4	8020023	2,140.000	Ft
0085	Driveway Opening, Conc, Det M	8020050	266.000	Ft
0090	Detectable Warning Surface	8030010	10.000	Ft
0095	Curb Ramp Opening, Conc	8030030	14.000	Ft
0100	Sidewalk, Conc, 4 inch	8030044	472.000	Sft
0105	Curb Ramp, Conc, 4 inch	8032001	262.000	Sft
0110	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	525.000	Ft
0115	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	380.000	Ft
0120	Pavt Mrkg, Waterborne, 6 inch, White	8110233	8,999.000	Ft
0125	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	21,132.000	Ft
0130	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	4,659.000	Ft
0135	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	21,132.000	Ft

0140	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0145	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	12.000	Ea
0150	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	5.000	Ea
0155	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	4.000	Ea
0160	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	1.000	Ea
0165	Protective Ovly, Snowmobile Trail Crossing	8110550	140.000	Syd
0170	Pavt Mrkg, Wet Reflective Waterborne, 2nd Application, 6 inch, White	8112001	4,340.000	Ft
0175	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0180	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0185	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0190	Ltg for Night Work	8120160	1.000	LSUM
0195	Minor Traf Devices	8120170	1.000	LSUM
0200	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0205	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0210	Sign Cover	8120310	5.000	Ea
0215	Sign, Type B, Temp, Prismatic, Furn	8120350	1,150.000	Sft
0220	Sign, Type B, Temp, Prismatic, Oper	8120351	1,150.000	Sft
0225	Traf Regulator Control	8120370	1.000	LSUM
0230	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	2,350.000	Ft
0235	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	3,000.000	Ft
0240	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	2,350.000	Ft
0245	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	3,000.000	Ft
0250	Rumble Strip, Temp, Portable, Furn	8122188	6.000	Ea
0255	Rumble Strip, Temp, Portable, Oper	8122189	6.000	Ea
0260	Slope Restoration, Non-Freeway, Type A	8162001	26.000	Syd
0265	Wireless Vehicle Detection System	8200422	1.000	Ea
0270	Wireless Vehicle Sensor Node	8200425	12.000	Ea
0275	Monument Box, Adj	8210005	16.000	Ea
0280	Protect Corners	8210020	1.000	Ea
0285	Gate Box, Adj, Case 1	8230431	5.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 057

Letting Date: November 7, 2025

Contract ID: 13044-221562-2

Description: 0.75 mi of single course microsurfacing, 4 to 3 lane reduction and concrete sidewalk ramp upgrades on I-94BL (Michigan Avenue) from Sycamore Street easterly to Liberty Street in the city of Marshall, Calhoun County. This project includes a 2 year pavement performance warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221562A	25A0547	N/A	CRUL 13044

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$41,000.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	222.000	Ft
0015	Pavt, Rem	2040050	57.000	Syd
0020	Sidewalk, Rem	2040055	254.000	Syd
0025	Embankment, CIP	2050010	24.000	Cyd
0030	Excavation, Earth	2050016	40.000	Cyd
0035	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	55.000	Ea
0045	Aggregate Base, 3 inch	3020008	120.000	Syd
0050	Aggregate Base, 4 inch	3020010	270.000	Syd
0055	Aggregate Base, 6 inch	3020016	31.000	Syd
0060	Aggregate Base, Conditioning	3020050	74.000	Syd
0065	Dr Structure Cover, Adj, Case 1	4030005	5.000	Ea
0070	Dr Structure, Adj, Add Depth	4030280	15.000	Ft
0075	HMA Surface, Rem	5010005	121.000	Syd
0080	Hand Patching	5010025	18.000	Ton
0085	Overband Crack Fill, Lane	5020003	2.470	Lnmi
0090	Micro-Surface, Single Cse, Warranty	5040020	23,710.000	Syd
0095	Conc Base Cse, Nonreinf, 7 1/2 inch	6020018	57.000	Syd
0100	Conc Pavt, Nonreinf, 6 inch	6020100	14.000	Syd
0105	Curb and Gutter, Conc, Det F4	8020038	6.000	Ft
0110	Curb and Gutter, Conc, Det F6	8020040	24.000	Ft
0115	_ Curb and Gutter, Conc, Det F4, Modified	8027001	116.000	Ft
0120	_ Curb and Gutter, Conc, Det F6, Modified	8027001	66.000	Ft
0125	Detectable Warning Surface	8030010	187.000	Ft
0130	Curb Ramp Opening, Conc	8030030	94.000	Ft
0135	Curb Ramp, Conc, 4 inch	8032001	1,208.000	Sft

0140	Curb Ramp, Conc, 6 inch	8032002	994.000	Sft
0145	Fence, Protective	8080007	500.000	Ft
0150	Fence, Moving	8080120	500.000	Ft
0155	_ Fence, Protective, Temp Base	8087050	54.000	Ea
0160	Perforated Steel Square Tube Breakaway System	8100330	2.000	Ea
0165	Post Hole Through Conc for Steel Post	8100340	14.000	Ea
0170	Post, Steel, 3 pound	8100371	256.000	Ft
0175	Sign, Type III, Erect, Salv	8100402	5.000	Ea
0180	Sign, Type III, Rem	8100403	2.000	Ea
0185	Sign, Type IIIB	8100405	78.000	Sft
0190	Sign, Type V, Rem	8100421	1.000	Ea
0195	Sign, Type VB	8100425	24.000	Sft
0200	Reflective Panel for Permanent Sign Support, 6 foot	8100616	8.000	Ea
0205	Ground Mtd Sign Support, Rem	8102010	4.000	Ea
0210	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	2.000	Ea
0215	Pavt Mrkg, Waterborne, 6 inch, White	8110233	4,000.000	Ft
0220	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	8,350.000	Ft
0225	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	4,000.000	Ft
0230	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Yellow	8110254	8,350.000	Ft
0235	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, Blue	8110293	82.000	Ft
0240	Rem Spec Mrkg	8110343	1,020.000	Sft
0245	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	6,000.000	Ft
0250	_ Pavt Mrkg, Multipolymer, 12 inch, Cross Hatching, Yellow	8117001	800.000	Ft
0255	_ Pavt Mrkg, Multipolymer, 12 inch, Crosswalk	8117001	882.000	Ft
0260	_ Pavt Mrkg, Multipolymer, 24 inch, Stop Bar	8117001	185.000	Ft
0265	_ Pavt Mrkg, Multipolymer, 6 inch, Crosswalk	8117001	1,120.000	Ft
0270	_ Pavt Mrkg, Multipolymer, Lt Turn Arrow Sym	8117050	6.000	Ea
0275	_ Pavt Mrkg, Multipolymer, Merge Arrow Sym	8117050	1.000	Ea
0280	_ Pavt Mrkg, Multipolymer, Yield Triangle Sym	8117050	8.000	Ea
0285	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	87.000	Ea
0290	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	87.000	Ea
0295	Pedestrian Type II Barricade, Temp	8120026	46.000	Ea
0300	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	160.000	Ea
0305	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	160.000	Ea
0310	Connected Arrow Board, Type C, Furn	8120155	2.000	Ea
0315	Connected Arrow Board, Type C, Oper	8120156	2.000	Ea
0320	Ltg for Night Work	8120160	1.000	LSUM
0325	Minor Traf Devices	8120170	1.000	LSUM
0330	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	13,600.000	Ft
0335	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Crosswalk	8120255	1,120.000	Ft
0340	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	185.000	Ft

0345	Sign Cover	8120310	4.000	Ea
0350	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	4.000	Ea
0355	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	4.000	Ea
0360	Sign, Type A, Temp, Prismatic, Furn	8120340	176.000	Sft
0365	Sign, Type A, Temp, Prismatic, Oper	8120341	176.000	Sft
0370	Sign, Type B, Temp, Prismatic, Furn	8120350	1,343.000	Sft
0375	Sign, Type B, Temp, Prismatic, Oper	8120351	1,343.000	Sft
0380	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	6,000.000	Ft
0385	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	12,525.000	Ft
0390	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	882.000	Ft
0395	Pavt Mrkg, Wet Reflective, Type R, Tape, Merge Arrow Sym	8122139	1.000	Ea
0400	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, Cross Hatching, Yellow	8122181	800.000	Ft
0405	Fertilizer, Chemical Nutrient, CI B	8160021	3.000	Lb
0410	Mulch Blanket	8160027	123.000	Syd
0415	Seeding, Mixture TUF	8160042	6.000	Lb
0420	Topsoil Surface, Furn, 4 inch	8160062	123.000	Syd
0425	TS Face, Bag	8200458	10.000	Ea
0430	TS Face, Bag, Rem	8200459	10.000	Ea
0435	Contractor Staking	8240001	1.000	LSUM
0440	Staking Plan Errors and Extras, Max \$180/hour	8240002	5.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 058

Letting Date: November 7, 2025

Contract ID: 18000-225019

Description: 4.18 mi of hot mix asphalt overlay, intersection approaches and driveway approaches on Tobacco Drive from Clarabella Road to Beaverton Road, Clare County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
225019A	25A0992	N/A	STL 18000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$54,000.00	1100001	1.000	LSUM
0010	Pavt, Rem	2040050	185.000	Syd
0015	HMA Surface, Rem	5010005	610.000	Syd
0020	Pavt for Butt Joints, Rem	5010008	400.000	Syd
0025	HMA Approach	5010061	364.000	Ton
0030	HMA, 4EL	5012024	5,450.000	Ton
0035	Driveway, Nonreinf Conc, 6 inch	8010005	185.000	Syd
0040	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0045	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0060	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0065	Sign Cover	8120310	32.000	Ea
0070	Sign, Type B, Temp, Prismatic, Furn	8120350	520.000	Sft
0075	Sign, Type B, Temp, Prismatic, Oper	8120351	520.000	Sft
0080	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	60.000	Sft
0085	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	60.000	Sft
0090	Traf Regulator Control	8120370	1.000	LSUM
0095	Monument Box, Adj	8210005	3.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 059

Letting Date: November 7, 2025

Contract ID: 50000-220158

Description: Traffic signal modernization including mast arm mounted LED traffic signals, back plates and countdown pedestrian signals on Hoover Road at Common Road in the city of Warren, Macomb County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220158A	25A1090	N/A	HSIP 50000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Preconstruction Audio-Visual Filming	1027051	1.000	LSUM
0010	_ Reimbursed Permit Fees	1077060	7,500.000	Dlr
0015	Mobilization, Max \$25,000.00	1100001	1.000	LSUM
0020	Exploratory Investigation, Vertical	2040080	10.000	Ft
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0030	Fence, Protective	8080007	100.000	Ft
0035	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0040	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0045	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0060	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0065	Sign, Type B, Temp, Prismatic, Furn	8120350	350.000	Sft
0070	Sign, Type B, Temp, Prismatic, Oper	8120351	350.000	Sft
0075	Traf Regulator Control	8120370	1.000	LSUM
0080	Water, Sodding/Seeding	8160090	5.000	Unit
0085	Slope Restoration, Non-Freeway, Type A	8162001	225.000	Syd
0090	Conduit, Directional Bore, 2, 3 inch	8182037	100.000	Ft
0095	Conduit, DB, 1, 1 1/2 inch	8182048	20.000	Ft
0100	Conduit, DB, 3, 3 inch	8182056	30.000	Ft
0105	Cable Pole, TS, Disman	8182210	2.000	Ea
0110	Hh, Round, 3 foot dia	8182319	1.000	Ea
0115	Wood Pole, Fit Up, TS Cable Pole	8182387	3.000	Ea
0120	Case Sign, Rem	8200020	1.000	Ea
0125	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	4.000	Ea
0130	Pedestal Fdn, Rem	8200106	1.000	Ea
0135	Pedestal, Rem	8200110	1.000	Ea

0140	Span Wire, Rem	8200141	1.000	Ea
0145	TS, Bracket Arm Mtd, Rem	8200175	1.000	Ea
0150	TS, Pedestal Mtd, Rem	8200179	1.000	Ea
0155	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	4.000	Ea
0160	TS, Pedestrian, Pedestal Mtd, Rem	8200181	2.000	Ea
0165	TS, Span Wire Mtd, Rem	8200182	4.000	Ea
0170	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	5.000	Ea
0175	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	1.000	Ea
0180	TS, One Way Mast Arm Mtd (LED)	8200359	8.000	Ea
0185	TS Face, Bag	8200458	4.000	Ea
0190	TS Face, Bag, Rem	8200459	4.000	Ea
0195	Casing, 42 inch	8200485	25.000	Ft
0200	Backplate, TS	8200501	10.000	Ea
0205	Mast Arm Pole, Cat I	8202010	2.000	Ea
0210	Mast Arm, 30 foot, Cat I	8202015	3.000	Ea
0215	Mast Arm, 45 foot, Cat I	8202018	1.000	Ea
0220	Mast Arm Pole Fdn, 6 Bolt	8202034	31.000	Ft
0225	_ Cabinet Painting	8207050	1.000	Ea
0230	_ Pole Coating	8207050	6.000	Ea
0235	_ St Name Sign, Two Way, LED, 6 foot	8207050	4.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 060

Letting Date: November 7, 2025

Contract ID: 77000-221321

Description: 0.55 mi of concrete curb, sidewalk and ramp, driveway replacement and pavement markings on Cox Road from Clinton Avenue to Vine Street in the city of St. Clair, St. Clair County. This is a Local Agency project. This is a Small Business Program project. Only those approved by MDOT as a Small Business may be eligible to bid as a prime contractor.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221321A	25A1034	N/A	TAU 77000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$30,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 6 inch to 18 inch	2020004	1.000	Ea
0015	_ Tree Root Trimming	2027050	12.000	Ea
0020	_ Tree Trimming	2027050	12.000	Ea
0025	Dr Structure, Rem	2030011	2.000	Ea
0030	Sewer, Rem, Less than 24 inch	2030015	232.000	Ft
0035	Curb and Gutter, Rem	2040020	232.000	Ft
0040	Sidewalk, Rem	2040055	57.000	Syd
0045	Excavation, Earth	2050016	250.000	Cyd
0050	_ Station Grading	2057002	29.000	Sta
0055	Erosion Control, Inlet Protection, Fabric Drop	2080020	13.000	Ea
0060	Aggregate Base, 4 inch	3020010	1,867.000	Syd
0065	Aggregate Base, 6 inch	3020016	198.000	Syd
0070	_ Aggregate Surface Cse, 4 inch	3067011	29.000	Syd
0075	Culv End Sect, Conc, 12 inch	4010047	1.000	Ea
0080	Culv End Sect, Metal, 12 inch	4010094	14.000	Ea
0085	Culv, CI A, CSP, 12 inch	4010199	297.000	Ft
0090	Sewer, CI IV, 12 inch, Tr Det A	4020960	27.000	Ft
0095	Dr Structure Cover, Adj, Case 2	4030006	2.000	Ea
0100	Dr Structure, 24 inch dia	4030200	2.000	Ea
0105	Dr Structure, 48 inch dia	4030210	1.000	Ea
0110	_ Catch Basin Cover, St. Clair	4037050	3.000	Ea
0115	_ Storm Mh Cover, St. Clair	4037050	1.000	Ea
0120	HMA Surface, Rem	5010005	257.000	Syd
0125	HMA Approach	5010061	80.000	Ton
0130	Driveway Opening, Conc, Det M	8020050	115.000	Ft
0135	Detectable Warning Surface	8030010	95.000	Ft

0140	Curb Ramp Opening, Conc	8030030	93.000	Ft
0145	Sidewalk, Conc, 4 inch	8030044	15,552.000	Sft
0150	Sidewalk, Conc, 6 inch	8030046	964.000	Sft
0155	_ Curb Ramp, Conc, 8 inch	8037010	650.000	Sft
0160	Post, Steel, 3 pound	8100371	70.000	Ft
0165	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0170	Sign, Type III, Rem	8100403	2.000	Ea
0175	Sign, Type IIIB	8100405	53.000	Sft
0180	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	690.000	Ft
0185	Pavt Mrkg, Ovly Cold Plastic, 18 inch, Stop Bar	8110044	25.000	Ft
0190	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	5.000	Ea
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	5.000	Ea
0200	Pedestrian Type II Barricade, Temp	8120026	2.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0210	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0215	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0220	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0225	Minor Traf Devices	8120170	1.000	LSUM
0230	Plastic Drum, Fluorescent, Furn	8120252	100.000	Ea
0235	Plastic Drum, Fluorescent, Oper	8120253	100.000	Ea
0240	Sign Cover	8120310	10.000	Ea
0245	Sign, Type B, Temp, Prismatic, Furn	8120350	500.000	Sft
0250	Sign, Type B, Temp, Prismatic, Oper	8120351	500.000	Sft
0255	Traf Regulator Control	8120370	1.000	LSUM
0260	Water, Sodding/Seeding	8160090	30.000	Unit
0265	Slope Restoration, Non-Freeway, Type A	8162001	3,607.000	Syd
0270	_ Irrigation Pipe	8167001	100.000	Ft
0275	_ Sprinkler Head	8167050	10.000	Ea
0280	Sanitary Structure Cover, Adj, Case 2	8252146	2.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 061

Letting Date: November 7, 2025

Contract ID: 41000-220185

Description: 0.53 mi of intersection reconstruction of a single lane roundabout, drainage improvements, sidewalk, lighting, signing and pavement markings at intersection of Myers Lake Avenue and 10 Mile Road, Kent County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220185A	25A1005	N/A	HSIP 41000
224879A	25A1014	N/A	CRU 41000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$226,800.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.100	Acre
0015	Stump, Rem, 19 inch to 36 inch	2020006	3.000	Ea
0020	Stump, Rem, 37 inch or Larger	2020007	1.000	Ea
0025	Stump, Rem, 6 inch to 18 inch	2020008	29.000	Ea
0030	Culv, Rem, Less than 24 inch	2030001	8.000	Ea
0035	Culv, Rem, 24 inch to 48 inch	2030002	4.000	Ea
0040	Curb and Gutter, Rem	2040020	516.000	Ft
0045	_ Exploratory Trenching	2047001	30.000	Ft
0050	Embankment, CIP	2050010	3,317.000	Cyd
0055	Excavation, Earth	2050016	6,044.000	Cyd
0060	Non Haz Contaminated Material Handling and Disposal, LM	2050031	160.000	Cyd
0065	Erosion Control, Inlet Protection, Fabric Drop	2080020	12.000	Ea
0070	Erosion Control, Silt Fence	2080036	1,200.000	Ft
0075	_ Filtration Log	2087001	200.000	Ft
0080	_ Project Cleanup, Modified	2097051	1.000	LSUM
0085	Subbase, CIP	3010002	4,838.000	Cyd
0090	_ Aggregate Base, 6 inch, Modified	3027011	14,686.000	Syd
0095	Maintenance Gravel, LM	3060021	20.000	Cyd
0100	_ Aggregate Surface Cse, 6 inch, Modified	3067011	142.000	Syd
0105	Approach, CI II, 6 inch	3070028	240.000	Syd
0110	Shld, CI II, 6 inch	3070128	588.000	Syd
0115	Culv End Sect, 12 inch	4010012	5.000	Ea
0120	Culv End Sect, 18 inch	4010018	1.000	Ea
0125	Culv End Sect, 30 inch	4010030	1.000	Ea
0130	Culv, CI F, 12 inch	4010607	87.000	Ft

0135	Culv, Slp End Sect, 1 on 4, 18 inch, Longit	4010919	6.000	Ea
0140	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 38 inch by 60 inch, Longit	4011063	1.000	Ea
0145	Sewer, CI E, 12 inch, Tr Det B	4020600	159.000	Ft
0150	Sewer, CI E, 18 inch, Tr Det B	4020602	761.000	Ft
0155	Sewer, CI E, 24 inch, Tr Det B	4020603	44.000	Ft
0160	Sewer, CI E, 30 inch, Tr Det B	4020604	28.000	Ft
0165	_ Sewer, Reinf Conc Ellip, HE CI E, 38 By 60 inch, Tr Det B, Modified	4027001	279.000	Ft
0170	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0175	Dr Structure Cover, Type B	4030010	3.000	Ea
0180	Dr Structure Cover, Type C	4030015	1.000	Ea
0185	Dr Structure Cover, Type G	4030040	1.000	Ea
0190	Dr Structure Cover, Type J	4030045	10.000	Ea
0195	Dr Structure Cover, Type Q	4030065	1.000	Ea
0200	Dr Structure, 24 inch dia	4030200	2.000	Ea
0205	Dr Structure, 48 inch dia	4030210	10.000	Ea
0210	Dr Structure, 72 inch dia	4030230	1.000	Ea
0215	Dr Structure, 108 inch dia	4030237	1.000	Ea
0220	Dr Structure, 120 inch dia	4030242	3.000	Ea
0225	_ Dr Structure, Reconst	4037001	1.000	Ft
0230	Underdrain Outlet, 6 inch	4040093	95.000	Ft
0235	_ Underdrain, Subbase, 6 inch, Modified	4047001	1,570.000	Ft
0240	HMA Surface, Rem	5010005	12,907.000	Syd
0245	Hand Patching	5010025	2.000	Ton
0250	HMA Approach	5010061	117.000	Ton
0255	HMA, 4EML	5012025	3,051.000	Ton
0260	HMA, 5EML	5012037	1,020.000	Ton
0265	Conc Pavt, Misc, Nonreinf, 6 inch	6020050	563.000	Syd
0270	Conc Pavt, Misc, Nonreinf, 8 inch	6020054	315.000	Syd
0275	Joint, Contraction, Cp	6020200	840.000	Ft
0280	Joint, Expansion, E3	6020208	240.000	Ft
0285	Curb, Conc, Det E1	8020001	74.000	Ft
0290	Curb, Conc, Det E2	8020002	136.000	Ft
0295	Curb and Gutter, Conc, Det B2	8020016	1,066.000	Ft
0300	Divider, Conc, Type I	8022000	1,649.000	Sft
0305	_ Curb and Gutter, Conc, Det B2, Modified	8027001	926.000	Ft
0310	_ Curb and Gutter, Conc, Det D2, Modified	8027001	236.000	Ft
0315	Curb Ramp Opening, Conc	8030030	246.000	Ft
0320	Sidewalk, Conc, 6 inch	8030046	2,867.000	Sft
0325	Curb Ramp, Conc, 6 inch	8032002	1,352.000	Sft
0330	Curb Slp, HMA	8050010	239.000	Ft
0335	Post, Mailbox	8070095	13.000	Ea
0340	Post Hole Through Conc for Steel Post	8100340	8.000	Ea
0345	Post, Steel, 3 pound	8100371	588.000	Ft

0350	Sign, Type IIA	8100398	30.000	Sft
0355	Sign, Type III, Rem	8100403	36.000	Ea
0360	Sign, Type IIIA	8100404	24.000	Sft
0365	Sign, Type IIIB	8100405	198.000	Sft
0370	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	4.000	Ea
0375	Reflective Panel for Permanent Sign Support, 3 foot	8100613	24.000	Ea
0380	Reflective Panel for Permanent Sign Support, 6 foot	8100616	4.000	Ea
0385	Ground Mtd Sign Support, Rem	8102010	31.000	Ea
0390	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	704.000	Ft
0395	Pavt Mrkg, Polyurea, 12 inch, White	8110111	78.000	Ft
0400	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	3,902.000	Ft
0405	Pavt Mrkg, Waterborne, 6 inch, White	8110233	4,207.000	Ft
0410	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	3,902.000	Ft
0415	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	4,207.000	Ft
0420	Recessing Pavt Mrkg, Longit	8110450	8,109.000	Ft
0425	Recessing Pavt Mrkg, Transv	8110451	391.000	Sft
0430	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	1.000	Ea
0435	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0440	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0445	Minor Traf Devices	8120170	1.000	LSUM
0450	Pavt Mrkg, Wet Reflective, Type NR, Paint, 4 inch, White, Temp	8120235	1,924.000	Ft
0455	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	2,190.000	Ft
0460	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	1,239.000	Ft
0465	Plastic Drum, Fluorescent, Furn	8120252	120.000	Ea
0470	Plastic Drum, Fluorescent, Oper	8120253	120.000	Ea
0475	Sign Cover	8120310	10.000	Ea
0480	Sign, Type B, Temp, Prismatic, Furn	8120350	1,165.000	Sft
0485	Sign, Type B, Temp, Prismatic, Oper	8120351	1,165.000	Sft
0490	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	100.000	Sft
0495	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	100.000	Sft
0500	Traf Regulator Control	8120370	1.000	LSUM
0505	Riprap, Plain	8130010	110.000	Syd
0510	Mulch Blanket	8160027	6,850.000	Syd
0515	Mulch Blanket, High Velocity	8160028	1,950.000	Syd
0520	_ Roadside Seeding	8167011	9,690.000	Syd
0525	Power Company (Estimated Cost to Contractor)	8180001	1,000.000	Dlr
0530	Conduit, Schedule 80, 1 inch	8182144	500.000	Ft
0535	DB Cable, in Conduit, 600V, 1/C#6	8182187	50.000	Ft
0540	DB Cable, in Conduit, 600V, 1/C#8	8182188	50.000	Ft
0545	DB Cable, in Conduit, 600V, 1/C#10	8182189	400.000	Ft
0550	Cable, Equipment Grounding Wire, 1/C#6	8182291	50.000	Ft
0555	Cable, Equipment Grounding Wire, 1/C#8	8182292	50.000	Ft

0560	Cable, Equipment Grounding Wire, 1/C#10	8182293	400.000	Ft
0565	Hh, Heavy Duty Cover	8182308	4.000	Ea
0570	Wood Pole, Rem	8182363	2.000	Ea
0575	Serv Disconnect, Rem	8182367	1.000	Ea
0580	Light Std Arm, 15 foot	8190269	4.000	Ea
0585	Light Std Fdn	8190279	4.000	Ea
0590	Light Std Shaft, 30 foot or less	8190285	4.000	Ea
0595	Luminaire	8190330	4.000	Ea
0600	_ Ltg Control Panel	8197050	1.000	Ea
0605	Controller and Cabinet, Rem	8200030	1.000	Ea
0610	Span Wire, Rem	8200141	1.000	Ea
0615	TS, Span Wire Mtd, Rem	8200182	2.000	Ea
0620	Monument Preservation	8210010	3.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 062

Letting Date: November 7, 2025

Contract ID: 77000-220156

Description: 0.19 mi of intersection reconstruction of a compact roundabout, hot mix asphalt crush and shape, drainage improvements, concrete curb and gutter, signing and pavement markings on Wadhams Road at St Clair Highway, St Clair County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220156A	25A1065	N/A	HSIP 77000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$44,200.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	1.000	Ea
0015	Culv, Rem, 24 inch to 48 inch	2030002	2.000	Ea
0020	Excavation, Earth	2050016	1,040.000	Cyd
0025	Non Haz Contaminated Material Handling and Disposal, LM	2050031	50.000	Cyd
0030	_ Embankment, CIP, Modified	2057021	1,180.000	Cyd
0035	_ Subgrade Undercutting, Modified	2057021	150.000	Cyd
0040	Erosion Control, Check Dam, Stone	2080012	40.000	Ft
0045	Project Cleanup	2090001	1.000	LSUM
0050	_ Aggregate Base, Modified	3027031	1,440.000	Ton
0055	HMA Base Crushing and Shaping	3050002	2,638.000	Syd
0060	_ Approach, CI II, Modified	3077031	34.000	Ton
0065	_ Shld, CI II, Modified	3077031	65.000	Ton
0070	Geotextile, Stabilization	3080010	500.000	Syd
0075	Culv, CI E, Conc, 18 inch	4010575	68.000	Ft
0080	Culv, CI F, Conc, 24 inch	4010644	23.000	Ft
0085	Culv, CI F, Conc, 30 inch	4010645	44.000	Ft
0090	HMA, 4EL, High Stress	5012072	841.000	Ton
0095	Conc Pavt, Nonreinf, 6 inch	6020100	205.000	Syd
0100	Conc Pavt, Nonreinf, 9 inch	6020106	154.000	Syd
0105	Joint, Expansion, E2	6020207	40.000	Ft
0110	Joint, Plane-of-Weakness, W	6020211	80.000	Ft
0115	Curb and Gutter, Conc, Det B2	8020016	887.000	Ft
0120	Shld Gutter, Conc, Det 2	8020056	4.000	Ea
0125	Shld Gutter, Conc, Det 3	8020057	3.000	Ea
0130	_ Curb and Gutter, Conc, Det D2, Modified, Central	8027001	186.000	Ft
0135	_ Curb and Gutter, Conc, Det D2, Modified, Splitter	8027001	861.000	Ft

0140	Pavt Mrkg, Polyurea, 6 inch, White	8110094	701.000	Ft
0145	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	717.000	Ft
0150	Pavt Mrkg, Polyurea, Yield	8110103	4.000	Ea
0155	Pavt Mrkg, Polyurea, 12 inch, White	8110111	234.000	Ft
0160	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	42.000	Ft
0165	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	16.000	Ea
0170	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	16.000	Ea
0175	Minor Traf Devices	8120170	1.000	LSUM
0180	Sign, Type B, Temp, Prismatic, Furn	8120350	337.000	Sft
0185	Sign, Type B, Temp, Prismatic, Oper	8120351	337.000	Sft
0190	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	200.000	Sft
0195	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	200.000	Sft
0200	Riprap, Plain	8130010	85.000	Syd
0205	Slope Restoration, Non-Freeway, Type F	8162006	2,590.000	Syd
0210	Slope Restoration, Non-Freeway, Type G	8162007	900.000	Syd
0215	Sinusoidal Corrugations, Non-Freeway, Milled, HMA Shld	8220035	1,600.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 063

Letting Date: November 7, 2025

Contract ID: 33000-218815

Description: 0.52 mi of shared-use path including hot mix asphalt paving, grading, and permanent pavement markings on M-43 (E. Saginaw Street) from Shiawassee Street to Saginaw Street in the city of Lansing, Ingham County. This is a Local Agency project. This is a Small Business Program project. Only those approved by MDOT as a Small Business may be eligible to bid as a prime contractor.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
218815A	25A1124	N/A	TAU 33000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$25,000.00	1100001	1.000	LSUM
0010	Clearing	2010001	0.710	Acre
0015	Tree, Rem, 6 inch to 18 inch	2020004	2.000	Ea
0020	Curb and Gutter, Rem	2040020	22.000	Ft
0025	Fence, Rem	2040025	120.000	Ft
0030	Sidewalk, Rem	2040055	12.000	Syd
0035	Embankment, CIP	2050010	250.000	Cyd
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0045	Subbase, CIP	3010002	2.000	Cyd
0050	Aggregate Base, 6 inch	3020016	2,416.000	Syd
0055	Shld, CI II, 6 inch	3070128	665.000	Syd
0060	Hand Patching	5010025	10.000	Ton
0065	Curb and Gutter, Conc, Det F4	8020038	22.000	Ft
0070	Sidewalk, Conc, 4 inch	8030044	108.000	Sft
0075	_ Detectable Warning Surface, Modified	8037001	6.000	Ft
0080	Shared use Path, Grading	8060030	1,566.000	Ft
0085	Shared use Path, HMA	8060040	287.000	Ton
0090	Fence, Chain Link, 48 inch	8080011	1,361.000	Ft
0095	Post, Steel, 3 pound	8100371	42.000	Ft
0100	Sign, Type IIIB	8100405	19.000	Sft
0105	Pavt Mrkg, Ovly Cold Plastic, Bike, Small Sym	8110058	7.000	Ea
0110	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	2.000	Ea
0115	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	2.000	Ea
0120	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	1.000	Ea
0125	Pavt Mrkg, Ovly Cold Plastic, Thru and Rt Turn Arrow Sym	8110077	1.000	Ea

0130	Pavt Mrkg, Ovly Cold Plastic, Thru Arrow Sym	8110078	3.000	Ea
0135	Pavt Mrkg, Waterborne, 6 inch, White	8110233	3,119.000	Ft
0140	Pavt Mrkg, Waterborne, 2nd Application, 6 inch, White	8110253	3,119.000	Ft
0145	Rem Spec Mrkg	8110343	84.000	Sft
0150	Pavt Mrkg, Ovly Cold Plastic, Bike Thru Arrow Sym	8112165	7.000	Ea
0155	_ Pavt Mrkg, Waterborne, 12 inch, Cross Hatching, White	8117001	214.000	Ft
0160	_ Pavt Mrkg, Waterborne, 24 inch, Stop Bar	8117001	130.000	Ft
0165	_ Pavt Mrkg, Waterborne, 2nd Application, 12 inch, Cross Hatching, White	8117001	214.000	Ft
0170	_ Pavt Mrkg, Waterborne, 2nd Application, 24 inch, Stop Bar	8117001	130.000	Ft
0175	_ Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Crosswalk	8117001	620.000	Ft
0180	_ Pavt Mrkg, Waterborne, 6 inch, Crosswalk	8117001	620.000	Ft
0185	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0190	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0195	Lighted Arrow, Type B, Furn	8120130	1.000	Ea
0200	Lighted Arrow, Type B, Oper	8120131	1.000	Ea
0205	Minor Traf Devices	8120170	1.000	LSUM
0210	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	2,066.000	Ft
0215	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	130.000	Ft
0220	Sign, Portable, Changeable Message, Furn	8120330	1.000	Ea
0225	Sign, Portable, Changeable Message, Oper	8120331	1.000	Ea
0230	Sign, Type B, Temp, Prismatic, Furn	8120350	190.000	Sft
0235	Sign, Type B, Temp, Prismatic, Oper	8120351	190.000	Sft
0240	_ Turf Establishment, Performance	8167011	1,000.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 064

Letting Date: November 7, 2025

Contract ID: 70000-215254

Description: 0.25 mi of hot mix asphalt reconstruction, concrete curb, gutter and sidewalk and pavement markings on Church Street from Washington Avenue to Central Avenue in the city of Zeeland, Ottawa County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215254A	25A1003	N/A	STUL 70000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$373,000.00	1100001	1.000	LSUM
0010	Tree, Rem, 19 inch to 36 inch	2020002	2.000	Ea
0015	Tree, Rem, 6 inch to 18 inch	2020004	1.000	Ea
0020	Dr Structure, Rem	2030011	6.000	Ea
0025	Sewer, Rem, Less than 24 inch	2030015	200.000	Ft
0030	Curb and Gutter, Rem	2040020	2,450.000	Ft
0035	Pavt, Rem	2040050	300.000	Syd
0040	Sidewalk, Rem	2040055	1,600.000	Syd
0045	_ Roadway Grading	2057002	14.000	Sta
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	22.000	Ea
0055	Subbase, CIP	3010002	2,000.000	Cyd
0060	_ Aggregate Base, 21AA, 12 inch, Modified	3027011	60.000	Syd
0065	_ Aggregate Base, 21AA, 4 inch, Modified	3027011	700.000	Syd
0070	_ Aggregate Base, 21AA, 8 inch, Modified	3027011	6,150.000	Syd
0075	Sewer, CI E, 12 inch, Tr Det B	4020600	104.000	Ft
0080	Sewer, CI E, 18 inch, Tr Det B	4020602	75.000	Ft
0085	_ Sewer, 18 inch in Stone Trench	4027001	550.000	Ft
0090	_ Sewer, CI E, 12 inch, Tr Det B, Modified	4027001	30.000	Ft
0095	Dr Structure Cover, Adj, Case 1	4030005	16.000	Ea
0100	Dr Structure Cover, Type B	4030010	12.000	Ea
0105	Dr Structure Cover, Type D	4030025	2.000	Ea
0110	Dr Structure Cover, Type K	4030050	6.000	Ea
0115	Dr Structure, 48 inch dia	4030210	7.000	Ea
0120	Dr Structure, Tap, 18 inch	4030318	1.000	Ea
0125	Dr Structure, Temp Lowering	4030390	16.000	Ea
0130	_ Underdrain, Subbase, 6 inch, Modified	4047001	1,100.000	Ft
0135	HMA Surface, Rem	5010005	6,050.000	Syd

0140	Hand Patching	5010025	50.000	Ton
0145	HMA, 3EL	5012012	65.000	Ton
0150	HMA, 4EL	5012024	840.000	Ton
0155	HMA, 5EL	5012036	515.000	Ton
0160	_ Conc Header, 12 inch	6027001	150.000	Ft
0165	_ Conc Base, 4 inch, Modified	6027011	175.000	Syd
0170	_ Conc Base, 7 inch, Modified	6027011	60.000	Syd
0175	Driveway, Nonreinf Conc, 7 inch	8010006	185.000	Syd
0180	_ Driveway, Nonreinf Conc, 7 inch, Modified	8017011	75.000	Syd
0185	Driveway Opening, Conc, Det M	8020050	80.000	Ft
0190	_ Curb and Gutter, Conc, Det F4, Modified	8027001	2,250.000	Ft
0195	Detectable Warning Surface	8030010	105.000	Ft
0200	Curb Ramp Opening, Conc	8030030	105.000	Ft
0205	Sidewalk, Conc, 4 inch	8030044	350.000	Sft
0210	_ 2 inch Styrofoam Insulation, High Density	8037010	21,100.000	Sft
0215	_ 3/4 inch PEX Snowmelt Tubing	8037010	21,100.000	Sft
0220	_ Brick Paver, 4 inch x 8 inch x 2-1/4 inch	8037010	1,450.000	Sft
0225	_ Brick Paver, 4 inch x 8 inch x 2-3/4 inch	8037010	500.000	Sft
0230	_ Curb Ramp, Conc, 6 inch, Modified	8037010	1,150.000	Sft
0235	_ Sidewalk, Conc, 5 inch, Modified	8037010	12,000.000	Sft
0240	_ Sidewalk, Conc, 7 inch, Modified	8037010	3,950.000	Sft
0245	_ Snow/Ice Sensor	8037050	2.000	Ea
0250	Fence, Protective	8080007	500.000	Ft
0255	Post, Steel, 3 pound	8100371	210.000	Ft
0260	Sign, Type IIIA	8100404	74.000	Sft
0265	Sign, Type IIIB	8100405	19.000	Sft
0270	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	580.000	Ft
0275	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	160.000	Ft
0280	Pavt Mrkg, Waterborne, 4 inch, White	8110231	100.000	Ft
0285	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	200.000	Ft
0290	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	2.000	Ea
0295	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	2.000	Ea
0300	Pavt Mrkg, Waterborne, For On-Street Parking, 4 inch, White	8110425	550.000	Ft
0305	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	15.000	Ea
0310	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	15.000	Ea
0315	Pedestrian Type II Barricade, Temp	8120026	12.000	Ea
0320	Dust Palliative, Applied	8120100	4.000	Ton
0325	Minor Traf Devices	8120170	1.000	LSUM
0330	Sign Cover	8120310	10.000	Ea
0335	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0340	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0345	Sign, Type B, Temp, Prismatic, Furn	8120350	560.000	Sft
0350	Sign, Type B, Temp, Prismatic, Oper	8120351	560.000	Sft

0355	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	115.000	Sft
0360	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	115.000	Sft
0365	Traf Regulator Control	8120370	1.000	LSUM
0370	Site Preparation, Max \$12,000	8150001	1.000	LSUM
0375	_ Amelanchier x grandiflora 'Juneberry', 2 1/2 inch, single stem	8157050	1.000	Ea
0380	_ Carpinus caroliniana 'American Hornbeam', 2 1/2 inch	8157050	5.000	Ea
0385	_ Liquidambar styraciflua 'Sweetgum', 2 1/2 inch	8157050	5.000	Ea
0390	_ Liriodendron tulipifera 'Tuliptree', 2 1/2 inch	8157050	2.000	Ea
0395	_ Tilia cordata 'Little-leaf Linden', 2 1/2 inch	8157050	1.000	Ea
0400	_ Turf Establishment	8167011	1,000.000	Syd
0405	_ Propylene Glycol	8167022	1,050.000	Gal
0410	Conduit, DB, 1, 1 1/4 inch	8182047	1,260.000	Ft
0415	Hh, Polymer Conc	8182309	4.000	Ea
0420	_ Conduit, DB, 1, 6 inch	8187001	435.000	Ft
0425	_ Conduit, DB, 2, 2 inch	8187001	250.000	Ft
0430	_ Conduit, Directional Bore, 2, 6 inch	8187001	264.000	Ft
0435	_ Light Pole Fdn	8187050	17.000	Ea
0440	_ Light Pole Fdn, Rem	8187050	5.000	Ea
0445	_ Water Main, D.I. CL 53, 16 inch with PolyWrap, including sand backfill	8237001	40.000	Ft
0450	_ Water Main, D.I. CL 53, 6 inch with PolyWrap, including sand backfill	8237001	100.000	Ft
0455	_ Water Main, D.I. CL 53, 8 inch with PolyWrap, including sand backfill	8237001	1,100.000	Ft
0460	_ Water Service, Copper, Type K, 1.5 inch	8237001	100.000	Ft
0465	_ Water Service, Copper, Type K, 2 inch	8237001	60.000	Ft
0470	_ Bend, 22.5 Degree, 8 inch	8237050	4.000	Ea
0475	_ Bend, 45 Degree, 16 inch	8237050	4.000	Ea
0480	_ Bend, 45 Degree, 8 inch	8237050	14.000	Ea
0485	_ Bend, 90 Degree, 6 inch	8237050	1.000	Ea
0490	_ Cross, 8 inch x 8 inch x 8 inch x 8 inch	8237050	1.000	Ea
0495	_ Curb Stop and Box, 1.5 inch	8237050	5.000	Ea
0500	_ Curb Stop and Box, 2 inch	8237050	1.000	Ea
0505	_ Exploratory Investigation, Water Service	8237050	6.000	Ea
0510	_ Hydrant, 5 inch	8237050	3.000	Ea
0515	_ Reducer, 8 inch x 6 inch	8237050	2.000	Ea
0520	_ Sleeve, 16 inch	8237050	2.000	Ea
0525	_ Sleeve, 6 inch	8237050	2.000	Ea
0530	_ Sleeve, 8 inch	8237050	8.000	Ea
0535	_ Tap for Water Service, including Corporation Stop and Collar, 1.5 inch	8237050	5.000	Ea
0540	_ Tap for Water Service, including Corporation Stop and Collar, 2 inch	8237050	1.000	Ea
0545	_ Tee, 8 inch x 8 inch x 6 inch	8237050	3.000	Ea
0550	_ Valve and Box, 6 inch	8237050	6.000	Ea

0555	_ Valve and Box, 8 inch	8237050	4.000	Ea
0560	_ Valve Box, Adj	8237050	8.000	Ea
0565	_ Valve Box, Furnished	8237050	10.000	Ea
0570	_ Water Service Connection	8237050	6.000	Ea
0575	_ Remove Existing Water Main, Hydrants and Fittings	8237051	1.000	LSUM
0580	_ Sanitary Sewer Lateral, SDR 26, 6 inch, including sand backfill	8257001	150.000	Ft
0585	_ Sanitary Sewer, 27 inch, including sand backfill	8257001	1,270.000	Ft
0590	_ Sanitary Sewer, SDR 26, 10 inch, including sand backfill	8257001	15.000	Ft
0595	_ Sanitary Sewer, SDR 26, 12 inch, including and backfill	8257001	30.000	Ft
0600	_ Sanitary Sewer, SDR 26, 15 inch, including sand backfill	8257001	20.000	Ft
0605	_ Sanitary Sewer, SDR 26, 8 inch, including sand backfill	8257001	40.000	Ft
0610	_ Sewer Televising	8257001	1,300.000	Ft
0615	_ Core & Boot on 27 inch Sanitary Sewer, 6 inch	8257050	13.000	Ea
0620	_ Sanitary Sewer Lateral Connection	8257050	13.000	Ea
0625	_ Sanitary Sewer Manhole, 48 inch, with cover	8257050	3.000	Ea
0630	_ Sanitary Sewer Manhole, 60 inch, with cover	8257050	2.000	Ea
0635	_ Maintain Sewer Flow	8257051	1.000	LSUM
0640	_ Remove Existing Sanitary Sewer System	8257051	1.000	LSUM
0645	_ 3 inch DR 11 Pipe, HDPE	8507001	800.000	Ft
0650	_ 4 inch DR 11 Pipe, HDPE	8507001	4,550.000	Ft
0655	_ 3 inch DR 11 90 degree elbows	8507050	16.000	Ea
0660	_ 30 inch x 48 inch box with 3 inch valves and manifolds	8507050	8.000	Ea
0665	_ 30 inch x 48 inch box with 4 inch valves and bypass	8507050	4.000	Ea
0670	_ 4 inch x 4 inch x 3 inch DR 11 reducing tee	8507050	16.000	Ea
0675	_ Archaeological Monitoring	8507060	10,000.000	Dlr
0680	_ Contaminated Material, Storage, Handling and Disposal	8507060	10,000.000	Dlr
0685	_ Irrigation Repair Allowance	8507060	30,000.000	Dlr



Schedule of Pay Items

Report v1

Letting Call: 251107 065

Letting Date: November 7, 2025

Contract ID: 25000-216282

Description: 1.09 mi of hot mix asphalt crushing, shaping, cold milling and resurfacing, replace culvert and pavement markings on Seymour Road from Reid Road to Hill Road, Genesee County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216282A	25A1018	N/A	STL 25000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$128,000.00	1100001	1.000	LSUM
0010	Culv, Rem, Less than 24 inch	2030001	35.000	Ea
0015	Culv, Rem, 24 inch to 48 inch	2030002	11.000	Ea
0020	Curb and Gutter, Rem	2040020	20.000	Ft
0025	Pavt, Rem	2040050	778.000	Syd
0030	Structures, Rem	2040060	1.000	LSUM
0035	Ditch Cleanout	2050006	3.000	Sta
0040	Embankment, CIP	2050010	4,360.000	Cyd
0045	Excavation, Earth	2050016	4,036.000	Cyd
0050	Erosion Control, Check Dam, Stone	2080012	325.000	Ft
0055	Erosion Control, Sediment Trap	2080034	11.000	Ea
0060	_ Aggregate Base, Modified	3027031	205.000	Ton
0065	HMA Base Crushing and Shaping	3050002	17,549.000	Syd
0070	_ Maintenance Gravel, Modified	3067031	350.000	Ton
0075	Trenching	3070200	113.000	Sta
0080	_ Approach, CI II, 6 inch, Modified	3077011	1,170.000	Syd
0085	_ Shld, CI II, Modified	3077031	805.000	Ton
0090	Culv End Sect, 12 inch	4010012	38.000	Ea
0095	Culv End Sect, 18 inch	4010018	28.000	Ea
0100	Culv End Sect, 24 inch	4010024	14.000	Ea
0105	Culv End Sect, 36 inch	4010036	2.000	Ea
0110	Culv End Sect, Conc, 18 inch	4010049	2.000	Ea
0115	Culv End Sect, Conc, 24 inch	4010051	4.000	Ea
0120	Culv, CI A, Conc, 18 inch	4010167	77.000	Ft
0125	Culv, CI A, Conc, 24 inch	4010168	172.000	Ft
0130	Culv, CI F, 12 inch	4010607	611.000	Ft
0135	Culv, CI F, 18 inch	4010609	496.000	Ft

0140	Culv, CI F, 24 inch	4010610	220.000	Ft
0145	Culv, CI F, 36 inch	4010612	40.000	Ft
0150	Cold Milling HMA Surface	5010002	406.000	Syd
0155	Hand Patching	5010025	120.000	Ton
0160	HMA Approach	5010061	45.000	Ton
0165	HMA, 3EL	5012012	3,135.000	Ton
0170	HMA, 5EL	5012036	2,090.000	Ton
0175	_ HMA Driveway, Spec	5017031	169.000	Ton
0180	_ Driveway, Nonreinf Conc, 5 inch, Modified	8017011	374.000	Syd
0185	Curb and Gutter, Conc, Det D2	8020031	20.000	Ft
0190	Post, Mailbox	8070095	42.000	Ea
0195	Post, Steel, 3 pound	8100371	432.000	Ft
0200	Sign, Type III, Erect, Salv	8100402	4.000	Ea
0205	Sign, Type III, Rem	8100403	27.000	Ea
0210	Sign, Type IIIA	8100404	18.000	Sft
0215	Sign, Type IIIB	8100405	129.000	Sft
0220	Reflective Panel for Permanent Sign Support, 6 foot	8100616	20.000	Ea
0225	Ground Mtd Sign Support, Rem	8102010	29.000	Ea
0230	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	20.000	Ft
0235	Pavt Mrkg, Waterborne, 4 inch, White	8110231	11,317.000	Ft
0240	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	9,002.000	Ft
0245	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	11,317.000	Ft
0250	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	9,002.000	Ft
0255	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	20.000	Ea
0260	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	20.000	Ea
0265	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea
0270	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0275	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0280	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0285	Minor Traf Devices	8120170	1.000	LSUM
0290	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	204.000	Ft
0295	Pavt Mrkg, Type NR, Paint, 24 inch, Stop Bar	8120216	50.000	Ft
0300	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, White, Temp	8120245	2,000.000	Ft
0305	Pavt Mrkg, Wet Reflective, Type R, Tape, 4 inch, Yellow, Temp	8120246	2,000.000	Ft
0310	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0315	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0320	Sign Cover	8120310	50.000	Ea
0325	Sign, Type B, Temp, Prismatic, Furn	8120350	150.000	Sft
0330	Sign, Type B, Temp, Prismatic, Oper	8120351	150.000	Sft
0335	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	50.000	Sft
0340	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	50.000	Sft
0345	Traf Regulator Control	8120370	1.000	LSUM

0350	Slope Restoration, Non-Freeway, Type E	8162005	24,400.000	Syd
0355	Monument Preservation	8210010	1.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 066

Letting Date: November 7, 2025

Contract ID: 82000-219472

Description: 1.80 mi of hot mix asphalt shared-use path and pedestrian signal work on the south side of Seven Mile Road from east of Pierson Drive to Northville Road, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219472A	25A1021	N/A	TA 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, CSX	1027060	1.000	Dir
0010	_ Audio Video Route Survey	1047051	1.000	LSUM
0015	_ Reimbursed Permit Fees	1077060	10,000.000	Dir
0020	Mobilization, Max \$199,000.00	1100001	1.000	LSUM
0025	Tree, Rem, 19 inch to 36 inch	2020002	25.000	Ea
0030	Tree, Rem, 37 inch or Larger	2020003	8.000	Ea
0035	Tree, Rem, 6 inch to 18 inch	2020004	61.000	Ea
0040	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0045	Culv, End, Rem, 24 inch to 48 inch	2030006	2.000	Ea
0050	Dr Structure, Rem	2030011	1.000	Ea
0055	Sewer, Rem, Less than 24 inch	2030015	45.000	Ft
0060	Curb, Rem	2040021	628.000	Ft
0065	Fence, Rem	2040025	55.000	Ft
0070	Pavt, Rem	2040050	1,457.000	Syd
0075	Sidewalk, Rem	2040055	903.000	Syd
0080	Exploratory Investigation, Vertical	2040080	305.000	Ft
0085	Embankment, CIP	2050010	1,461.000	Cyd
0090	Excavation, Earth	2050016	2,069.000	Cyd
0095	Non Haz Contaminated Material Handling and Disposal, LM	2050031	20.000	Cyd
0100	Subgrade Undercutting, Type III	2050042	200.000	Cyd
0105	Subgrade Undercutting, Type IV	2050043	500.000	Cyd
0110	Erosion Control, Inlet Protection, Fabric Drop	2080020	24.000	Ea
0115	Erosion Control, Silt Fence	2080036	8,800.000	Ft
0120	Project Cleanup	2090001	1.000	LSUM
0125	Maintenance Gravel	3060020	100.000	Ton
0130	Geotextile, Stabilization	3080010	1,556.000	Syd
0135	Culv End Sect, 12 inch	4010012	1.000	Ea

0140	Culv End Sect, Conc, 48 inch	4010055	2.000	Ea
0145	Culv, CI E, Conc, 48 inch	4010580	46.000	Ft
0150	Culv, CI F, Conc, 12 inch	4010641	261.000	Ft
0155	Sewer Bulkhead, 15 inch	4021231	1.000	Ea
0160	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0165	Dr Structure Cover, Type B	4030010	1.000	Ea
0170	Dr Structure Cover, Type G	4030040	2.000	Ea
0175	Dr Structure, 24 inch dia	4030200	1.000	Ea
0180	HMA Surface, Rem	5010005	1,448.000	Syd
0185	Hand Patching	5010025	10.000	Ton
0190	HMA Approach	5010061	50.000	Ton
0195	Conc Pavt with Integral Curb, Nonreinf, 9 inch	6020166	28.000	Syd
0200	Lane Tie, Epoxy Anchored	6030030	500.000	Ea
0205	Driveway, Nonreinf Conc, 8 inch	8010007	1,957.000	Syd
0210	Curb and Gutter, Conc, Det F4	8020038	40.000	Ft
0215	Driveway Opening, Conc, Det M	8020050	885.000	Ft
0220	Detectable Warning Surface	8030010	165.000	Ft
0225	Curb Ramp Opening, Conc	8030030	223.000	Ft
0230	Sidewalk, Conc, 4 inch	8030044	125.000	Sft
0235	Sidewalk, Conc, 6 inch	8030046	257.000	Sft
0240	Curb Ramp, Conc, 6 inch	8032002	2,323.000	Sft
0245	Shared use Path, HMA	8060040	2,463.000	Ton
0250	_ Shared use Path, Grading, Modified	8067001	9,002.000	Ft
0255	_ Shared use Path, Aggregate, 8 inch	8067011	14,350.000	Syd
0260	_ Fence, Ornamental Alum, 42 inch	8087001	200.000	Ft
0265	_ Wood Safety Fence	8087001	220.000	Ft
0270	Delineator Reflector, White	8100134	4.000	Ea
0275	Post, Steel, 3 pound	8100371	288.000	Ft
0280	Sign, Type III, Rem	8100403	18.000	Ea
0285	Sign, Type IIIB	8100405	122.000	Sft
0290	Post, Flexible, Delineator, Ground Mtd	8100555	4.000	Ea
0295	Pavt Mrkg, Ovly Cold Plastic, 6 inch, White	8110025	105.000	Ft
0300	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	1,060.000	Ft
0305	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	140.000	Ft
0310	Pavt Mrkg, Ovly Cold Plastic, Railroad Sym	8110069	2.000	Ea
0315	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	25.000	Ea
0320	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	25.000	Ea
0325	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea
0330	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	250.000	Ea
0335	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	250.000	Ea
0340	Lighted Arrow, Type C, Furn	8120140	6.000	Ea
0345	Lighted Arrow, Type C, Oper	8120141	6.000	Ea
0350	Minor Traf Devices	8120170	1.000	LSUM

0355	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	220.000	Ft
0360	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	61.000	Ft
0365	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0370	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0375	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	400.000	Sft
0380	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	400.000	Sft
0385	Traf Regulator Control	8120370	1.000	LSUM
0390	Riprap, Plain	8130010	10.000	Syd
0395	_ Bench	8157050	3.000	Ea
0400	Slope Restoration, Non-Freeway, Type A	8162001	10,000.000	Syd
0405	Slope Restoration, Non-Freeway, Type F	8162006	6,667.000	Syd
0410	_ Non-Selective Weed Spray Under Asphalt	8167010	110,000.000	Sft
0415	Conduit, Directional Bore, 1, 3 inch	8182035	75.000	Ft
0420	Conduit, DB, 1, 1 1/2 inch	8182048	110.000	Ft
0425	Conduit, DB, 1, 3 inch	8182050	35.000	Ft
0430	Conduit, DB, 2, 3 inch	8182053	15.000	Ft
0435	Conduit, DB, 3, 3 inch	8182056	10.000	Ft
0440	Conduit, DB, 4, 3 inch	8182059	5.000	Ft
0445	Cable, Rem	8182196	100.000	Ft
0450	Cable, P.J., 600V, 1, 20/C#14	8182224	100.000	Ft
0455	Cable, Sec, 600V, 1, 3/C#6	8182238	50.000	Ft
0460	Hh, Round	8182310	4.000	Ea
0465	Hh, Round, 3 foot dia	8182319	1.000	Ea
0470	Hh, Adj	8182328	14.000	Ea
0475	Serv Disconnect	8182366	1.000	Ea
0480	Wood Pole, Fit Up, TS Cable Pole	8182387	3.000	Ea
0485	Controller and Cabinet, Rem	8200030	1.000	Ea
0490	Controller Fdn, Base Mtd	8200045	1.000	Ea
0495	Global Positioning System Module	8200050	2.000	Ea
0500	Splice Box	8200085	1.000	Ea
0505	Pedestal, Alum	8200100	4.000	Ea
0510	Pedestal, Fdn	8200105	6.000	Ea
0515	Pedestal, Pushbutton, Alum	8200118	2.000	Ea
0520	Pushbutton and Sign	8200121	4.000	Ea
0525	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	1.000	Ea
0530	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	3.000	Ea
0535	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0540	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	4.000	Ea
0545	_ Cabinet, NEMA Type, Modified	8207050	1.000	Ea
0550	_ Controller, NEMA, ATC Type, Modified	8207050	1.000	Ea
0555	Monument Box, Adj	8210005	1.000	Ea
0560	_ Gate Well Cover, Adj, Add Depth	8237001	2.000	Ft
0565	_ Gate Well Cover, Adj	8237050	11.000	Ea

0570	_ Irrigation System Repr	8237050	2.000	Ea
0575	_ Sprinkler Head Repr	8237050	170.000	Ea
0580	Sanitary Structure Cover, Adj, Case 1	8252145	6.000	Ea
0585	Sanitary Structure Cover, Adj, Case 2	8252146	9.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 067

Letting Date: November 7, 2025

Contract ID: 52000-220595

Description: 0.48 mi of hot mix asphalt surface removal and resurfacing, drainage improvements and pavement markings on Werner Street east of County Road 505 and County Road 505 south of Venture Drive, Marquette County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220595A	25A0877	N/A	ER 52000
220596A	25A0761	N/A	ER 52000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$9,200.00	1100001	1.000	LSUM
0010	Ditch Cleanout	2050006	6.000	Sta
0015	Project Cleanup	2090001	1.000	LSUM
0020	Aggregate Base, Conditioning	3020050	1,292.000	Syd
0025	Video Taping Sewer and Culv Pipe	4021275	2,190.000	Ft
0030	Dr Structure Lead, Cleaning, 18 inch	4030118	140.000	Ft
0035	Dr Structure Lead, Cleaning, 24 inch	4030124	513.000	Ft
0040	Dr Structure Lead, Cleaning, 30 inch	4030130	211.000	Ft
0045	Dr Structure, Cleaning	4030290	26.000	Ea
0050	HMA Surface, Rem	5010005	1,292.000	Syd
0055	HMA Approach	5010061	4.000	Ton
0060	HMA, 5EML	5012037	244.000	Ton
0065	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	36.000	Ea
0070	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	36.000	Ea
0075	Lighted Arrow, Type C, Furn	8120140	4.000	Ea
0080	Lighted Arrow, Type C, Oper	8120141	4.000	Ea
0085	Minor Traf Devices	8120170	1.000	LSUM
0090	Sign, Type B, Temp, Prismatic, Furn	8120350	416.000	Sft
0095	Sign, Type B, Temp, Prismatic, Oper	8120351	416.000	Sft
0100	Traf Regulator Control	8120370	1.000	LSUM
0105	Slope Restoration, Non-Freeway, Type F	8162006	682.000	Syd



Schedule of Pay Items

Report v1

Letting Call: 251107 068

Letting Date: November 7, 2025

Contract ID: 25000-216182

Description: 0.96 mi of hot mix asphalt cold milling and resurfacing, concrete curb, gutter, sidewalk and ramps, signing and pavement markings on Broad Street from Bridge Street to Ripley Road in the city of Linden, Genesee County. This project includes a 1 year HMA warranty. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
216182A	25A0973	N/A	STU 25000
221499A	25A0974	N/A	STUL 25000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Reimbursed Permit Fees	1077060	800.000	Dir
0010	Mobilization, Max \$88,200.00	1100001	1.000	LSUM
0015	Curb and Gutter, Rem	2040020	786.000	Ft
0020	Sidewalk, Rem	2040055	333.000	Syd
0025	Excavation, Earth	2050016	70.000	Cyd
0030	Subgrade Undercutting, Type IV	2050043	160.000	Cyd
0035	Erosion Control, Inlet Protection, Fabric Drop	2080020	38.000	Ea
0040	Subbase, CIP	3010002	42.000	Cyd
0045	Aggregate Base, 6 inch	3020016	3,359.000	Syd
0050	Dr Structure Cover, Adj, Case 1	4030005	16.000	Ea
0055	Dr Structure Cover, Adj, Case 2	4030006	1.000	Ea
0060	_ Dr Structure, Reconst	4037001	20.000	Ft
0065	Cold Milling HMA Surface	5010002	16,439.000	Syd
0070	HMA Surface, Rem	5010005	3,224.000	Syd
0075	Hand Patching	5010025	1,639.000	Ton
0080	HMA, 5EML	5012037	2,330.000	Ton
0085	Curb and Gutter, Conc, Det C4	8020023	503.000	Ft
0090	Detectable Warning Surface	8030010	155.000	Ft
0095	Curb Ramp Opening, Conc	8030030	201.000	Ft
0100	Sidewalk, Conc, 4 inch	8030044	1,575.000	Sft
0105	Curb Ramp, Conc, 6 inch	8032002	1,470.000	Sft
0110	Post Hole Through Conc for Steel Post	8100340	1.000	Ea
0115	Post, Steel, 3 pound	8100371	98.000	Ft
0120	Sign, Type III, Erect, Salv	8100402	10.000	Ea
0125	Sign, Type III, Rem, Salv	8102003	12.000	Ea
0130	Ground Mtd Sign Support, Rem	8102010	8.000	Ea

0135	Pavt Mrkg, Polyurea, 4 inch, White	8110091	258.000	Ft
0140	Pavt Mrkg, Polyurea, 4 inch, Yellow	8110092	9,477.000	Ft
0145	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	844.000	Ft
0150	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	122.000	Ft
0155	Pavt Mrkg, Preformed Thermopl, Accessible Sym	8110204	3.000	Ea
0160	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	3.000	Ea
0165	Pavt Mrkg, Polyurea, Only	8110410	5.000	Ea
0170	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	1.000	Ea
0175	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	2.000	Ea
0180	Pavt Mrkg, Polyurea, Thru Arrow Sym	8110418	1.000	Ea
0185	Pavt Mrkg, Polyurea, For On-Street Parking, 4 inch, White	8110420	160.000	Ft
0190	_ Pavt Mrkg, Polyurea, For On-Street Parking, 4 inch, Blue	8117001	310.000	Ft
0195	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	37.000	Ea
0200	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	37.000	Ea
0205	Pedestrian Type II Barricade, Temp	8120026	24.000	Ea
0210	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	150.000	Ea
0215	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	150.000	Ea
0220	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0225	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0230	Minor Traf Devices	8120170	1.000	LSUM
0235	Plastic Drum, Fluorescent, Furn	8120252	50.000	Ea
0240	Plastic Drum, Fluorescent, Oper	8120253	50.000	Ea
0245	Sign, Type B, Temp, Prismatic, Furn	8120350	441.000	Sft
0250	Sign, Type B, Temp, Prismatic, Oper	8120351	441.000	Sft
0255	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	120.000	Sft
0260	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	120.000	Sft
0265	Traf Regulator Control	8120370	1.000	LSUM
0270	Pedestrian Path, Temp	8122250	100.000	Ft
0275	Pedestrian Ramp, Temp	8122251	12.000	Ea
0280	Slope Restoration, Non-Freeway, Type A	8162001	200.000	Syd
0285	Monument Box	8210001	2.000	Ea
0290	Monument Box, Adj	8210005	2.000	Ea
0295	Monument Preservation	8210010	1.000	Ea
0300	Protect Corners	8210020	1.000	Ea
0305	Gate Box, Adj, Case 1	8230431	5.000	Ea
0310	_ Curb Ramp Layout	8247051	1.000	LSUM
0315	Sanitary Structure Cover, Adj, Case 1	8252145	7.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 069

Letting Date: November 7, 2025

Contract ID: 70000-215834

Description: 0.62 mi of hot mix asphalt reconstruction, concrete curb, gutter and sidewalk ramps and pavement markings on Highland Drive from 32nd Avenue to Creek View Drive in the city of Hudsonville, Ottawa County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215834A	25A1017	N/A	STU 70000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$84,500.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	376.000	Ft
0015	Sidewalk, Rem	2040055	100.000	Syd
0020	Subgrade Undercutting, Type II	2050041	50.000	Cyd
0025	_ Roadway Grading	2057002	28.000	Sta
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	26.000	Ea
0035	Subbase, CIP	3010002	250.000	Cyd
0040	Aggregate Base, LM	3020002	40.000	Cyd
0045	Aggregate Base, 8 inch	3020020	12,525.000	Syd
0050	Aggregate Base, Conditioning	3020050	3,100.000	Syd
0055	Maintenance Gravel, LM	3060021	80.000	Cyd
0060	_ Geotextile, Separator, Spec	3087011	12,450.000	Syd
0065	Dr Structure Cover, Adj, Case 1	4030005	3.000	Ea
0070	Dr Structure Cover, Type K	4030050	1.000	Ea
0075	Dr Structure, Tap, 6 inch	4030306	14.000	Ea
0080	Dr Structure, Temp Lowering	4030390	14.000	Ea
0085	_ Dr Structure Cover, Adj, Case 1, Spec	4037050	13.000	Ea
0090	Underdrain, Subbase, 6 inch	4040063	3,600.000	Ft
0095	HMA Surface, Rem	5010005	15,622.000	Syd
0100	HMA Approach	5010061	20.000	Ton
0105	HMA, 4EML	5012025	3,620.000	Ton
0110	Curb and Gutter, Conc, Det F4	8020038	66.000	Ft
0115	Driveway Opening, Conc, Det M	8020050	240.000	Ft
0120	Curb Ramp Opening, Conc	8030030	70.000	Ft
0125	Curb Ramp, Conc, 4 inch	8032001	440.000	Sft
0130	Curb Ramp, Conc, 6 inch	8032002	384.000	Sft
0135	_ Detectable Warning Surface, Metal, Spec	8037001	50.000	Ft

0140	Post, Steel, 3 pound	8100371	56.000	Ft
0145	Sign, Type III, Erect, Salv	8100402	1.000	Ea
0150	Sign, Type III, Rem	8100403	5.000	Ea
0155	Sign, Type IIIA	8100404	7.000	Sft
0160	Sign, Type IIIB	8100405	6.000	Sft
0165	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	700.000	Ft
0170	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	83.000	Ft
0175	Pavt Mrkg, Waterborne, 4 inch, White	8110231	550.000	Ft
0180	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	6,500.000	Ft
0185	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	550.000	Ft
0190	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	6,500.000	Ft
0195	Rem Spec Mrkg	8110343	200.000	Sft
0200	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	4.000	Ea
0205	Pavt Mrkg, Polyurea, Only	8110410	4.000	Ea
0210	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	1.000	Ea
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	12.000	Ea
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	12.000	Ea
0225	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
0230	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	80.000	Ea
0235	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	80.000	Ea
0240	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0245	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0250	Minor Traf Devices	8120170	1.000	LSUM
0255	Sign Cover	8120310	35.000	Ea
0260	Sign, Type B, Temp, Prismatic, Furn	8120350	724.000	Sft
0265	Sign, Type B, Temp, Prismatic, Oper	8120351	724.000	Sft
0270	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	51.000	Sft
0275	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	51.000	Sft
0280	Traf Regulator Control	8120370	1.000	LSUM
0285	_ Turf Restoration	8167011	150.000	Syd
0290	TS Face, Bag	8200458	1.000	Ea
0295	TS Face, Bag, Rem	8200459	1.000	Ea
0300	Monument Box	8210001	1.000	Ea
0305	Monument Box, Adj	8210005	1.000	Ea
0310	Monument Preservation	8210010	1.000	Ea
0315	Gate Box, Adj, Temp, Case 1	8230391	2.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 070

Letting Date: November 7, 2025

Contract ID: 58000-221089

Description: 0.50 mi of concrete pavement reconstruction, pavement joint repair, concrete sidewalk and ramps, and permanent pavement markings on M-50 from north of Research Parkway to south of Granite Road in the village of Dundee, Monroe County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221089A	25A0938	N/A	STUL 58000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$51,800.00	1100001	1.000	LSUM
0010	Curb and Gutter, Rem	2040020	924.000	Ft
0015	Pavt, Rem	2040050	1,373.000	Syd
0020	Sidewalk, Rem	2040055	135.000	Syd
0025	Excavation, Earth	2050016	100.000	Cyd
0030	Erosion Control, Inlet Protection, Fabric Drop	2080020	20.000	Ea
0035	Project Cleanup	2090001	1.000	LSUM
0040	Aggregate Base, Conditioning	3020050	1,440.000	Syd
0045	Dr Structure Cover, Adj, Case 1	4030005	3.000	Ea
0050	Pavt, Cleaning	5010001	1.000	LSUM
0055	HMA Surface, Rem	5010005	70.000	Syd
0060	Conc Pavt, Misc, Nonreinf, 9 inch	6020056	1,440.000	Syd
0065	Joint, Expansion, E2	6020207	20.000	Ft
0070	Joint, Expansion, E3	6020208	403.000	Ft
0075	Saw Cut, Intermediate	6030090	403.000	Ft
0080	Resealing Trans Joints with Hot-Poured Rubber	6030100	1,163.000	Ft
0085	Resealing Longit Joints with Hot-Poured Rubber	6030101	4,742.000	Ft
0090	_ Joint, Tied, 2.5 foot	6037001	3,867.000	Ft
0095	_ Pavt Repr, 2.5 foot, Nonreinf, 9 Inch	6037011	1,112.000	Syd
0100	_ Pavt Repr, 2.5 foot, Rem	6037011	1,112.000	Syd
0105	Curb, Conc, Det E1	8020001	41.000	Ft
0110	Curb and Gutter, Conc, Det F5	8020039	884.000	Ft
0115	Detectable Warning Surface	8030010	37.000	Ft
0120	Curb Ramp Opening, Conc	8030030	49.000	Ft
0125	Sidewalk, Conc, 4 inch	8030044	595.000	Sft
0130	Curb Ramp, Conc, 6 inch	8032002	263.000	Sft
0135	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	205.000	Ft

0140	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	46.000	Ft
0145	Pavt Mrkg, Waterborne, 6 inch, White	8110233	114.000	Ft
0150	Pavt Mrkg, Waterborne, 6 inch, Yellow	8110234	364.000	Ft
0155	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	670.000	Ft
0160	Rem Curing Compound, for Spec Mrkg	8110321	320.000	Sft
0165	Witness, Log, \$1,250.00	8110351	1,250.000	Dir
0170	Pavt Mrkg, Polyurea, Only	8110410	1.000	Ea
0175	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	1.000	Ea
0180	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	40.000	Ea
0185	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	40.000	Ea
0190	Pedestrian Type II Barricade, Temp	8120026	4.000	Ea
0195	Pedestrian Type II Channelizer, Temp	8120027	50.000	Ft
0200	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0205	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0210	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0215	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0220	Minor Traf Devices	8120170	1.000	LSUM
0225	Sign, Portable, Changeable Message, Furn	8120330	2.000	Ea
0230	Sign, Portable, Changeable Message, Oper	8120331	2.000	Ea
0235	Sign, Type B, Temp, Prismatic, Furn	8120350	320.000	Sft
0240	Sign, Type B, Temp, Prismatic, Oper	8120351	320.000	Sft
0245	Pedestrian Path, Temp	8122250	20.000	Ft
0250	Pedestrian Ramp, Temp	8122251	2.000	Ea
0255	Slope Restoration, Non-Freeway, Type A	8162001	41.000	Syd
0260	Traf Loop	8200170	2.000	Ea
0265	Wireless Vehicle Sensor Node, Salv	8200427	2.000	Ea
0270	TS Face, Bag	8200458	2.000	Ea
0275	TS Face, Bag, Rem	8200459	2.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 071

Letting Date: November 7, 2025

Contract ID: 63000-221323

Description: 0.40 mi of hot mix asphalt shared-use path and boardwalk on Beck Road along ITC Corridor on the southside of Bosco Fields (located at 11 mile and Beck Road) in the city of Novi, Oakland County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221323A	25A1123	N/A	TAU 63000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Pre-Construction Audio Visual	1047051	1.000	LSUM
0010	Mobilization, Max \$132,000.00	1100001	1.000	LSUM
0015	Tree, Rem, 19 inch to 36 inch	2020002	7.000	Ea
0020	Tree, Rem, 37 inch or Larger	2020003	2.000	Ea
0025	Tree, Rem, 6 inch to 18 inch	2020004	20.000	Ea
0030	Culv, Rem, 24 inch to 48 inch	2030002	1.000	Ea
0035	_ Subgrade Undercutting, Spec	2057021	85.000	Cyd
0040	Erosion Control, Silt Fence	2080036	1,500.000	Ft
0045	_ Aggregate Base, 21AA Limestone, 6 inch	3027011	2,538.000	Syd
0050	_ Geogrid, Triaxial, Spec	3087011	254.000	Syd
0055	_ Helical Pile, 20 Foot	7057050	154.000	Ea
0060	_ Helical Pile, Add 5 Foot Sect	7057050	270.000	Ea
0065	_ Helical Pile, Battered	7057050	5.000	Ea
0070	_ Helical Pile Equipment, Furn	7057051	1.000	LSUM
0075	_ Conc Headwall	7067050	2.000	Ea
0080	_ Boardwalk Railing	7097001	598.000	Ft
0085	_ Boardwalk Substructure, Beams and Joists	7097001	598.000	Ft
0090	_ Boardwalk Decking Boards	7107011	931.000	Syd
0095	Sidewalk, Conc, 4 inch	8030044	240.000	Sft
0100	Shared use Path, HMA	8060040	572.000	Ton
0105	_ Shared use Path, Grading, Spec	8067001	2,075.000	Ft
0110	Post, Steel, 3 pound	8100371	40.000	Ft
0115	Sign, Type IIIA	8100404	10.000	Sft
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0125	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0130	Pedestrian Type II Barricade, Temp	8120026	8.000	Ea

0135	Minor Traf Devices	8120170	1.000	LSUM
0140	Traf Regulator Control	8120370	1.000	LSUM
0145	_ Boulder, Relocate	8157050	2.000	Ea
0150	_ Slope Restoration, Spec	8167001	2,075.000	Ft



Schedule of Pay Items

Report v1

Letting Call: 251107 072

Letting Date: November 7, 2025

Contract ID: 50031-219696

Description: Traffic signal upgrade including vehicle detection with automated traffic signal on M-97 at various intersections, Macomb County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219696A	25A0895	N/A	CRU 50031

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Railroad Protection, at Grade Crossing, Grand Trunk Western Railroad	1027060	8,000.000	Dlr
0010	Mobilization, Max \$212,000.00	1100001	1.000	LSUM
0015	Curb, Rem	2040021	55.000	Ft
0020	Sidewalk, Rem	2040055	123.000	Syd
0025	Exploratory Investigation, Vertical	2040080	45.000	Ft
0030	Non Haz Contaminated Material Handling and Disposal, LM	2050031	20.000	Cyd
0035	Detectable Warning Surface	8030010	55.000	Ft
0040	Curb Ramp Opening, Conc	8030030	55.000	Ft
0045	Sidewalk, Conc, 4 inch	8030044	1,125.000	Sft
0050	_ Curb Ramp, Conc, 9 inch, Spec	8037010	314.000	Sft
0055	Pedestrian Type II Barricade, Temp	8120026	36.000	Ea
0060	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0065	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0070	Lighted Arrow, Type C, Furn	8120140	2.000	Ea
0075	Lighted Arrow, Type C, Oper	8120141	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	Sign Cover	8120310	10.000	Ea
0090	Sign, Type B, Temp, Prismatic, Furn	8120350	120.000	Sft
0095	Sign, Type B, Temp, Prismatic, Oper	8120351	120.000	Sft
0100	Traf Regulator Control	8120370	1.000	LSUM
0105	_ Turf Establishment, Performance	8167011	330.000	Syd
0110	Conduit, DB, 1, 1/2 inch	8182046	532.000	Ft
0115	Conduit, DB, 1, 3 inch	8182050	78.000	Ft
0120	Conduit, DB, 2, 3 inch	8182053	174.000	Ft
0125	Conduit, DB, 4, 3 inch	8182059	60.000	Ft
0130	Hh, Round, 3 foot dia	8182319	3.000	Ea
0135	Wood Pole, Fit Up, TS Cable Pole	8182387	14.000	Ea

0140	Steel Pole, Fit Up, TS Cable Pole	8182397	4.000	Ea
0145	Anchor Guy	8200001	1.000	Ea
0150	Span Wire	8200140	1.000	Ea
0155	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	2.000	Ea
0160	Bracket, Truss, Salv	8200385	12.000	Ea
0165	Bracket, Truss, Rem	8200388	30.000	Ea
0170	_ ATC Cabinet Fdn, 340	8207050	3.000	Ea
0175	_ ATC Cabinet Operational Test Certification	8207050	3.000	Ea
0180	_ ATC Cabinet, 340, 32 Output, Black	8207050	3.000	Ea
0185	_ ATC Controller	8207050	3.000	Ea
0190	_ Hemispherical Video Detection Camera, Modified	8207050	67.000	Ea
0195	_ Hemispherical Video Detection System, Modified	8207050	34.000	Ea
0200	_ Pedestal and Fdn, Black	8207050	2.000	Ea
0205	_ Pushbutton and Sign, Black	8207050	18.000	Ea
0210	_ Pushbutton Post and Fdn, Black	8207050	16.000	Ea
0215	_ Radar Detection, Adj	8207050	9.000	Ea
0220	_ Radar Detection, Rem	8207050	102.000	Ea
0225	_ Steel Truss Arm, Mast Standard Mtd, 18 Foot, Black	8207050	9.000	Ea
0230	_ Steel Truss Arm, Mast Standard Mtd, 6 Foot, Black	8207050	3.000	Ea
0235	_ Steel Truss Arm, Steel Pole Mtd, 18 Foot	8207050	9.000	Ea
0240	_ Steel Truss Arm, Steel Pole Mtd, 6 Foot	8207050	1.000	Ea
0245	_ Steel Truss Arm, Wood Pole Mtd, 18 Foot	8207050	14.000	Ea
0250	_ Steel Truss Arm, Wood Pole Mtd, 18 Foot, Black	8207050	1.000	Ea
0255	_ Wireless Interconnect, Integrated Radio	8207050	32.000	Ea
0260	_ Wireless Interconnect, Integrated Radio, 900P	8207050	2.000	Ea
0265	_ Wireless Interconnect, Integrated Radio, Proxim	8207050	2.000	Ea
0270	_ Wireless Interconnect, Integrated Radio, Rem	8207050	29.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 073

Letting Date: November 7, 2025

Contract ID: 82000-222966

Description: 1.30 mi of concrete roadway reconstruction, concrete sidewalk and ramps, storm sewer and pavement markings on Cogswell Street south of Van Born Road to south of Ecorse Road in the city of Romulus, Wayne County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
222966A	25A1064	N/A	EAR 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Audio Visual Record of Construction Area	1027051	1.000	LSUM
0010	Mobilization, Max \$49,700.00	1100001	1.000	LSUM
0015	Dr Structure, Rem	2030011	1.000	Ea
0020	Sewer, Rem, Less than 24 inch	2030015	15.000	Ft
0025	Curb and Gutter, Rem	2040020	500.000	Ft
0030	Pavt, Rem	2040050	515.000	Syd
0035	Sidewalk, Rem	2040055	140.000	Syd
0040	Embankment, CIP	2050010	75.000	Cyd
0045	Excavation, Earth	2050016	75.000	Cyd
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	20.000	Ea
0055	Erosion Control, Silt Fence	2080036	200.000	Ft
0060	Aggregate Base, 4 inch	3020010	140.000	Syd
0065	Aggregate Base, 6 inch	3020016	100.000	Syd
0070	Aggregate Base, 8 inch	3020020	630.000	Syd
0075	Sewer, CI IV, 12 inch, Tr Det B	4020987	15.000	Ft
0080	Sewer Tap, 12 inch	4021204	1.000	Ea
0085	Dr Structure Cover, Adj, Case 2	4030006	25.000	Ea
0090	Dr Structure Cover, Type B	4030010	15.000	Ea
0095	Dr Structure Cover, Type D	4030025	10.000	Ea
0100	Dr Structure, 48 inch dia	4030210	1.000	Ea
0105	Dr Structure, Adj, Add Depth	4030280	12.000	Ft
0110	_ Dr Structure, Reconstruct	4037001	30.000	Ft
0115	Underdrain, Subgrade, 6 inch	4040073	430.000	Ft
0120	Conc Pavt with Integral Curb, Nonreinf, 10 inch	6020168	530.000	Syd
0125	Joint, Contraction, Cp	6020200	2,000.000	Ft
0130	Joint, Expansion, E2	6020207	35.000	Ft
0135	Joint, Contraction, Crg	6030020	2,300.000	Ft

0140	Lane Tie, Epoxy Anchored	6030030	2,000.000	Ea
0145	Pavt Repr, Nonreinf Conc, 11 inch	6030050	1,875.000	Syd
0150	Pavt Repr, Rem	6030080	1,875.000	Syd
0155	Saw Cut, Intermediate	6030090	1,000.000	Ft
0160	Driveway, Reinf Conc, 6 inch	8010001	100.000	Syd
0165	Detectable Warning Surface	8030010	45.000	Ft
0170	Sidewalk, Conc, 4 inch	8030044	150.000	Sft
0175	Curb Ramp, Conc, 4 inch	8032001	360.000	Sft
0180	Curb Ramp, Conc, 7 inch	8032003	400.000	Sft
0185	Pavt Mrkg, Polyurea, 4 inch, White	8110091	160.000	Ft
0190	Pavt Mrkg, Polyurea, 4 inch, Yellow	8110092	500.000	Ft
0195	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	35.000	Ft
0200	Rem Curing Compound, for Longit Mrkg, 4 inch	8110307	660.000	Ft
0205	Rem Curing Compound, for Spec Mrkg	8110321	172.000	Sft
0210	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0215	Pavt Mrkg, Polyurea, Rt Turn Arrow Sym	8110412	2.000	Ea
0220	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	6.000	Ea
0225	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	6.000	Ea
0230	Pedestrian Type II Barricade, Temp	8120026	7.000	Ea
0235	Lighted Arrow, Type B, Furn	8120130	2.000	Ea
0240	Lighted Arrow, Type B, Oper	8120131	2.000	Ea
0245	Minor Traf Devices	8120170	1.000	LSUM
0250	Plastic Drum, Fluorescent, Furn	8120252	80.000	Ea
0255	Plastic Drum, Fluorescent, Oper	8120253	80.000	Ea
0260	Sign, Type B, Temp, Prismatic, Furn	8120350	700.000	Sft
0265	Sign, Type B, Temp, Prismatic, Oper	8120351	700.000	Sft
0270	Slope Restoration, Non-Freeway, Type A	8162001	500.000	Syd
0275	TS Face, Bag	8200458	4.000	Ea
0280	TS Face, Bag, Rem	8200459	4.000	Ea
0285	Monument Box, Adj	8210005	1.000	Ea
0290	Monument Preservation	8210010	1.000	Ea
0295	Sanitary Structure Cover, Adj, Case 2	8252146	10.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 074

Letting Date: November 7, 2025

Contract ID: 63000-219309

Description: 0.60 mi of concrete reconstruction and widening from 3 to 5 lanes, drainage, concrete curb, gutter, sidewalk, ramps, signing, pavement markings, and pedestrian signals on Beck Road from 11 Mile Road to Grand River Avenue in the city of Novi, Oakland County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
219309A	25A1093	N/A	EAR 63000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Pre-Construction Audio-Visual	1027051	1.000	LSUM
0010	Mobilization, Max \$505,500.00	1100001	1.000	LSUM
0015	Clearing	2010001	0.200	Acre
0020	Tree, Rem, 6 inch to 18 inch	2020004	8.000	Ea
0025	Culv, Rem, Less than 24 inch	2030001	11.000	Ea
0030	Culv, Rem, 24 inch to 48 inch	2030002	2.000	Ea
0035	Culv, End, Rem, Less than 24 inch	2030005	1.000	Ea
0040	Dr Structure, Rem	2030011	10.000	Ea
0045	Sewer, Rem, Less than 24 inch	2030015	459.000	Ft
0050	_ Abandon Utility, Rem	2037001	545.000	Ft
0055	Curb and Gutter, Rem	2040020	2,490.000	Ft
0060	Pavt, Rem	2040050	885.000	Syd
0065	Sidewalk, Rem	2040055	913.000	Syd
0070	_ Boardwalk, Rem	2047001	369.000	Ft
0075	Embankment, CIP	2050010	4,132.000	Cyd
0080	Excavation, Earth	2050016	8,167.000	Cyd
0085	Non Haz Contaminated Material Handling and Disposal, LM	2050031	10.000	Cyd
0090	_ Phragmites Plant Material Handling and Disposal, LM	2057021	3,000.000	Cyd
0095	_ Subgrade Undercutting, Spec (1 X 3)	2057021	1,000.000	Cyd
0100	Erosion Control, Inlet Protection, Fabric Drop	2080020	45.000	Ea
0105	Erosion Control, Inlet Protection, Sediment Trap	2080024	11.000	Ea
0110	Erosion Control, Silt Fence	2080036	5,000.000	Ft
0115	_ Aggregate Base, 21AA Limestone, 10 inch	3027011	21,808.000	Syd
0120	_ Aggregate Base, 21AA Limestone, 4 inch	3027011	3,013.000	Syd
0125	_ Aggregate Base, 21AA Limestone, 6 inch	3027011	860.000	Syd
0130	_ Road Grade Triaxial Geogrid	3027011	21,808.000	Syd

0135	Maintenance Gravel, LM	3060021	400.000	Cyd
0140	Geotextile, Separator	3080005	37.000	Syd
0145	Culv End Sect, 12 inch	4010012	4.000	Ea
0150	Culv End Sect, 18 inch	4010018	1.000	Ea
0155	Culv, CI A, 18 inch	4010133	7.000	Ft
0160	Culv, CI E, 12 inch	4010539	28.000	Ft
0165	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 24 inch by 38 inch, Transv	4011056	1.000	Ea
0170	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 43 inch by 68 inch, Transv	4011066	2.000	Ea
0175	Dr Marker Post	4011109	4.000	Ea
0180	Sewer, CI A, 12 inch, Tr Det B	4020033	270.000	Ft
0185	Sewer, CI A, 15 inch, Tr Det B	4020034	380.000	Ft
0190	Sewer, CI A, 24 inch, Tr Det B	4020036	210.000	Ft
0195	Sewer, CI E, 12 inch, Tr Det B	4020600	1,962.000	Ft
0200	Sewer, CI E, 15 inch, Tr Det B	4020601	50.000	Ft
0205	Sewer, CI E, 18 inch, Tr Det B	4020602	271.000	Ft
0210	Sewer Tap, 12 inch	4021204	1.000	Ea
0215	Sewer Tap, 18 inch	4021206	2.000	Ea
0220	Sewer, Reinf Conc Ellip, HE CI A, 19 inch by 30 inch, Tr Det B	4021301	551.000	Ft
0225	Sewer, Reinf Conc Ellip, HE CI A, 24 inch by 38 inch, Tr Det B	4021303	30.000	Ft
0230	Sewer, Reinf Conc Ellip, HE CI A, 43 inch by 68 inch, Tr Det B	4021307	104.000	Ft
0235	Dr Structure Cover, Type B	4030010	11.000	Ea
0240	Dr Structure Cover, Type G	4030040	2.000	Ea
0245	Dr Structure Cover, Type K	4030050	42.000	Ea
0250	Dr Structure, 24 inch dia	4030200	13.000	Ea
0255	Dr Structure, 48 inch dia	4030210	33.000	Ea
0260	Dr Structure, 60 inch dia	4030220	7.000	Ea
0265	_ DPW Structure Cover, Adj, Add Depth	4037001	5.000	Ft
0270	_ DPW Structure Cover, Adj, Case 1	4037050	4.000	Ea
0275	_ DPW Structure Cover, Adj, Case 2	4037050	3.000	Ea
0280	_ Stormwater Hydrodynamic Separator No. MH-10610	4037051	1.000	LSUM
0285	_ Stormwater Hydrodynamic Separator No. MH-10621	4037051	1.000	LSUM
0290	Underdrain, Subgrade, Open-Graded, 6 inch	4040083	5,992.000	Ft
0295	HMA Surface, Rem	5010005	17,367.000	Syd
0300	HMA, Temp Pavt (4EML)	5012103	45.000	Ton
0305	Joint, Contraction, Cp	6020200	12,320.000	Ft
0310	Joint, Expansion, E2	6020207	154.000	Ft
0315	Joint, Expansion, E3	6020208	110.000	Ft
0320	Conc Pavt, Nonreinf, 9 inch, High Performance	6020502	19,836.000	Syd
0325	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	123.000	Syd
0330	Joint, Expansion, Erg	6030021	116.000	Ft
0335	_ Maintain Flow, Temp (43 inch by 68 inch Elliptical)	7047051	1.000	LSUM
0340	Driveway, Nonreinf Conc, 6 inch	8010005	188.000	Syd

0345	Driveway, Nonreinf Conc, 8 inch	8010007	354.000	Syd
0350	Curb and Gutter, Conc, Det F1	8020035	5,968.000	Ft
0355	Driveway Opening, Conc, Det M	8020050	857.000	Ft
0360	Detectable Warning Surface	8030010	199.000	Ft
0365	Curb Ramp Opening, Conc	8030030	270.000	Ft
0370	Sidewalk, Conc, 4 inch	8030044	20,775.000	Sft
0375	Sidewalk, Conc, 6 inch	8030046	671.000	Sft
0380	Curb Ramp, Conc, 6 inch	8032002	2,425.000	Sft
0385	Post, Mailbox	8070095	3.000	Ea
0390	Fence, Protective	8080007	200.000	Ft
0395	Fence, Chain Link, 48 inch	8080011	240.000	Ft
0400	Post, Steel, 3 pound	8100371	514.000	Ft
0405	Sign, Type II, Rem	8100397	1.000	Ea
0410	Sign, Type IIB	8100399	6.000	Sft
0415	Sign, Type III, Erect, Salv	8100402	9.000	Ea
0420	Sign, Type III, Rem	8100403	24.000	Ea
0425	Sign, Type IIIA	8100404	45.000	Sft
0430	Sign, Type IIIB	8100405	98.000	Sft
0435	Sign, Type VB	8100425	20.000	Sft
0440	Sign, Type III, Rem, Salv	8102003	9.000	Ea
0445	Ground Mtd Sign Support, Rem	8102010	25.000	Ea
0450	Pavt Mrkg, Sprayable Thermopl, 4 inch, White	8110153	1,730.000	Ft
0455	Pavt Mrkg, Sprayable Thermopl, 4 inch, Yellow	8110154	6,365.000	Ft
0460	Pavt Mrkg, Sprayable Thermopl, 12 inch, White	8110159	350.000	Ft
0465	_ Pavt Mrkg, Waterborne, 24 inch, Stop Bar	8117001	260.000	Ft
0470	_ Pavt Mrkg, Waterborne, 2nd Application, 24 inch, Stop Bar	8117001	260.000	Ft
0475	_ Pavt Mrkg, Waterborne, 2nd Application, 6 inch, Crosswalk	8117001	945.000	Ft
0480	_ Pavt Mrkg, Waterborne, 6 inch, Crosswalk	8117001	945.000	Ft
0485	_ Pavt Mrkg, Waterborne, 2nd Application, Lt Turn Arrow Sym	8117050	4.000	Ea
0490	_ Pavt Mrkg, Waterborne, 2nd Application, Only	8117050	4.000	Ea
0495	_ Pavt Mrkg, Waterborne, 2nd Application, Rt Turn Arrow Sym	8117050	5.000	Ea
0500	_ Pavt Mrkg, Waterborne, 2nd Application, Thru and Rt Turn Arrow Sym	8117050	1.000	Ea
0505	_ Pavt Mrkg, Waterborne, Lt Turn Arrow Sym	8117050	4.000	Ea
0510	_ Pavt Mrkg, Waterborne, Only	8117050	4.000	Ea
0515	_ Pavt Mrkg, Waterborne, Rt Turn Arrow Sym	8117050	5.000	Ea
0520	_ Pavt Mrkg, Waterborne, Thru and Rt Turn Arrow Sym	8117050	1.000	Ea
0525	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	60.000	Ea
0530	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	60.000	Ea
0535	Pedestrian Type II Barricade, Temp	8120026	20.000	Ea
0540	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea

0545	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0550	Lighted Arrow, Type C, Furn	8120140	1.000	Ea
0555	Lighted Arrow, Type C, Oper	8120141	1.000	Ea
0560	Minor Traf Devices	8120170	1.000	LSUM
0565	Mobile Attenuator	8120180	1.000	Ea
0570	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	3,100.000	Ft
0575	Pavt Mrkg, Type NR, Paint, 24 inch, Stop Bar	8120216	24.000	Ft
0580	Plastic Drum, Fluorescent, Furn	8120252	480.000	Ea
0585	Plastic Drum, Fluorescent, Oper	8120253	480.000	Ea
0590	Pavt Mrkg, Wet Reflective, Type R, Tape, 24 inch, Stop Bar	8120265	44.000	Ft
0595	Sign Cover	8120310	45.000	Ea
0600	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea
0605	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0610	Sign, Type A, Temp, Prismatic, Furn	8120340	105.000	Sft
0615	Sign, Type A, Temp, Prismatic, Oper	8120341	105.000	Sft
0620	Sign, Type B, Temp, Prismatic, Furn	8120350	1,440.000	Sft
0625	Sign, Type B, Temp, Prismatic, Oper	8120351	1,440.000	Sft
0630	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	200.000	Sft
0635	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	200.000	Sft
0640	Traf Regulator Control	8120370	1.000	LSUM
0645	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	3,215.000	Ft
0650	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	5,800.000	Ft
0655	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	3,225.000	Ft
0660	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	2,950.000	Ft
0665	Riprap, Plain	8130010	72.000	Syd
0670	_ Mulch Blanket, Modified	8167002	35.000	Sta
0675	_ Turf Establishment, Performance, Modified	8167002	35.000	Sta
0680	Conduit, Rem	8182000	10.000	Ft
0685	Conduit, DB, 1, 1 1/2 inch	8182048	70.000	Ft
0690	Conduit, DB, 1, 3 inch	8182050	30.000	Ft
0695	Conduit, DB, 3, 3 inch	8182056	50.000	Ft
0700	Conduit, DB, 4, 3 inch	8182059	10.000	Ft
0705	Cable, Rem	8182196	2,930.000	Ft
0710	Cable, Sec, 600V, 1, 3/C#6	8182238	30.000	Ft
0715	Hh, Round	8182310	3.000	Ea
0720	Hh, Round, 3 foot dia	8182319	1.000	Ea
0725	Hh, Rem	8182330	4.000	Ea
0730	_ Cable, P.J., 600V, 1, 3/C#6	8187001	200.000	Ft
0735	_ Cable, P.J., 600V, 1, 5/C#16	8187001	2,310.000	Ft
0740	_ Cable, P.J., 600V, 1, 7/C#16	8187001	390.000	Ft

0745	_ Conduit, Directional Bore, 3, 3 inch RCOC	8187001	325.000	Ft
0750	Controller and Cabinet, Rem	8200030	1.000	Ea
0755	Controller Fdn, Base Mtd	8200045	1.000	Ea
0760	Controller Fdn, Rem	8200046	1.000	Ea
0765	TS, Managed Field Ethernet Switch, Rem	8200087	1.000	Ea
0770	TS, Managed Field Ethernet Switch, Salv	8200089	1.000	Ea
0775	Pedestal, Fdn	8200105	1.000	Ea
0780	Pedestal Fdn, Rem	8200106	5.000	Ea
0785	Pedestal, Rem	8200110	1.000	Ea
0790	Pedestal, Pushbutton, Rem	8200119	4.000	Ea
0795	Pushbutton, Rem	8200122	4.000	Ea
0800	Push Button Station and Sign	8200128	4.000	Ea
0805	TS, Pedestrian, Pedestal Mtd, Rem	8200181	1.000	Ea
0810	Pedestrian Signal System, Accessible	8200240	1.000	Ea
0815	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	1.000	Ea
0820	Video Traf Detection System, Rem	8200383	1.000	Ea
0825	Video Traf Detection Camera, Rem	8200384	1.000	Ea
0830	TS Head, Adj	8200452	2.000	Ea
0835	TS Face, Bag	8200458	13.000	Ea
0840	TS Face, Bag, Rem	8200459	13.000	Ea
0845	Cellular Modem, Salv	8200499	1.000	Ea
0850	_ Cabinet Equipment, Cellular Modem, Rem	8207050	1.000	Ea
0855	_ Cabinet, ITS Type, RCOC	8207050	1.000	Ea
0860	_ Controller, Digital Type, Delivered, Blue, RCOC	8207050	1.000	Ea
0865	_ Pedestal, Alum, RCOC	8207050	1.000	Ea
0870	_ Pushbutton Support Post, RCOC	8207050	4.000	Ea
0875	Hydrant, Relocate, Case 2	8230096	6.000	Ea
0880	Water Main Conflict, 16 inch	8232027	2.000	Ea
0885	Water Main Conflict, 24 inch	8232028	2.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 075

Letting Date: November 7, 2025

Contract ID: 74000-222019

Description: 1.90 mi of hot mix asphalt crushing, shaping and resurfacing, concrete curb and gutter and ramps, culvert replacement and pavement markings on Croswell Road from Peck Road to Seltzer Road and Seltzer Road from Croswell Road to Melvin Street in the village of Croswell, Sanilac County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
222019A	25A1050	N/A	TEDB 74000
222022A	25A0918	N/A	EMRP 74000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$102,000.00	1100001	1.000	LSUM
0010	Culv, Rem, 24 inch to 48 inch	2030002	2.000	Ea
0015	Guardrail, Rem	2040035	27.000	Ft
0020	Excavation, Earth	2050016	2,378.000	Cyd
0025	Machine Grading	2050030	5.000	Sta
0030	Subgrade Undercutting, Type I	2050040	100.000	Cyd
0035	Obliterate Old Road	2070001	3.000	Sta
0040	Erosion Control, Inlet Protection, Fabric Drop	2080020	2.000	Ea
0045	Erosion Control, Silt Fence	2080036	1,200.000	Ft
0050	Subbase, CIP	3010002	168.000	Cyd
0055	Aggregate Base, LM	3020002	125.000	Cyd
0060	Aggregate Base, 8 inch	3020020	8,085.000	Syd
0065	Maintenance Gravel, LM	3060021	25.000	Cyd
0070	Approach, CI II, 6 inch	3070028	429.000	Syd
0075	Shld, CI II, CIP	3070122	250.000	Cyd
0080	Culv End Sect, 36 inch	4010036	1.000	Ea
0085	Culv, CI A, 36 inch	4010136	50.000	Ft
0090	Culv, CI A, 48 inch	4010138	101.000	Ft
0095	Dr Structure Cover, Adj, Case 1	4030005	2.000	Ea
0100	Cold Milling HMA Surface	5010002	21,730.000	Syd
0105	HMA Surface, Rem	5010005	8,085.000	Syd
0110	HMA Approach	5010061	22.000	Ton
0115	HMA, 3EML	5012013	1,393.000	Ton
0120	HMA, 4EML	5012025	3,463.000	Ton
0125	Curb and Gutter, Conc, Det F4	8020038	160.000	Ft
0130	Curb Ramp Opening, Conc	8030030	80.000	Ft

0135	Curb Ramp, Conc, 6 inch	8032002	1,340.000	Sft
0140	_ Detectable Warning Surface, Modified	8037001	67.000	Ft
0145	Post, Steel, 3 pound	8100371	126.000	Ft
0150	Sign, Type III, Rem	8100403	2.000	Ea
0155	Sign, Type IIIA	8100404	9.000	Sft
0160	Sign, Type IIIB	8100405	35.000	Sft
0165	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	152.000	Ft
0170	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	24.000	Ft
0175	Pavt Mrkg, Waterborne, 4 inch, White	8110231	19,344.000	Ft
0180	Pavt Mrkg, Waterborne, 4 inch, Yellow	8110232	20,687.000	Ft
0185	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, White	8110251	19,344.000	Ft
0190	Pavt Mrkg, Waterborne, 2nd Application, 4 inch, Yellow	8110252	20,687.000	Ft
0195	Pavt Mrkg, Polyurea, Lt Turn Arrow Sym	8110405	1.000	Ea
0200	Pavt Mrkg, Polyurea, Thru and Rt Turn Arrow Sym	8110417	1.000	Ea
0205	Recessing Pavt Mrkg, Transv	8110451	250.000	Sft
0210	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	22.000	Ea
0215	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	22.000	Ea
0220	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	100.000	Ea
0225	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	100.000	Ea
0230	Minor Traf Devices	8120170	1.000	LSUM
0235	Plastic Drum, Fluorescent, Furn	8120252	20.000	Ea
0240	Plastic Drum, Fluorescent, Oper	8120253	20.000	Ea
0245	Sign, Type B, Temp, Prismatic, Furn	8120350	606.000	Sft
0250	Sign, Type B, Temp, Prismatic, Oper	8120351	606.000	Sft
0255	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	153.000	Sft
0260	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	153.000	Sft
0265	Traf Regulator Control	8120370	1.000	LSUM
0270	Slope Restoration, Non-Freeway, Type A	8162001	1,600.000	Syd
0275	Monument Box	8210001	1.000	Ea
0280	Monument Preservation	8210010	1.000	Ea
0285	Gate Box, Adj, Case 1	8230431	12.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 076

Letting Date: November 7, 2025

Contract ID: 82000-217004

Description: 0.50 mi of hot mix asphalt cold milling and resurfacing, storm sewer, curb ramps and pavement markings on Glendale Avenue from Hamilton Avenue northeasterly to Woodward Avenue (M-1) in the city of Highland Park, Wayne County. This is a Local Agency.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
217004A	25A1082	N/A	STU 82000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$86,600.00	1100001	1.000	LSUM
0010	Dr Structure, Rem	2030011	16.000	Ea
0015	Curb, Rem	2040021	1,040.000	Ft
0020	Sidewalk, Rem	2040055	261.000	Syd
0025	Erosion Control, Inlet Protection, Fabric Drop	2080020	26.000	Ea
0030	Aggregate Base, 4 inch	3020010	58.000	Syd
0035	Sewer, CI E, 12 inch, Tr Det B	4020600	80.000	Ft
0040	Dr Structure Cover, Adj, Case 1	4030005	11.000	Ea
0045	Dr Structure Cover, Type D	4030025	16.000	Ea
0050	Dr Structure, 24 inch dia	4030200	16.000	Ea
0055	Dr Structure, Temp Lowering	4030390	11.000	Ea
0060	Pavt, Cleaning	5010001	1.000	LSUM
0065	Cold Milling HMA Surface	5010002	12,425.000	Syd
0070	HMA, 4EL	5012024	2,734.000	Ton
0075	Curb, Conc, Det E2	8020002	940.000	Ft
0080	Detectable Warning Surface	8030010	100.000	Ft
0085	Curb Ramp Opening, Conc	8030030	100.000	Ft
0090	Sidewalk, Conc, 4 inch	8030044	1,759.000	Sft
0095	Curb Ramp, Conc, 4 inch	8032001	590.000	Sft
0100	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Crosswalk	8110041	900.000	Ft
0105	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	85.000	Ft
0110	Pavt Mrkg, Thermopl, 4 inch, Yellow	8110196	4,800.000	Ft
0115	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	10.000	Ea
0120	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	10.000	Ea
0125	Pedestrian Type II Barricade, Temp	8120026	4.000	Ea
0130	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	200.000	Ea

0135	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	200.000	Ea
0140	Minor Traf Devices	8120170	1.000	LSUM
0145	Sign, Type B, Temp, Prismatic, Furn	8120350	210.000	Sft
0150	Sign, Type B, Temp, Prismatic, Oper	8120351	210.000	Sft
0155	Slope Restoration, Non-Freeway, Type B	8162002	347.000	Syd
0160	Gate Box, Adj, Case 1	8230431	1.000	Ea
0165	Contractor Staking	8240001	1.000	LSUM
0170	Staking Plan Errors and Extras, Max \$180/hour	8240002	40.000	Hr



Schedule of Pay Items

Report v1

Letting Call: 251107 077

Letting Date: November 7, 2025

Contract ID: 50000-220743

Description: Installation of 6 Level 2 EV Charging Stations including concrete pad, power supply conduits, and permanent pavement markings in the city of Roseville, Macomb County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
220743A	25A1031	N/A	CRU 50000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Audio Visual Record of the Construction Influence Area	1027051	1.000	LSUM
0010	_ Reimbursed Permit Fees	1027060	3,000.000	Dlr
0015	Mobilization, Max \$68,000.00	1100001	1.000	LSUM
0020	Sidewalk, Rem	2040055	12.000	Syd
0025	_ Aggregate Base, 4 inch, Modified	3027011	36.000	Syd
0030	_ Bollard	8007050	20.000	Ea
0035	Sidewalk, Conc, 4 inch	8030044	346.000	Sft
0040	Pavt Mrkg, Waterborne, for Rest Areas, Parks, and Lots, 4 inch, White	8110294	620.000	Ft
0045	_ Pavt Mrkg, Polyurea, EV Sym, White	8117050	20.000	Ea
0050	Minor Traf Devices	8120170	1.000	LSUM
0055	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	460.000	Ft
0060	Sodding	8160055	70.000	Syd
0065	Topsoil Surface, Furn, 3 inch	8160061	70.000	Syd
0070	Water, Sodding/Seeding	8160090	7.000	Unit
0075	Power Company (Estimated Cost to Contractor)	8180001	100,000.000	Dlr
0080	Cable, Equipment Grounding Wire, 1/C#3	8182289	57.000	Ft
0085	Cable, Equipment Grounding Wire, 1/C#4	8182290	32.000	Ft
0090	Cable, Equipment Grounding Wire, 1/C#6	8182291	35.000	Ft
0095	Cable, Equipment Grounding Wire, 1/C#8	8182292	526.000	Ft
0100	_ Cable, Sec, 600V, 1/C 3/0	8187001	105.000	Ft
0105	_ Cable, Sec, 600V, 1/C#3	8187001	1,547.000	Ft
0110	_ Cable, Sec, 600V, 1/C250 KCMIL	8187001	96.000	Ft
0115	_ Cable, Sec, 600V, 1/C500 KCMIL	8187001	171.000	Ft
0120	_ Conductor, Equipment Grounding Wire, 1/C 4/0	8187001	40.000	Ft
0125	_ Conduit, 1 1/2 inch	8187001	526.000	Ft
0130	_ Conduit, 4 inch	8187001	124.000	Ft
0135	_ 100A Fused Switch	8187050	10.000	Ea

0140	_ 80A Fused Switch	8187050	20.000	Ea
0145	_ Equipment Enclosure	8187050	4.000	Ea
0150	_ EV Charger	8187050	10.000	Ea
0155	_ Ground Rod	8187050	12.000	Ea
0160	_ Meter Socket	8187050	4.000	Ea
0165	_ Slotted Steel Support Structure	8187050	4.000	Ea
0170	_ Wireway	8187050	3.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 078

Letting Date: November 7, 2025

Contract ID: 81000-215244

Description: Traffic signal modernization, signal upgrades, grid smart vehicle and pedestrian detection system installation on various routes at multiple intersections in the city of Ann Arbor, Washtenaw County. This is a Local Agency project.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
215244A	25A0945	N/A	CPMG 81000

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Mobilization, Max \$144,000.00	1100001	1.000	LSUM
0010	_ Sidewalk, Sidewalk Ramp, and Driveway Approach, Any Thickness, Rem	2047010	1,690.000	Sft
0015	_ Aggregate Base, 4 In, 21AA, CIP	3027011	190.000	Syd
0020	Detectable Warning Surface	8030010	52.000	Ft
0025	_ Conc, Sidewalk, Drive Approach or Ramp, 6 inch	8037010	1,690.000	Sft
0030	Sign, Type III, Rem	8100403	4.000	Ea
0035	Sign, Type IIIA	8100404	24.000	Sft
0040	Sign, Type IIIB	8100405	13.000	Sft
0045	_ Pavt Mrkg, Polyurea, 24 In, Stop Bar, Modified	8117001	33.000	Ft
0050	_ Pavt Mrkg, Polyurea, 4 In, White, Modified	8117001	200.000	Ft
0055	_ Rem Pavt Mrkg, Longit	8117001	400.000	Ft
0060	_ Rem Pavt Mrkg, Transverse	8117001	22.000	Ft
0065	_ Rem Spec Mrkg	8117010	34.000	Sft
0070	_ Pavt Mrkg, Polyurea, Lt Turn Arrow Sym, Modified	8117050	1.000	Ea
0075	_ Pavt Mrkg, Polyurea, Rt Turn Arrow Sym, Modified	8117050	2.000	Ea
0080	Minor Traf Devices	8120170	1.000	LSUM
0085	_ Turf Restoration	8167011	10.000	Syd
0090	Power Company (Estimated Cost to Contractor)	8180001	6,000.000	Dir
0095	Conduit, Directional Bore, 1, 3 inch	8182035	1,535.000	Ft
0100	Conduit, DB, 1, 3 inch	8182050	272.000	Ft
0105	Conduit, DB, 2, 3 inch	8182053	322.000	Ft
0110	Conduit, DB, 4, 3 inch	8182059	84.000	Ft
0115	Cable, Sec, 600V, 1, 3/C#6	8182238	500.000	Ft
0120	Hh, Rem	8182330	19.000	Ea
0125	Serv Disconnect	8182366	3.000	Ea
0130	Serv Disconnect, Rem	8182367	3.000	Ea
0135	_ Conduit, DB, 1, 2 Inch	8187001	215.000	Ft

0140	_ Hh, Polymer Conc, 24 Inch X 36 Inch, Modified	8187050	3.000	Ea
0145	_ Hh, Polymer Conc, Modified	8187050	13.000	Ea
0150	Luminaire, Rem	8190360	4.000	Ea
0155	_ Luminaire, Modified	8197050	8.000	Ea
0160	Case Sign, Rem	8200020	8.000	Ea
0165	Controller and Cabinet, Rem	8200030	3.000	Ea
0170	Controller Fdn, Rem	8200046	1.000	Ea
0175	Fdn, Rem	8200065	11.000	Ea
0180	Pedestal, Alum	8200100	9.000	Ea
0185	Pedestal Fdn, Rem	8200106	7.000	Ea
0190	Pedestal, Rem	8200110	7.000	Ea
0195	Pushbutton, Rem	8200122	14.000	Ea
0200	Push Button Station and Sign	8200128	18.000	Ea
0205	TS, Bracket Arm Mtd, Rem	8200175	2.000	Ea
0210	TS, Mast Arm Mtd, Rem	8200177	48.000	Ea
0215	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	7.000	Ea
0220	TS, Pedestrian, Pedestal Mtd, Rem	8200181	7.000	Ea
0225	Pedestrian Signal System, Accessible	8200240	3.000	Ea
0230	Pedestrian Signal System, Accessible, Rem	8200241	3.000	Ea
0235	TS, One Way Mast Arm Mtd, FYA (LED)	8200304	3.000	Ea
0240	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	5.000	Ea
0245	TS, Pedestrian, Two Way Bracket Arm Mtd (LED) Countdown	8200339	1.000	Ea
0250	TS, One Way Pedestal Mtd (LED)	8200340	4.000	Ea
0255	TS, Pedestrian, One Way Pedestal Mtd (LED) Countdown	8200345	8.000	Ea
0260	TS, Pedestrian, Two Way Pedestal Mtd (LED) Countdown	8200347	1.000	Ea
0265	TS, One Way Mast Arm Mtd (LED)	8200359	51.000	Ea
0270	Bracket, Truss, with 18 foot Arm	8200378	8.000	Ea
0275	Detector, Microwave Vehicle, Rem	8200403	1.000	Ea
0280	Hemispherical Video Detection Camera	8200444	11.000	Ea
0285	Hemispherical Video Detection System	8200445	9.000	Ea
0290	Hemispherical Video Detection Camera, Rem	8200446	3.000	Ea
0295	Hemispherical Video Detection System, Rem	8200447	3.000	Ea
0300	Hemispherical Video Detection System, Salv	8200449	2.000	Ea
0305	Casing, 42 inch	8200485	165.000	Ft
0310	Backplate, TS	8200501	52.000	Ea
0315	Backplate, TS, Rem	8200502	50.000	Ea
0320	Mast Arm, Rem	8202004	11.000	Ea
0325	Mast Arm Std, Rem	8202005	11.000	Ea
0330	Mast Arm Pole, Cat III	8202012	11.000	Ea
0335	Mast Arm, 30 foot, Cat III	8202029	4.000	Ea
0340	Mast Arm, 35 foot, Cat III	8202030	2.000	Ea
0345	Mast Arm, 45 foot, Cat III	8202032	3.000	Ea

0350	Mast Arm, 50 foot, Cat III	8202033	2.000	Ea
0355	Mast Arm Pole Fdn, 6 Bolt	8202034	165.000	Ft
0360	TS, One Way Bracket Arm Mtd, FYA (LED), Long Life	8202206	1.000	Ea
0365	TS, One Way Pedestal Mtd, FYA (LED), Long Life	8202257	5.000	Ea
0370	_ Broadband Single Radio System, Rem	8207050	1.000	Ea
0375	_ Broadband Single Radio, Rem	8207050	1.000	Ea
0380	_ Cabinet, NEMA Type, Modified	8207050	3.000	Ea
0385	_ Controller Fdn, Base Mtd, Modified	8207050	3.000	Ea
0390	_ Pedestal Fdn, Modified	8207050	9.000	Ea
0395	_ SCOOT Enabled Controller	8207050	3.000	Ea
0400	_ St Name Sign, Mast Arm Mtd, Rem & Salv	8207050	11.000	Ea



Schedule of Pay Items

Report v1

Letting Call: 251107 079

Letting Date: November 7, 2025

Contract ID: 11014-221576

Description: 0.29 mi of partial reconstruction of the New Buffalo Weigh Station including replacement of the static scale and pavement markings on I-94 Eastbound at the New Buffalo Weigh Station, Berrien County.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
221576A	25A1122	N/A	NH 11014

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	Conc Quality Initiative	10000030	26,030.000	Dir
0010	Mobilization, Max \$162,500.00	1100001	1.000	LSUM
0015	Conc Barrier, Rem	2040010	145.000	Ft
0020	Fence, Rem	2040025	26.000	Ft
0025	Pavt, Rem	2040050	5,915.000	Syd
0030	Sidewalk, Rem	2040055	60.000	Syd
0035	Embankment, CIP	2050010	235.000	Cyd
0040	Excavation, Earth	2050016	1,895.000	Cyd
0045	Erosion Control, Check Dam, Stone	2080012	75.000	Ft
0050	Erosion Control, Inlet Protection, Fabric Drop	2080020	1.000	Ea
0055	Erosion Control, Maintenance, Sediment Rem	2080026	15.000	Cyd
0060	Erosion Control, Sediment Trap	2080034	3.000	Ea
0065	Erosion Control, Silt Fence	2080036	2,800.000	Ft
0070	Subbase, CIP	3010002	1,720.000	Cyd
0075	Aggregate Base, 6 inch	3020016	6,095.000	Syd
0080	Shld, CI II, CIP	3070122	250.000	Cyd
0085	Underdrain, Subbase, 6 inch	4040063	2,800.000	Ft
0090	Underdrain Outlet, 6 inch	4040093	240.000	Ft
0095	Underdrain, Outlet Ending, 6 inch	4040113	12.000	Ea
0100	Video Inspection of Underdrain	4040200	3,040.000	Ft
0105	Conc Pavt, Nonreinf, 12 inch	6020112	3,710.000	Syd
0110	Shld, Nonreinf Conc	6020222	1,030.000	Syd
0115	Conc Pavt, Bridge Approach, Reinf	6020600	320.000	Syd
0120	_ Speaker, Public Address	8007050	6.000	Ea
0125	_ Speaker, Public Address, Rem	8007050	3.000	Ea
0130	_ Static Scale	8007051	1.000	LSUM
0135	Shld Gutter, Conc, Det 2	8020056	2.000	Ea
0140	Divider, Conc, Type I	8022000	5,590.000	Sft

0145	_ Curb and Gutter, Conc, Det B1, Modified	8027001	225.000	Ft
0150	_ Curb and Gutter, Conc, Det C3, Modified	8027001	155.000	Ft
0155	Sidewalk, Conc, 6 inch	8030046	560.000	Sft
0160	Conc Barrier, Single Face, Type C	8040003	120.000	Ft
0165	Guardrail Approach Terminal, Type 2M	8070044	1.000	Ea
0170	Guardrail Reflector	8070080	2.000	Ea
0175	Guardrail Anch, Bridge, Det M1	8070130	1.000	Ea
0180	Band, Sign	8100010	2.000	Ea
0185	Delineator Reflector, Red	8100131	17.000	Ea
0190	Delineator Reflector, Yellow	8100132	6.000	Ea
0195	Delineator Reflector, Green	8100133	4.000	Ea
0200	Delineator Reflector, White	8100134	22.000	Ea
0205	Delineator, Rem	8100349	38.000	Ea
0210	Post, Rigid, Delineator	8100361	29.000	Ea
0215	Post, Steel, 3 pound	8100371	98.000	Ft
0220	Post, Wood, 4 inch by 6 inch	8100380	124.000	Ft
0225	Sign, Type III, Erect, Salv	8100402	5.000	Ea
0230	Sign, Type V, Erect, Salv	8100422	2.000	Ea
0235	Post, Flexible, Delineator, Ground Mtd	8100555	7.000	Ea
0240	Reflective Panel for Permanent Sign Support, 3 foot	8100613	4.000	Ea
0245	Sign, Type III, Rem, Salv	8102003	5.000	Ea
0250	Sign, Type V, Rem, Salv	8102005	2.000	Ea
0255	Ground Mtd Sign Support, Rem	8102010	13.000	Ea
0260	_ Hand Digging Sign Post	8107050	6.000	Ea
0265	_ Sign, Changeable Message, Forward/Backward, Install Salv	8107050	1.000	Ea
0270	_ Sign, Changeable Message, Forward/Backward, Rem and Salv	8107050	1.000	Ea
0275	_ Sign, Changeable Message, Speed Limit, Install Salv	8107050	2.000	Ea
0280	_ Sign, Changeable Message, Speed Limit, Rem and Salv	8107050	2.000	Ea
0285	Pavt Mrkg, Polyurea, 6 inch, White	8110094	2,125.000	Ft
0290	Pavt Mrkg, Polyurea, 6 inch, Yellow	8110095	2,090.000	Ft
0295	Pavt Mrkg, Polyurea, 12 inch, White	8110111	255.000	Ft
0300	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
0305	Recessing Pavt Mrkg, Longit	8110450	4,470.000	Ft
0310	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	8.000	Ea
0315	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	8.000	Ea
0320	Channelizing Device, 42 inch, Fluorescent, Furn	8120035	50.000	Ea
0325	Channelizing Device, 42 inch, Fluorescent, Oper	8120036	50.000	Ea
0330	Minor Traf Devices	8120170	1.000	LSUM
0335	Sign Cover	8120310	1.000	Ea
0340	Sign Cover, Type I	8120320	2.000	Ea
0345	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	2.000	Ea

0350	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	2.000	Ea
0355	Sign, Type B, Temp, Prismatic, Furn	8120350	26.000	Sft
0360	Sign, Type B, Temp, Prismatic, Oper	8120351	26.000	Sft
0365	Riprap, Plain	8130010	6.000	Syd
0370	Slope Restoration, Freeway, Type A	8162013	1,255.000	Syd
0375	Conduit, Rem	8182000	820.000	Ft
0380	Conduit, DB, 1, 3 inch	8182050	60.000	Ft
0385	Hh, Round	8182310	2.000	Ea
0390	Hh, Adj	8182328	3.000	Ea
0395	Hh, Rem	8182330	4.000	Ea
0400	Luminaire, Rem	8190360	2.000	Ea
0405	_ Flood Light, LED	8197050	2.000	Ea
0410	Pedestal, Alum	8200100	8.000	Ea
0415	Pedestal, Fdn	8200105	8.000	Ea
0420	Pedestal Fdn, Rem	8200106	5.000	Ea
0425	Pedestal, Rem	8200110	5.000	Ea
0430	Traf Loop	8200170	10.000	Ea
0435	TS, Pedestal Mtd, Rem	8200179	2.000	Ea
0440	TS, One Way Pedestal Mtd	8200230	2.000	Ea
0445	Contractor Staking	8240001	1.000	LSUM
0450	Staking Plan Errors and Extras, Max \$180/hour	8240002	34.000	Hr