



Schedule of Pay Items

Report v1

Letting Call: 251121 701

Letting Date: ,November 21
2025

Contract ID: 82022-201225

Description: 10.49 mi of concrete reconstruction, concrete pavement repairs, interchange reconfiguration, concrete inlay, drainage, traffic signal upgrades, signing, freeway lighting, guardrail, ITS, landscaping, noise wall, pavement markings and rehabilitation of 24 structures on I-94 from Wayne Road to east of Greenfield Road and M-39 from I-94 to Outer Drive in the cities of Romulus, Taylor, Allen Park, Dearborn Heights, Dearborn, and Melvindale, Wayne County. This project is an Alternate Pavement Bid project. Alternate 1 (Section 2) is a Hot Mix Asphalt Alternate with 16 inch OGDC. Alternate 2 (Section 3) is a Hot Mix Asphalt Alternate with 6 inch CTPB and 10 inch OGDC. Alternate 3 (Section 4) is a Concrete Alternate with 16 inch OGDC. Alternate 4 (Section 5) is a Concrete Alternate with 6 inch CTPB and 10 inch OGDC. This project includes two 5 year materials and workmanship pavement warranties, a 2 year concrete surface warranty, a 5 year epoxy performance warranty and a 2 year bridge coating warranty.

Project Information

Project Number	Federal Project Number	Federal Item Number	Control Section
201225A	25A1067	N/A	ST 82022
202486A	25A1061	N/A	BFPI 82022
205354A	25A1060	N/A	BFPI 82022
208609A	25A1059	N/A	RBMP 82022
211426A	25A1058	N/A	NH 82022
211957A	25A1057	N/A	STG 82022
214929A	N/A	N/A	M 82022
215038A	25A1056	N/A	BFP 82192
217336A	N/A	N/A	M 82022
218689A	25A1054	N/A	HSIP 82022

List of Items by Section

Line Num	Item Description	Item ID	Quantity	Units
Section: 1				
0005	_ Interim Completion Incentive	1027060	310,000.000	Dlr
0010	Dispute Review Board, Hearing	1040010	56,400.000	Dlr
0015	Dispute Review Board, Progress Meeting	1040050	184,800.000	Dlr
0020	_ Technical Proposal	1047060	25,000.000	Dlr
0025	Critical Path Method Schedule	1080005	15,000.000	Dlr
0030	Mobilization, Max \$33,156,000.00	1100001	1.000	LSUM
0035	Clearing	2010001	57.270	Acre
0040	Clearing, Fence	2010002	659.000	Sta
0045	Tree, Rem, 19 inch to 36 inch	2020002	18.000	Ea
0050	Tree, Rem, 37 inch or Larger	2020003	2.000	Ea
0055	Tree, Rem, 6 inch to 18 inch	2020004	392.000	Ea
0060	Culv, Rem, Less than 24 inch	2030001	56.000	Ea

0065	Culv, Rem, 24 inch to 48 inch	2030002	45.000	Ea
0070	Culv, End, Rem, Less than 24 inch	2030005	72.000	Ea
0075	Culv, End, Rem, 24 inch to 48 inch	2030006	55.000	Ea
0080	Culv, End, Rem, Over 48 inch	2030007	2.000	Ea
0085	Dr Structure, Abandon	2030010	4.000	Ea
0090	Dr Structure, Rem	2030011	674.000	Ea
0095	Sewer, Rem, Less than 24 inch	2030015	32,202.000	Ft
0100	Sewer, Rem, 24 inch to 48 inch	2030016	6,347.000	Ft
0105	Sewer, Rem, Over 48 inch	2030017	458.000	Ft
0110	_ Abandon Utility, Rem	2037001	7,525.000	Ft
0115	Conc Barrier, Rem	2040010	24,757.000	Ft
0120	Curb and Gutter, Rem	2040020	16,769.000	Ft
0125	Curb, Rem	2040021	59.000	Ft
0130	Fence, Rem	2040025	58,462.000	Ft
0135	Guardrail, Rem	2040035	29,182.000	Ft
0140	Masonry and Conc Structure, Rem	2040045	100.000	Cyd
0145	Pavt, Rem	2040050	1,076,713.000	Syd
0150	Sidewalk, Rem	2040055	703.000	Syd
0155	Exploratory Investigation, Vertical	2040080	2,220.000	Ft
0160	_ Impact Attenuator, Rem and Disposal	2047050	3.000	Ea
0165	Berm Grading	2050008	1,150.000	Sta
0170	Excavation, Channel	2050015	8,750.000	Cyd
0175	Non Haz Contaminated Material Handling and Disposal, LM	2050031	21,000.000	Cyd
0180	Subgrade Undercutting, Type I	2050040	560.000	Cyd
0185	Subgrade Undercutting, Type II	2050041	1,390.000	Cyd
0190	Flowable Fill, Non-Structural	2050148	848.000	Cyd
0195	_ Dredging	2057021	681.000	Cyd
0200	_ Embankment, CIP, Clay Cap	2057021	12,604.000	Cyd
0205	_ Embankment, CIP, Noise Berm	2057021	19,734.000	Cyd
0210	_ Phragmites Plant Material Handling and Disposal, LM	2057021	51,022.000	Cyd
0215	_ Subgrade Undercutting, Modified	2057021	2,010.000	Cyd
0220	_ Subgrade Undercutting, Type IV, Modified	2057021	5,330.000	Cyd
0225	_ Geotechnical Instrumentation Installation and Monitoring	2057051	1.000	LSUM
0230	_ Backfill, Lightweight, Iron Blast Furnace Slag Aggregate, LM	2067021	1,100.000	Cyd
0235	_ Dewatering System, Excavation	2067050	25.000	Ea
0240	Erosion Control, Check Dam, Stone	2080012	1,612.000	Ft
0245	Erosion Control, Filter Bag	2080014	37.000	Ea
0250	Erosion Control, Gravel Access Approach	2080016	36.000	Ea
0255	Erosion Control, Gravel Filter Berm	2080018	356.000	Ft
0260	Erosion Control, Inlet Protection, Fabric Drop	2080020	900.000	Ea
0265	Erosion Control, Inlet Protection, Sediment Trap	2080024	97.000	Ea
0270	Erosion Control, Maintenance, Sediment Rem	2080026	592.000	Cyd

0275	Erosion Control, Sand Bag	2080028	4,987.000	Ea
0280	Erosion Control, Sediment Basin	2080032	293.000	Cyd
0285	Erosion Control, Sediment Trap	2080034	350.000	Ea
0290	Erosion Control, Silt Fence	2080036	122,681.000	Ft
0295	Erosion Control, Turbidity Curtain, Shallow	2080044	1,650.000	Ft
0300	_ Erosion Control, Sediment Log	2087001	17,818.000	Ft
0305	_ Stormwater Treatment, Check Dam, Stone	2087050	27.000	Ea
0310	Project Cleanup	2090001	1.000	LSUM
0315	Aggregate Base, 6 inch	3020016	108,518.000	Syd
0320	Aggregate Base, 8 inch	3020020	775.000	Syd
0325	Aggregate Base, 12 inch	3020030	34,611.000	Syd
0330	Aggregate Base, Conditioning	3020050	55.000	Syd
0335	_ Chemically Stabilized Subgrade	3027011	887,283.000	Syd
0340	_ Cement, Spec	3027031	26,804.000	Ton
0345	_ Fly Ash	3027031	1,000.000	Ton
0350	_ Lime	3027031	22,317.000	Ton
0355	_ Open-Graded Dr Cse, 4 inch	3037011	143.000	Syd
0360	_ Open-Graded Dr Cse, Conditioning	3037011	38,204.000	Syd
0365	Approach, CI II	3070021	48.000	Ton
0370	Shld, CI II, 7 inch	3070129	9.000	Syd
0375	Shld, CI II, 6 inch, Temp	3070183	14,980.000	Syd
0380	Geotextile, Stabilization	3080010	1,103.000	Syd
0385	Road Grade Biaxial Geogrid	3082002	46,142.000	Syd
0390	Culv End Sect, 12 inch	4010012	62.000	Ea
0395	Culv End Sect, 15 inch	4010015	10.000	Ea
0400	Culv End Sect, 18 inch	4010018	21.000	Ea
0405	Culv End Sect, 24 inch	4010024	65.000	Ea
0410	Culv End Sect, 30 inch	4010030	8.000	Ea
0415	Culv End Sect, 36 inch	4010036	7.000	Ea
0420	Culv End Sect, Conc, 24 inch	4010051	2.000	Ea
0425	Culv End Sect, Conc, 30 inch	4010052	2.000	Ea
0430	Culv End Sect, Conc, 36 inch	4010053	4.000	Ea
0435	Culv End Sect, Conc, 42 inch	4010054	5.000	Ea
0440	Culv End Sect, Conc, 48 inch	4010055	7.000	Ea
0445	Culv End Sect, Conc, 54 inch	4010056	1.000	Ea
0450	Culv End Sect, Conc, 60 inch	4010057	3.000	Ea
0455	Culv End Sect, Footing	4010072	247.000	Ea
0460	Culv End Sect, Metal, 48 inch	4010102	1.000	Ea
0465	Culv, CI A, 12 inch	4010131	220.000	Ft
0470	Culv, CI A, 15 inch	4010132	750.000	Ft
0475	Culv, CI A, 18 inch	4010133	670.000	Ft
0480	Culv, CI A, 24 inch	4010134	2,089.000	Ft
0485	Culv, CI A, 30 inch	4010135	803.000	Ft
0490	Culv, CI A, 36 inch	4010136	381.000	Ft
0495	Culv, CI A, 42 inch	4010137	133.000	Ft

0500	Culv, CI A, Conc, 30 inch	4010169	116.000	Ft
0505	Culv, CI A, Conc, 42 inch	4010171	288.000	Ft
0510	Culv, CI A, Conc, 72 inch	4010176	128.000	Ft
0515	Culv, CI A, Conc, 78 inch	4010177	296.000	Ft
0520	Culv, CI B, Conc, 48 inch	4010274	352.000	Ft
0525	Culv, CI B, Conc, 60 inch	4010276	224.000	Ft
0530	Culv, CI C, 24 inch	4010338	134.000	Ft
0535	Culv, CI C, 48 inch	4010342	220.000	Ft
0540	Culv, CI E, 24 inch	4010542	161.000	Ft
0545	Culv, CI E, 30 inch	4010543	51.000	Ft
0550	Culv, CI E, 36 inch	4010544	188.000	Ft
0555	Culv, Reinf Conc Ellip, HE CI A, 48 inch by 76 inch	4010817	512.000	Ft
0560	Culv, Reinf Conc Ellip, HE CI II, 29 inch by 45 inch	4010859	47.000	Ft
0565	Culv, Reinf Conc Ellip, HE CI II, 34 inch by 53 inch	4010860	340.000	Ft
0570	Culv, Reinf Conc Ellip, HE CI II, 58 inch by 91 inch	4010865	364.000	Ft
0575	Culv, Reinf Conc Ellip, HE CI II, 68 inch by 106 inch	4010867	264.000	Ft
0580	Culv, Reinf Conc Ellip, HE CI IV, 22 inch by 34 inch	4010903	110.000	Ft
0585	Culv, Reinf Conc Ellip, HE CI IV, 24 inch by 38 inch	4010904	118.000	Ft
0590	Culv, Reinf Conc Ellip, HE CI IV, 29 inch by 45 inch	4010905	186.000	Ft
0595	Culv, Reinf Conc Ellip, HE CI IV, 34 inch by 53 inch	4010906	121.000	Ft
0600	Culv, Slp End Sect, 1 on 4, 24 inch, Longit	4010923	2.000	Ea
0605	Culv, Slp End Sect, 1 on 4, 24 inch, Transv	4010924	3.000	Ea
0610	Culv, Slp End Sect, 1 on 4, 30 inch, Transv	4010928	7.000	Ea
0615	Culv, Slp End Sect, 1 on 4, 36 inch, Transv	4010930	2.000	Ea
0620	Culv, Slp End Sect, 1 on 6, 24 inch, Longit	4010955	9.000	Ea
0625	Culv, Slp End Sect, 1 on 6, 24 inch, Transv	4010956	7.000	Ea
0630	Culv, Slp End Sect, 1 on 6, 30 inch, Longit	4010959	6.000	Ea
0635	Culv, Slp End Sect, 1 on 6, 30 inch, Transv	4010960	2.000	Ea
0640	Culv, Slp End Sect, 1 on 6, 36 inch, Longit	4010961	1.000	Ea
0645	Culv, Slp End Sect, 1 on 6, 36 inch, Transv	4010962	2.000	Ea
0650	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 14 inch by 23 inch, Transv	4011050	1.000	Ea
0655	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 19 inch by 30 inch, Longit	4011051	1.000	Ea
0660	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 22 inch by 34 inch, Transv	4011054	2.000	Ea
0665	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 24 inch by 38 inch, Transv	4011056	2.000	Ea
0670	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 29 inch by 45 inch, Transv	4011060	2.000	Ea
0675	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 34 inch by 53 inch, Transv	4011062	6.000	Ea
0680	Culv, Slp End Sect, Ellip Pipe, 1 on 4, 38 inch by 60 inch, Longit	4011063	1.000	Ea
0685	Culv, Slp End Sect, Ellip Pipe, 1 on 6, 29 inch by 45 inch, Longit	4011089	2.000	Ea
0690	Culv, Slp End Sect, Ellip Pipe, 1 on 6, 48 inch by 76 inch, Transv	4011098	2.000	Ea

0695	Dr Marker Post	4011109	279.000	Ea
0700	Outfall Label	4011115	36.000	Ea
0705	_ Chemical Pipe Joint Grouting	4017001	7,160.000	Ft
0710	_ Culv, Reinf Conc Ellip, HE Cl II, 72 inch by 113 inch	4017001	290.000	Ft
0715	_ Culv Cleanout	4017050	1,580.000	Ea
0720	_ Culv End Sect, 42 inch	4017050	2.000	Ea
0725	Sewer, Cl A, 12 inch, Tr Det A	4020004	800.000	Ft
0730	Sewer, Cl A, 15 inch, Tr Det A	4020005	620.000	Ft
0735	Sewer, Cl A, 18 inch, Tr Det A	4020006	423.000	Ft
0740	Sewer, Cl A, 24 inch, Tr Det A	4020007	3,876.000	Ft
0745	Sewer, Cl A, 30 inch, Tr Det A	4020008	506.000	Ft
0750	Sewer, Cl A, 36 inch, Tr Det A	4020009	653.000	Ft
0755	Sewer, Cl A, 48 inch, Tr Det A	4020011	426.000	Ft
0760	Sewer, Cl A, 12 inch, Tr Det B	4020033	21,678.000	Ft
0765	Sewer, Cl A, 18 inch, Tr Det B	4020035	7,784.000	Ft
0770	Sewer, Cl A, 24 inch, Tr Det B	4020036	3,713.000	Ft
0775	Sewer, Cl A, 30 inch, Tr Det B	4020037	1,309.000	Ft
0780	Sewer, Cl A, 36 inch, Tr Det B	4020038	307.000	Ft
0785	Sewer, Cl A, 42 inch, Tr Det B	4020039	93.000	Ft
0790	Sewer, Cl A, 48 inch, Tr Det B	4020040	278.000	Ft
0795	Sewer, Cl A, 54 inch, Tr Det B	4020041	508.000	Ft
0800	Sewer, Cl A, 60 inch, Tr Det B	4020042	134.000	Ft
0805	Sewer, Cl B, 36 inch, Tr Det A	4020158	24.000	Ft
0810	Sewer, Cl B, 48 inch, Tr Det A	4020160	44.000	Ft
0815	Sewer, Cl B, 12 inch, Tr Det B	4020183	57.000	Ft
0820	Sewer, Cl B, 18 inch, Tr Det B	4020185	477.000	Ft
0825	Sewer, Cl B, 24 inch, Tr Det B	4020186	527.000	Ft
0830	Sewer, Cl B, 30 inch, Tr Det B	4020187	98.000	Ft
0835	Sewer, Cl E, 12 inch, Tr Det B	4020600	3,922.000	Ft
0840	Sewer, Cl E, 18 inch, Tr Det B	4020602	790.000	Ft
0845	Sewer, Cl E, 24 inch, Tr Det B	4020603	324.000	Ft
0850	Sewer, Cl E, 30 inch, Tr Det B	4020604	515.000	Ft
0855	Sewer, Cl II, 24 inch, Tr Det A	4020723	23.000	Ft
0860	Sewer, Cl II, 30 inch, Tr Det A	4020724	16.000	Ft
0865	Sewer, Cl II, 12 inch, Tr Det B	4020748	4,269.000	Ft
0870	Sewer, Cl II, 18 inch, Tr Det B	4020751	436.000	Ft
0875	Sewer, Cl II, 24 inch, Tr Det B	4020752	1,574.000	Ft
0880	Sewer, Cl II, 30 inch, Tr Det B	4020754	287.000	Ft
0885	Sewer, Cl II, 36 inch, Tr Det B	4020755	1,053.000	Ft
0890	Sewer, Cl II, 42 inch, Tr Det B	4020756	24.000	Ft
0895	Sewer, Cl III, 36 inch, Tr Det B	4020875	405.000	Ft
0900	Sewer, Cl IV, 24 inch, Tr Det A	4020963	72.000	Ft
0905	Sewer, Cl IV, 12 inch, Tr Det B	4020987	74.000	Ft
0910	Sewer, Cl IV, 18 inch, Tr Det B	4020989	120.000	Ft
0915	Sewer, Cl IV, 36 inch, Tr Det B	4020995	86.000	Ft

0920	Sewer, CI V, 24 inch, Tr Det A	4021083	906.000	Ft
0925	Sewer, CI IV, 48 inch, Jacked in Place	4021177	470.000	Ft
0930	Sewer Tap, 12 inch	4021204	4.000	Ea
0935	Sewer Tap, 18 inch	4021206	1.000	Ea
0940	Sewer Tap, 24 inch	4021207	7.000	Ea
0945	Sewer Tap, 30 inch	4021208	1.000	Ea
0950	Sewer Tap, 36 inch	4021209	1.000	Ea
0955	Sewer Bulkhead, 24 inch	4021234	2.000	Ea
0960	Video Taping Sewer and Culv Pipe	4021275	61,379.000	Ft
0965	Sewer, Reinf Conc Ellip, HE CI A, 38 inch by 60 inch, Tr Det A	4021286	53.000	Ft
0970	Sewer, Reinf Conc Ellip, HE CI II, 14 inch by 23 inch, Tr Det A	4021360	123.000	Ft
0975	Sewer, Reinf Conc Ellip, HE CI IV, 14 inch by 23 inch, Tr Det A	4021440	186.000	Ft
0980	Sewer, Reinf Conc Ellip, HE CI IV, 19 inch by 30 inch, Tr Det A	4021441	60.000	Ft
0985	Sewer, Reinf Conc Ellip, HE CI IV, 24 inch by 38 inch, Tr Det A	4021443	135.000	Ft
0990	Sewer, Reinf Conc Ellip, HE CI IV, 19 inch by 30 inch, Tr Det B	4021451	195.000	Ft
0995	Sewer, Reinf Conc Ellip, HE CI IV, 22 inch by 34 inch, Tr Det B	4021452	31.000	Ft
1000	Sewer, Reinf Conc Ellip, HE CI IV, 24 inch by 38 inch, Tr Det B	4021453	120.000	Ft
1005	_ Dewatering System for Contaminated Groundwater, Trench	4027001	600.000	Ft
1010	_ Storm Sewer Cleanout	4027001	9,302.000	Ft
1015	_ Dewatering System for Contaminated Groundwater, Site	4027050	1.000	Ea
1020	_ HAZWOPER 40 hour Training, MDOT personnel	4027050	2.000	Ea
1025	Dr Structure Cover, Adj, Case 2	4030006	69.000	Ea
1030	Dr Structure Cover, Type B	4030010	80.000	Ea
1035	Dr Structure Cover, Type C	4030015	7.000	Ea
1040	Dr Structure Cover, Type CX	4030020	58.000	Ea
1045	Dr Structure Cover, Type DX	4030030	12.000	Ea
1050	Dr Structure Cover, Type G	4030040	18.000	Ea
1055	Dr Structure Cover, Type J	4030045	33.000	Ea
1060	Dr Structure Cover, Type K	4030050	27.000	Ea
1065	Dr Structure Cover, Type R	4030070	1.000	Ea
1070	Dr Structure Cover, Type RX	4030075	1.000	Ea
1075	Dr Structure Cover, Type W	4030080	242.000	Ea
1080	Dr Structure Cover, Type VG	4030090	351.000	Ea
1085	Dr Structure, 24 inch dia	4030200	35.000	Ea
1090	Dr Structure, 48 inch dia	4030210	809.000	Ea
1095	Dr Structure, 60 inch dia	4030220	58.000	Ea
1100	Dr Structure, 72 inch dia	4030230	17.000	Ea
1105	Dr Structure, 84 inch dia	4030231	2.000	Ea
1110	Dr Structure, Add Depth of 84 inch dia, 8 foot to 15	4030232	5.000	Ft

	foot			
1115	Dr Structure, 96 inch dia	4030234	1.000	Ea
1120	Dr Structure, Add Depth of 96 inch dia, 8 foot to 15 foot	4030235	1.000	Ft
1125	Dr Structure, 108 inch dia	4030237	2.000	Ea
1130	Dr Structure, Add Depth of 108 inch dia, 8 foot to 15 foot	4030238	3.000	Ft
1135	Dr Structure, 120 inch dia	4030242	1.000	Ea
1140	Dr Structure, Add Depth of 120 inch dia, 8 foot to 15 foot	4030243	2.000	Ft
1145	Dr Structure, Add Depth of 48 inch dia, 8 foot to 15 foot	4030250	313.000	Ft
1150	Dr Structure, Add Depth of 48 inch dia, more than 15 foot	4030251	132.000	Ft
1155	Dr Structure, Add Depth of 60 inch dia, 8 foot to 15 foot	4030260	88.000	Ft
1160	Dr Structure, Add Depth of 60 inch dia, more than 15 foot	4030261	21.000	Ft
1165	Dr Structure, Add Depth of 72 inch dia, 8 foot to 15 foot	4030270	26.000	Ft
1170	Dr Structure, Add Depth of 72 inch dia, more than 15 foot	4030271	6.000	Ft
1175	Dr Structure, Adj, Add Depth	4030280	6.000	Ft
1180	Dr Structure, Cleaning	4030290	30.000	Ea
1185	Dr Structure, Tap, 6 inch	4030306	35.000	Ea
1190	Dr Structure, Tap, 12 inch	4030312	11.000	Ea
1195	Dr Structure, Tap, 18 inch	4030318	6.000	Ea
1200	Dr Structure, Tap, 24 inch	4030324	7.000	Ea
1205	Dr Structure, Tap, 30 inch	4030330	1.000	Ea
1210	Dr Structure, Tap, 36 inch	4030336	1.000	Ea
1215	Dr Structure, Tap, 48 inch	4030348	1.000	Ea
1220	_ Dr Structure Cover, Catch Basin, Wayne County	4037050	111.000	Ea
1225	_ Dr Structure Cover, Manhole, Wayne County	4037050	37.000	Ea
1230	_ Dr Structure Cover, Type B, Modified	4037050	7.000	Ea
1235	_ Dr Structure Cover, Type D, Modified	4037050	1.000	Ea
1240	_ Dr Structure Cover, Type VG, Modified	4037050	21.000	Ea
1245	_ Utility Structure Cover, Adj, Case 1	4037050	1.000	Ea
1250	_ Utility Structure Cover, Adj, Case 2	4037050	5.000	Ea
1255	Underdrain, Pipe, Open-Graded, 6 inch	4040043	391,595.000	Ft
1260	Underdrain, Subbase, 6 inch	4040063	7,900.000	Ft
1265	Underdrain, Subgrade, Open-Graded, 6 inch	4040083	2,890.000	Ft
1270	Underdrain Outlet, 6 inch	4040093	59,043.000	Ft
1275	Underdrain, Outlet Ending, 6 inch	4040113	4.000	Ea
1280	Video Inspection of Underdrain	4040200	481,328.000	Ft
1285	_ Underdrain, Subgrade, 6 inch, Modified	4047001	14,824.000	Ft
1290	_ Underdrain Outlet Ending, Modified	4047050	1,285.000	Ea
1295	Cold Milling HMA Surface	5010002	73,236.000	Syd
1300	Bump Grinding	5010004	8,775.000	Syd
1305	HMA Surface, Rem	5010005	196,152.000	Syd

1310	Pavt for Butt Joints, Rem	5010008	357.000	Syd
1315	Pavt Joint and Crack Repr, Det 7	5010020	36,881.000	Ft
1320	Pavt Joint and Crack Repr, Det 8	5010021	36,881.000	Ft
1325	Hand Patching	5010025	5,613.000	Ton
1330	HMA Approach	5010061	715.000	Ton
1335	HMA, Temp Pavt (4EML)	5012103	56,584.000	Ton
1340	_ Ride Incentive	5017060	253,600.000	Dlr
1345	_ Asphalt Repr Mastic	5027001	12,300.000	Ft
1350	Conc Pavt, Misc, Nonreinf, 10 inch	6020058	1,357.000	Syd
1355	Conc Pavt, Nonreinf, 10 inch	6020108	27,454.000	Syd
1360	Conc Pavt with Integral Curb, Nonreinf, 11 inch	6020170	31.000	Syd
1365	Joint, Expansion, E3	6020208	3,388.000	Ft
1370	Cement	6030005	201.000	Ton
1375	Crack Sealing, Conc Pavt	6030010	1,099.000	Ft
1380	Non-Chloride Accelerator	6030035	8,517.000	Gal
1385	Pavt Repr, Nonreinf Conc, 6 inch	6030040	3,801.000	Syd
1390	Pavt Repr, Nonreinf Conc, 9 inch	6030046	135.000	Syd
1395	Pavt Repr, Nonreinf Conc, 10 inch	6030048	9,509.000	Syd
1400	Pavt Repr, Nonreinf Conc, 13 inch	6030053	8,816.000	Syd
1405	Pavt Repr, Rem	6030080	19,024.000	Syd
1410	Saw Cut, Intermediate	6030090	19,083.000	Ft
1415	Resealing Trans Joints with Hot-Poured Rubber	6030100	277,999.000	Ft
1420	Resealing Longit Joints with Hot-Poured Rubber	6030101	296,999.000	Ft
1425	_ Filling Shld Corrugations with Hot-Poured Rubber	6037001	89,375.000	Ft
1430	_ Pavt Repr, Nonreinf Conc, Additional Thickness	6037021	81.000	Cyd
1435	_ Bypass Pumping	7047050	14.000	Ea
1440	_ Construction Dam	7047050	22.000	Ea
1445	Reinforcement, Steel, Culv and Headwall	7060091	36,491.000	Lb
1450	_ Rapid-Setting Polymer Conc	7127020	35.000	Cft
1455	Obstruction Rem	7180100	35,000.000	Dlr
1460	Dynamic Message Sign, Fdn	7180200	40.000	Ft
1465	_ Fiber Optic, Cable, Reinstall	8007001	50.000	Ft
1470	_ Fiber Optic, Cable, Rem	8007001	230.000	Ft
1475	_ Cellular Modem, 4G	8007050	12.000	Ea
1480	_ Cellular Modem, Rem and Salv	8007050	6.000	Ea
1485	_ Closed Circuit Television Camera, Rem	8007050	9.000	Ea
1490	_ Digital Video Encoder, Rem	8007050	8.000	Ea
1495	_ Dynamic Message Sign, Full Color, 20 mm, 96 by 400	8007050	2.000	Ea
1500	_ Dynamic Message Sign, Large, Rem	8007050	2.000	Ea
1505	_ Dynamic Message Sign, Support Structure, Rem	8007050	2.000	Ea
1510	_ Impact Attenuator, Test Level-3, Furn and Install, Type 3	8007050	4.000	Ea
1515	_ ITS Cabinet, Standard Ground Mtd	8007050	3.000	Ea
1520	_ Power Distribution Unit	8007050	10.000	Ea

1525	_ Prest Spun Conc Pole, Rem, Shallow	8007050	8.000	Ea
1530	_ Radio, Rem	8007050	2.000	Ea
1535	_ Roadside Unit, Rem and Salv	8007050	10.000	Ea
1540	_ Underground Splice Enclosure	8007050	9.000	Ea
1545	_ Underground Splice Enclosure, Rem	8007050	13.000	Ea
1550	_ Integration, Advanced Traf Management System Software	8007051	1.000	LSUM
1555	_ System Testing	8007051	1.000	LSUM
1560	_ Vibration Monitoring, Utility	8007051	1.000	LSUM
1565	Driveway, Nonreinf Conc, 6 inch	8010005	129.000	Syd
1570	Curb, Conc, Det E4	8020004	66.000	Ft
1575	Curb and Gutter, Conc, Det B1	8020015	26.000	Ft
1580	Curb and Gutter, Conc, Det B2	8020016	41.000	Ft
1585	Driveway Opening, Conc, Det M	8020050	293.000	Ft
1590	Spillway, Conc	8020075	76.000	Ft
1595	Curb and Gutter, Bridge Approach, Det 1	8022010	562.000	Ft
1600	Detectable Warning Surface	8030010	144.000	Ft
1605	Curb Ramp Opening, Conc	8030030	174.000	Ft
1610	Sidewalk, Conc, 4 inch	8030044	4,922.000	Sft
1615	Sidewalk, Conc, 6 inch	8030046	4,269.000	Sft
1620	Curb Ramp, Conc, 6 inch	8032002	1,369.000	Sft
1625	Sealing Localized Conc Barrier Cracks	8040000	1.000	LSUM
1630	Conc Barrier, Single Face, Type A	8040001	2,266.000	Ft
1635	Conc Barrier, Single Face, Type C	8040003	3,687.000	Ft
1640	Conc Barrier, Double Face, Type A	8040005	6,751.000	Ft
1645	Conc Barrier, Double Face, Type B	8040006	40.000	Ft
1650	Conc Barrier, Split, Type A	8040010	205.000	Ft
1655	Conc Barrier, Split, Type B	8040011	431.000	Ft
1660	Glare Screen, Conc	8040015	1,260.000	Ft
1665	Glare Screen, Conc, Split	8040016	110.000	Ft
1670	_ Conc Barrier, Double Face, Type A, Modified, 0-2 Feet	8047001	1,220.000	Ft
1675	_ Conc Barrier, Double Face, Type B, Modified, 0-1.0 Foot	8047001	12,805.000	Ft
1680	Guardrail Anch, Bridge, Det T1	8070022	34.000	Ea
1685	Guardrail Anchored in Backslope, Type 4MGS-8	8070034	2.000	Ea
1690	Guardrail Approach Terminal, Type 3B	8070038	1.000	Ea
1695	Guardrail Approach Terminal, Type 2M	8070044	94.000	Ea
1700	Guardrail Approach Terminal, Type 2M, Temp	8070049	108.000	Ea
1705	Guardrail Departing Terminal, Type T	8070051	8.000	Ea
1710	Guardrail Departing Terminal, Type MGS	8070052	65.000	Ea
1715	Guardrail Departing Terminal, Type MGS, Temp	8070053	28.000	Ea
1720	Guardrail Approach Terminal, Type 3M	8070060	8.000	Ea
1725	Guardrail Reflector	8070080	1,629.000	Ea
1730	Guardrail Post, Furn and Install, 72 inch	8070101	11.000	Ea
1735	Guardrail Anch, Bridge, Det M1	8070130	16.000	Ea

1740	Guardrail Anch, Bridge, Det M2	8070131	1.000	Ea
1745	Guardrail Anch, Bridge, Det M4	8070133	16.000	Ea
1750	Guardrail Anch, Bridge, Det M7	8070136	2.000	Ea
1755	Cable Barrier, High Tension	8070198	39,508.000	Ft
1760	Cable Barrier Terminal, High Tension	8070199	42.000	Ea
1765	Cable, 1000 ft Spool	8070250	9.000	Ea
1770	Cable Barrier, Intermediate Line Post	8070251	378.000	Ea
1775	Cable Barrier, Misc Hardware, Intermediate Line Post	8070252	378.000	Ea
1780	Cable Barrier, Modified Line Post and Hardware	8070253	15.000	Ea
1785	Cable Barrier, Socket, Conc Fdn	8070254	150.000	Ea
1790	Cable Barrier, Driven Socket	8070255	150.000	Ea
1795	Cable Barrier, Turnbuckle	8070256	14.000	Ea
1800	Cable Barrier, Reflector	8070257	167.000	Ea
1805	Cable Barrier, Excluder Cap	8070258	378.000	Ea
1810	Cable Barrier, Wedge Lock Fitting	8070259	10.000	Ea
1815	Cable Barrier, Cable Splice Kit	8070260	66.000	Ea
1820	Cable Barrier Terminal, Materials	8070261	6.000	Ea
1825	Cable Barrier, High Tension, Repr Labor	8070262	98,000.000	Dlr
1830	Guardrail, Temp, Type MGS-8, 72 inch Post	8072004	23,819.000	Ft
1835	Guardrail Anch, Bridge, Det M1, Curved	8072036	4.000	Ea
1840	Guardrail Anch Bridge, Det T1, Curved	8072063	3.000	Ea
1845	Guardrail Anch Bridge, Det T2, Curved	8072064	1.000	Ea
1850	Guardrail Anch, Bridge, Det M1, Temp	8072084	12.000	Ea
1855	Guardrail, Long Span, Det MGS-1	8072121	4.000	Ea
1860	Guardrail, Curved, Type T, 84 inch Post	8072143	39.000	Ft
1865	Guardrail, Curved, Type B-CRT	8072154	88.000	Ft
1870	Guardrail, Type A, 72 inch Post	8072170	917.000	Ft
1875	Guardrail, Type B, 72 inch Post	8072171	50.000	Ft
1880	Guardrail, Type T, 84 inch Post	8072175	239.000	Ft
1885	Guardrail, Type T, 96 inch Post	8072176	600.000	Ft
1890	Guardrail, Type TD, 84 inch Post	8072177	375.000	Ft
1895	Guardrail, Type MGS-8, 72 inch Post	8072179	37,551.000	Ft
1900	Guardrail, Type MGS-8D, 72 inch Post	8072181	732.000	Ft
1905	_ Guardrail Anch, Bridge, Det T1, Curved, Modified	8077050	1.000	Ea
1910	_ Guardrail Terminal, Reflectorized Object Marker Panel, Rem and Replace	8077050	4.000	Ea
1915	_ Hand Digging Guardrail Post	8077050	75.000	Ea
1920	Fence, Woven Wire with Steel Post	8080002	61,322.000	Ft
1925	Fence Gate, 12 foot, for Woven Wire	8080005	1.000	Ea
1930	Fence, Chain Link, 60 inch	8080012	156.000	Ft
1935	_ Bridge Sign Connection, Steel, Type J, Rem	8087050	1.000	Ea
1940	Band, Sign	8100010	12.000	Ea
1945	Bridge Sign Connection, Conc, Type A1	8100031	30.000	Ea
1950	Bridge Sign Connection, Conc, Type C	8100033	3.000	Ea
1955	Bridge Sign Connection, Conc, Type R	8100043	8.000	Ea

1960	Bridge Sign Connection, Steel, Type A1	8100060	8.000	Ea
1965	Bridge Sign Connection, Steel, Type H	8100067	6.000	Ea
1970	Bridge Sign Connection, Steel, Type J	8100069	1.000	Ea
1975	Bridge Sign Connection, Type A, Rem	8100080	35.000	Ea
1980	Bridge Sign Connection, Type C, Rem	8100082	7.000	Ea
1985	Bridge Sign Connection, Type F, Rem	8100085	2.000	Ea
1990	Cantilever, Rem	8100090	7.000	Ea
1995	Cantilever, Type E	8100104	6.000	Ea
2000	Column, Breakaway, W8 x 13	8100120	8.000	Ea
2005	Column, Breakaway, W8 x 18	8100121	4.000	Ea
2010	Delineator Reflector, Red	8100131	516.000	Ea
2015	Delineator Reflector, Yellow	8100132	399.000	Ea
2020	Delineator Reflector, Green	8100133	380.000	Ea
2025	Delineator Reflector, White	8100134	1,164.000	Ea
2030	Delineator, Reflective Sheeting, 3 inch by 12 inch, Red	8100139	62.000	Ea
2035	Delineator, Reflective Sheeting, 3 inch by 12 inch, White	8100145	14.000	Ea
2040	Delineator, Reflective Sheeting, 3 inch by 12 inch, Yellow	8100146	194.000	Ea
2045	Fdn, Breakaway, W8 x 13	8100160	8.000	Ea
2050	Fdn, Breakaway, W8 x 18	8100161	4.000	Ea
2055	Fdn, Cantilever Sign Structure Type E, 48 inch dia, Cased	8100170	73.000	Ft
2060	Fdn, Cantilever Sign Structure Type E, 48 inch dia, Uncased	8100171	96.000	Ft
2065	Fdn, Cantilever, Rem	8100190	7.000	Ea
2070	Fdn, Column Breakaway, Rem	8100220	16.000	Ea
2075	Fdn, Truss Sign Structure Type E, 48 inch dia, Uncased	8100251	603.000	Ft
2080	Fdn, Truss Sign Structure Type E, 54 inch dia, Cased	8100252	756.000	Ft
2085	Fdn, Truss Sign Structure Type E, 54 inch dia, Uncased	8100253	269.000	Ft
2090	Fdn, Truss Sign Structure Type E, 72 inch dia, Cased	8100256	124.000	Ft
2095	Fdn, Truss, Rem	8100260	39.000	Ea
2100	Fdn, Wood Support, Rem	8100280	193.000	Ea
2105	Glare Screen Connection, Conc	8100290	1.000	Ea
2110	Installing MDOT Supplied Sign, Type III	8100302	12.000	Ea
2115	Median Barrier Connection, Conc, Perforated Steel Square Tube	8100311	32.000	Ea
2120	Perforated Steel Square Tube Breakaway System	8100330	69.000	Ea
2125	Fdn, Perforated Steel Square Tube Sign Breakaway System, Rem	8100331	69.000	Ea
2130	Post Hole Through Conc for Steel Post	8100340	6.000	Ea
2135	Post Hole Through Conc for Wood Post	8100341	4.000	Ea
2140	Delineator, Rem	8100349	1,060.000	Ea
2145	Post, Rigid, Delineator	8100361	1,742.000	Ea
2150	Post, Steel, 3 pound	8100371	8,921.000	Ft
2155	Post, Wood, 4 inch by 6 inch	8100380	1,612.000	Ft

2160	Post, Wood, 6 inch by 8 inch	8100382	2,256.000	Ft
2165	Sign, Type I, Erect, Salv	8100390	3.000	Ea
2170	Sign, Type I, Rem	8100391	90.000	Ea
2175	Sign, Type IA	8100392	14,384.000	Sft
2180	Sign, Type IB	8100393	192.000	Sft
2185	Sign, Type II, Erect, Salv	8100396	5.000	Ea
2190	Sign, Type II, Rem	8100397	209.000	Ea
2195	Sign, Type IIA	8100398	1,099.000	Sft
2200	Sign, Type IIB	8100399	984.000	Sft
2205	Sign, Type III, Erect, Salv	8100402	14.000	Ea
2210	Sign, Type III, Rem	8100403	502.000	Ea
2215	Sign, Type IIIA	8100404	1,673.000	Sft
2220	Sign, Type IIIB	8100405	1,625.000	Sft
2225	Transporting Salv MDOT Materials	8100420	1.000	LSUM
2230	Sign, Type V, Rem	8100421	3.000	Ea
2235	Sign, Type V, Erect, Salv	8100422	6.000	Ea
2240	Sign, Type VA	8100424	107.000	Sft
2245	Sign, Type VB	8100425	1,419.000	Sft
2250	Truss, Rem	8100440	16.000	Ea
2255	Truss, Type E, 70 foot	8100488	3.000	Ea
2260	Truss, Type E, 85 foot	8100491	1.000	Ea
2265	Truss, Type E, 90 foot	8100492	4.000	Ea
2270	Truss, Type E, 95 foot	8100493	3.000	Ea
2275	Truss, Type E, 110 foot	8100496	1.000	Ea
2280	Truss, Type E, 120 foot	8100498	1.000	Ea
2285	Truss, Type E, 125 foot	8100499	1.000	Ea
2290	Truss, Type E, 130 foot	8100500	2.000	Ea
2295	Truss, Type E, 135 foot	8100501	2.000	Ea
2300	Truss, Type E, 140 foot	8100502	1.000	Ea
2305	Post, Flexible, Delineator, Surface Mtd, 36 inch	8100551	400.000	Ea
2310	Post, Flexible, Delineator, Ground Mtd	8100555	364.000	Ea
2315	Reflective Panel for Permanent Sign Support, 3 foot	8100613	151.000	Ea
2320	Reflective Panel for Permanent Sign Support, 6 foot	8100616	116.000	Ea
2325	Sign, Type I, Rem, Salv	8102001	3.000	Ea
2330	Sign, Type III, Rem, Salv	8102003	9.000	Ea
2335	Ground Mtd Sign Support, Rem	8102010	823.000	Ea
2340	_ Bridge Sign Connection, Type R, Rem	8107050	4.000	Ea
2345	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Crosswalk	8110024	72.000	Ft
2350	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Cross Hatching, Yellow	8110040	992.000	Ft
2355	Pavt Mrkg, Ovly Cold Plastic, 24 inch, Stop Bar	8110045	349.000	Ft
2360	Pavt Mrkg, Ovly Cold Plastic, Wrong Way Arrow Sym	8110051	9.000	Ea
2365	Pavt Mrkg, Ovly Cold Plastic, Lt Turn Arrow Sym	8110063	46.000	Ea
2370	Pavt Mrkg, Ovly Cold Plastic, Only	8110068	4.000	Ea
2375	Pavt Mrkg, Ovly Cold Plastic, Rt and Lt Turn Arrow	8110070	5.000	Ea

	Sym			
2380	Pavt Mrkg, Ovly Cold Plastic, Rt Turn Arrow Sym	8110071	36.000	Ea
2385	Pavt Mrkg, Ovly Cold Plastic, Thru and Lt Turn Arrow Sym	8110076	2.000	Ea
2390	Pavt Mrkg, Polyurea, 6 inch, Crosswalk	8110093	1,060.000	Ft
2395	Pavt Mrkg, Polyurea, 12 inch, Cross Hatching, White	8110108	102.000	Ft
2400	Pavt Mrkg, Polyurea, 12 inch, Crosswalk	8110110	125.000	Ft
2405	Pavt Mrkg, Polyurea, 24 inch, Stop Bar	8110114	739.000	Ft
2410	Rem Curing Compound, for Longit Mrkg, 6 inch	8110308	12,118.000	Ft
2415	Rem Curing Compound, for Longit Mrkg, 12 inch	8110310	60.000	Ft
2420	Rem Curing Compound, for Spec Mrkg	8110321	645.000	Sft
2425	Witness, Log, \$1,250.00	8110351	1,250.000	Dlr
2430	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Wet Reflective, White	8110381	91,862.000	Ft
2435	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Wet Reflective, White	8110383	8,027.000	Ft
2440	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Wet Reflective, Yellow	8110385	10,055.000	Ft
2445	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Wet Reflective, Yellow	8110387	97.000	Ft
2450	Recessing Pavt Mrkg, Transv	8110451	3,840.000	Sft
2455	Recessing Pavt Mrkg, Guide Line	8110453	372.000	Ft
2460	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Dotted Turning Guide Line, White	8110562	176.000	Ft
2465	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Dotted Thru Guide Line, White	8110566	196.000	Ft
2470	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, White	8112115	229,658.000	Ft
2475	Pavt Mrkg, Wet Reflective Polyurea, 12 inch, White	8112116	73,610.000	Ft
2480	Pavt Mrkg, Wet Reflective Polyurea, 6 inch, Yellow	8112118	229,336.000	Ft
2485	_ Pavt Mrkg, Preformed Thermopl, I-94 Route Shield, 8 foot by 16 foot	8117050	1.000	Ea
2490	_ Pavt Mrkg, Preformed Thermopl, M-39 Route Shield, 8 foot by 16 foot	8117050	1.000	Ea
2495	Barricade, Type III, High Intensity, Double Sided, Lighted, Furn	8120012	417.000	Ea
2500	Barricade, Type III, High Intensity, Double Sided, Lighted, Oper	8120013	417.000	Ea
2505	Pedestrian Type II Barricade, Temp	8120026	6.000	Ea
2510	Conc Barrier Ending, Temp, Det 2, Adj	8120040	2.000	Ea
2515	Conc Barrier Ending, Temp, Det 2, Furn	8120041	8.000	Ea
2520	Conc Barrier Ending, Temp, Det 2, Oper	8120042	8.000	Ea
2525	Conc Barrier Ending, Temp, Det 2, Relocated	8120043	20.000	Ea
2530	Conc Barrier Reflector Replacement	8120070	906.000	Ea
2535	Conc Barrier, Temp, Adj	8120080	3,779.000	Ft
2540	Conc Barrier, Temp, Furn	8120081	90,500.000	Ft
2545	Conc Barrier, Temp, Oper	8120082	90,500.000	Ft
2550	Conc Barrier, Temp, Relocated	8120083	109,656.000	Ft
2555	Culv, Temp	8120090	2.000	Ea
2560	Delineator, Flexible, Temp, Furn	8120091	606.000	Ea

2565	Delineator, Flexible, Temp, Oper	8120092	606.000	Ea
2570	Glare Screen, Temp	8120094	90,500.000	Ft
2575	Glare Screen, Temp, Relocated	8120095	109,656.000	Ft
2580	High Intensity Light, Type B, Furn	8120110	6.000	Ea
2585	High Intensity Light, Type B, Oper	8120111	6.000	Ea
2590	Connected Arrow Board, Type C, Furn	8120155	11.000	Ea
2595	Connected Arrow Board, Type C, Oper	8120156	11.000	Ea
2600	Ltg for Night Work	8120160	1.000	LSUM
2605	Minor Traf Devices	8120170	1.000	LSUM
2610	Mobile Attenuator	8120180	16.000	Ea
2615	Pavt Mrkg, Longit, 6 inch or Less Width, Rem	8120210	441,715.000	Ft
2620	Pavt Mrkg, Longit, Greater than 6 inch Width, Rem	8120211	113,804.000	Ft
2625	Plastic Drum, Fluorescent, Furn	8120252	3,162.000	Ea
2630	Plastic Drum, Fluorescent, Oper	8120253	3,162.000	Ea
2635	Sign Cover	8120310	100.000	Ea
2640	Sign Cover, Type I	8120320	50.000	Ea
2645	Sign, Portable, Changeable Message, NTCIP-Compliant, Furn	8120332	19.000	Ea
2650	Sign, Portable, Changeable Message, NTCIP-Compliant, Oper	8120333	19.000	Ea
2655	Sign, Type A, Temp, Prismatic, Furn	8120340	3,980.000	Sft
2660	Sign, Type A, Temp, Prismatic, Oper	8120341	3,980.000	Sft
2665	Sign, Type B, Temp, Prismatic, Furn	8120350	23,770.000	Sft
2670	Sign, Type B, Temp, Prismatic, Oper	8120351	23,770.000	Sft
2675	Sign, Type B, Temp, Prismatic, Spec, Furn	8120352	1,851.000	Sft
2680	Sign, Type B, Temp, Prismatic, Spec, Oper	8120353	1,851.000	Sft
2685	Traf Regulator Control	8120370	1.000	LSUM
2690	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, White, Temp	8122000	677,686.000	Ft
2695	Pavt Mrkg, Wet Reflective, Type R, Tape, 6 inch, Yellow, Temp	8122002	456,964.000	Ft
2700	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, White, Temp	8122004	264,904.000	Ft
2705	Pavt Mrkg, Wet Reflective, Type NR, Paint, 6 inch, Yellow, Temp	8122006	191,684.000	Ft
2710	Pavt Mrkg, Wet Reflective, Type R, Tape, 12 inch, White, Temp	8122012	35,150.000	Ft
2715	Pavt Mrkg, Wet Reflective, Type NR, Tape, 12 inch, White, Temp	8122020	10,043.000	Ft
2720	Speed Radar Trailer, Temp	8122028	18.000	Ea
2725	Temp Rumble Strips (Orange), Advance of a Work Zone	8122187	6,804.000	Ft
2730	Pedestrian Path, Temp	8122250	180.000	Ft
2735	Pedestrian Ramp, Temp	8122251	6.000	Ea
2740	Rebuilding Michigan Sign, Type VA, Modified, Temp, Furn	8123000	8.000	Ea
2745	Rebuilding Michigan Sign, Type VA, Modified, Temp, Oper	8123001	8.000	Ea
2750	_ Barrier Gate, Temp, Furn	8127050	10.000	Ea

2755	_ Barrier Gate, Temp, Open/Close	8127050	20.000	Ea
2760	_ Barrier Gate, Temp, Oper	8127050	10.000	Ea
2765	_ Emergency Repr Traf Control Plan	8127050	20.000	Ea
2770	_ Traf Speed Sensor, Portable, Temp	8127050	18.000	Ea
2775	_ Control System, Dynamic Work Zone Traf Monitoring System	8127051	1.000	LSUM
2780	_ Safety Contingency	8127060	80,000.000	Dir
2785	Riprap, Plain	8130010	3,540.000	Syd
2790	Ditch, Plain Cobble	8140005	500.000	Syd
2795	Site Preparation, Max \$454,460.00	8150001	1.000	LSUM
2800	Watering and Cultivating, First Season, Min \$220,740.00	8150002	1.000	LSUM
2805	Watering and Cultivating, 2nd Season, Min \$272,680.00	8150003	1.000	LSUM
2810	Acer rubrum 'Red Sunset', 1 1/2 inch	8150143	116.000	Ea
2815	Acer x freemanii 'Celebration', 1 1/2 inch	8150223	86.000	Ea
2820	Aesculus x carnea 'Briotii', 1 1/2 inch	8150290	140.000	Ea
2825	Catalpa speciosa, 1 1/2 inch	8150765	37.000	Ea
2830	Celtis occidentalis, 1 1/2 inch	8150778	38.000	Ea
2835	Crataegus virdis 'Winter King', 1 1/2 inch	8151175	156.000	Ea
2840	Ginko biloba 'Autumn Gold', 1 1/2 inch	8151630	144.000	Ea
2845	Gleditsia triacanthos inermis 'Shademaster', 1 1/2 inch	8151655	53.000	Ea
2850	Gymnocladus dioicus, 1 1/2 inch	8151674	97.000	Ea
2855	Juniperus virginiana, 3 foot	8152030	41.000	Ea
2860	Juniperus virginiana, 6 foot	8152032	205.000	Ea
2865	Liriodendron tulipifera, 1 1/2 inch	8152175	71.000	Ea
2870	Malus 'Prairie Fire', 1 1/2 inch	8152313	56.000	Ea
2875	Nyssa sylvatica, 1 1/2 inch	8152511	31.000	Ea
2880	Ostrya virginiana, 1 1/2 inch	8152526	187.000	Ea
2885	Picea omorika, 4 foot	8152786	122.000	Ea
2890	Platanus x acerifolia 'Liberty' 1 1/2 inch	8152886	13.000	Ea
2895	Quercus bicolor, 1 1/2 inch	8153042	99.000	Ea
2900	Quercus imbricaria, 1 1/2 inch	8153070	51.000	Ea
2905	Quercus robur, 1 1/2 inch	8153111	37.000	Ea
2910	Quercus shumardii, 1 1/2 inch	8153139	73.000	Ea
2915	Syringa reticulata 'Ivory Silk', 1 1/2 inch	8153716	80.000	Ea
2920	Taxodium distichum, 1 1/2 inch	8153744	81.000	Ea
2925	Tilia cordata 'Greenspire', 1 1/2 inch	8153860	89.000	Ea
2930	Ulmus americana 'Valley Forge', 1 1/2 inch	8153910	18.000	Ea
2935	Ulmus 'Morton', 1 1/2 inch	8153923	87.000	Ea
2940	Ulmus x 'Pioneer', 1 1/2 inch	8153961	105.000	Ea
2945	_ Carpinus caroliniana, 1 1/2 inch	8157050	134.000	Ea
2950	_ Heptacodium miconiodes, 1 1/2 inch	8157050	139.000	Ea
2955	_ Malus 'Adams', 1 1/2 inch	8157050	61.000	Ea
2960	_ Malus 'Purple Prince', 1 1/2 inch	8157050	53.000	Ea
2965	_ Picea glauca var. densata, 6 foot	8157050	282.000	Ea

2970	_ Picea glauca var. densata, potted, 18-24 inch	8157050	128.000	Ea
2975	_ Picea omorika, potted, 18-24 inch	8157050	49.000	Ea
2980	_ Syringa pekinensis, 1 1/2 inch	8157050	86.000	Ea
2985	Weed Control	8160095	1,468.600	Acre
2990	Turf Reinforcement Mat	8162000	125.000	Syd
2995	Slope Restoration, Freeway, Type A	8162013	300,711.000	Syd
3000	Slope Restoration, Freeway, Type B	8162014	204,846.000	Syd
3005	Slope Restoration, Freeway, Type C	8162015	4,086.000	Syd
3010	Slope Restoration, Freeway, Type D	8162016	3,599.000	Syd
3015	_ Compacted Soil Restoration	8167011	2,945.000	Syd
3020	_ Turf Establishment, Performance	8167011	1,477,117.000	Syd
3025	Power Company (Estimated Cost to Contractor)	8180001	32,000.000	Dlr
3030	Conduit, Rem	8182000	95,230.000	Ft
3035	Conduit, Directional Bore, 1, 3 inch	8182035	3,470.000	Ft
3040	Conduit, Directional Bore, 2, 3 inch	8182037	6,615.000	Ft
3045	Conduit, Directional Bore, 3, 3 inch	8182039	390.000	Ft
3050	Conduit, Directional Bore, 4, 3 inch	8182040	29,830.000	Ft
3055	Conduit, DB, 1, 1 1/2 inch	8182048	135.000	Ft
3060	Conduit, DB, 1, 3 inch	8182050	62,615.000	Ft
3065	Conduit, DB, 2, 3 inch	8182053	600.000	Ft
3070	Conduit, DB, 3, 3 inch	8182056	155.000	Ft
3075	Conduit, DB, 4, 3 inch	8182059	245.000	Ft
3080	Conduit, DB, 1, 1 inch	8182060	40.000	Ft
3085	Conduit, Schedule 80, 3 inch	8182148	3,120.000	Ft
3090	DB Cable, in Conduit, 600V, 1/C#1/0	8182181	60.000	Ft
3095	DB Cable, in Conduit, 600V, 1/C#2	8182182	23,150.000	Ft
3100	DB Cable, in Conduit, 600V, 1/C#4	8182185	15,625.000	Ft
3105	DB Cable, in Conduit, 600V, 1/C#6	8182187	171,680.000	Ft
3110	Cable, Rem	8182196	2,010.000	Ft
3115	DB Cable, in Conduit, Rem	8182197	128,485.000	Ft
3120	Cable, Sec, 600V, 1, 3/C#6	8182238	1,564.000	Ft
3125	Cable, Sec, 600V, 2, 1/C#6	8182245	714.000	Ft
3130	Cable, Sec, 600V, 3, 1/C#6	8182246	10,590.000	Ft
3135	Cable, Equipment Grounding Wire, 1/C#2	8182288	3,320.000	Ft
3140	Cable, Equipment Grounding Wire, 1/C#4	8182290	5,225.000	Ft
3145	Cable, Equipment Grounding Wire, 1/C#6	8182291	61,988.000	Ft
3150	Hh, Heavy Duty Cover	8182308	434.000	Ea
3155	Hh, Round	8182310	12.000	Ea
3160	Hh, Round, 3 foot dia	8182319	72.000	Ea
3165	Hh, Adj	8182328	13.000	Ea
3170	Hh, Rem	8182330	243.000	Ea
3175	Metered Serv, Rem	8182339	2.000	Ea
3180	Wood Pole, Cl 4, 30 foot	8182349	4.000	Ea
3185	Wood Pole, Cl 4, 35 foot	8182350	2.000	Ea

3190	Wood Pole, Cl 4, 40 foot	8182351	2.000	Ea
3195	Wood Pole, Rem	8182363	6.000	Ea
3200	Serv Disconnect	8182366	5.000	Ea
3205	Serv Disconnect, Rem	8182367	3.000	Ea
3210	Wood Pole, Fit Up, Sec Serv Pole	8182382	2.000	Ea
3215	_ Hh, Round, Elec	8187050	6.000	Ea
3220	_ Hh, Type D	8187050	13.000	Ea
3225	Light Std Arm, 17 foot	8190270	317.000	Ea
3230	Light Std Arm, Install Salv	8190276	11.000	Ea
3235	Light Std Arm, Rem	8190277	372.000	Ea
3240	Light Std Arm, Rem and Salv	8190278	11.000	Ea
3245	Light Std Fdn	8190279	317.000	Ea
3250	Light Std Fdn, Rem	8190280	258.000	Ea
3255	Light Std, Frangible Transformer Base	8190281	255.000	Ea
3260	Light Std, Frangible Transformer Base, Rem	8190282	258.000	Ea
3265	Light Std Shaft, 31 foot to 40 foot	8190286	317.000	Ea
3270	Light Std Shaft, 41 foot to 50 foot	8190287	58.000	Ea
3275	Light Std Shaft, Install Salv	8190301	11.000	Ea
3280	Light Std Shaft, Rem	8190305	314.000	Ea
3285	Light Std Shaft, Rem and Salv	8190306	11.000	Ea
3290	Luminaire, Install Salv	8190350	383.000	Ea
3295	Luminaire, Rem and Salv	8190365	383.000	Ea
3300	_ Ltg Control Panel	8197050	2.000	Ea
3305	_ Ltg Control Panel, Rem	8197050	2.000	Ea
3310	_ Luminaire, Roadway	8197050	3.000	Ea
3315	_ Landscape Lighting, Rem	8197051	1.000	LSUM
3320	Case Sign (LED), One Way, 12 inch by 27 inch	8200019	12.000	Ea
3325	Case Sign, Rem	8200020	3.000	Ea
3330	Case Sign (LED), One Way, 24 inch by 30 inch	8200029	8.000	Ea
3335	Controller and Cabinet, Rem	8200030	2.000	Ea
3340	Controller Fdn, Base Mtd	8200045	4.000	Ea
3345	Global Positioning System Module	8200050	4.000	Ea
3350	Global Positioning System Module, Rem	8200053	2.000	Ea
3355	Fdn, Rem	8200065	28.000	Ea
3360	TS, Managed Field Ethernet Switch, Layer 2, Copper	8200088	4.000	Ea
3365	Pushbutton and Sign	8200121	4.000	Ea
3370	Pushbutton, Rem	8200122	4.000	Ea
3375	Span Wire	8200140	12.000	Ea
3380	Span Wire, Rem	8200141	2.000	Ea
3385	Span Wire Tether	8200142	12.000	Ea
3390	Steel Pole, Rem	8200145	11.000	Ea
3395	TS, 4th Level Arrow, Rem	8200176	2.000	Ea
3400	TS, Pedestrian, Bracket Arm Mtd, Rem	8200180	4.000	Ea
3405	TS, Span Wire Mtd, Rem	8200182	5.000	Ea
3410	Cabinet, Rem	8200184	14.000	Ea

3415	Cabinet, NEMA Type	8200186	4.000	Ea
3420	TS, One Way Bracket Arm Mtd	8200220	1.000	Ea
3425	TS, 4th Level, LTGA (LED)	8200329	2.000	Ea
3430	TS, Pedestrian, One Way Bracket Arm Mtd (LED) Countdown	8200336	4.000	Ea
3435	Bracket, Truss, with 18 foot Arm	8200378	2.000	Ea
3440	Wireless Vehicle Detection System	8200422	2.000	Ea
3445	Wireless Vehicle Sensor Node	8200425	19.000	Ea
3450	Hemispherical Video Detection Camera	8200444	2.000	Ea
3455	Hemispherical Video Detection System	8200445	2.000	Ea
3460	TS Head, Adj	8200452	25.000	Ea
3465	Junction Box, Span Wire	8200456	9.000	Ea
3470	Junction Box, Rem	8200457	5.000	Ea
3475	TS Face, Bag	8200458	73.000	Ea
3480	TS Face, Bag, Rem	8200459	73.000	Ea
3485	Strain Pole, Steel, 6 bolt, Size 2	8200466	16.000	Ea
3490	Strain Pole, Steel, 6 bolt, Size 3	8200467	5.000	Ea
3495	Strain Pole Fdn, 6 Bolt, 42 inch	8200475	90.000	Ft
3500	Strain Pole Fdn, 6 Bolt, 48 inch	8200476	284.000	Ft
3505	Cellular Modem, TS, 4th G	8200498	4.000	Ea
3510	Backplate, TS	8200501	32.000	Ea
3515	Hh, Lightning Protection	8200540	8.000	Ea
3520	TS, One Way Bracket Arm Mtd (LED), Long Life	8202200	1.000	Ea
3525	TS, One Way Span Wire Mtd, One Sect (LED), Long Life	8202275	1.000	Ea
3530	TS, One Way Span Wire Mtd (LED), Long Life	8202287	20.000	Ea
3535	TS, One Way Span Wire Mtd, LTGA (LED), Long Life	8202314	8.000	Ea
3540	TS, One Way Span Wire Mtd, RTGA (LED), Long Life	8202317	3.000	Ea
3545	_ Cellular Modem, Rem and Salv	8207050	6.000	Ea
3550	_ Controller, NEMA, ATC Type	8207050	4.000	Ea
3555	_ Fiber Optic, Hardware Assembly, Rem	8207050	14.000	Ea
3560	Monument Box	8210001	8.000	Ea
3565	Monument Box, Adj	8210005	8.000	Ea
3570	Monument Preservation	8210010	26.000	Ea
3575	Protect Corners	8210020	9.000	Ea
3580	Gate Valve, 12 inch	8230064	1.000	Ea
3585	Hydrant, Relocate, Case 1	8230095	2.000	Ea
3590	Water Main, 12 inch, Cut and Plug	8230134	2.000	Ea
3595	Water Main, DI, 8 inch, Tr Det G	8230156	23.000	Ft
3600	Water Main, DI, 12 inch, Tr Det G	8230166	87.000	Ft
3605	Gate Well, 60 inch dia	8230360	1.000	Ea
3610	Polyethylene Encasement	8230440	87.000	Ft
3615	Gate Well, Cover	8232000	1.000	Ea
3620	_ Water Main, HDPE, 12 inch, Directional Bore	8237001	332.000	Ft
3625	_ Water Main, Rem	8237001	50.000	Ft

3630	Contractor Staking	8240001	1.000	LSUM
3635	Staking Plan Errors and Extras, Max \$180/hour	8240002	3,606.000	Hr
3640	Grounding, Bonding, and Surge Protection	8260019	1.000	LSUM
3645	Lightning Protection, Pole	8260021	13.000	Ea
3650	Lightning Protection, Structure, Large Dynamic Message Sign	8260022	2.000	Ea
3655	Dynamic Message Sign, Support Structure	8260025	2.000	Ea
3660	Hh, Clean	8260030	80.000	Ea
3665	Conduit, Clean and Test	8260031	18,782.000	Ft
3670	Microwave Vehicle Detection System	8260040	13.000	Ea
3675	Microwave Vehicle Detection System, Rem	8260043	18.000	Ea
3680	Fiber Optic, Cable, Single Mode Fiber, 24 Strand	8260048	175,717.000	Ft
3685	Fiber Optic, Cable, Single Mode Fiber, 60 Strand	8260051	106,671.000	Ft
3690	Fiber Optic, Splice Cabinet	8260064	7.000	Ea
3695	Fiber Optic, Hardware Assembly, Small	8260065	15.000	Ea
3700	Fiber Optic, Hardware Assembly, Medium	8260066	4.000	Ea
3705	Fiber Optic, Hardware Assembly, Large	8260067	3.000	Ea
3710	Fiber Optic, Marker, Above Ground	8260069	200.000	Ea
3715	Tracer Wire	8260070	56,105.000	Ft
3720	Fiber Optic, Pigtail	8260071	80.000	Ea
3725	Fiber Optic, Jumper	8260072	30.000	Ea
3730	Managed Field Ethernet Switch, Layer 2	8260080	11.000	Ea
3735	Managed Field Ethernet Switch, Rem	8260087	12.000	Ea
3740	Power Serv, Underground, 30AMP, 120/240V	8260100	4.000	Ea
3745	Power Serv, Underground, 60AMP, 120/240V	8260101	2.000	Ea
3750	Safety Switch, Fusible	8260109	6.000	Ea
3755	Elec Rack	8260110	6.000	Ea
3760	Power Serv, Refurbish, 30AMP, 120/240V	8260111	2.000	Ea
3765	ITS Cabinet, Ground Mtd	8260130	7.000	Ea
3770	Uninterruptible Power Supply, ITS Cabinet	8260140	10.000	Ea
3775	Uninterruptible Power Supply, Rem	8260146	8.000	Ea
3780	Flowable Fill, Spun Pole Fdn	8260149	8.000	Cyd
3785	Spun Conc Pole, Type A	8260152	3.000	Ea
3790	Spun Conc Pole, Type B	8260153	1.000	Ea
3795	Drilled Shaft and Conc Skirt, Cased	8260155	4.000	Ea
3800	Surveillance System, Remote Site, Type A	8260157	8.000	Ea
3805	Surveillance System, Remote Site, Type B	8260158	1.000	Ea
3810	System Integration and Testing	8260160	1.000	LSUM
3815	_ Removing Rubbish	8507060	25,000.000	Dlr

Section: 2

3820	Conc Quality Initiative	10000030	191,800.000	Dlr
3825	Embankment, CIP	2050010	919,382.000	Cyd
3830	Excavation, Earth	2050016	1,465,052.000	Cyd

3835	Subbase, CIP	3010002	341,976.000	Cyd
3840	Open-Graded Dr Cse, CIP	3030030	480,506.000	Cyd
3845	Shld, CI II, CIP	3070122	22,401.000	Cyd
3850	Geotextile, Separator	3080005	1,209,902.000	Syd
3855	HMA Quality Initiative	5010007	1,925,140.000	Dlr
3860	_ HMA Approach, 10 inch	5017011	20,073.000	Syd
3865	_ HMA Approach, 8 inch	5017011	12,896.000	Syd
3870	_ HMA, 2EMH, 4 inch	5017011	482,060.000	Syd
3875	_ HMA, 2EMH, 5 inch	5017011	38,174.000	Syd
3880	_ HMA, 2EML, 4 inch	5017011	82,563.000	Syd
3885	_ HMA, 3EMH, 3 3/4 inch	5017011	520,234.000	Syd
3890	_ HMA, 3EMH, 3 inch	5017011	307,951.000	Syd
3895	_ HMA, 3EML, 3 3/4 inch	5017011	82,563.000	Syd
3900	_ HMA, 4EMH, 2 1/4 inch	5017011	520,234.000	Syd
3905	_ HMA, 4EMH, 2 inch	5017011	153,978.000	Syd
3910	_ HMA, 4EML, 2 1/4 inch	5017011	82,563.000	Syd
3915	Joint, Contraction, Cp	6020200	35,427.000	Ft
3920	Joint, Contraction, C3p	6020201	5,675.000	Ft
3925	Joint, Expansion, E2	6020207	2,365.000	Ft
3930	Joint, Expansion, E4	6020209	623.000	Ft
3935	Joint, Plane-of-Weakness, W	6020211	208.000	Ft
3940	Conc Pavt, Misc, Nonreinf, 10 1/2 inch, High Performance	6020517	3,127.000	Syd
3945	Conc Pavt, Misc, Nonreinf, 13 inch, High Performance	6020522	20,479.000	Syd
3950	Shld, Nonreinf Conc, High Performance	6020524	11,381.000	Syd
3955	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	8,398.000	Syd
3960	_ Conc Pavt, Bridge Approach, Reinf, HP, Modified	6027011	2,010.000	Syd
3965	Joint, Contraction, Crg	6030020	22,522.000	Ft
3970	Joint, Expansion, Erg	6030021	1,098.000	Ft
3975	Lane Tie, Epoxy Anchored	6030030	10,743.000	Ea
3980	Curb, Conc, Det G1	8020005	6,532.000	Ft
3985	_ Curb and Gutter, Bridge Approach, Det 5, Modified	8027001	1,943.000	Ft
3990	_ Curb and Gutter, Bridge Approach, Det 6, Modified	8027001	902.000	Ft
3995	_ Curb and Gutter, Conc, Det B1, Modified	8027001	27.000	Ft
4000	_ Curb and Gutter, Conc, Det B2, Modified	8027001	2,646.000	Ft
4005	_ Curb and Gutter, Conc, Det D1, Modified	8027001	1,482.000	Ft
4010	_ Curb and Gutter, Conc, Det D2, Modified	8027001	9,198.000	Ft
4015	_ Curb and Gutter, Conc, Det F5, Modified	8027001	5,977.000	Ft
4020	_ Curb and Gutter, Conc, Det F6, Modified	8027001	2,282.000	Ft
4025	_ Curb, Conc, Det G1, Modified	8027001	23,050.000	Ft
4030	_ Curb, Conc, Det G2, Modified	8027001	3,575.000	Ft
4035	_ Valley Gutter, Conc, Modified	8027001	51,535.000	Ft
4040	Conc Barrier Backfill, CIP	8040030	3,095.000	Cyd
4045	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Shadow Tape,	8110389	20,432.000	Ft

Black

4050	Recessing Pavt Mrkg, Longit	8110450	620,545.000	Ft
4055	Freeway Shld Corrugations, Milled, Conc	8222000	1,925.000	Ft
4060	Freeway Shld Corrugations, Milled, HMA	8222001	79,418.000	Ft

Section: 3

4065	Conc Quality Initiative	10000030	191,800.000	Dlr
4070	Embankment, CIP	2050010	920,167.000	Cyd
4075	Excavation, Earth	2050016	1,465,041.000	Cyd
4080	Subbase, CIP	3010002	342,000.000	Cyd
4085	Open-Graded Dr Cse, CIP	3030030	357,627.000	Cyd
4090	_ Open-Graded Dr Cse, 6 inch, Cement-Treated	3037011	619,937.000	Syd
4095	Shld, CI II, CIP	3070122	32,324.000	Cyd
4100	Geotextile, Separator	3080005	1,176,182.000	Syd
4105	Geotextile, Separator, Non-Woven	3082000	583,917.000	Syd
4110	HMA Quality Initiative	5010007	1,925,140.000	Dlr
4115	_ HMA Approach, 10 inch	5017011	20,073.000	Syd
4120	_ HMA Approach, 8 inch	5017011	12,896.000	Syd
4125	_ HMA, 2EMH, 4 inch	5017011	482,060.000	Syd
4130	_ HMA, 2EMH, 5 inch	5017011	38,174.000	Syd
4135	_ HMA, 2EML, 4 inch	5017011	82,563.000	Syd
4140	_ HMA, 3EMH, 3 3/4 inch	5017011	520,234.000	Syd
4145	_ HMA, 3EMH, 3 inch	5017011	307,951.000	Syd
4150	_ HMA, 3EML, 3 3/4 inch	5017011	82,563.000	Syd
4155	_ HMA, 4EMH, 2 1/4 inch	5017011	520,234.000	Syd
4160	_ HMA, 4EMH, 2 inch	5017011	153,978.000	Syd
4165	_ HMA, 4EML, 2 1/4 inch	5017011	82,563.000	Syd
4170	Joint, Contraction, Cp	6020200	35,427.000	Ft
4175	Joint, Contraction, C3p	6020201	5,675.000	Ft
4180	Joint, Expansion, E2	6020207	2,365.000	Ft
4185	Joint, Expansion, E4	6020209	623.000	Ft
4190	Joint, Plane-of-Weakness, W	6020211	208.000	Ft
4195	Conc Pavt, Misc, Nonreinf, 10 1/2 inch, High Performance	6020517	3,127.000	Syd
4200	Conc Pavt, Misc, Nonreinf, 13 inch, High Performance	6020522	20,479.000	Syd
4205	Shld, Nonreinf Conc, High Performance	6020524	11,381.000	Syd
4210	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	8,398.000	Syd
4215	_ Conc Pavt, Bridge Approach, Reinf, HP, Modified	6027011	2,010.000	Syd
4220	Joint, Contraction, Crg	6030020	22,522.000	Ft
4225	Joint, Expansion, Erg	6030021	1,098.000	Ft
4230	Lane Tie, Epoxy Anchored	6030030	10,743.000	Ea
4235	Curb, Conc, Det G1	8020005	6,532.000	Ft
4240	_ Curb and Gutter, Bridge Approach, Det 5, Modified	8027001	1,943.000	Ft
4245	_ Curb and Gutter, Bridge Approach, Det 6, Modified	8027001	902.000	Ft

4250	_ Curb and Gutter, Conc, Det B1, Modified	8027001	27.000	Ft
4255	_ Curb and Gutter, Conc, Det B2, Modified	8027001	2,646.000	Ft
4260	_ Curb and Gutter, Conc, Det D1, Modified	8027001	1,482.000	Ft
4265	_ Curb and Gutter, Conc, Det D2, Modified	8027001	9,198.000	Ft
4270	_ Curb and Gutter, Conc, Det F5, Modified	8027001	5,977.000	Ft
4275	_ Curb and Gutter, Conc, Det F6, Modified	8027001	2,282.000	Ft
4280	_ Curb, Conc, Det G1, Modified	8027001	23,050.000	Ft
4285	_ Curb, Conc, Det G2, Modified	8027001	3,575.000	Ft
4290	_ Valley Gutter, Conc, Modified	8027001	51,535.000	Ft
4295	Conc Barrier Backfill, CIP	8040030	3,145.000	Cyd
4300	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Shadow Tape, Black	8110389	20,432.000	Ft
4305	Recessing Pavt Mrkg, Longit	8110450	620,545.000	Ft
4310	Freeway Shld Corrugations, Milled, Conc	8222000	1,925.000	Ft
4315	Freeway Shld Corrugations, Milled, HMA	8222001	79,418.000	Ft

Section: 4

4320	Conc Quality Initiative	10000030	2,395,800.000	Dir
4325	Embankment, CIP	2050010	966,062.000	Cyd
4330	Excavation, Earth	2050016	1,332,583.000	Cyd
4335	Subbase, CIP	3010002	99,697.000	Cyd
4340	Open-Graded Dr Cse, CIP	3030030	487,664.000	Cyd
4345	Shld, CI II, CIP	3070122	28,713.000	Cyd
4350	Geotextile, Separator	3080005	1,214,239.000	Syd
4355	HMA Quality Initiative	5010007	1,640.000	Dir
4360	Joint, Contraction, Cp	6020200	347,007.000	Ft
4365	Joint, Contraction, C3p	6020201	138,846.000	Ft
4370	Joint, Expansion, E2	6020207	9,070.000	Ft
4375	Joint, Expansion, E4	6020209	3,403.000	Ft
4380	Joint, Plane-of-Weakness, W	6020211	7,124.000	Ft
4385	Joint, Contraction, Cp, Intersection	6020250	6,454.000	Ft
4390	Joint, Expansion, E2, Intersection	6020270	1,404.000	Ft
4395	Joint, Plane-of-Weakness, W, Intersection	6020310	837.000	Ft
4400	Conc Pavt, Nonreinf, 10 1/2 inch, High Performance	6020505	708.000	Syd
4405	Conc Pavt, Nonreinf, 13 inch, High Performance	6020510	450,926.000	Syd
4410	Conc Pavt, Misc, Nonreinf, 10 1/2 inch, High Performance	6020517	114,231.000	Syd
4415	Conc Pavt, Misc, Nonreinf, 13 inch, High Performance	6020522	84,252.000	Syd
4420	Shld, Nonreinf Conc, High Performance	6020524	169,658.000	Syd
4425	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	1,852.000	Syd
4430	_ Conc Pavt, Bridge Approach, Reinf, HP, Modified	6027011	8,556.000	Syd
4435	Joint, Contraction, Crg	6030020	23,059.000	Ft
4440	Joint, Expansion, Erg	6030021	1,154.000	Ft
4445	Lane Tie, Epoxy Anchored	6030030	29,578.000	Ea

4450	Curb and Gutter, Conc, Det B3	8020017	68.000	Ft
4455	_ Curb and Gutter, Bridge Approach, Det 5, Modified	8027001	1,943.000	Ft
4460	_ Curb and Gutter, Bridge Approach, Det 6, Modified	8027001	902.000	Ft
4465	_ Curb and Gutter, Conc, Det B1, Modified	8027001	2,605.000	Ft
4470	_ Curb and Gutter, Conc, Det D1, Modified	8027001	10,675.000	Ft
4475	_ Curb and Gutter, Conc, Det F5, Modified	8027001	8,245.000	Ft
4480	_ Curb and Gutter, Conc, Det F6, Modified	8027001	14.000	Ft
4485	_ Curb, Conc, Det G1, Modified	8027001	29,582.000	Ft
4490	_ Curb, Conc, Det G2, Modified	8027001	3,575.000	Ft
4495	_ Valley Gutter, Conc, Modified	8027001	51,535.000	Ft
4500	Conc Barrier Backfill, CIP	8040030	3,110.000	Cyd
4505	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Shadow Tape, Black	8110389	70,450.000	Ft
4510	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Shadow Tape, Black	8110390	2,235.000	Ft
4515	Recessing Pavt Mrkg, Longit	8110450	615,737.000	Ft
4520	Freeway Shld Corrugations, Milled, Conc	8222000	81,343.000	Ft

Section: 5

4525	Conc Quality Initiative	10000030	2,395,800.000	Dlr
4530	Embankment, CIP	2050010	968,284.000	Cyd
4535	Excavation, Earth	2050016	1,332,729.000	Cyd
4540	Subbase, CIP	3010002	99,697.000	Cyd
4545	Open-Graded Dr Cse, CIP	3030030	365,544.000	Cyd
4550	_ Open-Graded Dr Cse, 6 inch, Cement-Treated	3037011	619,937.000	Syd
4555	Shld, CI II, CIP	3070122	40,946.000	Cyd
4560	Geotextile, Separator	3080005	1,180,519.000	Syd
4565	Geotextile, Separator, Non-Woven	3082000	583,917.000	Syd
4570	HMA Quality Initiative	5010007	1,640.000	Dlr
4575	Joint, Contraction, Cp	6020200	347,007.000	Ft
4580	Joint, Contraction, C3p	6020201	138,846.000	Ft
4585	Joint, Expansion, E2	6020207	9,070.000	Ft
4590	Joint, Expansion, E4	6020209	3,403.000	Ft
4595	Joint, Plane-of-Weakness, W	6020211	7,124.000	Ft
4600	Joint, Contraction, Cp, Intersection	6020250	6,454.000	Ft
4605	Joint, Expansion, E2, Intersection	6020270	1,404.000	Ft
4610	Joint, Plane-of-Weakness, W, Intersection	6020310	837.000	Ft
4615	Conc Pavt, Nonreinf, 10 1/2 inch, High Performance	6020505	708.000	Syd
4620	Conc Pavt, Nonreinf, 13 inch, High Performance	6020510	450,926.000	Syd
4625	Conc Pavt, Misc, Nonreinf, 10 1/2 inch, High Performance	6020517	114,231.000	Syd
4630	Conc Pavt, Misc, Nonreinf, 13 inch, High Performance	6020522	84,252.000	Syd
4635	Shld, Nonreinf Conc, High Performance	6020524	169,658.000	Syd
4640	Conc Pavt, Bridge Approach, Reinf, High Performance	6022000	1,852.000	Syd

4645	_ Conc Pavt, Bridge Approach, Reinf, HP, Modified	6027011	8,556.000	Syd
4650	Joint, Contraction, Crg	6030020	23,059.000	Ft
4655	Joint, Expansion, Erg	6030021	1,154.000	Ft
4660	Lane Tie, Epoxy Anchored	6030030	29,578.000	Ea
4665	Curb and Gutter, Conc, Det B3	8020017	68.000	Ft
4670	_ Curb and Gutter, Bridge Approach, Det 5, Modified	8027001	1,943.000	Ft
4675	_ Curb and Gutter, Bridge Approach, Det 6, Modified	8027001	902.000	Ft
4680	_ Curb and Gutter, Conc, Det B1, Modified	8027001	2,605.000	Ft
4685	_ Curb and Gutter, Conc, Det D1, Modified	8027001	10,675.000	Ft
4690	_ Curb and Gutter, Conc, Det F5, Modified	8027001	8,245.000	Ft
4695	_ Curb and Gutter, Conc, Det F6, Modified	8027001	14.000	Ft
4700	_ Curb, Conc, Det G1, Modified	8027001	29,582.000	Ft
4705	_ Curb, Conc, Det G2, Modified	8027001	3,575.000	Ft
4710	_ Valley Gutter, Conc, Modified	8027001	51,535.000	Ft
4715	Conc Barrier Backfill, CIP	8040030	3,110.000	Cyd
4720	Pavt Mrkg, Ovly Cold Plastic, 6 inch, Shadow Tape, Black	8110389	70,450.000	Ft
4725	Pavt Mrkg, Ovly Cold Plastic, 12 inch, Shadow Tape, Black	8110390	2,235.000	Ft
4730	Recessing Pavt Mrkg, Longit	8110450	615,288.000	Ft
4735	Freeway Shld Corrugations, Milled, Conc	8222000	81,343.000	Ft

Section: 6

4740	_ Railroad Inspection and Flagging, Consolidated Rail Corporation (Conrail)	1027060	75,000.000	Dir
4745	_ Railroad Protection, Conrail	1027060	50,000.000	Dir
4750	Structures, Rem (S07 of 82022)	2040060	1.000	LSUM
4755	Structures, Rem (S08 of 82022)	2040060	1.000	LSUM
4760	Structures, Rem (S09 of 82022)	2040060	1.000	LSUM
4765	Structures, Rem (S10 of 82022)	2040060	1.000	LSUM
4770	Structures, Rem Portions (S11 of 82022)	2040061	1.000	LSUM
4775	Structures, Rem Portions (S28 of 82022)	2040061	1.000	LSUM
4780	Structure Demolition Plan, Complex (S09 of 82022)	2040064	1.000	LSUM
4785	Structure Demolition Plan, Complex (S10 of 82022)	2040064	1.000	LSUM
4790	Embankment, Structure, CIP	2050012	108.000	Cyd
4795	Backfill, Structure, CIP	2060002	27,926.000	Cyd
4800	Aggregate	2060005	1,165.000	Cyd
4805	Excavation, Fdn	2060010	57,388.000	Cyd
4810	_ PVC Liner for Expanded Polystyrene Block	2067011	10,258.000	Syd
4815	_ Conc Base Cse, Reinf, Spec	2067021	339.000	Cyd
4820	_ Fill, Lightweight, Expanded Polystyrene Block	2067021	17,856.000	Cyd
4825	Underdrain, Fdn, 6 inch	4040033	4,329.000	Ft
4830	Steel Sheet Piling, Temp	7040002	631.000	Sft
4835	Prebore, Fdn Piling	7050001	4,000.000	Ft
4840	Pile Driving Equipment, Furn (S07 of 82022)	7050002	1.000	LSUM
4845	Pile Driving Equipment, Furn (S08 of 82022)	7050002	1.000	LSUM

4850	Pile Driving Equipment, Furn (S09 of 82022)	7050002	1.000	LSUM
4855	Pile Driving Equipment, Furn (S10 of 82022)	7050002	1.000	LSUM
4860	Pile Driving Equipment, Furn (S11 of 82022)	7050002	1.000	LSUM
4865	Pile Driving Equipment, Furn (S28 of 82022)	7050002	1.000	LSUM
4870	Pile, Steel, Furn and Driven, 14 inch	7050034	53,330.000	Ft
4875	Test Pile, Steel, 14 inch	7050035	10.000	Ea
4880	Pile Point, Steel	7050039	534.000	Ea
4885	Pile, Steel, Splice	7050050	631.000	Ea
4890	Pile Protection	7052000	4,000.000	Ft
4895	_ Plugging Artesian Flow, H-Piles	7057050	10.000	Ea
4900	_ Test Pile, Dynamic Analysis	7057050	32.000	Ea
4905	_ Test Pile, Furn Dynamic Analysis Equipment	7057050	16.000	Ea
4910	Bridge Ltg, Furn and Rem (B01 of 82192)	7060001	1.000	LSUM
4915	Bridge Ltg, Furn and Rem (S07 of 82022)	7060001	1.000	LSUM
4920	Bridge Ltg, Furn and Rem (S08 of 82022)	7060001	1.000	LSUM
4925	Bridge Ltg, Furn and Rem (S09 of 82022)	7060001	1.000	LSUM
4930	Bridge Ltg, Furn and Rem (S10 of 82022)	7060001	1.000	LSUM
4935	Bridge Ltg, Furn and Rem (S11 of 82022)	7060001	1.000	LSUM
4940	Bridge Ltg, Furn and Rem (S28 of 82022)	7060001	1.000	LSUM
4945	Bridge Ltg, Oper and Maintain	7060002	4,031.000	Cyd
4950	Expansion Joint Device	7060050	2,177.000	Ft
4955	False Decking	7060060	162,334.000	Sft
4960	Reinforcement, Steel, Epoxy Coated	7060092	2,129,195.000	Lb
4965	Substructure Conc, High Performance	7060101	6,241.000	Cyd
4970	Superstructure Conc, Form, Finish, and Cure (B01 of 82192)	7060111	1.000	LSUM
4975	Superstructure Conc, Form, Finish, and Cure (S07 of 82022)	7060111	1.000	LSUM
4980	Superstructure Conc, Form, Finish, and Cure (S08 of 82022)	7060111	1.000	LSUM
4985	Superstructure Conc, Form, Finish, and Cure (S09 of 82022)	7060111	1.000	LSUM
4990	Superstructure Conc, Form, Finish, and Cure (S10 of 82022)	7060111	1.000	LSUM
4995	Superstructure Conc, Form, Finish, and Cure (S11 of 82022)	7060111	1.000	LSUM
5000	Superstructure Conc, Form, Finish, and Cure (S28 of 82022)	7060111	1.000	LSUM
5005	Superstructure Conc, Form, Finish, and Cure (S52 of 82022)	7060111	1.000	LSUM
5010	Superstructure Conc, Form, Finish, and Cure, Night Casting (B01 of 82192)	7060112	1.000	LSUM
5015	Superstructure Conc, Form, Finish, and Cure, Night Casting (S07 of 82022)	7060112	1.000	LSUM
5020	Superstructure Conc, Form, Finish, and Cure, Night Casting (S08 of 82022)	7060112	1.000	LSUM
5025	Superstructure Conc, Form, Finish, and Cure, Night Casting (S09 of 82022)	7060112	1.000	LSUM
5030	Superstructure Conc, Form, Finish, and Cure, Night Casting (S10 of 82022)	7060112	1.000	LSUM

5035	Superstructure Conc, Form, Finish, and Cure, Night Casting (S11 of 82022)	7060112	1.000	LSUM
5040	Superstructure Conc, Form, Finish, and Cure, Night Casting (S28 of 82022)	7060112	1.000	LSUM
5045	Superstructure Conc, Form, Finish, and Cure, Night Casting (S52 of 82022)	7060112	1.000	LSUM
5050	Superstructure Conc, High Performance	7060116	530.000	Cyd
5055	Superstructure Conc, Night Casting, High Performance	7060117	4,055.000	Cyd
5060	Wall Drain	7060130	60.000	Sft
5065	Water Repellent Treatment, Penetrating	7060140	1,880.000	Syd
5070	Sealing Localized Cracks (B01 of 82192)	7060220	1.000	LSUM
5075	Sealing Localized Cracks (S07 of 82022)	7060220	1.000	LSUM
5080	Sealing Localized Cracks (S08 of 82022)	7060220	1.000	LSUM
5085	Sealing Localized Cracks (S09 of 82022)	7060220	1.000	LSUM
5090	Sealing Localized Cracks (S10 of 82022)	7060220	1.000	LSUM
5095	Sealing Localized Cracks (S11 of 82022)	7060220	1.000	LSUM
5100	Sealing Localized Cracks (S28 of 82022)	7060220	1.000	LSUM
5105	Conc, Grade 3500, Subfooting	7062000	305.000	Cyd
5110	Conc, Grade 3500	7062001	3.000	Cyd
5115	Conc, Grade 3500HP	7062002	271.000	Cyd
5120	Conc, Grade 4500HP	7062004	376.000	Cyd
5125	Aesthetic Texturing	7062005	1,283.000	Syd
5130	_ Expansive Waterstop	7067001	228.000	Ft
5135	_ Fiber Reinf Polymer System for Prest Conc Beam Repr	7067010	1,467.000	Sft
5140	Bearing, Elastomeric, 1 3/4 inch	7070015	19,225.000	Sin
5145	Bearing, Elastomeric, 2 inch	7070016	10,700.000	Sin
5150	Bearing, Elastomeric, 2 1/4 inch	7070017	8,558.000	Sin
5155	Bearing, Elastomeric, 2 1/2 inch	7070018	4,750.000	Sin
5160	Bearing, Elastomeric, 2 3/4 inch	7070019	4,275.000	Sin
5165	Bearing, Elastomeric, 3 inch	7070020	4,900.000	Sin
5170	Bearing, Elastomeric, 3 1/4 inch	7070021	37,458.000	Sin
5175	Bearing, Elastomeric, 3 1/2 inch	7070022	60,715.000	Sin
5180	Bearing, Elastomeric, 3 3/4 inch	7070023	500.000	Sin
5185	Bearing, Elastomeric, 4 inch	7070024	750.000	Sin
5190	Shear Developers (S28 of 82022)	7070040	1.000	LSUM
5195	Steel Diaphragm, Prest Conc Beam, Furn and Fab	7070053	31,600.000	Lb
5200	Steel Diaphragm, Prest Conc Beam, Erect	7070054	31,600.000	Lb
5205	Structural Steel, Plate, Erect	7070060	160,170.000	Lb
5210	Structural Steel, Plate, Furn and Fab	7070061	160,170.000	Lb
5215	_ Structural Steel, Retrofit, Furn, Fab, and Erect, Modified	7077030	4,451.000	Lb
5220	_ Bolt Replacement	7077050	66.000	Ea
5225	_ Structural Steel, Rem, Retrofit and Erect (B01 of 82192)	7077051	1.000	LSUM
5230	Prest Conc Bulb-Tee Beam, Furn, 60 inch by 49 inch	7080130	1,569.000	Ft

5235	Prest Conc Bulb-Tee Beam, Erect, 60 inch by 49 inch	7080131	1,569.000	Ft
5240	Prest Conc Bulb-Tee Beam, Furn, 66 inch by 49 inch	7080135	2,950.000	Ft
5245	Prest Conc Bulb-Tee Beam, Erect, 66 inch by 49 inch	7080136	2,950.000	Ft
5250	Prest Conc Bulb-Tee Beam, Furn, 72 inch by 49 inch	7080140	4,420.000	Ft
5255	Prest Conc Bulb-Tee Beam, Erect, 72 inch by 49 inch	7080141	4,420.000	Ft
5260	_ Wood Noise Wall, Repr	7097010	2,200.000	Sft
5265	Joint Waterproofing	7100001	3,458.000	Sft
5270	Joint Waterproofing, Expansion	7100003	1,766.000	Sft
5275	Conc Surface Coating, Warranty (S07 of 82022)	7100009	1.000	LSUM
5280	Conc Surface Coating, Warranty (S08 of 82022)	7100009	1.000	LSUM
5285	Conc Surface Coating, Warranty (S09 of 82022)	7100009	1.000	LSUM
5290	Conc Surface Coating, Warranty (S10 of 82022)	7100009	1.000	LSUM
5295	Conc Surface Coating, Warranty (S11 of 82022)	7100009	1.000	LSUM
5300	Conc Surface Coating, Warranty (S28 of 82022)	7100009	1.000	LSUM
5305	Conc Surface Coating	7100011	318.000	Syd
5310	Substructure Horizontal Surface Sealer	7100030	1,563.000	Syd
5315	Substructure Horizontal Surface Sealer (S46 of 82022)	7100030	26.000	Syd
5320	Substructure Horizontal Surface Sealer (S48 of 82022)	7100030	59.000	Syd
5325	Substructure Horizontal Surface Sealer (S49 of 82022)	7100030	68.000	Syd
5330	Substructure Horizontal Surface Sealer (S50 of 82022)	7100030	65.000	Syd
5335	_ Silane Treatment	7107010	61,993.000	Sft
5340	Bridge Railing, Aesthetic Parapet Tube, High Performance	7110004	65.000	Ft
5345	Bridge Barrier Railing, Type 6, High Performance	7110017	138.000	Ft
5350	Bridge Barrier Railing, Aesthetic, Type 6, Det 2, High Performance	7112062	2,621.000	Ft
5355	_ Bridge Barrier Railing, Type 6, High Performance, Modified	7117001	371.000	Ft
5360	Hand Chipping, Shallow	7120003	32.000	Syd
5365	Hand Chipping, Deep	7120004	76.000	Syd
5370	Hand Chipping, Other Than Deck	7120007	1,790.000	Cft
5375	Patch, Full Depth	7120010	16.000	Cyd
5380	Patch, Forming	7120017	4,774.000	Sft
5385	Epoxy Ovly	7120020	1,584.000	Syd
5390	Epoxy Ovly, Rem	7120021	30,401.000	Syd
5395	Epoxy Ovly, Warranty	7120022	31,823.000	Syd
5400	Adhesive Anchoring of Horizontal Bar, 3/4 inch	7120028	392.000	Ea
5405	Adhesive Anchoring of Vertical Bar, 3/4 inch	7120034	349.000	Ea
5410	Bolt, Adhesive Anchored, 1/2 inch	7120040	12.000	Ea
5415	Structures, Rehabilitation, Rem Portions (S42 of 82022)	7120070	1.000	LSUM
5420	Structures, Rehabilitation, Rem Portions (S46 of 82022)	7120070	1.000	LSUM
5425	Structures, Rehabilitation, Rem Portions (S48 of 82022)	7120070	1.000	LSUM
5430	Structures, Rehabilitation, Rem Portions (S49 of 82022)	7120070	1.000	LSUM

5435	Structures, Rehabilitation, Rem Portions (S50 of 82022)	7120070	1.000	LSUM
5440	Structures, Rehabilitation, Rem Portions (S50-5 of 82022)	7120070	1.000	LSUM
5445	Structures, Rehabilitation, Rem Portions (S50-6 of 82022)	7120070	1.000	LSUM
5450	Structures, Rehabilitation, Rem Portions (S52 of 82022)	7120070	1.000	LSUM
5455	Structures, Rehabilitation, Rem Portions (S55 of 82022)	7120070	1.000	LSUM
5460	Deck Joint, Rem	7120071	1,310.000	Ft
5465	Flushing Cracks, Water	7120098	806.000	Ft
5470	Structural Crack, Repr	7120099	1,428.000	Ft
5475	Top Flanges and Beam Ends, Clean and Coat	7120100	69.000	Syd
5480	Patching Conc, C-L	7120112	91.000	Cyd
5485	Patching Conc, F-L	7120114	8.000	Cyd
5490	Hand Chipping, Full Depth	7122000	342.000	Cft
5495	Bridge Joint, Strip Seal Gland Replacement	7122005	1,836.000	Ft
5500	_ Bridge Joints, Clean and Seal	7127001	3,200.000	Ft
5505	_ Deck, Scaling	7127010	232.000	Sft
5510	_ Hand Chipping, Spec	7127010	540.000	Sft
5515	_ Latex Modified Conc, Spec	7127021	13.000	Cyd
5520	_ Embedded Galvanic Anode, High Performing	7127050	6,097.000	Ea
5525	_ Stud Type Shear Developer	7127050	4,347.000	Ea
5530	_ Stud Type Shear Developer, Rem	7127050	40.000	Ea
5535	_ Structures, Rehabilitation, Rem Portions, Spec (B01 of 82192)	7127051	1.000	LSUM
5540	Beam Plate, Seal Perimeter	7130010	680.000	Ft
5545	Structural Steel, Retrofit, Furn, Fab, and Erect	7130071	7,675.000	Lb
5550	Structural Steel, Welded Repr, Furn, Fab, and Erect	7130072	5,550.000	Lb
5555	Support, Column, Temp	7130080	232.000	Ea
5560	_ Heat Straightening for High Load Hit (S02-3 of 82192)	7137051	1.000	LSUM
5565	_ Heat Straightening for High Load Hit (X03 of 82022)	7137051	1.000	LSUM
5570	Protective Shield, Utility Pipe	7150025	64.000	Ft
5575	Steel Structure, Cleaning, Type 4 (B01 of 82192)	7150045	1.000	LSUM
5580	Steel Structure, Coating, Type 4 (B01 of 82192)	7150046	1.000	LSUM
5585	Steel Structure, Cleaning, Partial, Type 4 (X03 of 82022)	7150047	1.000	LSUM
5590	Steel Structure, Coating, Partial, Type 4 (X03 of 82022)	7150048	1.000	LSUM
5595	Field Repr of Damaged Coating (B01 of 82192)	7160001	1.000	LSUM
5600	Field Repr of Damaged Coating (S28 of 82022)	7160001	1.000	LSUM
5605	_ Joint Sealant	8007001	3,000.000	Ft
5610	Fence, Protective	8080007	5,500.000	Ft
5615	Fence, Structure	8080110	3,730.000	Sft
5620	Fence, Moving	8080120	540.000	Ft
5625	Bridge Sign Connection, Bolt Replacement	8100020	1.000	Ea

5630	Slope Paving Header	8130015	3,648.000	Ft
5635	Slope Paving, Conc	8130020	6,450.000	Syd
5640	_ Slope Protection, Rem	8137011	2,932.000	Syd
5645	_ Limestone Cap	8157001	150.000	Ft
5650	_ Limestone Cap, Reinstall	8157050	2.000	Ea
5655	Structure Survey During Construction	8240020	1.000	LSUM
5660	Structure Survey During Construction (S07 of 82022)	8240020	1.000	LSUM
5665	Structure Survey During Construction (S08 of 82022)	8240020	1.000	LSUM
5670	Structure Survey During Construction (S09 of 82022)	8240020	1.000	LSUM
5675	Structure Survey During Construction (S10 of 82022)	8240020	1.000	LSUM
5680	Structure Survey During Construction (S11 of 82022)	8240020	1.000	LSUM
5685	Structure Survey During Construction (S28 of 82022)	8240020	1.000	LSUM
5690	Structure Survey During Construction (S52 of 82022)	8240020	1.000	LSUM
5695	_ Noise Wall Panel, Adj	8507051	1.000	LSUM

Section: 7

5700	_ Calendar Days of Contract Time for Interim Completion	1027060	61,977.000	Dir
------	---	---------	------------	-----
