

MICHIGAN  
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION  
FOR  
**SIGN SUPPORT REMOVAL**

STM:MTH

1 of 1

APPR:MLO:AJU:02-08-23  
FHWA:APPR:03-03-23

**Delete the first paragraph of subsection 810.03.U, on page 8-52 of the Standard Specifications for Construction in its entirety and replace with the following:**

Remove and salvage Type I signs without damaging the sign. Haul, and stockpile Type I signs at the offsite location required. Coordinate all delivery of salvaged items with the Department contact person at least 72 hours before transporting to the Department property location as shown on the plans or as directed by the Engineer. For Superior Region projects, take ownership of Type I signs rather than salvaging them.

**Delete the second paragraph of subsection 810.03.U, on page 8-52 of the Standard Specifications for Construction in its entirety and replace with the following:**

Take ownership of all cantilever and truss sign supports, column breakaways, bridge connections, remaining signs, supports, and associated attaching or fastening hardware.

**Delete the seventh paragraph of subsection 810.03.U, on pages 8-52 and 8-53 of the Standard Specifications for Construction in its entirety.**