

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
UNACCEPTABLE PLANT REMOVAL

RSD:JLB

1 of 1

APPR:MRB:JN:04-03-20
FHWA:APPR:04-13-20

a. Description. This work consists of removing unacceptable plants in their entirety. Plants will be inspected per subsection 815.03.K of the Standard Specifications for Construction. Remove any plants considered unacceptable as defined in that subsection and identified by the Engineer.

b. Materials. None specified.

c. Construction. Removal of unacceptable plants includes complete removal of the root ball, wire basket, burlap, string, bracing, stakes and guying materials. Flush cutting of plants is prohibited. Repair ruts, voids, depressions, planting holes and turf damage resulting from plant removal and re-establish turf in these areas and where plants were removed in accordance with subsection 816.03 of the Standard Specifications for Construction and as directed by the Engineer.

Removed plants and associated materials are to be disposed of per subsection 815.03.K of the Standard Specifications for Construction.

d. Measurement and Payment. The completed work, as described, will not be paid for separately, but is considered to be included in the cost for providing the original plant material.