

MICHIGAN
DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION
FOR
SOLID-STATE FLASHING BEACON CONTROLLER AND CABINET, SALVAGE

SIG:EMS

1 of 1

APPR:HLO:NJB:04-29-20
FHWA:APPR:05-06-20

a. Description. This work consists of removing, storing, and re-installing a solid state flashing beacon controller and cabinet, including removal and installation of mounting brackets, surge protection, hardware, fittings, wiring, grounding, conduits, and other associated materials as required to ensure a complete removal and installation, at locations shown on the plans. This work includes disposal of removed material not re-installed on the project.

b. Materials. Provide materials, as directed by the Engineer, necessary to provide a complete and operating installation. Provide materials in accordance with sections 918 and 921 of the Standard Specifications for Constructions and this special provision.

c. Construction. Remove and re-install the solid state flashing beacon controller and cabinet, and associated materials, in accordance with sections 819 and 820 of the Standard Specifications for Construction, as shown on the plans, and as directed by the Engineer. Store the solid state flashing beacon controller and cabinet, and associated materials, to be re-installed on the project in a clean and protected environment. Dispose of all materials not re-installed on the project in accordance with section 204 of the Standard Specifications for Construction.

d. Measurement and Payment. The completed work, as described, will be measured and paid for at the contract unit price using the following pay item:

Pay Item**Pay Unit**

Flsh Beacon, Controller and Cabinet, Solid State, SalvEach