Pavement Demonstration Program Project Finalization Full-Depth Reconstructed Perpetual Hot Mix Asphalt Pavement – M-84 & I-96 (MDOT Job Numbers 31804 & 52803)

Final Technical Report

Prepared by:

Zhanping You, Ph.D., P.E. Lei Yin, Research Assistant Syed Waqar Haider, Ph.D., P.E Dongzhao Jin, Ph.D. Kwadwo Ampadu Boateng, Research Assistant

MTUengineering

CIVIL, ENVIRONMENTAL, AND GEOSPATIAL ENGINEERING

> Michigan Technological University 1400 Townsend Drive Houghton, MI 49931

> > Submitted to:

Michigan Department of Transportation 8885 Ricks Road Lansing, MI 48909

Report No. OR23-304, D

July 2024

TECHNICAL REPORT DOCUMENTATION PAGE

1. Report No.	2. Government Accession No.	3. Recipient's Catalog No.	
OR23-304, D	N/A	N/A	
4. Title and Subtitle	5. Report Date		
Pavement Demonstration Program Project	July 2024		
Full-Depth Reconstructed Perpetual Hot M	6. Performing Organization Code		
(MDOT Job Numbers 31804 & 52803)		N/A	
7. Author(s)		8. Performing Organization Report No.	
Zhanping You, Lei Yin, Syed W. Haider	, Dongzhao Jin, Kwadwo Ampadu	N/A	
Boateng			
9. Performing Organization Name and Address		10. Work Unit No.	
Michigan Technological University		N/A	
1400 Townsend Drive,		11. Contract or Grant No.	
Houghton, MI 49931-1295	Contract 2022-0432:Z1		
12. Sponsoring Agency Name and Address	5	13. Type of Report and Period Covered	
Michigan Department of Transportation (M	ADOT)	Final Report, 03/20/2023 -08/31/2024	
Research Administration			
8885 Ricks Road	14. Sponsoring Agency Code		
P.O. Box 33049	N/A		
Lansing, Michigan 48909			
15. Supplementary Notes			

Conducted in cooperation with the U.S. Department of Transportation, Federal Highway Administration. MDOT research reports are available at <u>www.michigan.gov/mdotresearch</u>.

16. Abstract

Pavement demonstration projects are used to evaluate their long-term performance and applicability as a Michigan Department of Transportation (MDOT) standard practice. This document provides a comprehensive report on the "Full-Depth Reconstructed Perpetual HMA Pavement" on M-84 southbound (SB) (MDOT job number 31804) and I-96 westbound (WB) (MDOT job number 52803). These projects were both completed in the fall of 2005. The pavement structures are comprised of hot mix asphalt (HMA) layers with total thickness of 6.5- and 14-inches for M-84 SB and I-96 WB, respectively. The design life for both projects was 40 years, designed so that the strain at the bottom of the HMA layer is lower than its endurance limit to prevent fatigue cracking. Typically, MDOT HMA reconstruction is designed with a 20-year design life with no specific emphasis on the endurance limit. M-84 SB exhibits acceptable pavement condition, with minor longitudinal cracking and IRI showing a stable annual increase rate. Coring and Falling Weight Deflectometer (FWD) data confirm adequate construction quality, and the perpetual section performs better in preventing bottom-up cracking than the standard section in NB. Despite the higher incidence of recorded transverse cracking in the M-84 SB perpetual section compared with the NB standard section in recent years, the transverse cracking appears to be limited to the surface. I-96 WB displays excellent overall performance, with both local and express lanes showing low incidences of cracking and potholes. However, it is important to note that certain deterioration related to construction quality was observed, such as cracks around the longitudinal joints between lanes and shoulders. Furthermore, Ground Penetrating Radar (GPR) tests revealed that thickness is insufficient at some locations. These issues emphasize the importance of construction quality control. The data derived from these projects provide cost and performance insights. These findings serve as valuable guides for future perpetual pavement projects.

FFFF					
17. Key Words		18. Distribution Statement			
Perpetual pavement; full-depth reconstruction; HMA overlay;		No restrictions. This document is also available to the			
distress; performance analysis, cost analysis; maintenance		public through the Michigan Department of Transportation.			
20. Security Classif. (of this page)		21. No. of Pages	22. Price		
Unclassified		128	N/A		
	MA overlay; intenance 20. Security (Unclassified	Image: MA overlay; intenance18. Distribution Statem No restrictions. This do public through the Micl20. Security Classif. (of this page) Unclassified	18. Distribution StatementMA overlay;No restrictions. This document is also avail public through the Michigan Department of20. Security Classif. (of this page)21. No. of Pages 128		

Form DOT F 1700.7 (8-72)

Reproduction of completed page authorized

Disclaimer

This report is disseminated to facilitate information exchange. The Michigan Department of Transportation (referred to as MDOT hereafter) explicitly denies any form of liability, regardless of nature or cause, that may arise from the use of this document or the information and data presented within it. MDOT also takes no responsibility for typographical errors or the accuracy of the information included in this content. MDOT does not provide any warranties or assurances regarding the quality, substance, comprehensiveness, suitability, sufficiency, order, accuracy, or timeliness of the provided information and data. Moreover, MDOT does not assert that the contents establish standards, specifications, or regulations.

Acknowledgments

The research work was sponsored by the Michigan Department of Transportation (MDOT). The authors extend their gratitude for the direction and engagement of Justin Schenkel, Andre Clover, Michael Eacker, Fawaz Kaseer, and Kevin Kennedy, all affiliated with MDOT. Additionally, the authors acknowledge Emily Kastamo for her role as the English editor for this report.

Disclaimer	III
Acknowledgments	III
Table of Contents	IV
List of Tables	V
List of Figures	VII
Introduction	1
Project Description	1
Traffic Data Assessment and ESAL Estimation	
Pavement Design and Distress Prediction	
Construction and Quality Control	
Pavement Condition Data Analysis	
Pavement Condition Survey Findings	
Performance Comparison and Evaluation	
Cost Comparison and Evaluation	
Conclusions and Recommendations	
References	
Appendix A: Proposed Pavement Construction Plans	
Appendix B: Traffic Data	
Appendix C: Pavement Design Data	74
Appendix D: Pre- and Post-Construction Related Records	
Appendix E: Field Evaluation Reports	
Appendix F: Field Evaluation Figures	

Table of Contents

List of Tables

Table 1. M-84 pavement cross-section	2
Table 2. I-96 WB pavement cross-section	3
Table 3. Traffic parameters for different pavement design methods	4
Table 4. Traffic data for the M-84 and I-96 original pavement designs	5
Table 5. M-84 and I-96 ESAL for 1993 AASHTO pavement design method	5
Table 6. Truck vehicle classification normalized volume distribution for the M-84 and I-	-96
projects	7
Table 7. TF calculation process using ME traffic and load distribution	8
Table 8. Calculated ESAL for simplistic ME method	9
Table 9. Traffic data for the M-84 project from TDMS	10
Table 10. Traffic data for the I-96 project from TDMS	10
Table 11. Simplistic ME method design parameters for the M-84 project	12
Table 12. Simplistic ME method design limiting criteria for the M-84 project	12
Table 13. Simplistic ME method design results for the M-84 project	14
Table 14. Simplistic ME method design parameters for the I-96 project	15
Table 15. Simplistic ME method design limiting criteria for the I-96 project	15
Table 16. MEPDG method design parameters for the I-96 project	16
Table 17. MEPDG design limiting criteria for the I-96 project	17
Table 18. Simplistic ME method design prediction results for the I-96 project	17
Table 19. Summary of distress predictions using ME-based methods for the I-96 project	18
Table 20. Soil classification summary of the I-96 WB samples	21
Table 21. Yearly progression of IRI, rutting, and DI for the M-84 project	29
Table 22. M-84 pavement DI per 0.1 mile in 2018	31
Table 23. Yearly Progression of IRI, rutting, and DI for the I-96 WB project	33
Table 24. I-96 WB pavement DI per 0.1 mile in 2019	35
Table 25. Summary of the M-84 perpetual demonstration program status reports	36
Table 26. Yearly cracking and pothole distress for the M-84 project	38
Table 27. Core cracking average results of the M-84 project	40
Table 28. Summary of the I-96 perpetual demonstration program status reports	41
Table 29. Yearly cracking and pothole distress for the I-96 project	42

Table 30. Estimated initial cost for the M-84 SB perpetual pavement, 40-year design life per uni
prices
Table 31. Estimated initial cost for the M-84 standard pavement, 20-year design life per unit prices
Table 32. Estimated initial cost for the I-96 WB perpetual pavement, 40-year design life per uni
prices
Table 33. Estimated initial cost for the I-96 standard pavement, 20-year design life per unit prices
Table 34. Initial paving cost per year of service life

List of Figures

Figure 1. M-84 project location
Figure 2. I-96 WB project location
Figure 3. 2004 to 2044 per year ESAL for the M-84 project using 1993 AASHTO design 6
Figure 4. 2006 to 2046 per year ESAL for the I-96 project using 1993 AASHTO design
Figure 5. Axle load weight distribution for the M-84 project7
Figure 6. Axle load weight distribution for the I-96 project
Figure 7. Comparison between TDMS measurements versus predicted two-way CAADT for the
M-84 project
Figure 8. Comparison between TDMS measurements versus predicted two-way CAADT for the
I-96 project
Figure 9. Limiting modulus criteria of unbound aggregate base and subbase layers
Figure 10. I-96 Original AASHTO 1993 pavement design, 40 years Cross-Section 14
Figure 11. Percent of compaction for different M-84 SB pavement layers
Figure 12. Moisture for different M-84 SB pavement layers 19
Figure 13. Stiffness and modulus for M-84 SB aggregate base layer
Figure 14. Average maximum deflection data for the M-84 NB inside lane
Figure 15. Average maximum deflection data for the M-84 NB outside lane
Figure 16. HMA thickness along the distance for the M-84 NB standard pavement
Figure 17. HMA thickness distribution for the M-84 NB standard pavement
Figure 18. HMA thickness along the distance for the M-84 SB perpetual pavement
Figure 19. HMA thickness distribution for the M-84 SB perpetual pavement
Figure 20. HMA thickness along the distance for the I-96 WB express lane section
Figure 21. HMA thickness distribution for the I-96 WB express lane section
Figure 22. HMA thickness along the distance for the I-96 WB local lane section
Figure 23. HMA thickness distribution for the I-96 WB local lane section
Figure 24. Lane configuration for M-84 SB, Google Maps Image, 2023 27
Figure 25. Lane configuration for I-96 WB, Google Maps Image, 2023
Figure 26. Yearly IRI data for the M-84 project
Figure 27. Yearly rutting data for the M-84 project
Figure 28. Yearly DI data for the M-84 project

Figure 29. DI per 0.1 mile along the M-84 project	32
Figure 30. Yearly IRI data for the I-96 WB project	33
Figure 31. Yearly rutting data for the I-96 WB project	
Figure 32. Yearly DI data for the I-96 WB project	
Figure 33. DI per 0.1 mile along the I-96 WB express section	35
Figure 34. Yearly transverse cracking per lane-mile of the M-84 project	38
Figure 35. 2020 coring locations for the M-84 project	39
Figure 36. Example of coring location and sample condition in M-84 SB coring	39
Figure 37. M-84 corrected subgrade resilient modulus	40
Figure 38. Comparison on M-84 DI trends with fix life of standard pavement	
Figure 39. Comparison on M-84 DI trend with service life of standard pavement	44
Figure 40. Comparison on I-96 DI trends with fix life of standard pavement	45
Figure 41. Comparison on I-96 DI trend with service life of standard pavement	45
Figure 42. Comparison between perpetual and standard HMA pavement	46
Figure 43. JN 31804A project location for the M-84 project	53
Figure 44. JN 31804A existing cross-sections for the M-84 project	54
Figure 45. JN 31804 typical cross-section for the M-84 SB perpetual and NB standard p	pavement
project	55
Figure 46. JN 52803 project location for the I-96 perpetual pavement project	56
Figure 47. JN 52803 typical cross-section for the I-96 perpetual pavement project	57
Figure 48. Office memorandum on M-84 traffic information, page 1	58
Figure 49. Office memorandum on M-84 traffic information, page 2	59
Figure 50. Office memorandum on M-84 traffic information, page 3	60
Figure 51. Office memorandum on M-84 traffic information, page 4	61
Figure 52. Office memorandum on M-84 traffic information, page 5	62
Figure 53. Office memorandum on M-84 traffic information, page 6	63
Figure 54. Office memorandum on M-84 traffic information, Page 7	64
Figure 55. Office memorandum on M-84 traffic information, Page 8	65
Figure 56. Office memorandum on I-96 traffic information, page 1	66
Figure 57. Office memorandum on I-96 traffic information, page 2	67
Figure 58. Office memorandum on I-96 traffic information, page 3	68

Figure 59. Office memorandum on I-96 traffic information, page 4
Figure 60. Office memorandum on I-96 traffic information, page 5
Figure 61. I-96 ESAL estimation using traffic and load distribution, page 1
Figure 62. I-96 ESAL estimation using traffic and load distribution, page 272
Figure 63. I-96 ESAL estimation using traffic and load distribution, page 373
Figure 64. M-84 Original AASHTO 1993 pavement design, 20 years
Figure 65. M-84 Estimated AASHTO 1993 pavement design, 40 years75
Figure 66. I-96 Original AASHTO 1993 pavement design, 20 years
Figure 67. I-96 Estimated AASHTO 1993 pavement design, 40 years
Figure 68. Sand subbase average repeated load resilient modulus test results extracted from LTPP
database for I-96 ME-based designs
Figure 69. Aggregate base (21AA) average repeated load resilient modulus test results extracted
from LTPP database for I-96 ME-based designs
Figure 70. HMA surface and leveling course layers monthly average dynamic modulus values per
Witczak dynamic modulus regression equation for ME-based designs
Figure 71. HMA base course layer (upper portion) monthly average dynamic modulus values per
Witczak dynamic modulus regression equation for ME-based designs
Figure 72. Moisture and density determination on M-84 SB HMA-top layer, page 1 80
Figure 73. Moisture and density determination on M-84 SB HMA-top layer, page 2
Figure 74. Moisture and density determination on M-84 SB HMA-top layer, page 3 82
Figure 75. Moisture and density determination on M-84 SB HMA-top layer, page 4
Figure 76. Moisture and density determination on M-84 SB HMA-leveling layer, page 1 84
Figure 77. Moisture and density determination on M-84 SB HMA-leveling layer, page 2
Figure 78. Moisture and density determination on M-84 SB HMA-leveling layer, page 3
Figure 79. Moisture and density determination on M-84 SB HMA-leveling layer, page 4 87
Figure 80. Moisture and density determination on M-84 SB HMA-base layer, page 1
Figure 81. Moisture and density determination on M-84 SB HMA-base layer, page 2
Figure 82. Moisture and density determination on M-84 SB aggregate base layer
Figure 83. Moisture and density determination M-84 SB subgrade (embankment), page 1 91
Figure 84. Moisture and density determination M-84 SB subgrade (embankment), page 2 92
Figure 85. Moisture and density determination M-84 SB subgrade (embankment), page 3 93

Figure 86. Moisture and density determination on M-84 SB subbase, page 1	4
Figure 87. Moisture and density determination on M-84 SB subbase, page 2	5
Figure 88. Moisture and density determination on M-84 SB subbase, page 3 9	6
Figure 89. Moisture and density determination on M-84 SB subbase, page 4	7
Figure 90. Soil stiffness and Young's modulus results on M-84 SB aggregate base layer	8
Figure 91. Office memorandum on I-96 soil recommendations, page 1	9
Figure 92. Office memorandum on I-96 soil recommendations, page 2 10	0
Figure 93. Office memorandum on I-96 soil recommendations, page 3 10	1
Figure 94. Sample identification note on I-96 WB existing soil 10	2
Figure 95. Moisture and density determination on I-96 WB existing subbase 10	3
Figure 96. Field permeability data on I-96 WB existing subbase 104	4
Figure 97. Aggregate inspection report on I-96 WB existing subbase 10.	5
Figure 98. Subgrade soil information for the I-96 WB project, page 1 10	б
Figure 99. Subgrade soil information for the I-96 WB project, page 2 10	7
Figure 100. Stabilized subgrade soil information for the I-96 WB project, page 1 10	8
Figure 101. Stabilized subgrade soil information for the I-96 WB project, page 2 10	9
Figure 102. Reclaimed (existing) subbase material information for I-96 WB, page 1 11	0
Figure 103. Reclaimed (existing) subbase material information for I-96 WB, page 211	1
Figure 104. Reclaimed (existing) subbase material information for I-96 WB, page 3 11	2
Figure 105. Field evaluation report of M-84 in 2022, page 1 11	3
Figure 106. Field evaluation report of M-84 in 2022, page 2 114	4
Figure 107. Field evaluation report of I-96 in 2022, page 1 11.	5
Figure 108. Field evaluation report of I-96 in 2022, page 2 11	6
Figure 109. Field evaluation of M-84 on 07-14-2005 11	7
Figure 110. Field evaluation of M-84 on 01-28-2010 11	7
Figure 111. Field evaluation of M-84 on 11-22-2010 11	8
Figure 112. Field evaluation of M-84 on 12-08-2011 11	8
Figure 113. Field evaluation of M-84 on 12-18-2012 11	9
Figure 114. Field evaluation of M-84 on 12-04-2013 11	9
Figure 115. Field evaluation of M-84 on 12-23-2014 12-	0
Figure 116. Field evaluation of M-84 on 12-16-2015 12	0

Figure 117. Field evaluation of M-84 on 12-21-2016	. 121
Figure 118. Field evaluation of M-84 on 04-24-2018	. 121
Figure 119. Field evaluation of M-84 on 04-01-2019	. 122
Figure 120. Field evaluation of M-84 on 04-22-2020	. 122
Figure 121. Field evaluation of M-84 on 05-03-2021	. 123
Figure 122. Field evaluation of M-84 on 01-23-2022	. 123
Figure 123. Field evaluation of I-96 on 10-07-2005	. 124
Figure 124. Field evaluation of I-96 on 11-09-2007	. 124
Figure 125. Field evaluation of I-96 on 02-03-2010	. 125
Figure 126. Field evaluation of I-96 on 11-23-2010	. 125
Figure 127. Field evaluation of I-96 on 12-20-2013	. 126
Figure 128. Field evaluation of I-96 on 12-11-2014	. 126
Figure 129. Field evaluation of I-96 on 11-21-2016	. 127
Figure 130. Field evaluation of I-96 on 03-25-2019	. 127
Figure 131. Field evaluation of I-96 on 05-04-2020	. 128
Figure 132. Field evaluation of I-96 on 04-21-2021	. 128

Introduction

Public Act 457 of 2016, MCL 247.651h, contains what is referred to as the pavement life-cycle law. This law requires the Michigan Department of Transportation (MDOT) to conduct a life-cycle cost analysis (LCCA) on projects with pavement costs of \$1.5 million or more. The LCCA process is a tool to select the lowest-cost pavement design over the expected service life of the pavement. By law, the LCCA process must include historical information for initial construction and maintenance costs and performance (service life). This information is unavailable for new pavement design types and technologies. Thus, it cannot be used in the pavement selection process until substantial information has been obtained. Accordingly, Public Act 457 of 2016, MCL 247.651i, the pavement demonstration law provides a means for trying new and innovative ideas through demonstration projects. These demonstration projects are not subject to an LCCA process. Pavement demonstration outcomes are intended to increase service life, improve pavement condition, improve ride quality, and/or lower service life costs. Future LCCAs may utilize the cost, performance, and maintenance information from the demonstration projects. Selection of candidate projects is collaborative among MDOT Construction Field Services pavement personnel, MDOT region personnel, and paving industry groups. Once the demonstration project is identified, it goes to MDOT's Engineering Operations Committee for formal approval. Once approved, the project becomes part of the Pavement Demonstration Program. All costs for the demonstration project are funded by the respective MDOT region's rehabilitation and reconstruction template budget. These projects are monitored until a final decision is made regarding the suitability of adopting them as MDOT standard practice. This report evaluates two projects for the "Full-Depth Reconstructed Perpetual Hot Mix Asphalt Pavement" pavement demonstration fix type on the M-84 southbound (SB) in Bay/Saginaw County, MDOT job number 31804, and the I-96 westbound (WB) in Wayne County, MDOT job number 52803.

Project Description

This report covers two full-depth reconstructed perpetual Hot Mix Asphalt (HMA) pavement projects: (1) the M-84 SB reconstruction project and (2) the I-96 WB reconstruction project. The M-84 SB project is a non-freeway, low-traffic-volume route, while the I-96 WB project is a hightraffic-volume route consisting of freeway express and local lane sections. The pavement construction plans for the two projects are shown in Appendix A, Figures 43-47. The two projects were designed using the "perpetual pavement" concept, intended to prohibit bottom-up cracking and constrain distress to the surface so that only surface repairs are needed, and subsequent fulldepth major fixes (rehabilitation or reconstruction) are delayed. Accordingly, both projects utilized a design life of 40 years to achieve a service life of at least 50 years. In contrast, MDOT standard practice is to use a 20-year design life for full-depth HMA reconstruction with a current service life estimated at 37 years. The design life of a pavement refers to the theoretical duration until a subsequent major reconstruction or rehabilitation is required, excluding any maintenance, serving as the basis for pavement design. Conversely, the service life pertains to the life cycle of the pavement, encompassing the estimated duration until a major reconstruction or rehabilitation is needed, including maintenance events. A component of the service life is its initial fix life projection, which is the duration until a subsequent major reconstruction or rehabilitation would

be required, excluding any maintenance. However, unlike design life, service and fix life are estimated per the measured data of in-service pavements.

The M-84 project was constructed over three years from 2003 to 2005, consisting of both the northbound (NB) and SB directions, where the SB lanes were designed as perpetual HMA reconstruction and the NB lanes as standard HMA reconstruction. The SB lanes were completed in the fall of 2005, whereas the NB lanes were completed in 2004. This project spans approximately 3 miles from Pierce Road to 1000 feet south of Delta Road in Saginaw County as shown in Figure 1. Note that the subsections shown in Figure 1 are for location milepoint identifiers and were not monitored separately or uniquely constructed. The existing two-lane M-84 road was converted into a four-lane boulevard section (two lanes in each direction), featuring a 5-lane configuration (two lanes in each direction and a middle lane) at the starting and ending locations. The SB cross-section consisted of 6.5 inches of HMA over 12 inches of dense-graded aggregate base (DGAB) over 13.5 inches of sand subbase. This design incorporated polymer-modified asphalt binder and a thicker unbound aggregate base for enhanced durability and reduced maintenance needs. In comparison, NB M-84 utilized a standard pavement cross-section, consisting of 6.5 inches of HMA over 18 inches of sand subbase. Table 1 details the pavement cross-section for both bounds on M-84.

The I-96 project completed construction in the fall of 2005, where the WB was designed as perpetual HMA reconstruction. This project includes the local and express lanes over approximately 2 miles from Schaefer Road to M-39/Southfield Freeway in Wayne County as shown in Figure 2. Both the local and express sections consist of three lanes each. Both WB sections consist of 14 inches of HMA over 16 inches of open-graded drainage course (OGDC) over 8 inches of sand subbase. The existing clay subgrade was stabilized with lime to a depth of 12 inches. Apart from the increased pavement thickness compared with standard HMA pavement, this project included Gap Graded Superpave (GGSP) (currently known as Stone Matrix Asphalt (SMA)) with polymer modified binder to improve cracking and rutting resistance. Additionally, to improve longitudinal joint density, the middle and right lanes were paved simultaneously with echelon paving, where two pavers placed asphalt pavement side-by-side. Table 2 details the pavement cross-section on WB I-96.

	M-84 SB (perpetual)			M-84 NB (standard)		
Layer	Thickness (inch)	Material Type	Binder PG	Thickness (inch)	Material Type	Binder PG
Top HMA course	1.5	5E3	70-28P*	1.5	5E3	70-28
Leveling HMA course	2	4E3	70-28P*	2	4E3	70-28
Base HMA course	3	3E3	70-28P*	3	3E3	58-22
Base	12	DGAB	-	6	DGAB	-
Subbase	13.5	Sand	-	18	Sand	-
Subgrade	-	Existing Clay Soils	-	-	Existing Clay Soils	-

Table 1. M-84 pavement cross-section

* "P" refers to polymer-modified.

Lovon	I-96 WB (local and express lanes)				
Layer	Thickness (inch)	Material Type	Binder PG		
Top HMA course	1.5	GGSP	76-22P*		
Leveling HMA course	2.5	4E30	76-22P*		
Base HMA course	10	3E30	70-22P*		
Base	16	OGDC	-		
Separator	-	Geotextile separator-fabric	-		
Subbase	8	Sand	-		
Subgrade	12	Clay stabilized with lime	-		

Table 2. I-96 WB pavement cross-section



Note: Using Version 23 of the PR (Physical Road) framework Figure 1. M-84 project location



Note: Using Version 23 of the PR framework Figure 2. I-96 WB project location

Traffic Data Assessment and ESAL Estimation

Pavement structure design heavily relies on traffic data, given its significant role in determining pavement performance and durability. This section will summarize the traffic data used for the original pavement designs as detailed in the 2003 MDOT report, *Pavement Structural Design Recommendations for Reconstruction and Widening of M-84* [1] and 2004 MDOT report, *Pavement Structural Analysis of the Design Recommendations for Reconstructing I-96 (M-39 to Schaeffer Road)* [2]. Both demonstration projects utilized and compared mechanistic-empirical (ME) based pavement design and the 1993 AASHTO empirical pavement design method. The design methods and their required traffic type parameters are listed in Table 3. The traffic data used for all pavement design methods is listed in Table 4.

Table 3. Traffic	parameters	for	different	pavement	design	methods
------------------	-------------------	-----	-----------	----------	--------	---------

Design Method	Traffic Parameter	Design Method Used in Original Analysis	
1993 AASHTO	ESAL, calculated using typical	M 84 and I 06	
pavement design	truck factor	WI-84 and 1-90	
	ESAL, calculated using typical		
Simplistic ME method	truck factor or traffic and load	M-84 and I-96	
	distribution		
MEDDC	CAADT, traffic, and axle load	I Qé	
MEPDO	distribution	1-90	

* ESAL: Equivalent Single Axle Load,

CAADT: Commercial Average Annual Daily Traffic, MEPDG: Mechanistic-Empirical Pavement Design Guide

Parameter	M-84	I-96
Annual Average Daily Traffic (AADT), both directions (Year Collected)	12,900 (2003)	191,800 (2005)
CAADT, both directions (Year Collected)	451 (2003)	9,600 (2005)
Traffic growth rate, compound	1.3%	2.0%

Table 4. Traffic data for the M-84 and I-96 original pavement designs

The estimated ESAL for the 1993 AASHTO design method was calculated using the equation below:

$$ESAL_{Estimated} = CAADT \times 365 \times DD \times LD \times TF \times GF$$

Where:

TF = Truck factor; DD = Directional Distribution Factor; LD = Lane Distribution Factor; GF = growth factor, $[(1+g)^n - 1]/g$ g = growth rate expressed as a decimal n = number of years

Table 5 show the resulting $ESAL_{Estimated}$ for the 1993 AASHTO pavement design method for the two projects. Note that the 40-year design ESAL for M-84 is estimated because there is no record of this value, and it was not specifically used as part of the report for the original pavement design [1]. Details of the calculation are shown in Appendix B, Figures 48 to 55 for M-84, Figures 56-60 for I-96.

Table 5. M-84 and I-96 ESAL for 1993 AASHTO pavement design method

Project	TF	DD	LD	Initial Annual ESAL (two-way)	ESAL (20 years)	ESAL (40 years)
M-84	0.77	0.50	0.80	126,870	1,150,650	2,640,000
I-96	0.68	0.56	0.70	2,382,720	22,694,400	56,400,000

Figures 3 and 4 depict the results of per-year ESAL calculations using the 1993 AASHTO pavement design method for M-84 and I-96, respectively.



Figure 3. 2004 to 2044 per year ESAL for the M-84 project using 1993 AASHTO design



Figure 4. 2006 to 2046 per year ESAL for the I-96 project using 1993 AASHTO design

For the ME design methods, the truck class and axle load distributions are needed in addition to the traffic data shown in Table 4. Table 6 shows the truck vehicle classification normalized volume distribution for the M-84 project in 2003 and the I-96 project in 2005. For the M-84 project, the original analysis utilized estimated values from MDOT and adjusted them relative to the MEPDG global default values for Truck Traffic Classification (TTC) group 16 (as derived from the Long-Term Pavement Performance (LTPP) pavement sections). This group is described as predominantly single-unit trucks. While for the I-96 project, the TTC group 3 was assumed for this roadway, which is described as predominantly single-trailer trucks.

Truck Vehicle	Normalized Volume Distribution, %			
Classification	M-84 (in 2003)	I-96 (in 2005)		
4	10.0	0.90		
5	17.2	11.6		
6	13.6	3.6		
7	1.0	0.2		
8	18.3	6.7		
9	17.0	62.0		
10	2.8	4.8		
11	0.6	2.6		
12	0.1	1.4		
13	19.4	6.2		

 Table 6. Truck vehicle classification normalized volume distribution for the M-84 and I-96 projects

Figure 5 shows the load distribution of single, tandem, and tridem axles for the M-84 project. Figure 6 shows the corresponding distribution for the I-96 project.



(c) Tridem axle load Figure 5. Axle load weight distribution for the M-84 project



Figure 6. Axle load weight distribution for the I-96 project

In addition to the MEPDG load and distribution data, the simplistic ME procedure requires a unique ESAL calculated per the load and distribution data (as shown in Table 6, Figures 5 and 6). For the M-84 project, the ME initial year ESAL in both directions ($ESAL_{InitialY}$) was estimated to be 220,602, while for the I-96 project, this was estimated to be 4,411,425. The calculations for $ESAL_{InitialY}$ are shown in Appendix B, Figures 61-63. Note that the detailed calculation process for the M-84 $ESAL_{InitialY}$ were not provided in the original pavement designs so M-84 calculations are estimated for this report. Accordingly, the TF for the M-84 and I-96 projects was separately computed as 1.340 and 1.259 using the $ESAL_{InitialY}$. The TF calculation process is presented in the equation below. Table 7 provides a summary of the $ESAL_{InitialY}$ and TF values for M-84 and I-96 projects.

$$TF = ESAL_{InitialY} / (CAADT \times 365)$$

T.LL. 5	1 . 1 . 4	• • • • • •	N ATT	4			1. 4 .1. 4.
l able 7	calculation	process using	NE	trattic at	na io	ad	distribution

Project	CAADT	Initial year ESALs (ESAL _{Initialy})	TF
M-84	451	220,602	1.340
I-96	9600	4,411,425	1.259

The ME ESAL values per 20- and 40-year design periods were calculated for the M-84 and I-96 projects using the equation below. The results are shown in Table 8. It should be noted that the DD and LD percentages match those used for the 1993 AASHTO pavement design (as shown in

Table 5), except for the M-84 design, where it was increased from 0.50 to 0.55. Notably, the ME ESAL values are nearly twice those employed in the 1993 AASHTO pavement design. This may be due to the different truck types in Michigan compared to those from the global database, or because a different TTC may have been better suited to represent the traffic. As a result, the ME ESAL values were not used for the I-96 simplistic ME design likely due to this difference. Instead, the I-96 simplistic ME design used the AASHTO 1993 ESAL values. While the M-84 pavement design continued to use the ME ESAL values, it did not use the 40-year value as part of the report for the original pavement design [1]. Therefore, in Table 8, the values not used in the original pavement design reports are estimated for informational purposes.

$ESAL = ESAL_{InitialY} \times DD \times LD \times GF$

Project	DD	LD	ESAL _{InitialY}	Growth rate (g)	ESAL (20 years)	ESAL (40 years)
M-84	0.55	0.80	220,602	1.3%	2,230,000	5,113,000*
I-96	0.56	0.70	4,411,425	2.0%	42,017,000*	104,452,000*

Table 8. Calculated ESAL for simplistic ME method

* Estimated since these were not used for original pavement designs

Since the future projections of traffic data used for the original designs were estimated for the pavement design period, assumptions such as growth rate may be inconsistent with actual conditions, potentially leading to inaccurate traffic predictions. Therefore, the actual measured traffic data will be compared with these traffic estimations and predictions. The actual measured traffic data was obtained from the MDOT Transportation Data Management System (TDMS) within the project limits, specifically TDMS location number 73-0585, located north of Pierce Road (around the south end of the project) for M-84, and TDMS location number 82-5577, located 0.5 mile west of Schaefer/Grand River Ave for I-96. Note that the I-96 TDMS measurements include traffic data for both express and local lanes. The traffic information for the two projects is shown in Tables 9 and 10. The TDMS data measurement positions are on the project routes. The comparison between the TDMS recorded traffic data and the traffic for design is shown in Figures 7 and 8.

The results show that the traffic estimates for both M-84 and I-96 projects were overestimated in the design period. Accordingly, if the future TDMS traffic continues to be lower relative to the estimated prediction, then there is a decreased risk of unanticipated pavement distress and potential improvement in the anticipated service life. It is worth noting that there has been a notable decrease in recorded CAADT in the year 2020, likely due to the COVID-19 pandemic. Since that time, a gradually increasing trend has been observed for both projects. Still, it should be noted that commercial traffic is largely estimated since it is not measured as frequently as the total AADT, so it is typically an assumed percentage of the total AADT. For M-84, the initial design estimated that commercial traffic was 3.5% of AADT, whereas for I-96, it is estimated to be 5%. Whereas, for the actual percentage of commercial traffic, this is estimated to be between 1.6% to 2.1% for M-84 and 3.5% to 6.7% for I-96. If the highest rate of commercial traffic percentage is used, then the measured values, while still lower for most years, are much closer to the estimated design values.

	2-Way			SB
Year	AADT	CAADT (FHWA Class 4 and above)	AADT	CAADT (FHWA Class 4 and above)
2023	14,885	312	7,528	159
2022	14,508	306	7,337	156
2021	18,210	309	N/A	N/A
2020	16,002	272	N/A	N/A
2019	20,027	340	N/A	N/A
2018	20,128	342	N/A	N/A
2017	20,128	337	N/A	N/A
2016	19,909	328	N/A	N/A
2015	19,292	N/A	N/A	N/A
2014	17,388	326	N/A	N/A
2013	16,980	318	N/A	N/A
2012	16,762	311	N/A	N/A
2011	17,277	307	N/A	N/A

 Table 9. Traffic data for the M-84 project from TDMS

Table 10. Traffic data for the I-96 project from TDMS

		2-Way	WB		
Year	AADT	CAADT	AADT	CAADT	
	AADI	(FHWA Class 4 and above)		(FHWA Class 4 and above)	
2023	131,193	8,134	69,208	4,291	
2022	117,215	7,267	64,918	4,025	
2021	111,396	6,907	54,253	N/A	
2020	128,168	7,946	66,331	N/A	
2019	147,945	9,912	73,437	N/A	
2018	148,688	9,962	73,806	N/A	
2017	162,406	9,852	81,241	N/A	
2016	146,000	7,931	N/A	N/A	
2015	N/A	N/A	N/A	N/A	
2014	135,680	7,683	N/A	N/A	
2013	132,500	5,553	N/A	N/A	
2012	115,800	5,428	N/A	N/A	
2011	112,400	5,306	N/A	N/A	
2010	137,500	5,295	N/A	N/A	
2009	144,700	5,091	N/A	N/A	
2008	160,800	6,690	N/A	N/A	



Figure 7. Comparison between TDMS measurements versus predicted two-way CAADT for the M-84 project



Figure 8. Comparison between TDMS measurements versus predicted two-way CAADT for the I-96 project

Pavement Design and Distress Prediction

As introduced in the previous section, the AASHTO 1993 and ME-based pavement design methods were employed to evaluate the original HMA perpetual pavement design for the M-84 and I-96 projects per the MDOT pavement design development reports [1-2]. Therefore, the traffic-related parameters for pavement design will not be repeated in this section; instead, it will detail the remaining design aspects. M-84 pavement design aspects will be described first, followed by I-96.

The result of the 1993 AASHTO pavement design for the M-84 project using a 20-year design life (per ESAL of 1,150,650) is 6-inches of HMA over 6-inches of aggregate base over 18-inches of sand subbase, See Appendix C, Figure 64 for more details. This design utilizes the MDOT standards of that time for structural and drainage coefficients.

The layer and general design parameters used for the ME-based, simplistic design for the M-84 HMA perpetual pavement are shown in Table 11. These values were estimated per test results of typical HMA and unbound materials of LTPP projects at that time. Accordingly, the model and associated design criteria limits are shown in Table 12 and Figure 9. The figure shows the graph used to determine the modulus ratio between two adjacent unbound pavement layers. This assumes that the long-term in-place modulus of unbound base and subbase layers are dependent on the modulus of the supporting layer due to potential loss of compaction. This is based on each layer's thickness and the supporting layer's modulus.

Table 11.	Simplistic	ME method	design	parameters fo	r the	M-84 project
	-		-	-		- •

Layer/Property	Value/Estimation
Tire pressure	120 psi (827 kPa)
Tire load	4,500 lbs (20kN) per tire
Sand subbase	Resilient modulus = $12,000$ psi; Poisson's ratio = 0.40
Aggregate base	Resilient modulus = 25,000 psi; Poisson's ratio = 0.35
НМА	Combined equivalent annual elastic layer modulus = $400,000$ psi; Poisson's ratio = 0.30
Subgrade soil	Resilient modulus = 6,000 psi (41,368 kPa)

Table 1	2. Si	mplistic	ME	method	design	limiting	criteria	for the	M-84	project
1 4010 1		mpmotie		meenou	acoign		CI I CO I I CA	101 0110		projece

Crite	Value/Estimation	
Resp	EVERSTRESS	
Desig	20 years / 2,230,000 ESAL	
Tensile strain at the bot	0.000174	
Vertical compressive	Top of sand subbase	0.000536
strain, in./in.	Top of subgrade	0.000455
Maximum deflection, in.	Full-depth/deep strength HMA	0.028
Unbound la	Thickness dependent per Figure 9	
Alligator cracking	10	
Subgrade dis	tortion (rutting), in.	0.5



Figure 9. Limiting modulus criteria of unbound aggregate base and subbase layers

Per the design layer inputs and design criteria using the EVERSTRESS response model, the results of the simplistic ME pavement design for the M-84 project are shown in Table 13. Note that recommended mixes and material types as presented in this table are per MDOT standards and best practices known at that time to reduce the potential for cracking and rutting and were not specifically evaluated as part of the ME-based design procedure. As shown, the simplistic ME design method results in a total HMA thickness of 7.5 inches. However, it is important to note that this thickness was not ultimately adopted. Instead, the 6.5-inch HMA structure with the polymermodified binder as shown in Table 1 was used for this HMA perpetual design. It is likely that the ME-based design result was used in support of AASHTO 1993 design, HMA binder selections, and aggregate base thickness. As previously explained, the ESAL traffic estimation for this MEbased 20-year design (2,230,000) was nearly the same as the estimated AASHTO 1993 ESAL at 40 years (2,640,000). Therefore, as shown in Appendix C, Figure 65, using current MDOT design standards with the estimated AASHTO 1993 40-year ESAL (2,640,000) and thicknesses as per the final design used in the construction plans, the 6.5-inch HMA structure would meet AASHTO 1993 design requirements. Accordingly, for the purposes of this report, the 40-year design life will serve as a reference for the following assessments.

Layer	Material Type	Asphalt Binder	Thickness (in.)
Top course	Top course HMA 5-Superpave, Gap-Graded		2.0
Leveling course	HMA 4-Superpave	PG 70-28	2.5
Base course	HMA 3-Superpave	PG 70-28	3.0
Base	21AA; Crushed Aggregate	-	12.0
Subbase	Non-frost Susceptible Sand	-	16.5
Separator	Geotextile	-	-
Subgrade	Sandy Clay Soil	-	-

Table 13. Simplistic ME method design results for the M-84 project

The result of the 1993 AASHTO pavement design for the I-96 project using a 20-year design life (per ESAL of 22.7 million) is 11.5-inches of HMA over 16-inches of aggregate base over 8-inches of sand subbase. See Appendix C, Figure 66 for details. MDOT estimated a 40-year design life (per ESAL 56 million) pavement section using the 1993 AASHTO pavement design to be used for the ME-based analyses. This design result was 14-inches of HMA over 16-inches of aggregate base over 8-inches of sand subbase as shown in Figure 10. Records of the original 40-year design calculations could not be located, so it was recreated for the purpose of this reporting. See Appendix C, Figure 67 for details.



Figure 10. I-96 Original AASHTO 1993 pavement design, 40 years Cross-Section

As per the layers and thicknesses in Figure 10, the layer and general design parameters used for the simplistic ME design method for the I-96 HMA perpetual pavement are shown in Table 14. These values were estimated per test results of typical HMA and unbound materials of LTPP

projects at that time. See Appendix C, Figures 68 to 71 for details. Note that subgrade stabilization was not considered or specifically included as part of any of the ME-based design procedures. In addition, trial iterations were used to verify the unbound layer modulus values to ensure that the theoretical and laboratory values provide consistent results. Accordingly, the theoretical modulus values to be used in the ME-based designs were adjusted according to these trial iterations and consideration for consistency. The simplistic ME design criteria limits are shown in Table 15.

Layer/Property	Value/Estimation
Tire pressure	120 psi (827 kPa)
Tire load	4,500 lbs (20kN) per tire
Sand subbase	Resilient modulus = $7,000$ psi; Poisson's ratio = 0.35
Aggregate base	Resilient modulus = $7,500$ psi; Poisson's ratio = 0.35
НМА	Combined equivalent annual elastic layer modulus = 892,000 psi; Poisson's ratio = 0.30
Subgrade soil	Resilient modulus = $5,200 \text{ psi}$, Poisson's ratio = 0.45

 Table 14. Simplistic ME method design parameters for the I-96 project

Table 15. Simplistic ME method design limiting criteria for the I-96 project

Criteria/Pro	operty	Value/Estimation		
Response n	nodel	EVERSTRESS		
Design life /	ESAL	20 years / 22,694,400 ESAL	40 years / 56,000,000 ESAL	
Tensile strain at bottom of	20% Cracking	0.000100	0.000075	
the HMA layers, in./in.	10% Cracking	0.000070	0.000053	
	In HMA layers	0.000091	0.000068	
(for rutting) in /in	Top of sand subbase	0.000284	0.000227	
(ior ruunig), in./in.	Top of subgrade	0.000235	0.000187	
Maximum deflection, in.	Full-depth HMA	0.017500	0.015800	
Unbound layer mo	odulus ratios	Thickness dependent per Figure 9		
Damage Ir	ndex	1.0		
Alligator cracking (botto	om-up fatigue), %	20		
Subgrade distortion	(rutting), in.	0.5		
HMA distortion (rutting), in.	0.	4	

The layer and design parameters used for the MEPDG design method for the I-96 HMA perpetual pavement are shown in Table 16. As shown, the MEPDG method requires several more inputs than those used in the simplistic ME method. Where inputs are similar, the MEPDG inputs mostly match those used for the simplistic ME method. Global default values for ME of that time were

used when insufficient data was available. Accordingly, the associated design criteria limits are shown in Table 17. It should be noted that a 30-year analysis period was used instead of 40 years because the results were found to be "unstable" beyond 30 years.

Layer/Property		Value/Estimation		
Initial IRI	65 in/mi			
	Resilient modulus = 7,000 psi			
	Poisson's ratio $= 0.33$	5		
	Plasticity Index $= 0$			
Sand subbase	Passing #200 Sieve = 10%			
	Passing #4 Sieve $= 7$	2%		
	Max Dry Unit Weigh	ht = 135 pcf		
	(all other parameters	calculated or default)		
	Resilient modulus =	7,500 psi		
	Poisson's ratio $= 0.33$	5		
	Plasticity Index $= 0$			
Aggregate base	Passing #200 Sieve =	= 7%		
Aggregate base	Passing #4 Sieve = 30%			
	Max Dry Unit Weight = 130 pcf			
	Optimum Water Content = 7%			
	(all other parameters calculated or default)			
	Binder parameters	A = 10.299; VTS = -3.426		
	(per ASTM D2493)	(Default ME Superpave, PG 70-22)		
		Poisson's ratio $= 0.35$		
		Effective Binder Content = 10.5% Top/Level; 9.5%		
	Volumetrics	Base		
HMA		Air Voids = 7.5 %		
		Total Unit Weight = 148 pcf		
		3/4-inch sieve = 100 Top; 100 Level; 90 Base		
	Mix Aggregates	3/8-inch sieve = 80 Top; 70 Level; 60 Base		
	% Passing	#4 sieve = 65 Top; 60 Level; 50 Base		
		#200 sieve = 6.5 Top; 6.0 Level; 5.5 Base		
	Resilient modulus = 5,200 psi			
	Poisson's ratio = 0.45			
	Plasticity Index = 15			
Subgrade soil	Passing #200 Sieve =	= 65%		
Subgrade son	Passing #4 Sieve = 9	3%		
	Max Dry Unit Weigh	ht = 116 pcf		
	Optimum Water Con	tent = 13%		
	(all other parameters	calculated or default)		

 Table 16. MEPDG method design parameters for the I-96 project

Layer/Property	Value/Estimation
Design life	30 years
Damage Index	1.0
Reliability (for all criteria), %	90
Terminal IRI, in./mi.	170
Top-Down Cracking, ft/500	2500
Bottom-Up Cracking (alligator fatigue), %	10
HMA Permanent Deformation (rutting), in.	0.35
Total Permanent Deformation (rutting), in.	0.60

 Table 17. MEPDG design limiting criteria for the I-96 project

Tables 18 and 19 provide distress prediction results from the two ME-based analysis methods (simplistic ME and MEPDG) for the proposed 14-inch HMA structure (as initially estimated per 1993 AASHTO pavement design). It should be noted that the simplistic ME distress predictions were converted to match the distress types of the MEPDG method for comparison in Table 19. According to the predicted distress results, the cross-sectional structure of the pavement design from the 40-year, 1993 AASHTO pavement design is suitable for addressing cracking since the highest predicted value for bottom-up fatigue cracking remains below 20 percent (which is the threshold criteria for simplistic ME as shown in Table 15). However, the results indicate potential excessive rutting. The MEPDG method anticipates rutting mainly in unbound layers and foundation soil, while the simplistic ME analysis method predicts rutting predominantly in the HMA layers. It is more likely that rutting is predominantly in the HMA layers because the resilient modulus values used for the unbound layers are lower than what were used for designs that use the global MEPDG default calibration coefficients. Therefore, the MEPDG method may be overestimating potential rutting in these unbound sub-layers.

To address the concern of potential HMA rutting, an additional design iteration using the simplistic ME method was used with assumptions for top and leveling HMA to use PG 76-22P, instead of PG 70-22P. As shown in Table 19, this reduces the predicted rutting to a value below the desired design criteria (as shown in Table 17), so it was recommended that top and leveling courses use this increased binder grade. As a result, the 14-inch HMA design with increased binder grades for top and leveling courses was adopted for the plans used for construction (per Table 2).

Criteria/Pr	Predicted Value					
Tensile strain at the bottom of	0.000050					
	In HMA layers	0.000092*				
Vertical compressive Strain (for rutting) in /in	Top of sand subbase	0.000099				
5train (101 ruting), in./in.	Top of subgrade	0.000089				
Maximum deflection, in.	Full-depth HMA	0.010800				

 Table 18. Simplistic ME method design prediction results for the I-96 project

* This value exceeds the 20- and 40-year design criteria values as shown in Table 15.

Pred	Simplis Met	tic ME hod	MEPDG Method		
	20-Year	40-Year	20-Year	30-Year	
Estique Creelving	Damage Index	0.324	0.801	0.028	0.047
Faligue Cracking	Area cracking, %	2.0	6.0	8.4	11.9*
Top-down cracking	N/A	N/A	267	274	
Thermal cracking, ft./mi.		N/A	N/A	40	211
Total mutting in	Per PG 70-22 design	0.48	0.70*	0.77*	0.86*
Total futting, III.	Per PG 76-22 design	0.36	0.54	N/A	N/A
Layer rutting or	Per PG 70-22 design	0.48	0.70	0.21	0.26
distortion, in.	Unbound layers	0.00	0.00	0.56	0.60
IRI, in./mi.	N/A	N/A	120	134	

Table 19. Summary of distress predictions using ME-based methods for the I-96 project

* This value exceeds the design criteria values as shown in Table 17.

Construction and Quality Control

This section provides a summary of the construction conditions and initial construction results. It includes records of tests conducted before and after construction, encompassing parameters of the cross-section material classifications, moisture levels, densities, thicknesses, and strength characteristics. It should be noted that the information presented in this section was not necessarily used for construction acceptance. Instead, this data was collected for informational purposes of the demonstration projects.

For M-84 SB, moisture and density tests were conducted on HMA layers (top, leveling, and base), aggregate base, sand subbase, and subgrade (embankment) using the nuclear method during construction in 2005. Adequate density of compacted materials is important to ensure their long-term performance and structural support. For M-84 SB, measurements were taken on both outside and inside lanes. Note that these measurements were taken independently of those used for construction acceptance, solely to characterize the material properties of the pavement demonstration. The percent of compaction was calculated based on the measured density and the maximum dry density. The percent of compaction and moisture results for different M-84 SB pavement layers are listed in Figures 11 and 12. Note that these results are presented in the original sequential order from the recording files, not by specific locations. Detailed station and lane location information can be found in Appendix D, Figures 72-89.



Figure 11. Percent of compaction for different M-84 SB pavement layers



Figure 12. Moisture for different M-84 SB pavement layers

According to the testing results on the percent of compaction of different M-84 SB pavement layers, the compaction of the tested HMA layers almost all meets the 92% minimal requirement. Only one test point of the tested HMA-base layer is slightly lower than the 92% criterion. The variance in compaction of HMA layers is small, indicating that the compaction process on M-84 SB HMA is uniform and well controlled. The tested subbase compaction range is larger than that of the HMA layers, with 5 out of 37 total test points falling below the 95% criterion. The compaction for tested subgrade (embankment/backfill) is slightly better than that for the subbase, with only one test point below the 95% criterion. Note that aggregate base max dry density was not obtained which was likely due to density testing challenges as according to the original test records.

Accordingly, the percent compaction could not be determined. However, conservatively, at least half of the 8 tests appear to achieve 98% compaction. Therefore, the density requirements for all M-84 SB layers appear to be largely achieved with very few exceptions.

The moisture levels for tested M-84 SB pavement layers indicate that the tested subbase and subgrade (embankments/backfill) areas exhibit similar higher moisture levels compared to other layers. The tested aggregate base material shows the lowest moisture content. The order of moisture levels for HMA layers is HMA-top course, followed by the HMA-leveling course, and HMA-base course with the lowest moisture level.

In addition to the density testing, stiffness and Young's modulus were tested for the aggregate base using GeoGauge testing, as shown in Figure 13. The original record with the test location information is shown in Appendix D, Figure 90. The results indicate that the average Young's modulus for the M-84 SB aggregate base layer is approximately 28.5 ksi, with a minimum of 16.85 ksi. Considering that the resilient modulus used for the aggregate base in the design process is 25 ksi, the base material generally meets the requirement. It should be noted that GeoGauge is not currently used by MDOT to measure strength parameters, so this data is for informational purposes only.



Figure 13. Stiffness and modulus for M-84 SB aggregate base layer

For I-96 WB, moisture and density tests for the reclaimed (existing) subbase were conducted during construction in 2005 using the nuclear method, as depicted in Appendix D, Figures 94-96. According to the tests, compaction of the tested subbase all exceed the 95% minimum requirement. The in-place moisture content was 6.0 to 8.0 percent. In addition to the density testing, the associated aggregate inspection for soil classification of the material was conducted as shown in Appendix D, Figure 97. Accordingly, the subbase meets acceptable MDOT Class IIA subbase material. Additional soil classification testing was conducted for the sand subbase, as shown in Appendix D, Figures 102-104. This tested subbase material is consistent with the samples taken for density testing as it also meets the MDOT specifications for Class IIA subbase. Further soil

classification testing was conducted for the non-stabilized and lime stabilized subgrade samples, with the results displayed in Appendix D, Figures 98-101. The soil classification test results are summarized in Table 20. As shown, the subgrade stabilization appears to have improved the material quality such that it is classified as an improved material type with less fines (as expressed by the percent passing the #200 sieve).

Material	Station	Offset	Percent Passing #100 Sieve	Loss by Wash Percent Passing #200 Sieve	Liquid Limit	Plasticity Index	Natural Moisture Percentage by Weight	Classification
Subgrade	314+25	Center of middle lane	83	78	39	22	19.1	Lean Clay with Sand (CL)
Subgrade	317+00	Center of rightmost lane	83	77	40	22	20.0	Lean Clay with Sand (CL)
Stabilized Subgrade	314+25	18-feet left of centerline	58	49	38	16	20.0	Sandy Silt (ML)
Stabilized Subgrade	317+00	42-feet left of centerline	57	50	38	10	22.9	Clayey Sand (SC)
Reclaimed (existing) Subbase	314+00 to 315+66	-	25	9.7	-	-	-	Meets MDOT Class IIA
Reclaimed (existing) Subbase	315+66 to 317+33	-	25	10.3	-	-	-	Meets MDOT Class IIA
Reclaimed (existing) Subbase	317+33 to 319+00	-	18	8.9	-	-	-	Meets MDOT Class IIA

Table 20. Soil classification summary of the I-96 WB samples

To further evaluate these materials and to assess the initial pavement construction and subgrade strength characteristics on NB M-84, Falling Weight Deflectometer (FWD) testing was conducted on M-84 NB in May 2005, encompassing both the outside and inside lanes. The results shown in Figures 14 and 15 depict the measured deflections along the length of the project for both the NB inside and outside lanes. Note that station length measurements are in metric and begin near College Drive. The maximum deflection at 0 inches (load plate) is indicative of the strength of the entire pavement structure, while the maximum deflection at 60 inches is used to estimate the strength of the subgrade. Analysis of the FWD data unveiled varying deflection patterns along the project's length, with notably high deflections observed near specific locations such as the Contractor Yard (1,300-feet south of Freeland Road), Box Culvert (350-feet south of Kara Drive), Kara Drive, and Amelith Road areas. These notable areas could indicate potential issues, but these are relative to the project itself and do not necessarily indicate poor strength, so as discussed in the following condition sections, these areas were not found to exhibit uniquely different performance. Generally, even those areas with the highest deflection are fair for both the pavement structure and its subgrade.



Figure 14. Average maximum deflection data for the M-84 NB inside lane



Figure 15. Average maximum deflection data for the M-84 NB outside lane

For the I-96 project, FWD at construction was not available, but according to the office memorandum in 2001 to describe soil conditions, the in-situ subgrade soil classification is 72% Firm Silty Clay, 18% Plastic Silty Clay, and 9% Soft Silty Clay, with 3,000 psi estimated resilient modulus for 1993 AASHTO pavement design. See Appendix D, Figures 91-93 for more details. This is lower quality subgrade material, but serviceable as a construction platform. Still, given its low quality, stabilizing was warranted. As a result, the subgrade support and its consistency are significantly improved from these initial estimations. This is confirmed by the soil classification tests conducted during construction as previously noted.

In addition to the material properties, a crucial structural component for performance of the constructed perpetual pavement is the thickness of HMA. Adequate pavement thickness will reduce fatigue cracking and avoid functional maintenance within the design period. Ground

Penetrating Radar (GPR) tests were conducted on the M-84 and I-96 WB (local and express) pavement projects to measure the thickness of the HMA layers. It should be noted that GPR measurements are estimates since core data is not available to confirm them. However, M-84 cores taken in 2020 show that average thicknesses correlate with the GPR measurements.

For the M-84 project, thickness data for an approximately 15,700-foot (2.97-mile) pavement section, measured at 10-foot intervals, was collected in both NB and SB directions. The scatter and distribution of HMA thickness for the M-84 NB standard pavement are presented in Figures 16 and 17, while Figures 18 and 19 show the M-84 SB perpetual pavement thicknesses. The distance of 0 feet refers to the starting point at the southern end, with the distance increasing towards the northern endpoint.



Figure 16. HMA thickness along the distance for the M-84 NB standard pavement



Figure 17. HMA thickness distribution for the M-84 NB standard pavement



Figure 18. HMA thickness along the distance for the M-84 SB perpetual pavement



Figure 19. HMA thickness distribution for the M-84 SB perpetual pavement

According to the thickness data for M-84, most of the pavement on both bounds meet or exceed the designed 6.5-inch thickness. The NB standard pavement has an average thickness of 6.92-inches, while the SB perpetual pavement has an average thickness of 6.74-inches. Of the tested pavement locations, 73% and 68% are at least 6.5-inches thick for the NB standard pavement and SB perpetual pavement, respectively. For the SB perpetual pavement, 32% of tested locations are less than 6.5-inches, most of these are still at least 6-inches thick with only 7% of tested locations less than 6-inches. For the SB perpetual pavement, thinnest paved areas are north of College Dr. to 500-feet north of the first turnaround north of College Dr. and 500-feet north and south of Matthew Dr. For the NB standard pavement, thinnest paved areas are from the northernmost turnaround to 500-feet north and 1000-feet south of Amelith Rd. to 500-feet south of Amelith Rd. However, as will be further discussed int the following sections, it should be noted that there was no discernable difference in pavement performance at these locations.

For the I-96 project, thickness data for a 10,240-foot (1.94-mile) pavement section, measured at 10-foot intervals, were collected starting at the east endpoint, near Schaefer Rd (0-feet) and ending at the west endpoint, near the bridge for M-39 (10,240-feet). The scatter and distribution of HMA

thickness for the express lane are presented in Figures 20 and 21, while those for the local lane are presented in Figures 22 and 23.



Figure 20. HMA thickness along the distance for the I-96 WB express lane section



Figure 21. HMA thickness distribution for the I-96 WB express lane section



Figure 22. HMA thickness along the distance for the I-96 WB local lane section


Figure 23. HMA thickness distribution for the I-96 WB local lane section

The thickness data for the I-96 project reveals that most pavement sections do not meet the designed 14-inch thickness, especially for the local lanes. The express lane pavement has an average thickness of 13.79-inches, while local lane pavement has an average thickness of 12.76-inches. Of the tested pavement locations, 32% and 6% are at least 14-inches thick for the express and local pavement, respectively. For the express pavement, thinnest paved areas from the start of the most west off ramp for the local lanes (to Evergreen Rd.) to its 22-foot point. For the local pavement, the thinnest paved areas from the start of the off ramp for Greenfield Road to the Greenfield Road overpass. It's important to note that there may be some variability in the GPR measurements as these can be influenced by the equipment and data processing. Nevertheless, insufficient thicknesses for I-96 WB may accelerate the development of pavement distress, most notably for the local lanes.

In summary, almost all construction-related sampled materials for both the M-84 and I-96 meet or exceed the requirements for material classifications, moisture levels, densities, and strength characteristics. Additionally, M-84 meets the design requirements for pavement thickness. However, test results for I-96 reveal a notable deficiency in its pavement thicknesses. As a result, there are no notable construction concerns for M-84, whereas I-96 findings suggest that its pavement thicknesses may not adequately resist bottom-up fatigue cracking and could experience accelerated distress. It is important to note that this summary does not consider the construction density of the HMA longitudinal joints since these were not measured or documented in the construction records. This is notable since these joints were found to be a performance issue for I-96. Since the construction of I-96, MDOT has implemented changes to its construction requirements to ensure the density of the longitudinal construction joints, aiming to prevent long-term performance issues.

Pavement Condition Data Analysis

For MDOT roadways, pavement condition (used for performance assessment) for each project is measured by a variety of methods, including rutting, MDOT's Distress Index (DI), and International Roughness Index (IRI). Rutting is the difference in elevation across the pavement surface plane defined by its transverse cross slope, measured in each wheel path separately in inches. The DI measurement is the total accumulated distress point value for a given pavement section normalized to a 0.1-mile length, collected per a sampling of the 0.1-mile length. It is a unitless value that indicates a pavement's 2-dimensional surface distress condition (so faulting and rutting are not included). The IRI measurement is the roughness of the road profile in inches/mile (so that physical distresses such as faulting and rutting can impact its measurement).

Condition data measurements are to be taken in the rightmost lane (outside lane) unless this lane was unavailable due to construction or other lane obstruction. Lane configurations for the M-84 and I-96 projects are presented in Figures 24 and 25, respectively.



Figure 24. Lane configuration for M-84 SB, Google Maps Image, 2023



(b) Local lanes Figure 25. Lane configuration for I-96 WB, Google Maps Image, 2023

Note that historically through 2019, MDOT network-level data collection for DI, IRI, and rut-or-fault was intended to be obtained every other year for any given route segment (including both directions of divided routes). However, the following is a list of exceptions to that biennial schedule:

- Starting in 2009, the annual IRI collection began in at least one direction of all National Highway System (NHS) routes.
- Starting in 2018, the annual IRI collection on at least one direction of all NHS routes was reduced to only Interstate routes.
- Also, starting in 2018, the annual collection of DI and rut-or-fault began (in addition to IRI) on one direction of the Interstate routes.
- Schedules for data collection are subject to roadway availability, so construction or similar operations may prevent data collection for that anticipated year.

A summary of yearly IRI, rutting, and DI data for both bounds of the M-84 project are presented in Table 21 and Figures 26 to 28. Note that the data is separated into two subsections due to location milepoint identifiers that separate how the data is organized and output. The limits of subsections (1) and (2) are shown in Figure 1. As shown, subsection (1) is from Pierce Rd to approximately 1 mile north while subsection (2) begins where (1) ends to approximately 2 miles north (to the end). It is worth noting that the project area has experienced 3 crack treatment projects and occasional minor repair events that have been isolated to spot repairs, typically spanning less than 50 feet in length. Since this work is relatively minor, the overall pavement condition data is minimally impacted by these events.

The IRI data in Table 21 and Figure 26 indicates a consistent increase in roughness with pavement age for both the M-84 SB perpetual pavement and NB standard HMA sections. All subsections of the pavement have remained reasonably smooth, with the IRI consistently well below 170 inches/mile, which is the FHWA threshold for fair condition (per FHWA 23 CFR 490.313). Still, the IRI values in the SB sections are slightly lower than those in the NB sections, suggesting a smoother surface for the demonstration project. According to the FHWA threshold for good IRI condition, below 95 inches/mile (per FHWA 23 CFR 490.313), the SB perpetual pavement subsection (1) still remains within the good range and subsection (2) has remained good until age of 13 years. In comparison, the IRI values for the NB standard subsections (1) and (2) were considered good until 10 years and 12 years, respectively.

The data in Figure 27 shows that the overall average rutting is low for all M-84 subsections, remaining below 0.2 inches, which meets the FHWA threshold for good condition (per FHWA 23 CFR 490.313). Although early rutting values were relatively higher than later ones, this may be attributed to factors such as traffic compaction after construction and/or data noise. Both bounds indicate a strong structure as average rutting values have remained low. There are minimal discernable trends or differences between the two bounds.

As shown in Figure 28, all subsection DI values remain low, far below 50 DI, which is the value used in the *MDOT Pavement Selection Manual* [3] to approximate the end of service life. This indicates that both bounds of the project have been in good to fair condition. Comparing the sections, before year 9, the DI between the SB perpetual sections and NB standard sections are quite similar. However, thereafter, the SB subsections DI values begin to exhibit slightly higher

DI values than the NB subsections. Still, the NB subsections show steeper slopes in DI increase, which may indicate a more rapid rate of deterioration of the NB standard HMA pavement in the future years. As a result, the M-84 SB perpetual pavement seemingly exhibits more favorable long-term DI values compared to the NB standard pavement. Nonetheless, the most recent DI values for all subsections are quite similar, suggesting comparable DI for both bounds.

Data Year		Pavement section										
(Pavement	S	B (Perpeti	al)	S	B (Perpeti	ial)	NB (Standard)			NB (Standard)		
Age of		D	(I) DI		D	(2)	Subsection (1)			Subsection (2)		
SB) *	IKI	Rutting	DI	IKI	Rutting	DI	IKI	Rutting	DI	IKI	Rutting	DI
2006 (1)	57	0.13	0	-	-	-	73	0.12	0.01	79	0.09	0.04
2007 (2)	-	-	-	65	0.11	0.18	-	-	-	63	0.09	0.01
2008 (3)	58	0.14	0.01	-	-	-	73	0.12	0.26	-	-	-
2009 (4)	-	-	-	-	-	-	76	0.14	-	63	0.12	-
2010 (5)	63	0.16	3.17	66	0.15	3.39	75	0.15	2.06	65	0.13	-
2011 (6)	-	-	-	-	-	-	79	0.17	-	70	0.14	-
2012 (7)	62	0.06	1.25	71	0.05	1.65	79	0.07	3.06	69	0.06	1.85
2013 (8)	-	-	-	-	-	-	82	-	-	71	-	-
2014 (9)	77	0.09	3.57	80	0.07	5.64	94	0.08	3.57	82	0.06	4.42
2015 (10)	-	-	-	-	-	-	99	-	-	88	-	-
2016 (11)	82	0.09	13.07	88	0.07	13.17	103	0.09	6.21	94	0.07	9.32
2017 (12)	-	-	-	-	-	-	108	-	-	97	-	-
2018 (13)	88	0.07	22.22	102	0.05	22.66	115	0.06	22.92	106	0.04	25.31
2019 (14)	-	-	-	-	-	-	-	-	-	-	-	-
2020 (15)	-	-	-	-	-	-	-	-	-	-	-	-
2021 (16)	94	0.13	-	107	0.10	-	126	0.09	-	115	0.07	-
2022 (17)	-	-	-	-	-	-	-	-	-	-	-	-

Table 21. Yearly progression of IRI, rutting, and DI for the M-84 project

* The pavement age corresponds to the SB perpetual pavement section. For the NB standard pavement, the age should be adjusted by adding 1 year since it was completed one year earlier.



Figure 26. Yearly IRI data for the M-84 project



Figure 27. Yearly rutting data for the M-84 project



Figure 28. Yearly DI data for the M-84 project

To identify distinct areas of pavement performance, detailed breakdown of the latest pavement DI (in 2018) per tenth mile along the M-84 project length is shown in Table 22 and visually shown in Figure 29. Accordingly, the DI along the M-84 SB perpetual pavement project is shown to be mostly evenly distributed, with standard deviations of 6.6 for SB and 7.1 for NB. This mostly even distribution in DI data indicates that the performance of the M-84 project is relatively uniform along the entire distance. Overall, the NB standard HMA section generally shows a higher DI compared to the SB perpetual section at the same milepoint. This suggests that SB may be outperforming NB. However, it is important to consider that SB is one year younger than NB, so this may change when SB reaches the same age as NB.

Pavement Length (Mile, South to North Direction) *	M-84 SB (Perpetual)	M-84 NB (Standard)
0.1	11.025	22.09
0.2	21.275	26.34
0.3	19.48	20.37
0.4	31.22	35.185
0.5	19.96	23.835
0.6	17.585	21.875
0.7	21.465	28.57
0.8	17.815	19.275
0.9	29.48	14.215
1.0	32.182	18.423
1.1	27.49	35.265
1.2	31.185	37.795
1.3	33.765	21.56
1.4	19.05	24.4
1.5	14.695	24.885
1.6	15.51	29.3
1.7	21.16	23.785
1.8	23.835	15.525
1.9	11.36	35.21
2.0	21.51	25.07
2.1	17.655	26.33
2.2	17.685	24.215
2.3	21.29	24.46
2.4	35.025	13.595
2.5	30.695	15.805
2.6	17.69	15.4
2.7	24.945	16.48
2.8	21.335	23.63
2.9	26.74	38.9
Average	22.6	24.2

Table 22. M-84	pavement DI	per 0.1	mile in	2018
----------------	-------------	---------	---------	------

* 0 to 1.0 miles are per subsection (1) and 1.1 to 2.9 miles are per subsection (2).



Figure 29. DI per 0.1 mile along the M-84 project

A summary of yearly IRI, rutting, and DI data for the I-96 project are presented in Table 23 and Figures 30 to 32. Condition data is separated by the local and express lane sections. It is worth noting that the project area has experienced repair events in 2020 and 2021 to repair segregation and raveling at the longitudinal construction joints between some of the lanes and shoulders. Since most of this work was not within the vehicle wheel paths, the pavement condition data for these two years are largely unaffected by these events.

As shown in Table 23 and Figure 30, both the local and express lane sections exhibit low IRI values as both sections consistently remained below the threshold for good condition of 95 inches/mile. The express section demonstrates a slightly lower IRI than the local lane.

Both the local and express sections demonstrate low rutting, measuring less than 0.2 inches, as shown in Figure 31. The express section exhibits slightly more rutting than the local lanes, but this is minimal. Overall, both sections indicate adequate structure as average rutting values have remained low.

Figure 32 shows that the DI remained very low for both sections throughout the first 12 years after construction. However, the last recorded DI for the express lane at age 14 shows a dramatic increase. Still, the DI for that year (13.11) still indicates satisfactory conditions as this value is well below 50 DI. This single year DI increase could be attributed to the development of segregation and raveling at the longitudinal construction joints that were observed in field condition survey reviews as is discussed in the following section of this report. These types of excessive distress within the longitudinal construction joints will be included in DI measurements, but some of this may have been overly captured, even in areas with fair construction joints. Therefore, additional DI after 2019 would be beneficial to verify the accuracy of the DI increase found in 2019.

Data Year	I-9	6 WB (Loc	al)	I-96 WB (Express)			
(Pavement Age)	IRI	Rutting	DI	IRI	Rutting	DI	
2006 (1)	-	-	-	-	-	-	
2007 (2)	77	0.12	0.20	77	0.14	0.01	
2008 (3)	-	-	-	-	-	-	
2009 (4)	81	-	2.73	80	0.16	0.05	
2010 (5)	-	-	-	-	-	-	
2011 (6)	87	-	4.25	79	0.18	5.53	
2012 (7)	-	-	-	-	-	-	
2013 (8)	87	0.08	0.14	82	0.10	3.27	
2014 (9)	-	-	-	-	-	-	
2015 (10)	89	0.08	0.69	84	0.10	0.11	
2016 (11)	-	-	-	-	-	-	
2017 (12)	87	0.11	0.46	84	0.11	1.67	
2018 (13)	-	-	-	-	-	-	
2019 (14)	93	0.06	-	87	0.08	13.11	
2020 (15)	-	-	-	-	-	-	
2021 (16)	-	-	-	79	0.09	-	
2022 (17)	92	0.11	-	-	-	-	

Table 23. Yearly Progression of IRI, rutting, and DI for the I-96 WB project



Figure 30. Yearly IRI data for the I-96 WB project



Figure 31. Yearly rutting data for the I-96 WB project



Figure 32. Yearly DI data for the I-96 WB project

To identify distinct areas of pavement performance, detailed breakdown of the latest pavement DI (in 2019) per tenth mile along the I-96 project length is shown in Table 24, with corresponding visual representation in Figure 33. Note that the local lane section is not shown because DI data was not measured in 2019 and due to its very low values in 2017, its relative differences are low and would not show identifying differences along the route. As shown, the DI along the I-96 WB express section tends to be relatively high near M-39 and its off ramps but decreases as it progresses to the east. This could be attributed to variations in traffic control measures and/or constructability issues near this transition area of the project.

Pavement Length (Mile, West to East Direction)	I-96 WB Express Section
0.1	5.625
0.2	14.005
0.3	22.62
0.4	17.64
0.5	26.3
0.6	38.84
0.7	14.88
0.8	7.4
0.9	7.065
1.0	6.8
1.1	8.28
1.2	7.56
1.3	7.46
1.4	11.485
1.5	7.12
1.6	7.18
1.7	15.06
1.8	11.16
1.9	9.5
2.0	16.89
Average	13.1

 Table 24. I-96 WB pavement DI per 0.1 mile in 2019



Figure 33. DI per 0.1 mile along the I-96 WB express section

Pavement Condition Survey Findings

Annual pavement condition field assessments of all MDOT demonstration projects are documented in the MDOT Pavement Demonstration Program Legislative Status Report, *Pavement Demonstration Program Status Report Public Act 457 of 2016* [4]. Typically, this annual report includes a summary of visual distress conditions, including cracking and repairs. These reports are derived from the field survey notes. As an example, the 2022 field evaluation notes are shown in Appendix E. Survey pictures are shown in Appendix F. Annual surveys collected data in all mainline through lanes (excluding ramps and turn lanes) of the two projects, so the pavement condition data measurements (used for performance assessments) may not be directly comparable to the annual site surveys since condition data measurements are taken in one lane. Note that observed crack lengths exclude those at the longitudinal construction joint since this is a common crack occurrence due to construction operations and may not indicate the pavement's structural characteristics. The survey on the M-84 project includes both the NB standard and SB perpetual sections from 2007 to 2022 for comparison. Key survey observations for both directions in each survey year are summarized in Table 25.

Report Date	Key Observations
Jan. 2007	Both Directions: Pavement in as-constructed condition with no distress.
Jan. 2008	Both Directions: Several short areas, in both directions, were milled and resurfaced during construction, to improve ride quality. <u>NB</u> : 1 minor transverse crack observed. SB: No distresses was noted.
Feb. 2009	Both Directions: Construction related longitudinal cracking observed at the paving joints. <u>NB</u> : 15 transverse cracks observed (previously filled in 2008). <u>SB</u> : No distresses was noted.
Mar. 2010	<u>NB</u> : 29 transverse cracks observed, 337-feet total length. <u>SB</u> : 3 minor transverse cracks observed, 16-feet total length.
Feb. 2011	<u>NB</u> : Minimal increase in transverse cracking from 2010. <u>SB</u> : No change from 2010.
Jan. 2012	<u>NB</u> : Significant increase in transverse cracking to 848-feet total length. <u>SB</u> : Significant increase in transverse cracking to 218-feet total length. However, many of these cracks are short.
Feb. 2013	<u>Both Directions</u> : Note that this year's crack counts included turn lanes. <u>NB</u> : Transverse cracking was 959-feet in total length. <u>SB</u> : Transverse cracking was 388-feet in total length. Most of this cracking is at and near turnaround left lanes.
Jan. 2014	<u>NB</u> : Transverse cracking increased to 1,782-feet total length with less than 200 feet of longitudinal cracking observed. <u>SB</u> : Transverse cracking increased to 514-feet total length with less than 30 feet of longitudinal cracking observed.
Jan. 2015	<u>Both Directions</u> : Note that this year's crack counts focused on unsealed cracking because this was representative of the new cracking from the previous year. <u>NB</u> : Unsealed transverse cracking increased to 2,710-feet total length. <u>SB</u> : Unsealed transverse cracking increased to 1,318-feet total length.

	<u>NB</u> : Transverse cracking increased by 3,054-feet to 7,512-feet in total length. Longitudinal
Lan. 2016	cracking was 75-feet total length.
Jan. 2016	<u>SB</u> : Transverse cracking significantly increased by 6,336-feet to 8,216 total length. This is
	an increase of 336 percent. Longitudinal cracking was 24-feet total length.
	<u>NB</u> : Transverse cracking increased by 2,911-feet. Longitudinal cracking was 126-feet total
Ian 2017	length.
Jall. 2017	<u>SB</u> : Transverse cracking increased by 4,900-feet. Longitudinal cracking was 165-feet total
	length.
Jun 2018	<u>NB</u> : Transverse cracking increased by 2,990-feet. Longitudinal cracking was minimal.
Juli. 2018	<u>SB</u> : Transverse cracking increased by 600-feet. Longitudinal cracking was minimal.
	<u>NB</u> : Transverse cracking increased by 269 feet/lane-mile. Transverse cracks are widening.
Jun 2019	Longitudinal cracking was minimal.
Juli. 2019	<u>SB</u> : Transverse cracking increased by 1,029 feet/lane-mile. While this increase is higher
	than NB, the cracks are consistently narrower. Longitudinal cracking was minimal.
	<u>NB</u> : Transverse cracking increased by 217 feet/lane-mile. Transverse cracks continue widen
Jun 2020	with some faulting at these cracks. Longitudinal cracking was minimal.
Juli. 2020	<u>SB</u> : Transverse cracking increased by 351 feet/lane-mile. Cracks continue to remain narrow.
	Longitudinal cracking was minimal.
	<u>NB</u> : Transverse cracking increased by 126 feet/lane-mile. Transverse cracks continue widen
Jun 2021	with some faulting at these cracks. Longitudinal cracking remains low.
Juli: 2021	<u>SB</u> : Transverse cracking increased by 513 feet/lane-mile. Cracks continue to remain narrow.
	Longitudinal cracking remains low.
	<u>NB</u> : Transverse cracking increased by 71 feet/lane-mile to 2,534 feet/lane-mile in total.
	Transverse cracks are wider than SB with some faulting at these cracks. Longitudinal
Jun. 2022	cracking remains low.
	<u>SB</u> : Transverse cracking increased by 699 feet/lane-mile to 4,654 feet/lane-mile in total.
	Cracks continue to remain narrow. Longitudinal cracking remains low.

For further details, Table 26 provides comprehensive data on pavement cracking (including transverse and longitudinal types) per lane-mile, as well as pothole distresses observed on both bounds of M-84 since 2014 (age of 9 years), (with exception of 2018 since its raw data could not be confirmed). This table highlights recent-year data, particularly showing the inflection of crack propagation. As shown, longitudinal cracking is minimal and stable in both directions of M-84 project, so both sections seem to be resisting fatigue cracking. However, as shown in Figure 34, transverse cracking per lane-mile since 2017 (age of 12 years) has been very high for both sections. Transverse cracking on the M-84 SB perpetual section was lower than that on the NB standard prior to 2016, but has remained higher than NB after 2016. According to the survey reports, despite the SB perpetual pavement having a greater increase in transverse cracking after the year 2016, most of its cracks remain narrow (approximately 1/16th of an inch) and short (approximately 2'), while cracks on NB are much wider (approximately 1 inch) and longer (full width -12'). Therefore, the observed transverse cracking in SB is likely limited to the surface, preserving the HMA sublayers, so the surface layer can be milled and resurfaced to eliminate most of this cracking. Yet, for NB, since these cracks are much wider, milling with resurface will be less effective, so cracks are likely to reemerge faster, lowering the overall pavement service life. Therefore, overall, while both bounds are performing poorly in thermal cracking, the latest field survey annual reporting has described the SB perpetual pavement overall structural performance as good. It should be noted that annual reporting condition ratings of good, fair, and/or poor are assigned to each project based on a subjective evaluation of the condition at the time of the latest field visit and are only intended to provide a general sense of the performance (in terms of anticipated distress and ride quality per the design type), so this qualifier may not reflect the final recommendation of this pavement after all relevant information is obtained to make a final determination.

	Pavement Age*	1	NB (Standard)		SB (Perpetual)			
Year		Transverse Cracks	Longitudinal Cracks	Potholes (total	Transverse Cracks	Longitudinal Cracks	Potholes (total	
		(feet/ lane-mile)	(feet/ lane-mile)	number)	(feet/ lane-mile)	(feet/ lane-mile)	number)	
2014	9	298	-	-	86	-	-	
2015	10	746	-	-	313	-	-	
2016	11	1,257	13	-	1,369	4	-	
2017	12	1,744	21	-	2,185	27	-	
2018	13	-	-	-	-	-	-	
2019	14	2,119	-	-	3,092	-	-	
2020	15	2,337	28	3	3,442	27	3	
2021	16	2,463	157	2	3,955	48	8	
2022	17	2,534	104	4	4,654	63	3	

Table 26. Yearly cracking and pothole distress for the M-84 project

* The pavement age corresponds to the SB perpetual pavement section. For the NB standard pavement, the age should be adjusted by adding 1 year since it was completed one year earlier.



Figure 34. Yearly transverse cracking per lane-mile of the M-84 project

During April and May of 2020, in addition to the annual visual survey, additional assessments of the M-84 project were conducted through pavement coring and falling weight deflectometer (FWD) testing. Specifically, to confirm that transverse cracking was within the surface of the perpetual HMA pavement, 22 cores with 11 cores per direction were randomly extracted from evenly distributed transverse cracks within the outer lanes. The focus was on cracks with varying lengths and widths, excluding those exceeding a width of ¹/₄ inch since these were assumed to be full depth. The coring locations along M-84 are shown in Figure 35.

The M-84 sampled core average results are presented in Table 27. An example of coring location and sample condition is illustrated in Figure 36. Per the cores, the mean pavement depth measured 6.73 inches for the NB samples and 6.77 inches for the SB samples. Notably, the NB lanes exhibited generally longer and broader cracks, with an average crack length of 7.6 feet and a width of 0.094 inches, compared with the SB lanes' averages of 6.2 feet and 0.075 inches, respectively. The average crack depth was similar for both directions, but SB was less than NB with a 5.4-inch average depth for SB versus 5.6-inches for NB. This result is expected since the distribution of all sampled cracks were those that were less than ¼-inches in width. Full-depth cracks were on average, 8.7-feet long whereas those of partial depth were 4.8-feet long. Since most of the cracks on SB are short (2' length) and narrow, this further suggests that most cracks on SB are partial depth and constrained to the surface course layer.



(a) NB (b) SB **Figure 35. 2020 coring locations for the M-84 project**



(a) Location (b) core top view (c) core side view **Figure 36. Example of coring location and sample condition in M-84 SB coring**

Direction	Crack Length (ft)	Crack Surface Width (in)	Pavement Thickness (in)	Crack Depth (in)
NB (standard)	7.6	0.094	6.73	5.58
SB (perpetual)	6.2	0.075	6.77	5.43

Table 27. Core cracking average results of the M-84 project

The FWD test covered 15,700 feet (2.97 miles) in the NB standard HMA pavement and 15,730 feet (2.97 miles) in the SB perpetual pavement sections. Figure 37 illustrates the M-84 corrected subgrade resilient modulus derived from the FWD tests, indicating similar modulus values at corresponding locations along both bounds of the M-84 project. On average, subgrade support slightly decreases from Pierce Road north to the Point of Ending (POE) in both directions. Notably, the SB direction exhibits marginally higher subgrade support than the NB direction, with average subgrade resilient modulus values of 7,387 psi and 7,064 psi, respectively. Despite the FWD tests being conducted under spring conditions, which typically lead to lower modulus values due to wet and softer conditions, the calculated values are relatively high. Minimum values remain fair (above 3,000 psi) and occur intermittently, indicating the absence of poor locations or lengths. The FWD subgrade resilient modulus values at the sampled crack locations reveal no discernible trends, suggesting that subgrade conditions are not impacting cracking or its propagation. Overall, the subgrade demonstrates good performance, and it is likely that cracking and its propagation are being most significantly influenced by the pavement material and is unrelated to subgrade conditions.



Figure 37. M-84 corrected subgrade resilient modulus

For the I-96 project, annual surveys were conducted on WB local and express lanes. Accordingly, observations on local and express sections were tracked separately. The key survey observations for each survey year are summarized in Table 28.

Report Date	Key Observations
Jan. 2007	All lanes: Pavement in as-constructed condition with no distress.
Jan. 2008	All lanes: Pavement still in as-constructed condition with no distress.
Feb. 2009	All lanes: Pavement still in as-constructed condition with no distress.
Mar. 2010	Local: Possibly 3 faint cracks observed within a 15-foot section.
Feb. 2011	All lanes: No change from previous year.
Jan. 2012	<u>All lanes</u> : Construction related longitudinal cracking starting to appear at the paving joints.
Feb. 2013	All lanes: No change from previous year.
Len. 2014	<u>All lanes</u> : Construction related longitudinal cracking increasing at the paving joints, specifically between the right lane and right shoulder.
Jan. 2014	<u>Local</u> : I wo straight transverse cracks, approximately 6 feet apart observed with settlement between them. It is unclear if this is due to recent utility work or loss of support over a utility trench.
Jan. 2015	<u>All lanes</u> : Construction related longitudinal cracking continues to increase at the paving joints, specifically between the right lane and right shoulder. Where echelon paving was used between the middle and right lanes, these longitudinal joints are still performing well. <u>Express</u> : The longitudinal construction joint between the left and middle lanes has intermittent locations with significant segregation.
Jan. 2016	<u>All lanes</u> : Construction related longitudinal cracking continues to increase at the paving joints. The longitudinal joints have been sealed with overband crack sealant. <u>Express</u> : Possibly two sealed longitudinal cracks observed in the leftmost lane.
Jan. 2017	<u>All lanes</u> : Mostly unchanged from previous year with the longitudinal construction joints exhibiting the most distress.
Jun. 2018	<u>All lanes</u> : Mostly unchanged from previous year. The longitudinal construction joints continue to show widening, specifically, the joint between the outside lane and the on/off ramps have significant segregation.
Jun. 2019	<u>All lanes</u> : Mostly unchanged from previous year with the longitudinal construction joints exhibiting the most distress. The observed pavement distress is very low for both sections.
Jun. 2020	<u>All lanes</u> : Overall, the observed pavement distress is very low for both sections. <u>Local</u> : Segregation and raveling of the longitudinal construction joint between the outside lane and the on/off ramps along the project length remains mostly stable, but there are some infrequent random longitudinal joint pop-outs between lanes. <u>Express</u> : Longitudinal joint separation and raveling observed between the leftmost and middle lanes. Also observed between the rightmost lane and right shoulder. Significant separation observed at two separate locations approximately 1,000-feet in length.
Jun. 2021	<u>All lanes</u> : The longitudinal construction joints continue to exhibit the most distress. Otherwise, the overall observed pavement distress is very low for both sections. <u>Local</u> : Segregation and raveling of the longitudinal construction joint between the outside lane and ramps are notably increasing, up to 2-feet wide. Other longitudinal joints between lanes are starting to separate. <u>Express</u> : A minor amount of intermittent repair patches was conducted prior to this year's review. This comprises about 0.5 percent of the surface area.
Jun. 2022	<u>All lanes</u> : A large amount of intermittent repair patches was conducted in both the local and express lane sections prior to this year's review. This comprises about 7.6 and 10.6 percent of the surface area of the local and express sections, respectively. Almost all patching was within the longitudinal joints (between lanes and the shoulders) to repair joint raveling and segregation. Overall, the observed pavement distress remains very low for both sections.

Table 28. Summary of the I-96 perpetual demonstration program status reports

Detailed pavement cracking (transverse, longitudinal) per lane-mile and pothole distresses for both sections of I-96 since 2019 (age of 14 years) are shown in Table 29. As shown in this table and summarized by the key observations in Table 28, other than the construction related longitudinal joint segregation, both local and express lanes have exhibited very low amounts of cracking and potholes throughout its life. The express lane appears to have slightly more cracking than the local lanes, which could be attributed to differences in traffic and/or construction.

			Local Lanes		Express Lanes			
Year	Pavement Age	Transverse Cracks (feet/ lane-mile)	Longitudinal Cracks (feet/ lane-mile)	Potholes (total number)	Transverse Cracks (feet/ lane-mile)	Longitudinal Cracks (feet/ lane-mile)	Potholes (total number)	
2019	14	0	0	2	6	0	10	
2020	15	0	6	8	6	3	11	
2021	16	0	7	18	21	30	27	
2022	17	12	21	29	41	110	35	

Table 29. Yearly cracking and pothole distress for the I-96 project

As of the most recent Demonstration Program Status Reports in both 2021 and 2022, the general condition of the pavement has largely remained stable, with some noteworthy developments. For all lanes, the longitudinal construction joints continue to separate and ravel. However, patching repairs at poor longitudinal joint areas have mitigated these issues. Otherwise, areas with limited sunlight beneath bridges, hindering water evaporation and leading to prolonged water exposure, have been found to have the most potholes. Despite these localized challenges, the overall performance of both pavement sections is classified as good. As previously noted, annual reporting condition ratings of good, fair, and/or poor are assigned to each project based on a subjective evaluation of the condition at the time of the latest field visit and are only intended to provide a general sense of the performance (in terms of anticipated distress and ride quality per the design type), so this qualifier may not reflect the final recommendation of this pavement after all relevant information is obtained to make a final determination.

Performance Comparison and Evaluation

A performance comparison was conducted to evaluate the relative pavement performance of the two full-depth reconstructed perpetual pavement demonstration projects against MDOT standard reconstructed HMA pavement as per data in the *MDOT Pavement Selection Manual* [3]. For comparison, the estimated fix life (estimated pavement life without maintenance per 50 DI) of the M-84 and I-96 pavement sections with standard pavement are shown in Figures 38 and 40, respectively. Note that the M-84 subsection annual DI values have been grouped together per each direction using the weighted average of their milepoint lengths. The service life (estimated pavement life with maintenance per 50 DI) of the standard pavement with the M-84 and I-96 DI values are shown on Figures 39 and 41, respectively. It should be noted that the demonstration project DI values may exhibit more variability than the statewide project values since its data is derived from a few project sections rather than a broad set of values.

As shown in Figure 38, the M-84 project has recorded enough data points to show a reasonable DI data trend with pavement ages, indicating fix lives of about 16 years for both bounds, which is approximately 2 years less than the standard alternative. The DI for the M-84 SB and NB sections remained relatively low within the first 10 years post-construction. However, the DI noticeably increased thereafter. It is noteworthy that limited structural distress in terms of longitudinal cracking was observed in both sections. However, the development of transverse cracking in both the SB and NB sections have likely contributed to the rapid increase in DI, as revealed in the condition field survey results. Despite the faster increase of transverse cracking in the SB perpetual pavement as compared to the NB standard section, the shorter and narrower width of cracks in the SB perpetual section indicates that most of its cracks are isolated to the top layer of HMA and do not penetrate the full depth. Thus, the upgraded materials in the M-84 SB perpetual pavement have been seemingly effective in reducing the severity of its cracking. Still, the DI values in the SB section may be overestimated, as the reduced severity of its transverse cracks may not be effectively accounted for within the calculation of its DI. Nevertheless, while the initial fix life projections of NB and SB are very similar, the subsequent maintenance events for SB should provide more years of service life beyond that of NB and result in lower long term DI values.

To date, M-84 has had 3 maintenance events over the last 18 years of service, which is the same as the standard alternative over that same timeframe. However, these have all consisted of crack treatments, which are relatively minor, so, the first substantial maintenance event (i.e. HMA overlay) has not yet occurred as is expected for standard HMA reconstruction. Nevertheless, per the projected fix life and raw number of maintenance events, the data indicates that the demonstration has about the same service life as that of the standard version, which would be 37 years. This is significantly less than the anticipated 50 years of service life, but as noted, the first substantial maintenance event has not yet occurred and it should be more effective, so 37 years is likely underestimated.



Figure 38. Comparison on M-84 DI trends with fix life of standard pavement



Figure 39. Comparison on M-84 DI trend with service life of standard pavement

According to Figure 40, the I-96 WB project express lane section has similar fix life as standard HMA reconstruction, but the local section is nearly infinite due to its consistent DI values and no inflection point. As a result, its single projection does not yet appear to reasonably estimate its initial fix life performance curve. Regardless, both the local and express lane sections of I-96 WB maintained a very low level of DI within its initial 12 years after construction without major maintenance. However, the most recent DI data in the express section at 14 years (year 2019) demonstrates a noticeable increase, though it remains relatively low. Since there was no available DI data after the year 2019, it is unclear if the local section also increases in DI. However, combining with the condition survey findings in 2019 and 2020 in Table 29, potholes and cracking started to show up around year 2019, which may contribute to increased DI. Additionally, as previously observed, increased DI may be attributed to the development of segregation and raveling at the longitudinal construction joints that were observed in field condition survey reviews. Some of this may have been overly accounted for within the express section DI measurement for 2019 as it may have included areas with fair construction joints. This was found to be an issue primarily for DI measurements in 2018 and 2019 as technology automation was incorporated to aid in DI calculation for these years. Nevertheless, this distress is largely a construction-related issue due to inadequate density at construction joints and are not representative of the integrity of the pavement structure. Therefore, the improved structural performance of the I-96 WB project is seemingly being limited by its construction conditions and distress found in the longitudinal joints.

In consideration of estimated service life, if the first maintenance event is assumed to be at the pavement age of 15 years in 2020 (despite primarily being repairs for longitudinal construction joints), this would be is 7 years after the first maintenance event for the standard alternative. As shown in Figure 41, if we assume the same number of maintenance events, timing between each,

and similar improvements to DI as estimated for the standard alternative, then the I-96 express section could be estimated to have a service life of approximately 44 years. While this estimation is slightly lower than the anticipated 50 years of service life, if longitudinal construction joint issues can be constrained by the repairs that have taken place, then this service life will likely increase and reach the anticipated life.



Figure 40. Comparison on I-96 DI trends with fix life of standard pavement



Figure 41. Comparison on I-96 DI trend with service life of standard pavement

Figure 42 shows the composite fix life curve derived from the perpetual full-depth reconstruction project sections on M-84 SB and I-96 WB as compared to the standard alternative. As shown, the

perpetual reconstruction projects exhibit a significantly lower increase in the DI within the first 10 years post-construction. However, the overall DI progression of the perpetual HMA reconstruction demonstration project is slightly worse than that of standard HMA reconstruction. Specifically, the estimated resulting fix life for the demonstration sections is estimated to be 16 years, whereas it is projected to be 18 years for the standard alternative. As previously noted, several factors may be contributing to this, including the transverse cracking issues on M-84 and longitudinal construction joint issues on I-96. Moreover, the absence of subsequent DI datapoints and limited sample size as compared to the standard dataset may be impacting the accuracy of the curve projections. Consequently, the fix life projection may be underestimated. To enhance the reliability of these results, additional DI datapoints and/or future demonstration projects may be needed to verify or improve the accuracy of the demonstration performance curve.



Figure 42. Comparison between perpetual and standard HMA pavement

Cost Comparison and Evaluation

The estimated initial and long-term costs of the pavement demonstration projects will be compared with the estimated costs of MDOT standard reconstructed HMA pavement. Costs included in this report were adjusted to 2019 dollars for comparison with the standard costs included in the *MDOT Pavement Selection Manual* [3] by using the procedure as denoted in Chapter 6, Section F of that manual. This manual explains the Life Cycle Cost Analysis (LCCA) procedure and MDOT's guidelines for pavement selection. The initial cost for construction was approximated by using MDOT LCCA unit prices and the estimation method for the pavement costs as described in Chapter 2, Section A of the *MDOT Pavement Selection Manual*.

Since both M-84 SB and I-96 WB demonstration projects were finished construction in year 2005, the historical unit price from August 2006 will be used to estimate the initial construction cost of the two demonstration projects, since these prices captured construction in 2005 (cost will be inflated to 2019 dollars). The actual project bid prices will not be used since these can be highly variable due to the project quantities and do not provide costs for other mix types needed for comparison. Additionally, it is not clear if binder grade adjustments alone have significant cost

impacts, so this will not be included in the cost analysis. However, since mix types and layer thicknesses have a significant impact on overall cost, the cost comparison will use these parameters. Note that I-96 WB included subgrade stabilization, but since this was not directly considered as part of any of the design procedures which could have impacted the design recommendation of other layers, it will not be included in the cost analysis. However, since unbound base thicknesses were considered and are variable per the design, these will be included.

The estimated perpetual HMA pavement, 40-year design life initial cost for the M-84 SB and the I-96 WB projects are estimated to be approximately \$283,000 and \$454,000 per lane-mile, respectively, as shown in Tables 30 and 32. In contrast, to estimate the initial cost of the standard alternatives, the standard 1993 AASHTO pavement designs using 20-year design life as shown in Appendix C will be used. Accordingly, as shown in Tables 31 and 33, this is estimated to be approximately \$227,000 and \$401,000 per lane-mile for M-84 and I-96, respectively. Therefore, the M-84 perpetual reconstruction initial cost is about \$56,000 per lane-mile or 1.25 times the initial pavement cost more than its standard HMA reconstruction alternative. Similarly, the I-96 perpetual reconstruction initial cost is about \$53,000 per lane-mile or 1.13 times the initial pavement cost more than its standard HMA reconstruction alternative. As a result, it appears that the high-volume traffic route of I-96 may be more effective for perpetual pavement application since its relative cost increase was less than the low volume route of M-84.

Layer	Туре	Thickness (inch)	Application Rate (lbs/syd)	Total Tons	Unit Price in 2006	Cost per Lane-Mile	
HMA - Top	5E3	1.5	165	581 ton	\$44.31	\$25,735.25	
HMA - Level	4E3	2	220	774 ton	\$45.19	\$34,995.14	
HMA - Base	3E3	3	330	1,162 ton	\$42.33	\$49,170.53	
Base	DGAB	12	-	7,040 syd	\$10.44	\$73,497.60	
Subbase Sand		13.5	-	2,640 cyd	\$8.20	\$21,648.00	
	\$205,046.51						
	Total	Cost per Lane-	Mile (Adjust to 2	019)		\$282,604.69	

Table 30. Estimated initial cost for the M-84 SB perpetual pavement, 40-year design life per unit prices

Table 31. Estimated initial cost for the M-84 standard pavement, 20-year design life per unit prices

Layer	Туре	Type Thickness Appl (inch) Rate (Total Tons	Unit Price in 2006	Cost per Lane-Mile
HMA - Top	5E3	1.5	165	581 ton	\$44.31	\$25,735.25
HMA - Level	4E3	2	220	774 ton	\$45.19	\$34,995.14
HMA - Base	3E3	3	330	1,162 ton	\$42.33	\$49,170.53
Base	DGAB	6	-	7,040 syd	\$3.71	\$26,118.40
Subbase Sand		- 18		3,520 cyd	\$8.20	\$28,864.00
		\$164,883.31				
	Total	Cost per Lane-	Mile (Adjust to 2	(019)		\$227,249.89

Layer	Туре	TypeThickness (inch)Application Rate (lbs/syd)Total		Unit Price in 2006	Cost per Lane-Mile	
HMA - Top	GGSP	1.5	165	581 ton	\$53.80	\$31,247.04
HMA - Level	4E30	2.5	2.5 275		\$46.04	\$44,566.72
HMA - Base	3E30	10	1100	3872 ton	\$42.07	\$162,895.04
Base	OGDC	16	16 -		\$11.36	\$79,974.40
Subbase	Subbase	8	-	1,564 cyd	\$6.73	\$10,528.71
	\$329,211.91					
	Total	Cost per Lane-	Mile (Adjust to 2	(019)		\$453,735.25

Table 32. Estimated initial cost for the I-96 WB perpetual pavement, 40-year design life per unit prices

Table 33. Estimated initial cost for the I-96 standard pavement, 20-year design life per unit prices

Layer	Туре	ThicknessApplication(inch)Rate (lbs/syd)		Total	Unit Price in 2006	Cost per Lane-Mile
HMA - Top	GGSP	2	220	774 ton	\$53.80	\$41,662.72
HMA - Level	4E30	2.5	275	968 ton	\$46.04	\$44,566.72
HMA - Base	3E30	7	770	2710 ton	\$42.07	\$114,026.53
Base	OGDC	16 -		7,040 syd	\$11.36	\$79,974.40
Subbase	Subbase	8	-	1,564 cyd	\$6.73	\$10,528.71
	\$290,759.08					
	Total	Cost per Lane-	Mile (Adjust to 2	019)		\$400,737.76

While the initial paving costs for perpetual pavement projects are higher than the standard HMA reconstruction project, the service life for both are anticipated to be longer than its standard alternative. Per the MDOT Pavement Section Manual, the standard HMA reconstruction pavement service life is 37 years, while the anticipated service life of the perpetual alternative is at least 50 years. However, as observed in the previous section, both projects currently suggest lower service lives of roughly 37 and 44 years for M-84 and I-96, respectively. Therefore, as shown in Table 34, the M-84 perpetual alternative initial cost per year of its service life may range from \$5,660 to \$7,650 per lane-mile, while its standard alternative is \$6,135 per lane-mile. For I-96, this is \$9,080 to \$10,320 per lane-mile with standard alternative being \$10,840 per lane-mile. It is important to note that this per year cost does not include the benefit of delayed major rehabilitation or reconstruction, which becomes more significant with longer service life. Still, in terms of the initial paving cost, the perpetual alternative is more cost-effective than the standard if at least 47 and 41 years of service life are achieved for the M-84 and I-96 projects, respectively. Based on current rough estimates of their service lives, I-96 is on track to achieve this, but M-84 may not be. This seems to further support that the high-volume traffic route of I-96 may be more suitable for perpetual pavement applications as it appears to already be more cost effective and would require fewer years of service life in order to achieve this.

Туре	Initial Pavement Cost	Service life (years)	Yearly average cost	
M-84 perpetual HMA	¢292.000	37	\$7,650	
reconstruction	\$283,000	50	\$5,660	
M-84 standard HMA	\$227.000	27	\$6 125	
reconstruction	\$227,000	57	\$0,155	
I-96 perpetual HMA	\$454,000	44	\$10,320	
reconstruction	\$434,000	50	\$9,080	
I-96 standard HMA	\$401.000	37	\$10.840	
reconstruction	φ 4 01,000	57	φ10 , 040	

Table 34. Initial paving cost per year of service life

In addition to the pavement's initial cost, maintenance considerations play a crucial role in influencing costs. According to the *MDOT Pavement Selection Manual*, for the MDOT standard HMA reconstruction pavement, preventive maintenance cycles occur on average after 8, 13, 17, and 22 years, with rehabilitation or reconstruction estimated to occur after 37 years. Accordingly, the maintenance cost per lane-mile of these maintenance fixes is estimated at \$28,071, \$41,342, \$44,005, and \$32,411, respectively, so their total cost is \$145,829 per lane-mile.

Records show that the M-84 project underwent three maintenance projects since its initial construction. These were conducted on both directions and all involving crack treatment. The maintenance costs per lane-mile of these were \$2,315 for cycle 1 in 2008 (age 3), \$3,429 for cycle 2 in 2013 (age 8), and \$3,596 for cycle 3 in 2016 (age 11), bringing their total cost to \$9,340 per lane-mile (as adjusted to 2019 cost). Considering that the pavement life is 18 years in 2023, the number of maintenance events is the same as the standard HMA reconstruction projects over that same period but is \$104,078 less in total cost. This seems to indicate that the M-84 maintenance events have been less extensive than what is typically seen on standard pavements.

For I-96 WB, one programmed maintenance project is scheduled for 2024, containing cold milling with a HMA single-course overlay. Prior to this, no contracted maintenance activities have occurred. Still, as previously noted, minor repairs were observed during field surveys to have been performed in 2020 and 2021. This type of non-contracted minor repair work is commonly conducted on various routes throughout the state, but it isn't easy to compare or assess the relative amount of this work per route because this type of minor repair work is not fully tracked for every roadway segment. Still, to assess the maximum potential cost of maintenance work, considering the total number of repairs observed, it can be approximated that the minor repair work is roughly equal to a single contracted maintenance cycle. Therefore, the I-96 WB maintenance events will be estimated as 2 cycles, occurring at ages 15 and 19. The costs of these maintenance activities can be roughly assumed to be similar to that of standard HMA reconstruction. However, the number of maintenance events is 1 less than that of the standard HMA reconstruction projects over that same time period, so that the overall cost of I-96 WB maintenance has been less than the standard alternative.

Therefore, to date, the maintenance costs of both perpetual HMA reconstruction projects on M-84 and I-96 are lower than standard HMA reconstruction projects. While their initial costs are higher, the potential increased service life would reduce the overall long-term cost of the pavement.

Therefore, considering the increased service life and reduced maintenance costs, this demonstration fix type should provide a cost-effective option based on current service life estimates. Specifically, its advantages may be more pronounced for high-volume traffic routes, where the initial cost increase may be relatively less than the added cost on low-volume routes.

Conclusions and Recommendations

This report presents the finalization evaluation of the "Full-Depth Reconstructed Perpetual HMA" pavement demonstration projects on M-84 SB, MDOT Job Number 31804 and I-96 WB, MDOT Job Number 52803. It includes summary and evaluation of each project and its pavement design, construction quality control, condition, performance, costs, and comparisons. Conclusions and recommendations are presented as follows.

For M-84, both bounds were found to be consistently constructed and consistent with design plans as per GPR results. Furthermore, FWD results show that both bounds have relatively uniform subgrade offering fair to good support. This project location has accumulated sufficient condition data since its construction in 2005. While transverse cracking continues to increase, more so in SB than NB, the severity of these cracks for SB are lower as the width of transverse cracking in the SB perpetual sections is lower than that in the NB standard sections. This is confirmed by the coring results, showing that the perpetual section in SB has performed better in preventing full-depth transverse cracking than the standard HMA section in NB. Longitudinal cracking has remained steady and minor throughout the pavement life of both bounds, with SB performing slightly better than NB. However, according to the DI analysis, the SB perpetual did not show a distinct advantage compared to the NB standard sections. This is likely due to the higher count of transverse cracks in SB than NB. Still, the reduced severity of these cracks may not be fully demonstrated by the DI alone. As a result, while the initial fix life projections of NB and SB are very similar, the subsequent maintenance events for SB should provide more years of service life beyond that of NB.

For I-96, analysis of thickness data from GPR tests revealed that a significant portion of the pavement sections are less than the designed 14-inch thickness, achieving 12.8- and 13.8-inches in average thickness for the local and express lane sections, respectively. In addition, notable longitudinal construction joint failure attributable to insufficient density and/or inadequate bonding was found intermittently throughout the project for both sections. This highlights the need to ensure the success of perpetual HMA reconstruction by addressing construction quality control for similar future projects. Nevertheless, the I-96 WB project has demonstrated excellent performance in both local and express lanes since completion in 2005. However, the express lane section, while still relatively low, had a relatively noticeable increase in DI and observed cracking in 2019 (at age 14). This increased cracking in recent years may be partially contributing to the DI increase as shown in that year. However, due to the intermittent longitudinal construction joint raveling and segregation, DI may be overstated and not fully represent the performance of the perpetual design as this distress is largely a construction-related issue and not representative of the integrity of the pavement structure. It should be noted that since the construction of I-96, MDOT has implemented changes to its construction requirements to ensure the density of the longitudinal construction joints, aiming to prevent long-term performance issues. Interestingly, despite being

mostly thicker than the local lane section, the express lane section has shown slightly more cracking and potholes than the local section. This may be attributed to differences in traffic and/or construction. Despite the initial high cost of the I-96 WB project due to the increased HMA thickness, the long-term maintenance costs have been significantly reduced. If the longitudinal construction joint issues can be constrained by the repairs that have taken place, then this service life will likely increase leading to overall cost savings.

The full-depth reconstructed perpetual HMA demonstration pavements have generally collected a sufficient amount of condition data. Still, there is some uncertainty about the forecasted fix life of these pavements due to the currently available DI measurements. Factors contributing to this uncertainty include the observed high quantity but low severity transverse cracking on M-84 and longitudinal construction joint issues on I-96 that may be overly influencing current DI values. Moreover, the absence of recent (2020 and newer) DI datapoints and limited sample size as compared to the standard dataset may be impacting the accuracy of performance curve projections. Consequently, the fix life and/or service life projections may be currently underestimated.

Nevertheless, since an adequate amount of time has passed and enough data is available to fully evaluate these projects, it is recommended that MDOT consider standardization and implementation of full-depth reconstructed perpetual HMA pavement. Per the findings and conclusions of this report, as compared to standard HMA reconstruction, perpetual pavement offers potential advantages in terms of longer service life and lower overall cost due to reduced long-term maintenance needs. Consequently, less frequent maintenance and reconstruction events will lead to reduced disruptions to traffic. This highlights its promise as a sustainable and cost-effective pavement solution.

However, if the service life projection does not reasonably accommodate practical use as compared to standard alternatives or as necessary for MDOT life cycle procedures, then MDOT may consider the construction of additional projects using this demonstration fix type or continue to wait for additional data on the existing sections prior to standardizing. If more projects are to be constructed, then construction quality standards should be ensured to uphold the integrity of the design. Furthermore, high-volume traffic routes should be prioritized as the high-volume traffic route of I-96 has shown more overall cost savings due to the lower relative increased cost from standard design. These pavements may also benefit more as this provides less traffic interruption due to anticipated pavement maintenance.

Regardless, since the primary issue is that of establishing and validating the performance curve and because additional detailed annual reviews would not enhance the conclusions from these projects, it is recommended that the MDOT end its annual monitoring and status reporting of the M-84 SB and I-96 WB demonstration projects. If needed, future data collection for fix type evaluation can be solely facilitated by the standard networkwide MDOT condition data measurements and standard MDOT project tracking.

References

- 1. Harold Von Quintus. Pavement Structural Design Recommendations for Reconstruction and Widening of M-84. Michigan Department of Transportation. April 2003.
- 2. Harold Von Quintus. Pavement Structural Analysis of the Design Recommendations for Reconstructing I-96 (M-39 to Schaeffer Road). Michigan Department of Transportation. August 2004.
- 3. Michigan Department of Transportation Pavement Selection Manual. Pavement selection. 2021.
- 4. Schenkel J. Pavement Demonstration Program Status Report Public Act 457 of 2016 [Internet]. 2022. Available from: https://www.michigan.gov/mdot/about/governmentalaffairs



Appendix A: Proposed Pavement Construction Plans

Figure 43. JN 31804A project location for the M-84 project



Figure 44. JN 31804A existing cross-sections for the M-84 project



Figure 45. JN 31804 typical cross-section for the M-84 SB perpetual and NB standard pavement project



Figure 46. JN 52803 project location for the I-96 perpetual pavement project



Figure 47. JN 52803 typical cross-section for the I-96 perpetual pavement project

Appendix B: Traffic Data



29

7%

Figure 48. Office memorandum on M-84 traffic information, page 1

Job # 48271 Delta Road to I-75	Data Type	2000	2003	2023
	Total ADT	17,500	17,800	19,600
	Directional ADT	8,750	8,900	9,650
	AM Peak (NB/SB)	655/660	665/670	755/760
	PM Peak (NB/SB)	1140/1025	1160/1045	1310/1180
	ADT Growth Rate		0.5% .	
	Pattern Type	7	7	7
Job # 48271	Data Type	2000	2003	2023
Interstate-75 to Euclid	Total ADT	12,800	12,900	13,600
Avenue	Directional ADT	6,400	6,450	6,800
	AM Peak (NB/SB)	590/570	590/575	610/595
	PM Peak (NB/SB)	730/725	735/730	755/755
	Growth Rate		0.3%	
	Pattern Type	7	7	7

The following table shows locations where each classification count and ESAL calculation is applicable.

Vehicle Class Count Locations:	Applicable M-84 Truck Segment:
Station 503: 0.1 mile S, of Kochville Road	M-58 (Davenport Rd.) to Pierce Rd.
Station 271: 0.25 mile SW of Delta Road	Pierce Rd. to I-75
Station 505: 100' NE of I-75	I-75 to Two Mile Rd.
Station 17: 0.1 mile SW of Salzburg Road.	Two Mile Rd. to M-13 (Euclid Ave.)

cc: Chris Burnell, Dave Geiger

54

.

30

Figure 49. Office memorandum on M-84 traffic information, page 2

24

									M-84 N	of I-75						
		NORTHBOUND			SOUTHBO	DUND			NORTHBOUND			SOUTHBOUND				
	HR END	WKDAY	WKEND	7 DAYS	WKDAY	WKEND	7 DAYS	HR END	WKDAY	WKEND	7 DAYS	WKDAY	WKEND	7 DAYS	HR END	
	1	54	98	66	38	59	44	1	0.7%	1.9%	1.0%	0.5%	1.2%	0.7%	1	
	2	46	61	50	27	41	31	2	0.6%	1.1%	0.7%	0.4%	0.8%	0.5%	2	
	3	25	42	29	23	43	29	3	0.3%	0.8%	0.4%	0.3%	0.9%	0.4%	3	
	4	30	31	31	42	22	30	4	0.4%	0.0%	0.4%	4 48/	0.4%	4 0%	-	
	5	21	23	21	19	57	128	6	0.3%	0.4%	0.3%	2 2%	1.2%	2.0%	6	
	0	164	62	135	340	113	275	7	2.2%	1.2%	2.0%	4.8%	2.3%	4.3%	7	
	2	381	105	288	609	146	477	8	4.8%	2.0%	4.2%	8.6%	3.0%	7.4%	8	
	0	348	129	286	490	181	402	9	4.7%	2.4%	4.2%	6.9%	3.7%	6.2%	9	
	10	343	216	307	435	247	381	10	4.6%	4.1%	4.5%	6.1%	5.0%	5.9%	10	
	11	430	286	388	470	306	423	11	5.7%	5.4%	5.7%	6.6%	6.2%	6.5%	11	
	12	478	339	438	498	358	458	12	6.4%	6.4%	6.4%	7.0%	7.3%	7.1%	12	
w	13	529	408	495	548	389	502	13	7.1%	7.7%	7.2%	7.7%	7.9%	7.8%	13	
	14	470	427	457	413	405	410	14	6.3%	8.1%	6.7%	5.8%	8.2%	6.4%	14	
	15	532	450	508	426	403	419	15	7.1%	8.5%	7.4%	6.0%	8.2%	6.5%	15	
	16	622	456	574	461	388	440	16	8.3%	8.6%	8.4%	6.5%	7.9%	6.8%	16	
	17	652	404	581	430	365	411	17	8.7%	7.6%	8.5%	6.1%	7.4%	6.4%	17	
	18	627	394	560	467	349	433	18	8.4%	7.4%	8.2%	6.6%	7.1%	5.7%	18	
	19	473	326	431	354	285	334	19	6.3%	6.2%	6.3%	5.0%	5.8%	5.2%	19	
	20	361	282	338	254	218	244	20	4.8%	5.3%	4.9%	3.6%	4.4%	3.8%	20	
	21	324	251	303	181	184	182	21	4.3%	4.1%	9.4%	2.0%	3.170	2.0%	22	
	22	262	205	245	143	14/	144	24	3.57	3.3%	3.0%	4 79/	2 2%	4 9%	23	
	23	160	13/	153	120	108	110	2.	4 40	2.0%	1 6%	1.0%	1.5%	1.1%	24	
	24	102	135	112	7077	4015	6450	24	1009/	100%	100%	100%	100.0%	100%		
		/4/0	5280	0000	10/1	4815	0403		1007	10070	10070					

Figure 50. Office memorandum on M-84 traffic information, page 3

									M-84 S	of I-75						
		NORTHBOUND			SOUTHBOUND				NORTHBOUND			SOUTHBOUND				
	HR END	WKDAY	WKEND	7 DAYS	WKDAY	WKEND	7 DAYS	HR END	WKDAY	WKEND	7 DAYS	WKDAY	WKEND	7 DAYS	HR END	
	1	77	139	95	60	97	70	1	0.7%	1.7%	1.0%	0.6%	1.2%	0.7%	1	
	2	58	83	65	37	55	42	2	0.6%	1.0%	0.7%	0.4%	0.7%	0.4%	2	1.1
	3	47	72	54	28	68	39	3	0.4%	0.9%	0.5%	0.3%	0.9%	0.4%	3	
	4	58	43	54	48	31	43	4	0.6%	0.5%	0.5%	0.5%	0.4%	0.4%	4	
	5	100	58	88	72	37	62	5	0.9%	0.7%	0.9%	0.7%	0.5%	0.6%	5	
	6	220	64	176	192	61	155	6	2.1%	0.8%	. 1.8%	1.8%	0.8%	1.6%	6	
	7	398	162	331	439	165	361	7	3.8%	1.9%	3.3%	4.2%	2.1%	3.7%	7	
	8	571	205	466	868	270	697	8	5.4%	2.5%	4.7%	8.3%	3.5%	7.2%	8	
	9	510	266	440	753	317	628	9	4.8%	3.2%	4.4%	7.2%	4.1%	6.5%	9	
	10	484	359	449	617	431	564	10	4.6%	4.3%	4.5%	5,9%	5.5%	5.8%	10	
	11	591	461	554	711	502	651	11	5.6%	5.5%	5.6%	6.8%	6.5%	5./%	11	
	12	682	512	633	762	586	712	12	6.4%	6.1%	6.4%	7.3%	7.5%	7.4%	12	
20	13	648	601	635	697	650	684	13	6.1%	7.2%	5.4%	6.7%	8.4%	7.1%	13	
~	14	653	662	655	630	663	639	14	6.2%	7.9%	5.5%	5.1%	8.5%	0.0%	14	
	15	718	692	711	623	623	623	15	5.8%	8.3%	7.176	6.0%	7 70/	6.0%	15	
	16	771	643	734	699	598	- 6/0	16	7.5%	7 70/	7 60/	0.170	7 6%	6.7%	17	
	17	805	642	/58	6/4	597	000	17	7.0%	7.0%	7.0/0	7 2%	7 3%	7 2%	18	
	18	802	585	/40	/49	00/	097	10	0.070	c 39/	C 49/	5 3%	3 50/	A 996	19	
	19	644	519	608	553	2/3	4/3	19	0.17e	0.2/e	5 40/	3 7%	A 7%	4.0%	20	
	20	526	463	508	389	308	303	20	5.0 %	0.07e	A E0/.	2 7%	3 0%	3.0%	21	
	21	469	387	445	282	300	287	21	3,470	9.0%	3 0%	2 1%	3 2%	2.4%	22	
	22	401	316	376	170	240	230	22	3.0 %	2.0%	2 2%	1 7%	2.1%	1.8%	23	
	23	219	219	219	1/9	100	1174	24	1 2%	2.076	1.5%	1 1%	1.5%	1.2%	24	
	24	127	192	140	110	7776	0640	7.4	100%	100%	100%	100%	100.0%	100%		
		10580	0341	3340	10388	1115	5045		10074	10070						
						1										

Figure 51. Office memorandum on M-84 traffic information, page 4
LOCATION	M-84	S of KOCHVILLE ROA	D					
CONTROL SECTION	9011							
CONSTRUCTION YEAR	2002	1						
NUMBER OF DESIGN YEARS (1-30)	20	1						
COMMERCIAL GROWTH RATE								
TYPE OF GROWTH RATE - COMPOUND, AVERAGE (C OR A)	Selection C	1						
DIRECTION DISTRIBUTION FACTOR	62%							
ANE DISTRIBUTION FACTOR	80%							
COMMERCIAL ADT IN BASE YEAR	561		561	CONSTRUCTION YEAR	R CADT, 2	-Way		
OPTION - AVERAGE, MEDIUM/HEAVY, CLASSIFICATION (A,MH,	CS CS		1993	COUNT YEAR			1926	
AVERAGE ESAL - RIGID	0.76		1-10-14	NUMBER OF DAILY C	OUNT CO	LUMNS L	JSED	A MARKAGE
AVERAGE ESAL - FLEXIBLE	0.59		0.9500	SEASONAL FACTOR	RAWON	E-WAY	DAILY CI	ASSIFIC
COMMERCIAL CLASSIFICATION PERCENTAGES	-		PCT	ROW SUM	1	2	3	4
5 (Single Unit, 2 Axle)	20.25%	2AX	20.25%	213	10% - 53	2019 51.		16,余竹 58
6 (Single Unit, 3 Axle)	27.47%	3AX	27.47%	289	12.0126	St115	indel5:	1. a
7 (Single Unit, 4 Axle)	1.81%	4AX	1.81%	19	D	13302	4:4-3.2;	1
8 (Single Trailer, 4 Axle)	33.84%	4AX	33.84%	356	. 89	122	63-	82
9 (Single Trailer, 5 Axle)	3.80%	5AX	3.80%	40	-1: 12 - 13 P	The 12-	9	13 7, 10
10 (Single Trailer, 6 Axle)	3.04%	6AX	3.04%	32	1221.6	1 same	. 10	Jours 9
11 (Double Trailer, 5 Axle)	1.90%	5AX	1.90%	20	15 th 10 0	n. n. 10	10000	A.32 (Sec3)
12 (Double Trailer, 6 Axle)	0.48%	6AX	0.48%	5	4443441	(合意) 2-	1.00534	THE R.
13 (Double Trailer, 7 Axle)	7,41%	7AX	7,41%	78	. 9	21	- 6 × 24-	[
TOTAL (MUST EQUAL 100%)	100.00%			1,052	306	342	176	228
DATE: 16-May-00 LOCATION: M-84 CONTROL SECTION: 9011 COMMERCIAL ADT 561 IN BASE YEAR 2002 DESIGN LIFE OF ROAD 20								
		RIGID		FLEXIBLE				
Growth Rate (percent)		1.30%		1.30%				
Type of Growth		Compound		Compound				
Initial Yearly 18-kip ESAL (both directions)		155,700	-	120,880				
Directional Distribution Factor		02%		02%				
The second s		80%		1 220 200				
Lane Distribution Factor		1 720 660		L L L L L L L L L L L L L L L L L L L				

Figure 52. Office memorandum on M-84 traffic information, page 5

OCATION	M-84	SW of DELTA						
CONTROL SECTION	9011							
CONSTRUCTION YEAR	2003							
NUMBER OF DESIGN YEARS (1-30)	20							
COMMERCIAL GROWTH RATE	1.30%							
TYPE OF GROWTH RATE - COMPOUND, AVERAGE (C OR A)	PHE							
DIRECTION DISTRIBUTION FACTOR	51%							
ANE DISTRIBUTION FACTOR	80%							
COMMERCIAL ADT IN BASE YEAR	312		312	CONSTRUCTION YEA	R CADT, 2	-Way		
PTION - AVERAGE, MEDIUM/HEAVY, CLASSIFICATION (A,MH)	C CS		1995	COUNT YEAR				
VERAGE ESAL - RIGID	0.85		12.4	NUMBER OF DAILY C	OUNT COL	LUMNS U	SED	
VERAGE ESAL - FLEXIBLE	0.67		0.9200	SEASONAL FACTOR	RAW ON	E-WAY I	DAILY CL	ASSIFIC.
COMMERCIAL CLASSIFICATION PERCENTAGES			PCT	ROW SUM	1	2	3	4
5 (Single Unit, 2 Axle)	27.82%	2AX	27.82%	170	53:133-	.57	3%%2418	1:4-1-39.
6 (Single Unit, 3 Axle)	7.20%	3AX	7.20%	. 44	acak; 13;	TN: 85 9 .	Assembly.	3336.11
7 (Single Unit, 4 Axle)	2.95%	4AX	2.95%	18	persent.	mercia:4	Sing 5	N25-273;
8 (Single Trailer, 4 Axle)	36.33%	4AX	36.33%	222	winter 43	(h. S. 72)	50	-Ra#5.57
9 (Single Trailer, 5 Axle)	5.89%	5AX	5.89%	36	指读的现7-	120 g to 9:		asianal2
10 (Single Trailer, 6 Axle)	4.91%	6AX	4.91%	30	NEWS H 6	+ 5 × 10,	123.272;	12.
11 (Double Trailer, 5 Axle)	3.44%	5AX	3.44%	21	line and 3	.49	A	· 这段书刊;
12 (Double Trailer, 6 Axle)	0.98%	6AX	0.98%	6	addised.	enze 2		3-12.3
13 (Double Trailer, 7 Axle)	10.47%	7AX	10.47%	64	17.80.9.	6	A 15	22m 34
TOTAL (MUST EQUAL 100%)	100.00%			611	121	178	134	178
DATE: 15-May-00 LOCATION: M-84 CONTROL SECTION: 9011 COMMERCIAL ADT 312 N BASE YEAR 2003 DESIGN LIFE OF ROAD 20	1							
		RIGID		FLEXIBLE				
		1.30%		1.30%				
Growth Rate (percent)		Compound		Compound				
Growth Rate (percent) Type of Growth		- 08.600		76,220				
Growth Rate (percent) Type of Growth Initial Yearly 18-kip ESAL (both directions)		50,000						
Growth Rate (percent) Type of Growth Initial Yearly 18-kip ESAL (both directions) Directional Distribution Factor		51%		51%				
Growth Rate (percent) Type of Growth nitial Yearly 18-kip ESAL (both directions) Directional Distribution Factor Lane Distribution Factor		51% 80%		51% 80%				

Figure 53. Office memorandum on M-84 traffic information, page 6

OCATION	M-84	NE of I-75					
CONTROL SECTION	9011						
CONSTRUCTION YEAR	2003						
NUMPER OF DESIGN VEARS (1.30)	2000	•					
COMMERCIAL CROWTH PATE	1 30%						
TWO AS AD ANTE ANTE COMPANIED AVERAGE (C OP A)	1.00%						
DIDECTION DISTRIBUTION FACTOR	50%						
LANE DISTRIBUTION FACTOR	80%						
	451	451	CONSTRUCTION YEA	R CADT. 2	-Wav		
COMMERCIAL ADT IN DAGE TEAR	-1+ CS	- 1995	COUNT YEAR				
AVEDAGE EGAL . DIGID	1.04	1.1.5/r 41	NUMBER OF DAILY O	COUNT CO	LUMNS U	ISED	
	0.77	0.9200	SEASONAL FACTOR	RAWON	E-WAYI	DAILY CI	ASSIFI
COMMERCIAL CLASSIFICATION PERCENTAGES	0.17	PCT	ROW SUM	1	2	3	4
5//Single Linit 2 Avia)	19.10%	2AX 19.10%	169	20- 43	43.	- tes41-	Scor 42
S (Single Unit 3 Ayle)	15.14%	3AX 15.14%	134	. 31	- es- 31-	4=539	Retrail33
7 (Single Unit 4 Ayle)	1.24%	4AX 1.24%	11	22330 4	patien 2	Section 3	NE HAR2
81/Single Trailer 4 Ayle)	20.45%	4AX 20.45%	181	- 39	46	Scholy 51	Sectore45
Q (Single Trailer 5 Ayle)	18,76%	5AX 18.76%	166	33.04 48.	40	Sec.1237	41
10//Single Trailer, 6 Avie)	3 16%	6AX 3.16%	28	-54Che114	1.5000031	100-16	With start &
11 (Double Trailer 5 Axle)	0.68%	5AX 0.68%	6	Assist	Sec. 31	progent.	S. Preside
12 (Double Trailer, 5 Axle)	0.11%	6AX 0.11%	1			pene ante	1.076 688
13 (Double Trailer 7 Axle)	21.36%	7AX 21.36%	189	1. 1. 45	1463	37:37	20244961
TOTAL (MUST EOUAL 100%)	100.00%		885	222	214	216	233
DATE: 12-May-00 LOCATION: M-84 CONTROL SECTION: 9011 COMMERCIAL ADT 451 IN BASE YEAR 2003 DESIGN LIFE OF ROAD 20							
		RIGID	FLEXIBLE				
Growth Rate (percent)		1.30%	1.30%				
Type of Growth		Compound	Compound				
Initial Yearly 18-kip ESAL (both directions)		1/1,350	120,870				
Directional Distribution Factor		50%	50%				
		8078	0070				
Lane Distribution Factor		1 554 150	1 150 650 1				

Figure 54. Office memorandum on M-84 traffic information, Page 7

LOCATION .	M-84 SV	V of SALZBURG RD							
CONTROL SECTION	9011								
	2003								
NUMBER OF DESIGN VEARS (1.30)	20.								
COMMERCIAL CROWTH PATE	1 30%								
COMMERCIAL GROWTH RATE	C.								
DIDECTION DISTRIBUTION EACTOR	Ter. 67%								
LANE DISTRIBUTION FACTOR	80%								
CANE DISTRIBUTION PAGE VEAP	389		389	CONSTRUCTION YEA	R CAD	T, 2-	Way		
COMMERCIAL ADT IN DAGE I CAN	CS		-1996	COUNT YEAR					
AVEDACE EDAL BIGID	0.86		- 4	NUMBER OF DAILY C	OUNT	COL	UMNS U	ISED	
AVERAGE ESAL - RIGID	0.66		1.0000	SEASONAL FACTOR	RAW	ON	E-WAY I	DAILY CL	ASSIFIC
AVERAGE EGAL + FLEAIDLE	0.04		PCT	ROW SUM		1	2	3	4
COMMERCIAL CLASSIFICATION FERCENTAGES	12 80%	2AX	12.80%	91		19	29		23.24
5 (Single Unit, 2 Axie)	32 77%	3AX	32.77%	233	See.	16	1. dag 20.	604.117.	A. 16,80
6 (Single Unit, 5 Axie)	2 1 1 96	44X	2.11%	15	344.227	5.	realized In	section 4	diameters.
/ (Single Unit, 4 Axie)	28.55%	4AX	28.55%	203	2:10	44	mart41a	176.2 46	·
8 (Single Trailer, 4 Axie)	7 74%	5AX	7.74%	55	12.4	19		ami(12:	11.10-11
9 (Single Trailer, 5 Axie)	1.1470	BAX	4 50%	32	42-41	- 1	12005	12	····· 14
10 (Single Trailer, 6 Axie)	2 25%	54X	2.25%	16	24987.4	0	dentable 0 -	Jak 1. 7:	Starts 9
11 (Double Trailer, 5 Axie)	0.4296	6AX	0.47%	3	SL Qr	0	0.5258.04	2.	\$940%s-1
12 (Double Trailer, 6 Axie)	0.42.70	74X	8 86%	63		7		×	18
13 (Double Trailer, 7 Axie)	100.00%	1755	0.0070	711	1	11	125	241	234
DATE: 12-May-00 LOCATION: M-84 CONTROL SECTION: 9011 COMMERCIAL ADT 389 IN BASE YEAR 2003									
DESIGN LIFE OF ROAD 20		RIGID		FLEXIBLE					
Growth Rate (percent)		1.30%		1.30%					
Trend of Crowth		Compound		00 000					
Type of Growth		122,150		87%					
Initial Yearly 18-kip ESAL (both directions)		D/%	1	0775					
Initial Yearly 18-kip ESAL (both directions) Directional Distribution Factor		600/	-	80%					
Initial Yearly 18-kip ESAL (both directions) Directional Distribution Factor Lane Distribution Factor		80%		1 101 540					

Figure 55. Office memorandum on M-84 traffic information, Page 8



OFFICE MEMORANDUM

DATE: July 27, 2001

TO: Dave Wresinski Manager Project Planning Section

FROM: Mark J. Grazioli Supervising Geotechnical Engineer - Metro

 SUBJECT:
 C.S. 82122 & 82123 J.N. 52803; I-96, M-39 to Schaefer Rd.

 82122 Milepoints - 11.72 to 12.05
 82123 Milepoints - 0.00 to 2.53

 ESAL Loading request for Life Cycle Cost Analysis (LCCA)

Please provide 20 year flexible and rigid ESAL loading projections for the above listing **2005** reconstruction project. In addition, please supply a base year total ADT, commercial ADT, growth rates for both commercial and total ADT, pattern type, 24 hour ADT distribution for weekdays and weekends, lane distribution and directional distribution.

Attached for your reference is information your section provided us during project scoping. Please review the information to verify this is the most recent and representative data available. It should also be noted the original base year of the project has changed from 2001 to 2005.

I request this information be sent to myself and Curtis Bleech (Lansing C&T) by October 31, 2001 to begin work on the pavement design for the LCCA. If you have any questions, I can be contacted by phone at (248) 483-5164.

METRO REGION SOILS & MATERIALS OFFICE

Marth J. Duayoh

Attachment cc: R. Ostrowski C. Bleech S. Minton

11

Figure 56. Office memorandum on I-96 traffic information, page 1



OFFICE MEMORANDUM

Michigan Department of Transportation DATE: September 06, 2001

TAR # 735

TO: Mark J. Grazioli Supervising Geotechnical Engineer - Metro

FROM: Ron Katch Transportation Planner

 SUBJECT:
 ESAL Loading and Traffic Projections for I-96, M-39 to Schaefer Road

 CS 82122 MP 11.72 to 12.05, CS 82123 MP 0.00 to 2.53
 Wayne County, JN 45703

 52 807
 52 807

This report provides the requested traffic data as well as the 20 year flexible and rigid ESAL loading projections for the above 2005 reconstruction project.

CS 82122, JN 52803, MP 11.72 -12.05	2005
Total ADT	191,800
Commercial ADT	9,600
Total Growth Rate	1%
Commercial Growth Rate	2%
Pattern Type	3 Urban
Directional Distribution	56% at DHV

CS 82123, JN 52803, MP 0.00 - 2.53	2005
Total ADT	181,300
Commercial ADT	7,250
Total Growth Rate	1%
Commercial Growth Rate	2%
Pattern Type	3 Urban
Directional Distribution	56% at DHV

12

Figure 57. Office memorandum on I-96 traffic information, page 2

ESAL Loadings

DATE:	06-Sept-2001
LOCATION:	I-96, CS82122, MP 11.72-12.05
CONTROL SECTION:	82122
COMMERCIAL ADT	9,600
IN BASE YEAR	2005
DESIGN LIFE OF ROAD	20

	RIGID	FLEXIBLE
Growth Rate (percent)	2.00%	2.00%
Type of Growth	Compound	Compound
Initial Yearly 18-kip ESAL (both	3,468,960	2,382,720
directions) .		
Directional Distribution Factor	56%	56%
Lane Distribution Factor	70%	70%
Total 18 Kip Axle Loadings	33,040,350	22,694,380

ESAL Loadings

DATE:	06-Sept-2001
LOCATION:	I-96, CS82123, MP 0.00-2.53
CONTROL SECTION:	82123
COMMERCIAL ADT	7,250
IN BASE YEAR	2005
DESIGN LIFE OF ROAD	20

	RIGID	FLEXIBLE
Growth Rate (percent)	2.00%	2.00%
Type of Growth	Compound	Compound
Initial Yearly 18-kip ESAL (both	2,619,790	1,799,450
directions)		
Directional Distribution Factor	56%	56%
Lane Distribution Factor	70%	70%
Total 18 Kip Axle Loadings	24,952,370	17,138,990

13

Figure 58. Office memorandum on I-96 traffic information, page 3

24 Hou	ır Typic	al Weekday	Traffic Di	stribution by Hour*
1-96				
HOUR T	OTAL T	OTAL%		
1	1503	1.21%		
2	712	0.57%		
3	622	0.50%		
4	562	0.45%		
5	741	0.60%		
6	2811	2.26%		
7	9973	8.03%		
8	9774	7.87%		
9	9218	7.43%		
10	5621	4.53%		
11	4838	3.90%		
12	5131	4.13%		
13	4392	3.54%		
14	5219	4.20%		
15	7595	6.12%		
16	9045	7.29%		
17	8782	7.07%		
18	12226	9.85%		
19	7946	6.40%		
20	4948	3.99%		
21	3687	2.97%		
22	3481	2.80%		
23	2823	2.21%		
70TAL 4	2498	2.01%		
Notestata	124140 I traffic m	99.99%	ADT It will	renresent a tynical weekday
(Note: tota	i traffic file	bour of day)	ADT: It will	represent a typical weekday
traffic disu	noution by	nour or day)		
* A 24 hou	ır ADT dis	tribution for wee	ekends was no	ot available.
If you need	d additiona	l information ple	ease call me a	t 517-335-2942.
				Ren Titch Project Planning Division
82123JN5	2803.wpd			
cc: C.	Bleech			
			14	

Figure 59. Office memorandum on I-96 traffic information, page 4

Michigan De	IDOT	OFFICE MEMORANDU
DATE:	July 27, 2001	TAR
то:	Dave Wresinski Manager Project Plann	ing Section
FROM:	Mark J. Grazioli Supervising Geotechni	ical Engineer - Metro
SUBJECT:	C.S. 82122 & 82123 J. 82122 Milepoints - 11 82123 Milepoints - 0.0 ESAL Loading request	N. 52803; I-96, M-39 to Schaefer Rd. .72 to 12.05 00 to 2.53 t for Life Cycle Cost Analysis (LCCA)
Please provide reconstruction p rates for both co weekends, lane	20 year flexible and right project. In addition, please commercial and total ADT, distribution and direction	id ESAL loading projections for the above listing 20 e supply a base year total ADT, commercial ADT, grow pattern type, 24 hour ADT distribution for weekdays and distribution.
Attached for yo eview the info also be noted th	ur reference is information rmation to verify this is the original base year of the	n your section provided us during project scoping. Ple he most recent and representative data available. It sho e project has changed from 2001 to 2005.
request this in to begin work o by phone at (24	formation be sent to myse n the pavement design for 8) 483-5164.	If and Curtis Bleech (Lansing C&T) by October 31, 20 the LCCA. If you have any questions, I can be contac
Attachment cc: R. Ostrowsk C. Bleech S. Minton	ME 	Marth J. Huarish
		15

Figure 60. Office memorandum on I-96 traffic information, page 5

	Equ	ivalency facto	ors defined for a terminal serviceabilty	index of 2.5 and an SN of 4.0
Load		Total Month	ily Single Axle	Single Axle
Interval	1	Single Axle	s Equivalency Factor	ESALs per month
	3	22369.24	0.0009	20.13231
	4	17000.01	0.003	51.00004
	5	25415.21	0.006	152.4913
	6	23417.24	0.01	234,1724
	7	27215.42	0.02	544.3084
	8	36834.78	0.04	1473.391
	9	48729.55	0.07	3411.068
	10	57654.36	0.1	5765.436
	11	52850.35	0.15	7927.552
	12	39258.52	0.21	8244.289
	13	24251.62	0.29	7032.97
	14	15823.61	0.39	6171.207
	15	10639.11	0.51	5425.947
	16	8671.863	0.65	5636.711
	17	6492.234	0.81	5258.71
	18	5147.586	1	5147.586
	19	3956.407	1.22	4826.816
	20	3000.41	1.47	4410.603
	21	2206.793	1.76	3883.956
	22	1572.119	2.09	3285.729
	23	1177.366	2.47	2908.094
	24	807.4009	2.89	2333.389
	25	570.2987	3.37	1921.907
	26	477,4475	3.91	1866.82
	27	415.0758	4.52	1876.143
	28	229,1916	5.21	1194.088
	29	210.3431	5.97	1255.748
	30	115.0896	6.83	786.0623
	31	104.3596	7.79	812.9611
	32	139.7964	8.85	1237.198
	33	67.53683	10.03	677.3944
	34	42.14497	11.34	477.924
	35	33.02382	12.78	422.0444
	36	33.8574	14.38	486.8694
	37	25.58519	16.14	412.945
	38	21.68085	18.06	391.5561
	39	12.49529	20.18	252.155
	40	15.74817	22.5	354.3339
	41	0	25.03	0
			Total Single Axle ESALs	98571.71 Average Monthly Total

Figure 61. I-96 ESAL estimation using traffic and load distribution, page 1

Load	-	Total Monthly	Tandem Axle	Tandem Axle	9
Interval		Tandem Axles	Equivalency Factor	ESALs per n	nonth
	6	16081.51	0.001	16.08151	
	8	17610.85	0.004	70.44342	
	10	28335.5	0.01	283.355	
	12	32567.69	0.02	651.3538	
	14	33152.25	0.03	994.5675	
	16	30210.68	0.06	1812.641	
	18	25569.11	0.09	2301.22	
	20	24349.78	0.14	3408.969	
	22	23346.65	0.21	4902.796	
	24	22147.3	0.29	6422.716	
	26	22351.43	0.4	8940.571	
	28	23550.19	0.53	12481.6	
	30	26081.43	0.7	18257	
	32	25497.96	0.89	22693.18	
	34	22893.94	1.11	25412.27	
	36	18115.12	1.38	24998.87	
	38	13429.66	1.68	22561.84	
	40	9328.701	2.03	18937.26	
	42	6258.147	2.43	15207.3	
	44	4221.107	2.88	12156.79	
	46	2928.97	3.4	9958.499	
	48	1928.891	3.98	7676.985	
	50	1310.434	4.64	6080.414	
	52	878.2857	5.39	4733.96	
	54	730.9799	6.22	4546.695	
	56	447.6609	7.16	3205.252	
	58	300.2344	8.22	2467.927	
	60	205.6893	9.4	1933.479	
	62	172.3225	10.94	1885.208	
	64	117.4058	12.17	1428.829	
	66	123.6668	13.8	1706.602	
	68	86.26648	15.6	1345.757	
	70	77.74016	17.59	1367.449	
	72	53.3484	19.78	1055.231	
	74	30.95507	22.2	687.2026	
	76	27.33473	24.85	679.2682	
	78	20.08514	27.76	557.5636	
	80	31.49005	30.95	974.617	
	82	0	34.43	0	_
			Total Tandem Axle ESAI	Ls 254801.8	Average Monthly Total

Figure 62. I-96 ESAL estimation using traffic and load distribution, page 2

Load	Total Mont	hly Tridem Axle	Tridem Axle
Interval	Tridem Axl	es Equivalency Factor	ESALs per month
12	2874.867	0.004	11.49947
15	1584.6	0.01	15.846
18	1316.194	0.02	26.32388
21	1070.463	0.04	42.81853
24	968.7973	0.07	67.81581
27	953.9064	0.11	104.9297
30	990.1771	0.17	168.3301
33	1013.019	0.25	253.2547
36	1311.676	0.35	459.0866
39	1329.255	0.48	638.0422
42	1277.69	0.64	817.7216
45	1001.742	0.84	841.4629
48	1016.317	1.07	1087.46
51	727.588	1.34	974.9679
54	611.6328	1.66	1015.311
57	501.2638	2.02	1012.553
60	298.0641	2.44	727.2763
63	239.8152	2.92	700.2605
66	255.4777	3.47	886.5075
69	129.3208	4.09	528.922
72	124.6776	4.8	598.4526
75	104.839	5.59	586.0498
78	95.54993	6.49	620.119
81	52.70166	7.5	395.2624
84	54.05269	8.63	466.4747
87	19.59264	9.9	193.9671
90	20.4685	11.32	231.7034
93	24.38126	12.91	314.7621
96	8.41352	14.67	123.4263
99	9.148167	16.63	152.134
102	9.707705	18.8	182.5048
		Total Tridem Axle ESALs	14245.24 Average Monthly Total
		Cumulative Monthly ESALs	367618.7 Average Monthly Total - All Axles
		Cumulative Annual ESALs	4411425 Average Annual Total - All Axles
		ESALs per Truck Truck Equivalency Factor	1.258968 Average Annual Value

Figure 63. I-96 ESAL estimation using traffic and load distribution, page 3

Appendix C: Pavement Design Data



Figure 64. M-84 Original AASHTO 1993 pavement design, 20 years

1993 AASHTO Pavement Design

DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare Computer Software Product

Flexible Structural Design Module

M-84: Pierce Rd to Euclid Ave HMA Reconstruction - Perpetual - 40 Year Estimated

Flexible Structural Design

18-kip ESALs Initial Servicea Terminal Servi Reliability Lev Overall Standa Roadbed Soil J Stage Construc Calculated Des	Over Initial Performance Period ability iceability el rd Deviation Resilient Modulus stion sign Structural Number	Specifie	2,640,000 4.5 2.5 95 % 0.49 3,060 psi 1 5.64 in d Layer Des	ign		
Layer 1 2 3 4 5 Total	Material Description 5E3 - Top Course 4E3 - Leveling Course 3E3 - Base Course DGAB Sand Subbase -	Struct Coef. (Ai) 0.42 0.42 0.42 0.14 0.1	Drain Coef. (Mi) 1 1 1 1 -	Thickness (Di)(in) 1,5 2 3 12 13.5 32.00	Width (ft) - - - - -	Calculated <u>SN (in)</u> 0.63 0.84 1.26 1.68 1.35 5.76
			1 age 1			

Figure 65. M-84 Estimated AASHTO 1993 pavement design, 40 years

1993 AASHTO Pavement Design

DARWin Pavement Design and Analysis System

A Proprietary AASHTOWare Computer Software Product Michigan Dept of Transportation

Flexible Structural Design Module

196 from M39 to Schaeffer Rd. C.S. 82123 - Job 52803

Flexible Structural Design

22,700,000

4.5 2.5 95%

0.49

1

3,000 psi

18-kip ESALs Over Initial Performance Period Initial Serviceability Terminal Serviceability Reliability Level Overall Standard Deviation Roadbed Soil Resilient Modulus Stage Construction

Calculated Design Structural Number

Layered Thickness Design

Actual

7.46 in

Thickness precision

		Struct	Drain	Spec	Min	Elastic		Calculated	
		Coef.	Coef.	Thickness	Thickness	Modulus	Width	Thickness	Calculated
Layer	Material Description	(Ai)	(Mi)	(Di)(in)	(Di)(in)	(psi)	(ft)	<u>(in)</u>	SN (in)
1	Gap Graded SuperPave	0.42	1	2	-	390,000	12	2.00	0.84
2	Bit Mixture 4E30	0.42	1	2.5	-	390,000	12	2.50	1.05
3	Bit Mixture 3E30	0.36	1		-	275,000	12	7.02	2.53
4	OGDC 21AA Mod	0.14	1	16	-	30,000	12	16.00	2.24
5	Sand Subbase	0.1	1	8	-	13,500	12	8.00	0.80
Total	-	-	-	-	-	-	-	35.52	7.46

Figure 66. I-96 Original AASHTO 1993 pavement design, 20 years

	DARW1n Pave	ement De	esign an	d Analysis	System	
	A C	Proprietar omputer S	y AASHT oftware P	OWare roduct		
	Flexi	ble Struct	ural Desig	n Module		
	196 from	n M39 to Schaef 40 Ye	fer Rd. C.S. 821 ear Estimated	23 - Job 52803		
	1	Flexible St	ructural D	esign		
18-kip ESA Initial Servi Terminal Se Reliability I Overall Star Roadbed So Stage Const	Ls Over Initial Performance Period ceability rviceability .evel dard Deviation il Resilient Modulus ruction	5 4 2 9 0 0 3 1	6,000,000 .5 .5 5 % .49 ,000 psi			
Calculated I	Design Structural Number	8	.32 in			
		Specified	Layer Des	sign		
Layer 1 2 3 4 5 Total	Material Description Gap Graded SuperPave Bit Mixture 4E30 Bit Mixture 3E30 OGDC 21AA Mod Sand Subbase	Struct Coef. (<u>Ai</u>) 0.42 0.42 0.36 0.14 0.1	Drain Coef. <u>(Mi)</u> 1 1 1 1 -	Thickness (Di)(in) 1.5 2.5 10 16 8 38.00	Width (ft) - - - - -	Calculate <u>SN (in)</u> 0.63 1.05 3.60 2.24 0.80 8.32



Figure 68. Sand subbase average repeated load resilient modulus test results extracted from LTPP database for I-96 ME-based designs



Figure 69. Aggregate base (21AA) average repeated load resilient modulus test results extracted from LTPP database for I-96 ME-based designs



Figure 70. HMA surface and leveling course layers monthly average dynamic modulus values per Witczak dynamic modulus regression equation for ME-based designs



Figure 71. HMA base course layer (upper portion) monthly average dynamic modulus values per Witczak dynamic modulus regression equation for ME-based designs

Mi	chiga of Tr 05828	in Departm ansportation BM(11/01) DIST	nt RIBUTK	MOI	STUI	RE A	ND N neer, Ci	DEN UCLEAR OPIES - An	SITY I METHO ea Density : E SIDE	DETE D Superviso	RMINA	TIO	N (Lansing).	ILE 301	
DAT	E		CONTROL	SECTION ID		JOB NU	MBER		ROUTI	E NO. or STR	EET		GAUGE NO). 102020	• •	
DEN:	9-05 SITY I	NSPECTOR		CERTIF	ICATION NO	L	31 PR	804 OJECTENGINE	ER (MDOT)	M-84 S	B Bay Road		PROJEC	TU2839	PHONE NO.	
Kur	t S.	Bancroft			10513-	0408		Lou	is Taylor	E DENG	Mike Ea	cker	(517) 388	17) 388-1053	
TE	ST	w	T DENS	ITY	M	OISTURE	WIINA	D	RY DENSIT	Y		LOCATION OF T		ST		
ORIGINAL	RECHECK	COUNTS (DC)	TEST DEPTH mm	WET DENSITY kg /m ^a	COUNTS (MC)	MOIS- TURE kg/m ³	MOIS- TURE %	DRY DENSITY kg /m ³	MAX DENSITY kg /m ³	PERCENT OF COM- PACTION	STATION		FROM 3	E PLI E PLI PLI	AN OF WORK	
1	2	3	4	5	6	7	8	9	10	11	12	1	3	14 1	5 16	
LI		690	BS	2300	102	127.7	5.9		2436	94.4	14+240			.8	BT	
LI		683	BS	2311	100	124.7	5.7		2436	94.9	14+220		1	.8	BT	
LI		674	BS	2326	99	123.3	5.6		2436	95.5	14+200		1	.8	BT	
LI		671	BS	2331	103	129.1	5.9		2436	95.7	14+180		1	.8	BT	
LI		707	BS	2272	[11	140.9	6.6		2436	93.3	14+160		1	.8	BT	
LI		699	BS	2285	102	122.7	5.9		2436	93.8	14+140		1	.8	BT	
Ll		699	BS	2285	101	126.2	5.8		2536	93.8	14+120		1	.8	BT	
L1	.1 699 BS		2301	101	126.2	5.8		2436	94.5	14+100		1	.8	BT		
									-				-			
			DETER	MINATIO	OF MA	(IMUM I	DENSI	Y (Soil &	Bituminou	is)			N/	DTE.		
TE N	SТ 0.	MOIS- TURE	VOLU MOL		T SOIL + IOLD	MOLI	DENSI W	ET SOIL O	MINATION OMPACTED SOIL WET	MAX DENSITY Ko/m ³	OPTIMUM MOISTURE	T Vol. (o convert (ft ⁻³) x 0.00	t (ft ³) to (r 2832 = Vo	m ³): ∈(m ³)	
1		2	3		4	5		6	7	8	9	C	HART ST	ANDARD	\$ TURE	
							-					021	2598		656	
												2546		630		
												DEN	ERATING SITY	MOIS	RDS	
												2584		642		
										2-1100		BITUMIN	OUS MIX	DESIGN k	g/m ³	
EM	VRKS											2436				
M-8	4 Pe	rpetual P	avemen	t Demo Pr	oject Bit	uminou	s Top C	Course								
.1-8	SBO	L, L2=SI	BIL													
1.2						DENSI	INSPE)	CTOR'S SIGN	ATURE		AGENCY/CON	IPANY				

Appendix D: Pre- and Post-Construction Related Records

Figure 72. Moisture and density determination on M-84 SB HMA-top layer, page 1

FILE 301 Michigan Department of Transportation MOISTURE AND DENSITY DETERMINATION NUCLEAR METHOD 0582BM (11/01) DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing). SEE REVERSE SIDE DATE CONTROL SECTION ID JOB NUMBER ROUTE NO. or STREET GAUGE NO. 102839 M-84 SB Bay Road 11-9-05 09011 31804 DENSITY INSPECTOR CERTIFICATION NO. PROJECT ENGINEER (MDOT) PROJECT MANAGER FROJECT MANAGER PHONE NO Kurt S. Bancroft 10513-0408 Louis Taylor Mike Eacker (517) 388-1053 DETERMINATION OF IN-PLACE DENSITY TEST WET DENSITY MOISTURE LOCATION OF TEST DRY DENSITY DEPTH DISTANCE FROM £ ITEM ORIGINAL RECHECK TEST WET MOIS-MOIS DRY MAX PERCENT OF COUNTS TURE DENSITY OF COM-PACTION DEPTH DENSITY COUNTS TURE DENSITY STATION PLAN (DQ) kg /m⁸ (MC) kg /m^a kg /m³ kg/m² % mm LEFT RIGHT m * 16 6 4 7 8 10 11 1 2 3 5 9 12 13 14 15 L2 692 BS 2276 108 136.5 6.3 2436 94.2 14+2401.8 BT L2BS 663 2344 102 127.7 5.8 2436 96.2 14+220 1.8 BT L2 BS 5.9 659 2351 104 130.6 2436 96.5 14 + 2001.8ΒT L2 657 BS 2354 100 124.7 5.6 2436 96.6 14+1801.8BТ L2 654 BS 2360 100 124.7 5.6 2436 95.8 14 ± 160 1.8 BT L2668 BS 2336 103 129.1 5.9 95.9 ΒT 2436 14 + 1401.8L2 676 BS2322 101 126,2 5.7 2536 95.3 14+120 1.8 ΒT L.2 675 BS2324 99 123.3 95.4 14 + 1005.6 2436 1.8 BT DETERMINATION OF MAXIMUM DENSITY (Soil & Bituminous) NOTE: DENSITY DETERMINATION WET SOIL + To convert (ft 3) to (m3); MORS. TEST OPTIMUM VOLUME MAX DENSITY Kg/m³ MOLD WET SOIL COMPACTED TURE Vol. (ft3) x 0.02832 = Vol. (m3) NO. MCLD m³ MOLD SOIL WET 56 Kg Kg/ Kg 4 9 CHART STANDARDS 6 8 DENSITY MOISTURE 2598 656 2546 630 OPERATING STANDARDS DENSITY MOISTURE 2584 642 BITUMINOUS MIX DESIGN kg /m³ 2436 REMARKS M-84 Perpetual Pavement Demo Project Bituminous Top Course L1=SBOL, L2=SBIL DENSITY INSPECTOR'S SIGNATURE AGENCY/COMPANY (2-2)

Figure 73. Moisture and density determination on M-84 SB HMA-top layer, page 2

Mi	chiga of Ta 05828	n Departm ansportatio 3M(11/01)	ent n	MOI	STU	RE A	ND		SITY I	DETE	ERMINA	TION		FILE MED	
		DIST	RIBUTI	UN: ORIGI	NAC - Proj	ec, engi	neer, C	SEE REVERS	E SIDE	Subervier	n, Denaty Teo	mology (c.	anang/.		\wedge
DAT	E		CONTROL	SECTION ID		JOB NU	MBER		ROUTI	E NO. or STR	RET	GA	UGE NO.	0020	
11- DEN	9-05 SITY I	ISPECTOR		09011	CATEON NO	. I	31	0.IECT ENGINE	RIMDOD	M-84 S	B Bay Koad		PROJECT MAN	WGER PHD	NE NO.
Ku	tS.	Bancroft			10513-	0408		Lou	is Taylor		Mike Ea	cker	(517)	388-1	053
						DETER	MINA	TION OF	IN-PLAC	E DENS	SITY				
	ST	w	ET DENS	ITY	M	DISTURE	MOID	DEV	RY DENSITY	PERCENT		LOCATION	STANCE	DEPTH	ITEN
NIGINA	CHEC	COUNTS	DEPTH	DENSITY kg (m ²	COUNTS	TURE ko/m ³	TURE	DENSITY ka /m ³	DENSITY ka /m ³	OF COM-	STATION		FROM£	PLAN GRADE	OF WOR
_ <u>ð</u>	2	3	4	5 S	6	7	70	8	10	11	12	13	RIGHT 14	15	18
<u> </u>	-	693	BS	2295	103	129.1	6.0		2436	94.2	16+240		1.8		BT
LI		708	BS	2271	101	126.2	5.9		2436	93.2	16+220		1.8		BT
LI		689	BS	2301	103	129.1	5.9		2436	94.5	16+200		1.8		BT
LI		688	BS	2303	106	133.5	6.2		2436	94.5	16+180		1.8		BT
LI		681	BS	2314	104	130.6	6.0		2436	95.0	16+160		1.8		вт
Ll		695	BS	2292	103	125.1	6.0		2436	94.1	16+140		1.8		BT
Ll		685	BS	2308	98	121.8	5.6		2536	94.2	16+120		1.8		BT
Ll		674	BS	2326	97	120,3	5.5		2436	95.5	16+100		-1.8		BT
										-				1. n 1. n	s ýr
														- ¹	
			DETER	MINATIO	N OF MA	XIMUM	DENSI	TY (Soil &	l Bituminou	us)					L
т.	ет	MOIS.	1000	-			DENS	ITY DETER	MINATION	MAY	CARTINEM	То	convert (ft ³) to (m ³	k
N	10.	TURE	MO		MOLD	Ko	۰ I ۴		SOIL WET	DENSITY Ka/m ³	MOISTURE	Vol. (ff	^a) x 0.02832	= Vol. (m³)
	1	2	3		4	5	\pm	6	1	8	9	CH	ART STANE	ARDS	
												20ENS	598	MUISTL A	56
												2546	670	30	50
			+				+					2340 OPE	C.	NDARD	s
												DENS	ITY	MOISTL	IRE
•			-									2584	64	2	
												BITUMINO	US MIX DES	itaN kg h	nª
												2436			
REN M-S	arka 34 Pe	s erpetual I	avemer	it Demo Pi	roject Bi	tuminou	s Top (Course							
1.1-	SBC)[. [.2=8	BIL		J										
(1-1	0					DENSITY INSPECTOR'S SIGNATURE AGENCY/CC									
12-2	9														

Figure 74. Moisture and density determination on M-84 SB HMA-top layer, page 3

	07 114 0582B	M(11/01) DIST	" RIBUTK	ON: O	RIGI	NAL - Proj	ect Engi	h neer, Ci * ق	UCLEAR OPIES - An REE REVERS	R METHO ea Density - E SIDE	D Supervis	or, Density Tec	hnology (L	ansing).		iilc
DATI	E		CONTROL	SECTIO	NID		JOB NU	MBER		ROUT	E NO. or S1	TREET	G	NUGE NO.	00000	
11-9 DENK	9-05	PRECTOR		- 05	9011 CERTIE	ICATION NO		31	804	ER MOOD	M-84	SB Bay Road	. 1	PROJECT M	U2839	ME NO.
Kur	t S. 1	Bancroft				10513-	0408		Lou	is Taylor		Mike Ea	cker	(51	7) 388-1	053
							DETER	MINA	TION OF	IN-PLAC	E DEN	ISITY				
TE	ST	w	ET DENS	ITY		M	DISTURE		D	DRY DENSITY			LOCATION	N OF TEST	DEPTH	LITCH
DRIGINA	RECHEC	COUNTS (DC)	TEST DEPTH mm	DEN kg	AET ASITY /m ³	COUNTS (MC)	MOIS- TURE kg/m ³	MOIS- TURE %	DRY DENSITY kg /m ³	MAX DENSITY kg /m ³	OF COM PACTIO	NT N STATION	LEE	FROM £	BELOW PLAN GRADE	OF WOR
1	2	3	4		5	6	7	8	9	10	11	12	13	14	15	16
L2		669	BS	23	34	108	136.5	6.2		2436	95.8	16+240	1.8		_	ВТ
L2	_	662	BS	23	46	101	126.2	5.2		2436	96.3	16+220	1.8		-	BT
L2		694	BS	22	94	107	135.0	6.3		2436	94.2	16+200	1.8			BT
L2		703	BS	22	79	103	129.1	6.0		2436	93.5	16+160	1.8			BT
1.2	_	672	BS	23	29	107	135.0	6.2		2436	95.6	16+140	1.8		1.0	BT
.2		685	BS	23	07	108	136.5	6.3		2536	94.7	16+120				ВТ
.2		688	BS	23	03	103	129.1	5.9		2436	94.5	16+100	1.8			BT
-															-	
+															+	
			DETER	MINA	TION	N OF MAX	KIMUM	DENSI	TY (Soil &	Bituminou	is)			NOT		L
TE N	8T D.	MOIS- TURE	VOLL MOL	ME	WE:	t soil + Nold	MOL	DENS D V	VET SOIL	MINATION CMPACTED SOIL WET	MAX	OPTIMUM Y MOISTURE	To Vol. (ft	convert (f) (²) x 0.028	te: t ³) to (m ³) 32 = Vol. (): m ³)
	i	2	3	·		Kg4	Kg 5		к <u>а</u> 6	Kg/m ^{-o} 7	Kg/m ⁻³	9	СН	ART STAN	DARDS	
													DENS	ITY	MOISTU	JRE
													2546	598	630 -	50
													DENS	RATING ST	MOIST	\$ JRE
													2584	(542	7110
													BITUMINO	US MIX DE	SIGN kg /r	m ³ .
EM	ARKS												2436			
4-8	4 Pe	rpetual P	avemen	it Der	no Pr	roject Bit	uminou	s Top (Course							
.1-3	SBO	L, L2=S	BIL				DELICI	The second	070000.000			107101000	Contract of the second s			

Figure 75. Moisture and density determination on M-84 SB HMA-top layer, page 4

FILE 301 Michigan Department of Transportation 05828M(11/01) MOISTURE AND DENSITY DETERMINATION NUCLEAR METHOD DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing).
* SEE REVERSE SIDE DATE ROUTE NO. or STREET CONTROL SECTION ID JOB NUMBER GAUGE NO 102839 M-84 SB Bay Road 10-10-05 11090 31804 DENSITY INSPECTOR CERTIFICATION NO. PROJECT ENGINEER (MDCT) PROJECT MANAGER SOURCE MANAGER PHONE NO. 10513-0408 Mike Eacker (517) 388-1053 Kurt S. Bancroft Louis Taylor DETERMINATION OF IN-PLACE DENSITY TEST WET DENSITY DRY DENSITY LOCATION OF TEST MOISTURE DEPTH DRUGINAL RECHECK TEST DRY DISTANCE ITEM WET MOIS-MOIS-MAX BELOW PLAN GRADE PERCENT FROM£ OF COUNTS DEPTH DENSITY COUNTS TURE TURE DENSITY DENSITY CF COM STATION WORK (00) kg /m⁸ (MC) PACTION m kg/m³ kg /m³ kg /m³ % mm LEFT RIGHT m ÷ 8 11 6 7 16 1 2 3 4 5 ġ, 10 12 13 14 15 LI 672 BS 2327 89 107.8 4.9 2508 92.8 16+240 1.8 BLL2662 BS 2343 107.8 2508 93.4 16+24089 4.8 1.8 BL. 2372 L1645 BS 95 116.5 5.2 1.8 2508 94.6 16+220 BLL2 663 BS2341 90 109.2 4.9 2508 93.4 16 + 2201.8 BLLí 629 BS 2401 89 107.8 4.7 2508 95.7 16 ± 200 1.8 BL L2 644 BS 2374 5.0 92 112.2 2508 94.7 16+2001.8 BLL1 615 BS2427 89 107.8 4.6 2508 96.8 16+1801.8 BL L2 641 BS2379 90 109.2 4.8 2508 94.9 16+180 1.8 BL Ll 662 BS 2343 89 107.8 4.8 2508 93.4 16+160 1.8BLL2 638 BS2384 97 119.4 5.3 2508 95.1 16+160 1.8 BL. DETERMINATION OF MAXIMUM DENSITY (Soil & Bituminous) NOTE: DENSITY DETERMINATION MOIS-TURE TEST WET SOIL + OPTIMUM To convert (ft³) to (m³): VOLUME MOLD WET SOIL COMPACTED MAX Vol. (ft³) x 0.02832 = Vol. (m³) MOLD DENSITY Kg/m³ MOISTURE NO. MOLD SOL WET Ka 54 Kg Kgm CHART STANDARDS 3 5 2 4 6 9 DENSITY MOISTURE 2613 656 630 2561 OPERATING STANDARDS DENSITY MOISTURE 2576 646 BITUMINOUS MIX DESIGN kg /m⁸ 2508 REMARKS M-84 Perpetual Pavement Demo Project L1=SBOL, L2=SBIL Bituminous Leveling Course DENSITY INSPECTOR'S SIGNATURE AGENCY/COMPANY (1-2)

Figure 76. Moisture and density determination on M-84 SB HMA-leveling layer, page 1

	of Tr 05625	ansportation M(11/01) DIST	RIBUTI	ON: ORIGI	NAL - Proj	KE A	AND N ineer, C * s	UCLEA	R METHO	DE IE D Superviso	r, Density Tec	hnology (L	N .ansing).	ME	ist A		
DAT	E		CONTROL	SECTION ID		JOB NU	MBER	Auto Price Price	ROUT	E NO. or STR	EET	0	AUGE NO.	<i>*</i>	¢.		
10- DEN	10-0 SITY I	5		09011	ICATION NO		31	804 CLECTENON	EER (MDOT)	M-84 S	B Bay Road		Тевсияст	02839	WE B		
Ku	tS.	Bancroft			10513-	0408		Lo	uis Taylor		Mike Ea	cker	(517) 388-1053				
				19th d	[DETER	MINA	FION OF	F IN-PLACE DEN		ITY						
-16	×	W	TEST	WET	10	MOIS	MOIS	DRV	DRY DENSIT	PEDCENT		LOCATIO	N OF TES	T DEPTH	IT		
ORIGIN	RECHEC	COUNTS (DQ)	DEPTH	DENSITY kg /m ^a	CCUNTS (MC)	TURE kg/m ³	TURE %	DENSITY kg /m ³	DENSITY kg /m ⁸	OF COM- PACTION	STATION	LEFT	FROM £ m T RIGH	BELOW PLAN GRADE (T m	w		
1	2	3	4	5	6	7	8	9	10	15	12	13	14	15	1		
L1		673	BS	2325	91	110.7	5.0		2508	92.7	16+140		1.8		E		
L2		647	BS	2368	97	119.4	5.3		2508	94,4	16+140	1.8	3		E		
LI		661	BS	2345	95	116,5	5.2		2508	93.5	16+120		1.8		E		
L2		639	BS	2383	95	118.0	5.2		2508	95.0	16+120	1.8		_	F		
LI		645	BS	2372	90	109.2	4.8		2508	94.6	16+100		1.8		B		
L2		661	BS	2345	99	115.1	5.2		2508	93.5	16+100	1.8			В		
													_		_		
										_	_						
	_													_			
		_	DETER	MINATION	OF MAX	(INSUINA)	DENRIT	V (Call 9	Diturning								
			DETER		V OF MIAC		DENSI	TY DETER	RMINATION	is)			NOT	TE:			
N	ST 0.	MOIS- TURE %	MOL		f SOIL + MOLD Kg	MOLI Kg	> w	ET SOIL Kg	COMPACTED SOIL WET Kg/m ³	MAX DENSITY Kg/m ³	OPTIMUM MOISTURE %	Vol. (ft	2) x 0.028	t") lo (m") 32 = Vol. (r	r ³)		
		2	3		4	5		6	7	8	9	DENS	ART STAL	NDARDS MOISTL	IRE		
							_					2	613	6	56		
												2561	ATING	630			
			ĺ									DENS	ITY	MOISTU	IRE		
												2576	ľ	646			
												BITUMINO	US MIX DE	SIGN kg /n	n ⁹		
												2508					
кем/ M-8	arks 4 Pe	rpetual Pa	avemen	t Demo Pr	oject												
L1=9	SBO	L L2=SF	IL B	tuminous	eveline	Course											
(2-2)		_, 01			areing.	DENSIT	Y INSPEC	CTOR'S SIG	NATURE		AGENCY/COM	IPANY					

Г

Figure 77. Moisture and density determination on M-84 SB HMA-leveling layer, page 2

FILE 301 Michigan Department MOISTURE AND DENSITY DETERMINATION of Transportation 0582BM (11/01) NUCLEAR METHOD DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing). SEE REVERSE SIDE DATE CONTROL SECTION ID JOB NUMBER ROUTE NO. or STREET GAUGE NO. 9-21-05 09011 31804 M-84 SB Bay Road 102839 DENSITY INSPECTOR CERTIFICATION NO PROJECT ENGINEER (MDCT) PROJECT MANAGER PROJECT MANAGER PHONE NO. 10513-0408 Kurt S. Bancroft Louis Taylor Mike Eacker (517) 388-1053 DETERMINATION OF IN-PLACE DENSITY TEST WET DENSITY MOISTURE DRY DENSITY LOCATION OF TEST DEPTH BELOW PLAN GRVDE ORIGINAL DISTANCE FROM £ TEM RECHECK TEST DEPTH WET DENSITY MOIS MOIS-TURE DRY MAX DENSITY ERCENT COUNTS COUNTS TURE DENSITY OF STATION OF COM-WORK * (DC)mm kg /m³ (MD) kg/m³ % kg /m³ kg /m³ PACTION LEFT RIGHT m 1 2 ą 4 6 6 7 8 9 10 11 15 16 12 14 13 Ll 642 BS 2393 93 113.8 5.0 95.4 14 + 2402508 BL1.8 L2 623 BS 2418 92 112.4 4.92508 96.4 14+240 1.8 BL L1646 BS 2386 91 110.9 4.9 2508 95.1 14 + 2201.8 BL L2BS 2395 100.7 641 84 4.4 95.5 2508 14 + 2201.8BL L1 683 BS 2374 89 108.04.8 2508 94.7 14 + 2001.8 BLL2630 BS 2414 95 116.7 5.1 2508 96.7 14 + 2001.8 BL L1 659 BS 2363 95 116.7 5.2 2508 94.2 14 ± 180 1.8 BL L2 634 BS 2407 88 106.5 4,6 2508 96.0 14 + 1801.8BL LI 662 BS2358 94 115.3 5.12508 94.0 14 + 1601.8 BLL2631 BS 2412 95 118.2 5.2 2508 95.2 14+160 1.8 BL DETERMINATION OF MAXIMUM DENSITY (Soil & Bituminous) NOTE: DENSITY DETERMINATION MOIS-WET SOIL + To convert (ft³) to (m³): MOLD COMPACTED OPTIMUM TEST VOLUME MAY WET SOIL MOLD SOIL WET Kg/m³ DENSITY Kg/m³ NO. TURE MOLD MOISTURE Vol. (ft³) x 0.02832 = Vol. (m³) Kg % Kg Kg % CHART STANDARDS 3 4 9 DENSITY MOISTURE 2613 656 630 2561 OPERATING STANDARDS DENSITY MOISTURE 2611 645 BITUMINOUS MIX DESIGN kg /m⁵ 2508 REMARKS M-84 Perpetual Pavement Demo Project L1=SBOL, L2=SBIL Bituminous Leveling Course DENSITY INSPECTOR'S SIGNATURE AGENCY/COMPANY (1-2)

Figure 78. Moisture and density determination on M-84 SB HMA-leveling layer, page 3

Mi	chiga of Tr 05828	n Departm ansportatio \$M(11/01) DIS1	ent n TRIBUTI			STUI	RE A		NUCLE	NS AR	METHO	DETE D Superviso				isina).	M-D MET	
		210					out ang	*	SEE REVE	ERSE	SIDE	o aportioo	, Dennig 100		1) (200	10 m 12 11		
DAT 0.2	E 1.05		CONTROL	SECTIC	N ID 901.1		JOB NU	MBER	1204		ROUT	E NO. or STR MR4 SI	EET B. Bay Road		GAU	BE NO. 1	02839	
DEN	SITY	NSPECTOR			CERTIF	ICATION NO		1	ROJECTEN	ANEE	R (MDOT)	P1-04 D1	ROJECT MANAGER			ROJECT	VANAGER PHC	NE N
Kur	tS.	Bancroft				10513-	0408		L	.oui:	s Taylor		Mike Ea	cker		(51	517) 388-1053	
						C	DETER	MINA	TION C	DF I	N-PLAC	E DENS	ITY				F07	
TE	ST ¥	w	ET DENS	ЩУ.		M	DISTURE				Y DENSIT	Y		LOCATION OF 1		ANCE	DEPTH	l m
IGINA	CHEC	COUNTS	DEPTH	DE	VET	COUNTS	TURE	TURE	DENSI	TY	DENSITY	OF COM-	STATION		FF	ROM É	PLAN	wo
B	REC	(00)	mm	kg	/m²	(MC)	kg/m ^a	%	kg /n	n ^a	kg /m ³	PACTION			LEFT	RIG	IT m	1
1.	.2	3	4		?			B	9		10	11	12	-+	13	14	15	1
ы		650	BS	23	79	91	110.9	4.9			2508	94.9	14+140			1.8		B
L2		593	BS	23	08	86	103.6				2508	92.0	14+140		1.8			В
LI		653	BS	23	74	87	105.1				2508	94.7	14+120			1.8		в
L2		643	BS	23	91	93	113.8				2508	95.3	14+120		1.8			в
LI		659	BS	23	63	96	1182				2508	94.2	14+100			1.8	:	В
L2		647	BS	23	85	86	103.6				2508	95.1	14+100		1.8			в
		1	DETER	MIN/	TION	OF MA)	KIMUM	DENS	ITY (Soil	& E	Bituminou	is)		-		NO	ne:	
TE N	ST 0,	MOIS- TURE	VOLL	ME	WEI	I SOIL +	MOLI	DEN	WET SOIL	CO	MPACTED OIL WET	MAX	OPTIMUM MOISTURE	l v	To co (ol. (ft ³)	nvert { x 0.028	t ³) to (m ³) 32 = Vol. (r): m ³)
	1	2	3			Kg 4	<u>ка</u> б		6	+	7 7	8 Kg/m-*	9		CHAR	T STA	NDARDS	
															ENSIT	Y	MOISTU	JRE
										+					26	13	6	56
	-													256	1		630	
															OPERA ENSIT	TING S	MOIST	S
														2611			645	
										T				BITU	MINOUS	MX D	SIGN ka /r	n ³
										ĺ				2508				
REM	ARKS									1	l			I				
w1-8	4 Pc	rpetual P	avemen	t Der	no Pr	oject												
L1=:	SBO	L, L2=S	BIL Bit	umin	ous L	eveling (Course DENSI	TY INSP	ECTORS	IGNA	TURE		AGENCY/COM	IPAN	,			
(2-2))																	

Figure 79. Moisture and density determination on M-84 SB HMA-leveling layer, page 4

	f Tra 682B	Departme insportation M(11/01)	n 1	Ν	101	STU	RE A	NE	NUCLEA	ISITY I	DET	ERMINA	TIO	N	M	DOT
		DIST	RIBUTI	ON: 0	ORIGI	VAL - Proj	ect Engi	neer, (*	SEE REVER	vrea Density RSE SIDE	Supervis	sor, Density Tecl	nnology (Lansing		
DATE		0	CONTROL	SECTO	ON ID		JOB NU	MBER		ROUT	E NO. or S	TREET		GAUGE NO		·
10-3	-05			0	9011	ONTION NO		3	1804	550 AUD 070	M-84	SB Bay Road		ano in	102839	NONE NO
Kurt	S. E	Bancroft			CENTIP	10513-	0408	ľ	L	uis Tavlor		Mike Ea	cker	(517) 388-	1053
						0	ETER	MINA	TION O	F IN-PLAC	EDEN	ISITY				
TES	π	WE	T DENS	ITY		M	DISTURE			DRY DENSIT	Υ		LOCATIO	ON OF TE	ST	HLm
RIGINAL	ECHECK	COUNTS (DO)	TEST DEPTH mm	DE ke	MET NSITY 1/m ³	COUNTS (MC)	MOIS- TURE kg/m ³	MOIS- TURE %	DRY DENSIT	(DENSITY kg /m ³	OF COM PACTIC	NT M-STATION		FROM I	E BELO PLAT	
	2	3	4		5		7	8	9	10	11	12	1	3	811 m 14 15	+
LI		660	BS	23	350	72	84.6	3.7		2532	92.8	16+240		1	.8	В
L2		656	BS	23	356	78	93.5	4.1		2532	93.0	16+240	1	.8		в
L1		630	BS	24	402	74	87.6	3.8		2532	94.8	16+220		1	.8	В
L2		706	BS	22	275	77	92.1	4.2		2532	89.8	16+220	1	.8		в
LI		626	BS	24	409	73	86.1	3.7		2532	95.1	16+200		1	.8	в
L2		619	BS	24	421	84	102.4	4.4		2532	95.6	16+200	1	.8		в
LI		645	BS	2	375	77	92.1	4.0		2532	93,8	16+180		1	.8	В
L2		641	BS	23	382	77	92.1	4.0		2532	94.1	16+180	1	.8		В
LI		635	BS	23	397	73	86,1	3.7		2532	94.6	16+160		1	.8	в
L2		627	BS	2/	407	78	93.5	4.0		2532	95.1	16+160	1	.8		В
			DETER	IMIN	ATIO	OF MA	CIMUM	DENS	ITY (Soil	& Bituminou RMINATION	us)			N	DTE:	
TE8 NC	ST).	MOIS- TURE %	VOLL MOL	ME D	WE	T SOIL + MOLD Kg	MOLI Ke	P	WET SOIL Kg	COMPACTED SOIL WET Kg/m ³	MAX DENSIT Kg/m ³	Y OPTIMUM MOISTURE	Vol.	fo conver (ft ³) × 0.0	t (ft ³) lo (m 2832 = Vol.	^a): (m ³)
1		2	3		-	4	6		ô .	7	8	9	DEN	HART ST	ANDARDS	TUDE
														2613	MOIS	656
													1561	2013	630	000
													DEN	ERATING ISITY	MOIST	DS
													2580		636	
													BITUMIN	IOUS MIX	DESIGN kg	/m ³
													2532			
REMA	RKS															
M-84	4 Pe	rpetual P	avemen	t De	mo Pi	oject										
L1=8	во	L. L2=SI	BIL Bi	tumi	nous I	Base Com	se									
(1-2)	20			and the		and Coll	DENSI	TY INSP	ECTOR'S SI	SNATURE		AGENCY/CO	IPANY			

Figure 80. Moisture and density determination on M-84 SB HMA-base layer, page 1

Mi	chiga of Tri 05825	n Oepartm ansportatio 34 (11/01) DIST	ent n rRIBUTIO	MC	DISTU	RE A	NC		AR METHO	DETI D Supervis	ERMINA	TIO	N (Lansing)	FILE MI-D MET		
							*	SEE REVER	RSE SIDE		allocation and a		0.1150F 140			
DAT 10-1	E 3-05		CONTROL	SECTION IS 0901	2	JOB NU	MUER 3	1804	ROUT	E NO. or ST M-R4 9	REET SB Bay Road		GAUGE NO.	102839		
DEN	SITY I	NSPECTOR		CEF	TIFICATION NO	<u></u>	PROJECT ENGINEER (MDOT) PROJ				PROJECT MANAGER	OJECT MANAGER PROJECT				
Kur	tS.	Bancroft			10513-	0408		Le	ouis Taylor		Mike Eac	cker	(5	17) 388-1	053	
					1	DETER	MINA	TION O	F IN-PLAC	EDEN	SITY	100171		0.7		
	81	w	ETDENS	ITY NET		MOISTURE		nev	DRY DENSIT	r Increase		LOGATI	DISTANC	DEPTH	ITEM	
GING	E COUNTS DEPT		DEPTH	DENSI	TY COUNTS	TURE	TURE	DENSIT	Y DENSITY	OF COM	STATION		FROM	BELOW	w	
ß	ž	(00)	mm	kg /m	, (MC)	kg/m ³	56	kg /m	* kg /m³	PACTION	N	LE	FT RIG	HT m		
	2	3	.4	5		7	8	9	10	11	12		3. 1	4 15	-	
Ll		640	BS	2384	82	99.5	4.4		2532	94.1	16+140		1.	.8	B	
L2		643	BS	2378	79	95.0	4.2		2532	93.9	16+140	1	.8		B	
Ll		643	BS	2378	81	98.0	4.3		2532	93.9	16+120		1.	.8	B	
L2		644	BS	2377	78	93.5	4.1		2532	93.9	16+120	1	.8		В	
Ll		642	BS	2380	76	90.6	4.0		2532	94.0	16+100		- 1.	.8	В	
L2		632	BS	2398	82	99.5	4.3		2532	94.7	16+100	1	.8		B	
			DETER	MINAT	ION OF MA	XIMUM	DENS	ITY (Soil	& Bitumino	us}					I	
TE N	ST O.	MOIS- TURE	VOLL		NET SOIL + MOLD	MOL	DENS	WET SOIL	COMPACTED SOIL WET	MAX	OPTIMUM MOISTURE	Vol.	NC To convert (ft ³) x 0.02	7 TE: (ft ³) to (m ³ 832 = Vol. (): m ³)	
	1	2	3	,	Kg 4	Kg 5		Kg 6	Kg/m* 7	Kg/m* 8		0	HART ST	ANDARDS		
							T					DEN	ISITY	MOISTU	JRE	
												2561	2613	613 65 630		
			1									OP	ERATING	STANDARD	s	
												2580	ISITY	636		
												BITUMIN	IOUS MIX I	DESIGN kg /r	m ^a	
												2532				
REM M-8	arks 14 Pc	s apetual F	avemen	t Demo	Project											
L1=	SBC)L, L2=S	BIL Bit	uminou	s Base Cour	se										
(2-2)					DENS	TY INSP	ECTORSS	GNATURE		AGENCY/CO	IPANY				

Figure 81. Moisture and density determination on M-84 SB HMA-base layer, page 2

DATE 9-2 DENS Kur		DIST	RIBUTI	DN: ORIG	INAL - Proj	RE A	ND Neer, C	DEN NUCLEA	R METHO	DETE D Superviso	RMINA	TION	nsing).	ME	iri.		
9-2 DENS Kur	E		CONTROL	SECTION ID		JOB NU	MBER	SEE REVER	ROUT	E NO. or STR	EET	GAL	IGE NO.	<i>y</i>	Ø		
Kur	1-05			0901	1		31	804		M-84 S	B Bay Road		10	2839			
	t S. 1	ASPECTOR		CERT	IFICATION NO 10513-	0408	pa	ECLECTENCE LC	uis Tavlor	P	Mike Ea	cker	(517) 388-1	053		
					E	DETER	MINA	TION O	IN-PLAC	EDENS	ЯΤΥ			·			
TE	ST	WE	T DENS	ITY	M	OISTURE			DRY DENSIT	Y		LOCATION	OF TEST	DEPTH	Line		
DRIGINAL	RECHECK	COUNTS (DQ)	TEST DEPTH mm	WET DENSIT [®] kg /m ³	(MC)	MOIS- TURE kg/m ³	MOIS- TURE %	DRY DENSIT kg /m ²	MAX DENSITY kg /m ³	PERCENT OF COM- PACTION	STATION	F	TANCE ROM £ m RIGHT	BELOW PLAN GRADE	WO WO		
1	2	3	4	5	6	7	8	9	10	11	12	53	14	15	16		
LI		1154	200	2212	41	37.9	1.7	2174			16+240	1.8	<u> </u>		A		
L2	_	1116	200	2233	43	40.8	1.9	2192	_		16+240		1.8		A		
L1 12		1776	175	2239	48	48.1	2.2	2191			16+220	1.8	1.8		A		
L1	-	2058	125	2363	49	49.6	2.1	2313			16+200	1.8	1.0		A		
L2		2031	125	2374	46	45.2	1.9	2328	-		16+200		1.8		A		
Ll		2226	125	2301	50	51	2.3	2250			16+180	1.8			A		
L2		2234	125	2299	45	43.7	1.9	2255			16+180		1.8		A		
_	-																
															┝		
			DETER	MINATIO	N OF MA	XIMUM	DENSI	TY (Soil a	Bitumino	us)			NOT				
TE	ST 0.	MOIS- TURE	VOLU		et soil + Mold	MOL	DENS	VET SOIL	COMPACTED SOIL WET	MAX	OPTIMUM	To c Vol. (ft ³	onvert (ft ²) x 0.0283	=: ⁸) to (m ³ 2 = Vol. (); m ³ }		
	I	2	3		Kg 4	KQ 5		6	Kg/m² 7	Rgmi 8	9	СНА	RT STAN	RT STANDARDS		TANDARDS	
16+2	40L											DENSI	Y	MOIST	JRE		
												26 2561	2613 6 61 630		56		
												OPER/ DENSI	ATING ST.	MOIST	S		
												2611	6	45			
												BITUMINOU	S MIX DES	SIGN kg /	n ⁸		
REM	ARKS	1															
M-8	4 Pe	rpetual P	avemen	t Demo	Project Sa	imple ta	ken for	MD det	erminaion ir	Lab. A	gg. Base very	hard to te	stcoop	went ho	me.		
L1=3	SBC)L, L2=SI	BIL A	GGREG	ATE BASI	DENSI	ty inspe	CTOR'S SI	INATURE		AGENCY/CO	MPANY					

Figure 82. Moisture and density determination on M-84 SB aggregate base layer

FILE 301 Michigan Department MOISTURE AND DENSITY DETERMINATION of Transportation 0582EM (11/01) NUCLEAR METHOD DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing). * SEE REVERSE SIDE ROUTE NO. or STREET DATE CONTROL SECTION ID JOB NUMBER GAUGE NO 8-5-05 09011 31804 M-84 SB 102366 CERTIFICATION NO PROJECT ENGINEER (MOOT) PROJECT MANAGER OJECT MANAGER PHONE NO DENSITY INSPECTOR 10513-0408 (517) 388-1053 Mike Eacker Kurt S. Bancroft Louis Taylor DETERMINATION OF IN-PLACE DENSITY LOCATION OF TEST TEST WET DENSITY MOISTURE DRY DENSITY DISTANCE FROM £ ITEM OF ORIGINAL RECHECK TEST WET MOIS-MOIS DRY MAX PERCEN BELOW PLAN GRADE COUNTS DEPTH DENSITY COUNTS TURE TURE DENSITY DENSITY OF COM-PACTION STATION WORK ത mm kg /m^a 6400 kg/m² % kg /m³ kg /m⁸ LEFT RIGHT ٠ 10 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 L2841 200 2316 136 178.18.3 2138 1980 108. 14+100 1.82 Е 200 108.7 Е LI 835 2321 130 169.3 7.92152 1980 14 + 1001.82 L21110 2002148 127 164.9 8.3 1983 1980 100.1 14+120 1.82 Е Ll 888 200 2285 121 7.3 2129 1980 107.5 14+120 1.82 156. E L2875 200 2293 130 169.3 8.0 2134 1980 107.3 14 + 1401.82 Е Ll 932 200 2255 123 159.0 7.6 2096 1980 105.9 14+140 1.82 Е L2 2291 876 200 140 184.0 8.7 2107 1980 106.4 14 + 1601.82 E 836 LI 200 2321 127 164.9 7.6 2156 1980 108.9 14 + 1601.82Е L21085 200 2162 118 151.6 7.5 2011 1980 101.6 14+180 1.82 Е L1943 200 2248 7.8 125 161.9 2086 1980 105.4 14 + 1801.82 Е DETERMINATION OF MAXIMUM DENSITY (Soil & Bituminous) NOTE: DENSITY DETERMINATION To convert (ft³) to (m³): MOIS-WET SOIL + OPTIMUM TEST VOLUME MOLD MAX WET SOIL COMPACTED SOLWET DENSITY Kg/m³ NO. TURE MOLD MOLD MOISTURE Vol. (It³) x 0.02832 = Vol. (m³) Kg % Kg Kg Kg/m % CHART STANDARDS 1 2 3 5 6 8 9 DENSITY MOISTURE I 11.0 .001044 4621 2338 2.283 2186 1980 11.5 2422 661 635 2374 OPERATING STANDARDS DENSITY MOISTURE 2403 646 BITUMINOUS MIX DESIGN kg /m³ REMARKS M-84 Demo Project MD from MDOT Inspector Gail R (1-2) L1=OUTSIDE LANE L2=INSIDE LANE DENSITY INSPECTOR'S SIGNATURE AGENCY/COMPANY

Figure 83. Moisture and density determination M-84 SB subgrade (embankment), page 1

Mi	chige of Tri 05829	n Departme ansportation 3M(11/01)	int I	N	101	STU	RE A	ND			METHO		RMINA	T	ION		FILE MET	301	
		DIST	RIBUTK	DN: C	RIGI	NAL - Proj	ect Engi	neer, C	SEE REVE	Are RSE	a Density ESIDE	Supervisor	, Density Tec	nnok	ogy (La	nsing).			
DAT	E	0	CONTROL	SECTIC	N ID		JOB NU	MBER			ROUT	E NO. or STRI	EET		GAI	UGE NO.	2266		
B-5-	-05 SITY I	NSPECTOR		- 0	9011 CERTIF	ICATION NO		3	I 804 IOJECT ENGI	NEE	R (WDOT)	IMI PR	-84 S.D KOJECT MANAGER	2		PROJECT M	AMAGER PHK	WE NO.	
Kur	t S.	Bancroft				10513-	0408		L	oui	is Taylor		Mike Ea	cker		(517	7) 388-1	053	
			TOTHE	1957		0	DETER	MINA	TION O	FI	IN-PLAC	EDENS	ITY	1.00	ATION	OF TEST			
CINAL 3	HECK	COUNTS	TEST	U V DEI	VET	COUNTS	MOIS- TURE	MOIS- TURE	DRY DENSIT	Y	MAX	PERCENT OF COM-	STATION	100	DIS	TANCE	DEPTH BELOW PLAN	EPTH ITEN ELOW OF LAN WOR m *	
- OR	2 REC	(09	mm	kg	/m ³	(MC)	kg/m ³	%	kg /m	3	kg /m ³	PACTION	45		LEFT	RIGHT	- GRADE 		
I.2		996	200	22	214	132	172.2	8.4	2042		1980	103.1	14+200		1.82			E	
LI		851	200	23	10	132	172.2	8.1	2137		1980	107.9	14+200		1.82			E	
L2		1146	200	21	25	166	222.3	11.7	1903		1980	96.1	14+220		1.82			E	
Ll		924	200	22	257	171	229.6	11.3	2027	_	1980	102.4	14+220		1.82			E	
L2		833	200	23	22	133	173.7	8.1	2149		1980	108.5	14+240		1.82			E	
LI		840	200	23	17	140	184.0	8.6	2133		1980	107.7	14+240		1.82			E	
																-			
										_								-	
										_						+		-	
						1				_							_	ĺ	
			DETER	MIN	ATIO	OF MA	KIMUM	DENSI	TY (Soil	8. E	l Bituminou	JS)		Γ.					
TE N	ST O.	MOIS- TURE	VOLL	ME	WE	T SOIL +	MOL	DENS D V	VET SOIL		MINATION OMPACTED SOIL WET	MAX	OPTIMUM		To o Vol. (ft ³	onvert (ft) x 0.0283	⊑: ³) to (m ³ 12 = Val. ()∶ m ³)	
	1	2	3			к <u>а</u> 4	Кg 5		6		Kg/m ²	8	9		CHA	RT STAN	DARDS		
	1	11.0	.0010)44	4	1621	2338	3	2.283		2186	1980	11.5	\vdash	DENSITY MO		DENSITY MOISTURE		JRE
														23	76	2422 661 635		1001	
															DENSI	ATING ST	MOIST	JRE	
														239	5	6	48		
														вт	UMINOU	S MIX DE	SIGN kg /r	n ^a	
REM	ARKS	3												1					
M-8	4 D	emo Proje	ct	L1=0	DUTS	IDE LAN	NE, L2-	INSID	E LANE	5									
(2-2))						DENSI	TY INSPE	ECTOR'S SI	GN/	ATURE		AGENCY/CO	MPAN	IY				

Figure 84. Moisture and density determination M-84 SB subgrade (embankment), page 2



Figure 85. Moisture and density determination M-84 SB subgrade (embankment), page 3

м	ichig of Ti 0582	an Departr ransportati BM(11/01) DIS	nent on TRIBUT			ISTU	RE A	AN	D DE NUCLE	EAF	SITY R METH	OD	ERMI		ATIO	N Lansir	na).	M-C ME	E 301	
DAT	ſE		CONTRO	L SEC	TION ID		LIDE N	*	SEE REV	/ERS	ESIDE						- 347-		\sim	
8-1	6-05	5			09011			- more in	31804		ROL	M-84	SB Bay 1	Road	ı f	GAUGE	NO. 101	2366		
Km	isiity i rt S.	NSPECTOR Bancroft			CERTIF	ICATION NO 10513	0.408		PROJECT EN	GNE	ER (MDOT)		PROJECT MV	AGER		PRO	PROJECT MANAGER PHONE NO.			
		Suitter				10515	DETER	MIN	ATION	OF	IN-PLA		Mik	e Ea	cker		(517) 388-1053			
	ST	W	WET DENS		DENSITY		OISTUR	E		D	RY DENSI	ITY			LOCATIO	NOF	TEST			
ORIGINA	RECHECK	COUNTS (DO)	TEST DEPTH mm		WET ENSITY kg /m ³	COUNTS (MC)	MOIS- TURE kg/m ^a	MOIS TUR	S- DR E DENS kg/i	ү атү m ²	MAX DENSIT ¹ kg /m ³	Y OF COM	AT A- STAT	NON	C	FROM	TANCE ROM £	DEPTH BELOW PLAN GRADE	ITEM OF WORK	
- 1	2	э	4	-	5	6	7	8	9	_	10	11	1:	2	13	TR	14	m 15	* 16	
L2		1178	200	2	108	107	134.7	6.8	197	4	1970	100.2	16+	160			1.8		s	
LI		1167	200	2	114	105	131.0	6.6	198	2	1970	100.6	16+	160	1.8	3			s	
L2		1127	200	2	137	91	111.7	5.5	202	6	1970	102,8	16+	180			1.8		s	
LI		1109	200	2	145	113	143.5	7.9	200	2	1970	101.6	16+	180	1.8				s	
L2		1149	200	2	124	103	128.8	6.5	1995	5	1970	101.3	16+2	200			1.8		s	
	_	1153	200	2	122	96	118.6	5.9	2004	+	1970	101.7	16+2	200	1.8				s	
L2	-	1350	200	20	024	90	109.8	5.7	1915	;	1970	97.2	16+2	20			1.8		s	
	-	1432	200	19	987	90	109.8	5.8	1878	1	1970	95.3	16+2	20	1.8				s	
.2	-	1380	200	20	011	83	99.5	5.2	1912		1970	97.0	16+2	40		1	1.8		s	
	-	1312	200	20	043	87	105.4	5.4	1937	-	1970	98,3	16+2	40	1.8				s	
Ĺ			DETER	MINA	ATION	OF MAX	IMUM D	ENG	TV (Call											
TES	-	MOIS.					INIONIL	DENS	ITY (Soil	RM	INATION	18)		-		N	OTE:			
NO	-	TURE		D	MC	SOIL + SLD	Kg	ľ	WET SOIL Kg	CON SC	MPACTED XIL WET Kg/m ³	MAX DENSITY Kg/m ⁻³	OPTIMU MOISTU %	IM RE	To convert (ft ³ Vol. (ft ³) x 0.02832		To convert (ft ³) to (m ³): Vol. (ft ³) x 0.02832 = Vol. (m ³)		^b)	
6160	L2	6.8	.00133	38	30	190	1 202		3 799	-	7		9		CHART STANDARDS		C.			
							1.202		2.788		0084	1970	10.8		24	122	1	66	1	
								1						2	2374		635	5	~	
														-	OPER.		STAN	DARDS	-	
														2	379		651	UNATUR		
				_										В	TUMINOU	S MIX (DESIG	N kg /m ³		
MAR	KS D.							_												
-94]	OI	L2=SD1	T Sor	d Ser	io Proje	ect Not	c: Sta. 1	6+10	0, 16+12	0, 10	6+140 ur	navailable	e due to on	goii	ng constr	uction	n mac	hinery.		
-1)			L Gall	0.50	Dase		DENSITY	INSPE	CTOR'S SIG	NATI	JRE		AGENCY/C	OMP	NY					

Figure 86. Moisture and density determination on M-84 SB subbase, page 1

Michigan Department of Transportation 0582BM(11/01)

MOISTURE AND DENSITY DETERMINATION



DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing). * SEE REVERSE SIDE

ROUTE NO. or STREET GAUGE NO. DATE CONTROL SECTION ID JOB NUMBER 102366 M-84 SB 09011 31804 8-15-05 PROJECT MANAGER PROJECT WANAGER PHONE NO. CERTIFICATION NO. DENSITY INSPECTOR PROJECT ENGINEER (MDOT) (517) 388-1053 10513-0408 Mike Eacker Kurt S. Bancroft Louis Taylor DETERMINATION OF IN-PLACE DENSITY LOCATION OF TEST TEST WET DENSITY MOISTURE DRY DENSITY DEPTH BELOW PLAN GRADE DISTANCE FROM £ ITEM OF TEST WET DENSITY MOIS-TURE MOIS-TURE DRY MAX PERCENT ORIGINAL RECHECK COUNTS DENSITY DENSITY STATION COUNTS OF COM-PACTION DEPTH WORK (DQ) mm kg /m³ (MC) kg/m^a % kg /m³ kg /m³ LEFT RIGHT ٠ m 6 7 8 9 10 11 12 15 16 \$ з 4 5 13 14 2 1895 1925 98.4 14 + 100 \mathbf{S} L2 1364 200 2017 98 1224 6.5 1.8 L11446 200 1980 107 135.7 7.4 1844 1925 95.8 14+100 1.8 s L1 1448 200 1979 110 140.1 7.6 1839 1925 95.5 14 + 1201.8s s L21895 200 1810 85 103.2 6.0 1706 1925 88.6 14+120 1.8 71 1694 1925 88.0 14 ± 140 1.8 s L2 1997 200 1777 82.6 4.9 200 1903 113.6 1790 1925 93.0 14 + 1401.8 s LI 1635 72 6.3 1973 119,5 1853 1925 96.3 14+160 1.8 s 1465 200 96 6.4 LI s L.2 1847 1925 95.9 14 ± 160 1.8 1524 200 1948 84 101.8 5.5 200 106.2 1770 1925 92.0 14+180 1.8 s L2 1707 187687 6.0 s 1925 89.7 1.8 Ll 1741 200 1862 107 135.7 7.9 1727 14 ± 180 L11437 200 1985 87 106.2 5.7 1879 1925 97.6 14+2001.8 s DETERMINATION OF MAXIMUM DENSITY (Soil & Bituminous) NOTE: DENSITY DETERMINATION To convert (ft³) to (m³): OPTIMUM TEST NO. MOIS-VOLUME WET SOIL # MOLD WET SOIL COMPACTED MAX Vol. (ft³) x 0.02832 = Vol. (m³) MOLD m² SOIL WET Kg/m³ DENSITY Kg/m³ MOISTURE TURE MOLD Кg Kg % Kg CHART STANDARDS 1 2 4 5 6 8 9 3 DENSITY MOISTURE 14+100 12 6.5 .0013338 3.910 1.202 2.708 2030 1925 11.8 2422 661 635 2374 OPERATING STANDARDS DENSITY MOISTURE 2379 647 BITUMINOUS MIX DESIGN kg /m3 REMARKS M-84 Perpetual Pavement Demo Project Sand Subbase L1=SBOL, L2=SBIL DENSITY INSPECTOR'S SIGNATURE AGENCY/COMPANY (1-2)

Figure 87. Moisture and density determination on M-84 SB subbase, page 2

Michigan Department of Transportation 0582EM(11/01)

MOISTURE AND DENSITY DETERMINATION



DISTRIBUTION: ORIGINAL - Project Engineer, COPIES - Area Density Supervisor, Density Technology (Lansing).

		CONTROL	SECTION	ID.	LIOB MU	MBER		BOUT	E NO. or ST	REET		GAUG	E NO.		
-05		CONTROL (090	11	208 NU	31	1804	1001	e not or all	M-84 SB		-	102	2366	
TY INSPE	CTOR		CE	RTIFICATION NO		PF	ROJECT ENGINE	ER (MDCT)		PROJECT MANAGEP	{	P	KOUECT MAD	AAGER PHO	NE NK
S. Ban	croft			10513-	0408		Lou	is Taylor		Mike Ea	cker		(517)	388-10	053
				Ľ	DETER	MINA	TION OF	IN-PLAC	E DEN	SITY					
т	W	T DENS	ITY	M	DISTURE		D	RY DENSIT	Y		LOCAT	TION O	F TEST	L DC DC	
CO HECK	UNTS	TEST DEPTH	WE1 DENS	TY COUNTS	MOIS- TURE	MOIS- TURE	DRY DENSITY	MAX DENSITY	OF COM	IT STATION		DIST/ FR	NNCE OM £	DEPTH BELOW PLAN	
E (20)	mm	kg /m	n ³ (MC)	kg/m ^a	%	kg /m ³	kg /m ³	PACTIO	N	1	.EFT	RIGHT	m	1.1
2	3	4	5	6	7	8	9	10	11	12		13	14	15	1
1	508	200	1955	5 85	103.2	5,6	1852	1925	96.2	14+200			1.8		5
1	424	200	1990) 96	119.5	6.4	1871	1925	97.2	14+220			1.8		5
1	424	200	1991	l 93	115.0	6.1	1876	1925	97.4	14+220		1.8			5
1	487	200	1963	3 94	116.5	6.3	1847	1925	95.9	14+240		1.8			5
1	476	200	1968	3 100	125.3	6.8	1842	1925	95.7	14+240			1.8		
															Γ
		DETER	MINAT	ION OF MAX	XIMUM	DENSI	TY (Soil &	Bitumino	us)		_		NOTE		
т I в	NOIS-	1		WET SOIL &	1101	DENS	ITY DETER	MINATION	had V	OPTIMUM	-	To co	rivert (ft ³	') lo (m ³)):
) T	URE	MOL	D	MOLD *	MOL		WET SOIL	SOIL WET	DENSIT	Y MOISTURE	Vo	l. (ft ³)>	0.02832	e Vol. (r	m ³)
	2	<u>m</u>	<u>'</u>	Kg 4	Kg E		Kg .	Kg/m ³	Kg/m ^a	*		CHAR	TSTAN	APRO	
	4	×							0		DE	ENSITY	/	MOISTU	JRE
												242	22	6	61
											237/	1	6	35	
											2574	PERAT		NDARD	s
		1									DE	ENSITY	1110 017	MOISTL	JRE
											2379		64	7	
											BITUM	INCUS	MIX DES	ilGN kg /r	n ³
]				
RKS															
Perpe	tual P	avemen	t Demo	Project Sa	and Sub	base									
BOL	L2=SI	BIL													
					DENSI	TY INSPA	ECTOR'S SIGN	ATURE		AGENCY/CO	MPANY				
	-05 TY NSPE S. Ban OF 2 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1	-05 TY INSPECTOR S. Bancroft T T WI S COUNTS (CQ) 2 3 1508 1424 1424 1424 1427 1476 1476 5 5 MOIS- TURE 3 2	CONTROL 1 -05 -05 -05 -05 -05 -05 -05 -05 -05 -05	CONTROL SECTION 090 17 INSPECTOR S. Bancroft T T T COUNTS CO	CONTROL SECTION ID 09011 TY INSPECTOR S. Bancroft CERTFICATION NO 10513- IC IC T WET DENSITY 003 COUNTS 003 COUNTS 003 IC I 1424 200 1990 96 1424 200 1991 93 I 1424 200 1968 1000 I 1427 200 1963 94 I 1427 200 1963 94 I 1427 200 1968 1000 I 1487 200 1968 1000 I 1487 200 1968 1000 I I 1476 200 I I I I I I I I I I I I I I I I I I I	CONTROL SECTION ID 09011 JOB NU 09011 T WET DENSITY DETER MOISTURE 003 MOISTURE 003 T WET DENSITY MOISTURE 003 MOISTURE 003 MOISTURE 003 MOISTURE 004 MOISTURE 005 2 3 4 5 6 7 COUNTS DEFTER DEFTH DENSITY COUNTS MOIS- 102 MOIS- 103.2 1 1424 200 1990 96 119.5 1 1424 200 1991 93 115.0 1 1424 200 1963 94 116.5 1 1476 200 1968 100 125.3 1 1476 200 1968 100 125.3 DETERMINATION OF MAXIMUM Kg ST MOIS- TURE NCLD WET SOIL * MOLD MOL Kg 2 3 4 5 3 4 5 5 4 2 3 4 5	CONTROL SECTION ID JOB NUMBER -05 OONTROL SECTION ID JOB NUMBER IDS13-0408 IDS13-0408 DETERMINA T WET DENSITY MOISTURE COUNTS TEST MET MOIS- 003 MET MOIS- 1508 200 IDS13 MOIS- 1424 COUNTS TEST MOIS- 1424 COUNTS TEST MOIS- 1424 COUNTS TEST MOIS- 1424 200 1990 96 119.5 6.4 1424 200 1991 93 115.0 6.1 Ide Internation of Internating Internation of Internation of Internation of Internat	OCNTROL SECTION ID 09011 JOB NUMBER 31804 1Y INSPECTOR S. Bancroft CERTIFICATION NO. INSPECTOR INSPECTOR IPROJECT ENSING INSPECTOR INSPE	CONTRACL SECTION ID JOB MUMBER ROUT 0.05 0.9011 31804 ROUT S. Bancroft 10513-0408 Louis Taylor DETERMINATION OF IN-PLAC DETERMINATION OF IN-PLAC T WET DENSITY OBMUMBER DEVENTIVE DEVENTY COUNTS MOIS- MOIS	CONTROL SECTION ID U9011 JOS MUMBER 31804 ROUTE NO. or 83 1001 17 MISPECTOR S. Bancroft CERTFICATION PO. 10513-0408 PROJECT ENGINEER (MOT) Louis Taylor T WET DENSITY MOISTURE DEPTH (MOS) DRUE NO. FURE based (MOS) PROJECT ENGINEER (MOT) Louis Taylor 1 WET DENSITY MOTS DEPTH (MOS) MOSS (MOS) DRY DENSITY (PERSITY) DRY DENSITY (PERSITY) DRY DENSITY (PERSITY) DEVENTIY (PERSITY) DEVENTIY DEVENTIY	OST RECIDENCIAL JOS NUMBER ROUTE NO. or STREET M-84 SB 0.05 109011 31804 M-84 SB M-84 SB S. Bancroft 10513-0408 Louis Taylor MOLECT MANAGE VI NERRETOR DETERMINATION OF IN-PLACE DENSITY MOLECT MANAGE MARA 2 3 4 5 7 8 9 10 11 12 1508 200 1955 85 103.2 5.6 1852 1925 96.2 144:200 1424 200 1990 96 119.5 6.4 1871 1925 97.2 14+220 1424 200 1991 93 115.0 6.1 1876 1925 97.4 14+220 1424 200 1968 100 125.3 6.8 1842 1925 95.7 14+240 1476 200 1968 100 125.3 6.8 1842 1925 95.7 14+240 1476 200 1968 </td <td>OS CONTROL SECTION ID (99011 JIS04 INCUTE NO. or STREET M-84 SB 0.05 CONTROL SECTION ID (10513-0408 DETERMINATION OF IN-PLACE DENSITY DETERMINATION OF IN-PLACE DENSITY Milk Eacker 0.05 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor MILL A 2 3 4 6 7 8 9 10 11 12 1 5.6 1852 1925 96.2 14+220 14+220 1 1424 200 1991 93 115.0 6.1 1876 1925 97.2 14+240 14+240 1 1476 200 1968 100 125.3 6.8 1842 1925 95.7 14+240 1 1 1 10</td> <td>OSTREC BECTION ID 00011 JOB NUMBER 31804 ROUTE NO. WITHET NOTE NO. WITHET DAUG MARK 0.05 00011 00011 0101 01</td> <td>OS CONTROL BECTION ID 90011 CONVENENT 1013 POULE NO. #TREFFET 31804 POULE NO. #TREFFET MARKET MANAGER MARK SEALED MARK SEALED MARK</td> <td>ОБТИТИСЬ ВЕСТОКИ В 09011 ОСЯТИКА ВЕСТОКИ В 11804 ПОЛТЕ НО. ОГ. ВРЕТТ М. 4.84 ОПОДОСТ 102365 ОПОДОСТ 102365 ОПОДОСТ 102365 ОПОДОСТ</td>	OS CONTROL SECTION ID (99011 JIS04 INCUTE NO. or STREET M-84 SB 0.05 CONTROL SECTION ID (10513-0408 DETERMINATION OF IN-PLACE DENSITY DETERMINATION OF IN-PLACE DENSITY Milk Eacker 0.05 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor Milk Eacker 1 WET DENSITY MOIDS TO NO. PROJECT MANAGUA Louis Taylor MILL A 2 3 4 6 7 8 9 10 11 12 1 5.6 1852 1925 96.2 14+220 14+220 1 1424 200 1991 93 115.0 6.1 1876 1925 97.2 14+240 14+240 1 1476 200 1968 100 125.3 6.8 1842 1925 95.7 14+240 1 1 1 10	OSTREC BECTION ID 00011 JOB NUMBER 31804 ROUTE NO. WITHET NOTE NO. WITHET DAUG MARK 0.05 00011 00011 0101 01	OS CONTROL BECTION ID 90011 CONVENENT 1013 POULE NO. #TREFFET 31804 POULE NO. #TREFFET MARKET MANAGER MARK SEALED MARK	ОБТИТИСЬ ВЕСТОКИ В 09011 ОСЯТИКА ВЕСТОКИ В 11804 ПОЛТЕ НО. ОГ. ВРЕТТ М. 4.84 ОПОДОСТ 102365 ОПОДОСТ 102365 ОПОДОСТ 102365 ОПОДОСТ

Figure 88. Moisture and density determination on M-84 SB subbase, page 3

	0582	BM (04/2001) DIS	TRIBUT	ION: ORI	GINAL - Pro	oject Engi	neer, C	OPIES - A	R METHC	D Supervise	r, Density Tec	:hnology (La	ansing),	ME	ikic /
DAT	e .		CONTROL	SECTION ID	,	JOB NU	MBER	SEE REVER	ROUT	TE NO. or STR	RET	GA	UGE NO.	1	
DEN	SITY I	MSPECTOR	09	OT A	TIFICATION N	1318	<u>64</u> [FF	OJECT ENGIN	EER (MUQT)	Bay Road ROJECT MANAGER		102.36	59		
_6	ri	C 13/0	51					L-Tay	lor						
ŤΕ	ST	w	ET DEN	SITY	N	DETER	MINA		TIN-PLAC	CE DENS	SITY	LOCATION	OF TEST		
ORIGINAL	RECHECK	COUNTS DEPTH DENSITY		Y COUNTS (MC)	MOIS- TURE kg/m ^a	MOIS- TURE %	DRY DENSITY kg /m ³	MAX DENSITY kg /m ³	PERCENT OF COM- PACTION	STATION	DIS	TANCE ROM £	E DEPTH BELOW PLAN GRACE	ITEM OF WORK	
$\frac{1}{l}$	2	3	4	5	6	1	8	9	10	11	12	13	14	15	18
1		1251	200	2044	148	143,9	9.9	1860	1892	- 18.3	14-100) <	K	1-36	5
3		1030	100	1884	107	126.7	7,2	1757	1792	98,0	14+140	3,5,	N	F36	5
3		1402	200	1915	134	164,4	9.1	1810	1892	95,7	14+180	2	3.50	F36	5
4		1369	200	1989	144	1783	9.8	1810	1892	95,7	14+22	20 4	4	F36	5
5		1178	200	2079	174	220.1	11.8	1859	1892	98.3	14128	0	40	FSG	5
6		1549	206.	1913	133	163,0	9.3	1750	1792	47.7	14+34	0 3.5		FSC.	5
7		1515	200	1927	135	165.8	<i>.</i> 4	1761	1792	98.3	14+400	2 4	4	FSG	5
6		1725	200	1849	97	112.8	65	1737	1792	96.9	14+041	2 6	4	F56	5
9		1326	200	2008	144	178.2	97	1430	1892	96.7	13+980)	2.5	R6	<
10		326	200	1989	156	195.0	10.9	13794	123	2 1.22.1	13+920	0 C	1	FGG	5
i		1299	2500	2020	163	DONA	11.2	1415	1892	95.9	131-860	2	3	FSG	5
		1	DETER	MINATIO	ON OF MA	XIMUM	ENSIT	Y (Soil &	Bituminou	is)			-		
TES	ST),	MOIS- TURE	VOLU MOL m ²	IME W	ET SOIL + MOLD Kg	MOLD ka	DENSI W	ET SOIL C	COMPACTED SOIL WET	MAX DENSITY Ko/m ^a		Toc Vol. (ft 3)	onvert (ft ³) x 0.02832	to (m ³): = Vol. (n	n ³)
1	-	2	10013	1035	4	5	-	6	7	8	9	DENSIT	Y N	ARDS	RE
		1.1	. 04	61 3	931	1.223	12	.708	2074	1892	12.2	3349	6	61	\geq
2		1,2	100)	3095 <u>3</u> 1	713	1,223	3 2	.49	907	792	14.2	23	97 /	6	87
							_					DENSIT	Y N	OISTU	RE
												2370	2 (677	,
												BITUMINOUS	MIX DESK	SN kg /m	3
REMA	RKS	Sa	nd	for	50	oth	Bc	und	lane	25	Test	1 = Br.	h1- 0	Sold	
		E:	56=	E,	1 59	20 6	prad	٤	4 74 data!		Test 2	= Hann	Breto	time	Bring

Г

Figure 89. Moisture and density determination on M-84 SB subbase, page 4
Date:	9/20/2005		Control Section	9011		Job N	umber 3	1804
Project	Location:	M-84 SB						
		0.11-						
Site:	North Test	Site			Soil Stiffn	ess Range	= 17 - 399	klbf/in
SB					Young's M	lodulus Ra	nge = 3.8 - 89	kpsi
Toet	1	Toet L	ocation	laver	Soil	Youngs	Nuclear Gauge Me	A Moisture
No.	Station	Lane	Distance from CL	Туре	klbf/in	kpsi	kg/m3	%
	16+240	SO	1.8 m	AGG	116.05	27.99	2.174	1.7
	16+240	SI	1.8 m	AGG	116.55	28.11	2192	1.9
	16+220	SO	1.8 m	AGG	121.14	29.22	2191	2.2
	16+220	SI	1.8 m	AGG	117.61		28.37	2.2
	16+200	80	18 m	466	116.94	28.24	2313	21
	16+200	SI	1.8 m	AGG	90.86	21.91	2328	1.9
	16+180	SO	1.8 m	AGG	140.06	33.79	2250	2.3
	16+180	SI	1.8 m	AGG	136.32	32.88	2255	1.9
	16+160	SO	1.8 m	AGG	150.2	36.23		
	16+160	SI	1.8 m	AGG	110.59	26.68		
	10.110		10			00.70		
	16+140	<u>SO</u>	1.8 m	AGG	94.3	22.72		
	101140	51	1.0 111	A00	135.13	33.71		
	16+120	SO	1.8 m	AGG	137.68	33.21		
	16+120	SI	1.8 m	AGG	69.86	16.85		
	16+100	so	1.8 m	AGG	143.8	34.69		
	16+100	SI	1.8 m	AGG	86.07	20.75		
	I I							

Figure 90. Soil stiffness and Young's modulus results on M-84 SB aggregate base layer



Figure 91. Office memorandum on I-96 soil recommendations, page 1

SEP 03 2003 2:05 PM FR METRO CONSTRUCTION8 569 3302 TO 15173225664

P.06

July 31, 2001 CS 82123 - JN 52803 Page two

Materials -The aggregate shall be a natural aggregate or an iron blast-furnace slag meeting the following grading and physical requirements

Grading Requirements

MI Series		Sieve Analysis, Total Percent Passing										
& Class	37.5 mm	25.0 mm	12.5 mm	2.36 mm	0.60 mm	0.075 (LBW)						
21 AA MOD	100	80-100	40-70	15-35	5-20	8 max						

Physical Requirements

MI SERIES & CLASS	21AA MOD
Crushed Materials, min.	95%*
Loss, max., Los Angeles Abrasion (AASHTO T96)	45%

*The percentage of crushed material will be determined on that portion of the sample retained on all sieves down to and including the 9.5mm sieve.

Pavement History and Data

A majority of the pavement is a concrete surface with curb and gutter and enclosed drainage. The cross section consists primarily of divided highway with three local and three express lanes in each direction. The express and local lanes are separated by a median barrier wall.

There have been some full depth bituminous patches and a few maintenance overlays throughout the project limits. The concrete was constructed in 1974, 1976, and 1977 with an average concrete thickness of 246 mm (9.7"). The cores taken in overlaid and patched areas show the bituminous thickness to be an average 66 mm (2.6").

Sand Subbase

From analysis of the core/boring information, none of the existing subbase can be retained for the bituminous option. The concrete option will not require a sand subbase. Only 8% of the cores show a sand subbase depth which would allow for retention for the bituminous option. Sand samples from the areas that were of adequate depth failed Class IIA mechanical analysis requirements. Based on this information, I recommend replacing all of the existing sand subbase for the bituminous option.

Figure 92. Office memorandum on I-96 soil recommendations, page 2

P.07

July 31, 2000 CS 82123 - JN 52803 Page three

For the analysis, it was assumed the new top of pavement would be the same elevation as the top of existing concrete. Sand would need to be present from a depth of approximately 710 mm to 910 mm in order to be considered for retention. The average thickness of the existing sand subbase is 297 mm (11.7") and the aggregate base is an average 150 mm (5.9"). All calculations are on file in this office.

Geotextile Separator should be used for the both the concrete and bituminous option due to the recommended modified aggregate base. The pavement thickness needs to be kept to a minimum in order to achieve the required bridge underclearance.

Subgrade Conditions

The recommended Soil Resilient Modulus (M,) is 20.684 kPa (3000 psi) for pavement design. The subgrade soil classification is as follows: Firm Silty Clay (72%), Plastic Silty Clay (18%) and Soft Silty Clay (9%).

As always, the Metro C&T unit is available to assist in the LCCA and pavement design process if necessary. If you have any questions, I can be reached by phone at (248) 483-5167.

METRO REGION SOILS & MATERIALS OFFICE

St North

Steven D. Minton

SDM:dvd

Attachments cc: R. Safford R. Ostrowski M. Sweeney M. Grazioli R. Screws G. McDonald

27

** TOTAL PAGE.07 **

Figure 93. Office memorandum on I-96 soil recommendations, page 3

			File 302
\smile	SAMPLE	CONTROL SECTION 82123	
Michigan Department	IDENTIFICATION	JOB NUMBER/PO. NUMBER	DATE SAMPLED
of Transportation 1923 (09/04)	Send sample to MDOT C&T Laboratory 8885 Ricks Rd., Lansing, Michigan 48909	52603A LAB. NUMBER	5-12-05 DATE RECEIVED
	SEE INSTRUCTIONS BELOW		
AME OF MATERIAL RANUAL MATERIAL			
OURCE XISTING SOIL		ADORESS/PIT NUMBER	
ANUFACTURER		ADDRESS	
-A			
2123-52803A, 315+66	TO 317+33		
UANTITY OF MATERIAL F	REPRESENTED BY SAMPLE		
ONSIGNED TO			
ANS EXCAVATING		TITLE	
ICHAEL CORNACCHIA	A	ENGINEERING TECHNICIAN	
IBMITTED BY		TITLE	
AME		SAME	
AME		SAME	
AME ITENDED USE UBGRADE PECIFICATION		SAME SENDER'S SAMPLE I.D.	
AME NTENDED USE SUBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A	SAME SENDER'S SAMPLE I.D. 3 BAGS	
AME ITENDED USE UBGRADE PECIFICATION 003 STANDARD SPEC EMARKS EMONSTRATION SEC	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A	SAME SENDER'S SAMPLE LD. 3 BAGS	
AME ITENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS	SAME SENDER'S SAMPLE I.D. 3 BAGS S NEEDED.	
IAME ITENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS NOTE: The ID is the sole basis for ident PLEASE BE ACCUR	SAME SENDER'S SAMPLE I.D. SBAGS SNEEDED. SITuation and distribution of the report. ATE	2
IAME ITENDED USE SUBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SECT	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS NOTE: The ID is the sole basis for ident PLEASE BE ACCUR PLEASE BE ACCUR	SAME SENDER'S SAMPLE I.D. SBAGS SNEEDED. SITEATION and distribution of the report. ATE SHaman -	
W AME TENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC W $I k \in i$ $T \in ST S T$	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS NOTE: The ID is the sole basis for ident PLEASE BE ACCUR PLEASE ADDISE 2///S BM SIT O	SAME SENDER'S SAMPLE I.D. BAGS SNEEDED. SNEEDED. SNEEDED. SNEEDED. SNEEDED. SNEEDED. TE SNEEDED. TT.	
MAME TENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC' MIKE; TESTS T THAN	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS NOTE: The ID is the sole basis for ident PLEASE BE ACCUR PLEASE ADDISE 2///S BM SIT O KS	SAME SENDER'S SAMPLE I.D. BAGS SNEEDED. SNEEDED. SNEEDED. SNEEDED. SNEEDED. SNEEDED. TT.	
MAME TENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC' MIKE; TESTS T THAN, BI	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A INSTRUCTIONS NOTE: The ID is the sole basis for ident PLEASE BE ACCUR PLEASE ADDISE 2//S BA SIT O KS LL REDMOND	SAME SENDER'S SAMPLE I.D. BAGS SNEEDED. SNEEDED. SHarmon of the report. ATE SHarmon - D ITT.	
MAME TENDED USE UBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC Mikei TESTS T THAN, BI	IFICATION TION OF PROJECT, 315+66 TO 317+33, TEST A NOTE: The ID is the sole basis for iden PLEASE BE ACCUR PLEASE ADDISE 2//S BA SIT O KS IC REDMONDO 2-1209.	SAME SENDER'S SAMPLE I.D. BAGS SNEEDED.	
AMME TENDED USE SUBGRADE PECIFICATION 003 STANDARD SPECI EMARKS EMONSTRATION SEC Mikei TESTS T THAN BI	IFICATION TION OF PROJECT, 315+66 TO 317+33. TEST A NOTE: The ID is the sole basis for ident PLEASE BE ACCUR PLEASE ADDISE 2//S BA SIT O ks LC REDMONDO 2-/208	SAME SENDER'S SAMPLE I.D. BAGS SNEEDED. SNEEDED. SNEEDED. SMarcin TE SMarcin TT.	

Figure 94. Sample identification note on I-96 WB existing soil

				DISTR	IBUTION: C	RIGINAL -	Project En	gineer, COP	IES - Area D	ensity Sup	ervisor, Dens	ity Technol	logy (Lansir	ng).	
	DAT	TE ///	1/10	CONTROL	SECTION ID		JOB NUMBE	* SEE	REVERSE SIDE	TE NO, or STR	IEET	0	WUGE ND.		
	DE	VSITY I	NSPECT	TOR	CERTIF	ICATION NO.		PROJECT END	INTER (MDOT)	P	ROUGET WUNAGER		PROJECT	ANACED	
							DETER	MINATION	OF IN-PLA	CEDEN	eity		PHONE NO),	
	76	IST X		WET DENS	ΠY	MOL	TURE		DRY DENSIT	Y	5111	LOCATIO	N OF TEST		
	ORIGIN	RECHEC	COUN [DC]	TS DEPTH inch	DENSITY PCF	COUNTS T (MC)	IOIS- MO URE TU PCF 9	IIS- DRY RE DENȘII 6 PCF	Y DENSITY PCF	PERCENT OF COM- PACTION	STATION	D	STANCE FROM £ FT	DEPTH BELOW PLAN GRADE	OF WORK
		2	3	4	5	6	7 (9	1D	11	12	13	14	FT 15	16
3							·	_							
									_						
		-			1.										
-					15		:								
係・2															
								1							
	~18											-			
	1														
										·		_	_		
	-	-													
		inned. Ny room		DETER	MINATION	OF MAXIN	UM DEN:	SITY (Soil 8	Bituminou	s)			NOTE		
	TEST NO.	r I	MOIS-	VOLUME	WET SOIL	+ MOLD	DENS WET SOI	WET SOIL	MINATION COMPACTED	MAX	OPTIMUM	To a Wit. (g	convert (g) to) +453.59 = V	(ibs.): VI. (ibs.).	
	A	-	% B	CU. FT.	MOLD 9 D	9	9	lbs.	SOIL WET	DENSITY	MOISTURE %	. To Vol. (m ³)	convert (m ³) ÷0.02832 = 1	to (11. ³): Vol. (11. ³).	
	1	6	-1)	1.0448	3982	12.92	7690	5913	132.38	121	1175	DENSIT	Y M	NRDS	1
	G	8	0	0.0448	4051	1797	2759	6.08	135.03	7748	1.12				
						1.	- 14	. 440	עבדיין	120		OPER	ATING STAN	DARDS	\geq
		0	0	A AULIO	1105.	1000	07-00	1		1210		DENSIT	Y M	OISTURE	
		0.	0	0.0141	10.31	1212	2/57	6.08	135.8	126.8	10,3				
-		-										BITUMINOU	S MIX DESIG	NPCF	
ī	REMA	RKS		1.1		-									
-				Class	I I A	1. S	TA.								
				STA	3157	66 .	to 3	17:3	3						
-				-51/4	5101	00	ENBITY INSP	ECTOR'S SIGN	5 WATURE		AGENCY/COM	PANY		, "	

Figure 95. Moisture and density determination on I-96 WB existing subbase

	Michigan Departm	an	B-2 B-2	F E	7		wet Dry	#>,4	+33.0 105.3 7.7.7					-	M-DO METR	Īc			
	of Transportation 1005M (5/95) DATE	2/04			OP	FIE	LD P	ERM	EABI	LITY	DAT	A F	ROJECT N	10.					-
	TEST ID	MOLD + WET SOIL gms.	WT. MOLD, gms.	WT. WET SOIL, gms.	WT. WET SOIL Kg.	VOL. MOLD Cu. M	WET DENSITY Kg/m ²	MOIST. CONTENT, FROM	DRY DENSITY, Kg/m ³	QT. TOTAL FLOW,	L LENGTH OF SAMPLE,	h HEAD,	A CROSS SECT, AREA	Tt TOTAL TIME,	PE	RM	k PERM	SPECIFIC GRAVITY	
001	COL NOS	1	2	3	4	5	6	7	8	9	10	11	12 mm²	min. 13	14	4	15	16	
> 10	meable	3015	301	26383	2,638	0.00123	2144.7	0.06	20233	-	152.4	10.m							56
306	WAPERATEN PERE	2934.3	305	26293	2.629		Ź137.6	0.08	2016.6					1					7-9
1%	IMPERNEMPER	28563	301	25553	2,555		2077.2	0.064	1952.3										1-9
Г				141						-	·		ī	EST DAT.	A				1,20
	TEST ID	Vs VOLUME SOLIDS	Vv VOLUME VOIDS	DRAINED MOIST. CONTENT, SPEEDY	Vw VOLUME WATER	% SATURA, DRAINED	e VOID RATIO	Ne EFFECT POROSITY	k/ne RATIO		TEST FL ID N	OW TIME	TEST ID	FLOW ML	TIME MIN.	TEST ID	FLOW ML	TIME MIN.	
	COL. NOS	17	18	19	20	21	22	23	24				<u>.</u>						
			325				-		-			· .							
					S								-						
Ì	•							-			_								
0	CALCULATIONS									L									
· `.	Col. 4 = $\frac{\text{Col. 3}}{1000}$	Col. 6 =	Col. 4 Col. 5	Col. 8 =	Col. 6 ol. 7 + 1	Col. 9 =	Flow, ML >	(1000	Col. 14 = -	(Col. (Col. 11)	9) (Col. 10 (Col. 12) (() Col.13)	Col. 15 = (Col. 14 x 1	.44 (Col. 17 =	Col. 16	8 x 1000	
_	Col. 18 = 1 - Co	Col. 21	= Col. 20	x 100	Col. 22 =	Col. 18 Col. 17	Col.	Col. 23 = 1 - Col. 17 [(Col. 19) (Col. 16) + 1] C				Co	Col. 24 = Col. 15 Col. 24 = Col. 23						
- to	Notes: Col. 7 and Col. 19 Moisture content expressed as a decimal. Col. 7 fais assumed to be 2.68 unless determined by testing to be otherwise. Material Requirements: Col. 21 Maximum allowable percent saturation = 95% Col. 15 Minimum allowable Permeability. Col. 24 Minimum allowable k/ne Ratio =																		
R	EMARKS:	Clu	14 T	-A	Star	tion	315+	-66	to 3	17.+3	33		123.3	8	16.0	2 #/	(Se Kaj	e #8.)	

Figure 96. Field permeability data on I-96 WB existing subbase

AGGREGATE INSPECTION REPORT Call No.: 82123 JOB No.: DATE: 06/19 TIME: TIME: 9:57 MATERIAL: Class TIA PROJERON: DATE: DATE: 06/19 TIME: 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 00 </th <th></th> <th>·</th> <th></th> <th></th> <th></th> <th>-</th> <th><u>ن</u>ه</th> <th></th> <th>1 18 30</th> <th></th>		·				-	<u>ن</u> ه		1 18 30	
JOB No: 52803A TME: 9:57 MATERAL: Class IIA PROJUCER: N/A DATE SAMPLED : 05/12/05 PIT NUMBER: 00-000 CONTRACTOR: DANS EXCAVATING SAMPLED BY: MICHAEL CONNACCHIA PIT NUMME: EXISTING MATERIA OUNILLATIVE RESULTS SPEC. REPORT NUMBER: 2 05 SIEVE WEIGHT RETAINED WEIGHT RETAINED WEIGHT SAMPLED BY: MICHAEL CONNACCHIA SIEVE WEIGHT RETAINED WEIGHT AFTER WASHING 3250.0 0 1 Inch 0.0 0.0 100 100 WEIGHT AFTER WASHING 346.0 10 0 2 Inch 0.0 0.0 100 50'-100 ***(Dased on portion passing the '* sevel 10 0 34 Inch 6.3 36 66 MATERIAL SPECIFICATION Class III 0.0 0.0 NO. 8 234.0 5.5 11.8 88 MATERIAL SPECIFICATION Class III 0.0 NO. 10 26.8 75.5	AGGREGA	TE INSPECTION R	EPORT			C.Si No	: 82123		DATE:	06/19/ 6
MATERIAL: Class IIA PRODUCER: N/A DATE SAMPLED: 05/12/05 PIT NUMBER: 00-000 CONTRACTOR: DANS EXCAVATING SAMPLED ROM: GRADE AT JOBSITE PIT NUME: EXISTING MATERIAL PROJ. ENGINEER: VICTOR JUDNIC SAMPLED BY: MICHAEL CONNACCHIA Sive WEIGHT *RETAINED SAMPLED CONTACTOR SAMPLED BY: MICHAEL CONNACCHIA Sive *RETAINED *RETAINED WEIGHT *RESULTS SPEC. REPORT NUMBER: 2 05 Sinch 0.0 0.0 100 NTAL WEIGHT OF SAMPLE 3556.0 10 3 Inch 0.0 0.0 100 MEGHT AFTER WASHING 3255.0 10 1/2 Inch 0.0 0.0 100 60'-100					_	JOB No.	: 52803A		TIME:	9:57 AM
PT NUMBER: 00-000 OL-12 State Outre swampleb: OL-12 State State OL-12 State State State OL-12 State	MATERI	AL: Class	AIIA		PRODUCER-	N/A	DATE OF		- / /	
PT NAME: EXISTING MATERIAL PROJ ENGINE UITOD DUNIT SAMPLED PROF. GRADE AL COBSTIS NEWE EXISTING MATERIAL PROJ ENGINEER VICTO DUNITC SAMPLED BY MICHAEL CORNACCHTA NEWE WEIGHT % RETAINED % RETAINED % RETAINED % RETAINED % PASSING NTAL WEIGHT OF SAMPLE 3596.0 S Sinch 0.0 0.0 0.00 100 WEIGHT RESULTS % PASSING Sinch 0.0 0.0 0.00 100 WEIGHT OF SAMPLE 3596.0 S Sinch 0.0 0.0 0.00 100 WEIGHT AT SERVERSHING 3250.0 C 1/12 in 0.0 0.0 100 UCOS BY WASHING (LEW)** 346.0 10 0 1/12 in 0.0 0.0 0.00 100 60*100	PIT NUMBE	ER: 00-00	0		CONTRACTOR:	DANS EXCA	UATE SA		5/12/05	
RETAINED FRACTIONAL WEIGHT CUMULATIVE % RETAINED RESULTS % PASSING SPEC. % PASSING REPORT NUMBER: 2 05 2 05 SIRVE % RETAINED % RETAINED % PASSING % PASSING WEIGHT RESULTS % % SEGUE SPEC. REPORT NUMBER: 2 05 Sinch 0.0 0.0 0.0 100 Initial WEIGHT OF SAMPLE 3596.0 2 inch 0.0 0.0 100 100 WEIGHT AFTER WASHING 3250.0 4 inch 0.0 0.0 100 100 ICSS BY WASHING (LBW)** 346.0 10 0 1 inch 0.0 0.0 100 60 - 100 ***(based on potion passing the 1* size) ****(based on	PIT NA	ME: EXIST	NING MATERIAL	<u>L</u> PR	OJ. ENGINEER:	VICTOR JU	DNIC SAMPLED	IPLED BY: M	ICHAEL CORN	<u>ACC</u> HIA -
SIEVE WEIGHT % RETAINED % PASSING % PASSING % PASSING Maintal WEIGHT OF SAMPLE 3596.0 8 Inch 0.0 0.0 0.0 100 WEIGHT OF SAMPLE 3596.0		RETAINED	FRACTIONAL	CUMULATIVE	RESULTS	SPEC.	REPORT NUMBER:	2 05]	
6 Inch Image: Constraint of the state of th	SIEVE	WEIGHT	% RETAINED	% RETAINED	% PASSING	% PASSING		WEIGHT	RESULTS %	SPEC %
3 Inch 0.0 0.0 100 100 WEIGHT AFTER WASHING 3250.0 2 Inch 0.0 0.0 0.0 100 100 100 100 100 100 100 100 100 100 100 0.0 100 0.0 100 0.0 100 0.0 100 0.0 100 0.0 100 0.0 100 0.0 100 0.0<	6 inch		-				INITIAL WEIGHT OF SAMPLE	3596.0	TEODETO /S	0, 20, 75
2 inch 0.0 0.0 100 LOSS BY WASHING (LBW)** 346.0 10 0-1 1 inch 0.0 0.0 100 60-100 **(based on portion passing the 1' size) 346.0 10 0-1 1 inch 0.0 0.0 100 60-100 **(based on portion passing the 1' size) **(based on portion passing the 1' size) <td< td=""><td>3 inch</td><td>0.0</td><td>0.0</td><td>0.0</td><td>100</td><td>100</td><td>WEIGHT AFTER WASHING</td><td>3250.0</td><td></td><td></td></td<>	3 inch	0.0	0.0	0.0	100	100	WEIGHT AFTER WASHING	3250.0		
1-1/2 in 0.0 0.0 100	2 inch	0.0	0.0	0.0	100		LOSS BY WASHING (LBW)**	346.0	1.0	0 - 10
1 inch 0.0 0.0 100 60 - 100 3/4 inch 83.0 2.3 2.3 98 1/2 inch 78.0 2.2 4.5 96 3/8 inch 64.0 1.8 6.3 94 NO.4 198.0 5.5 11.8 88	1-1/2 in	0.0	0.0	0.0	100		(===)		10	
3/4 inch 83.0 2.3 2.3 98	1 inch	0.0	0.0	0.0	100	60 - 100	**(based on port)	on passing the 1"	tievel	
1/2 Inch 78.0 2.2 4.5 96 3/8 Inch 64.0 1.8 6.3 94 3/8 Inch 64.0 1.8 6.3 94 NO.4 198.0 5.5 11.8 88 NO.8 234.0 6.5 18.3 82 NO.8 234.0 6.5 18.3 82 NO.8 234.0 6.5 18.3 82 NO.8 235.0 7.0 25.3 75 NO.30 307.0 8.5 33.8 66 NO.100 964.0 26.8 79.3 21 035 PAN 399.0 11.1 *TONS / Cu.Yd. TESTED (This Report) 0.0 LBW. 346.0 9.6 *New CUMULATIVE TOTAL 0.0 LBW. 346.0 9.6 *New CUMULATIVE TOTAL 0.0 REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 *(Guantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 IT IS ACCEPTED Project Engineer Notified: THIS MATERIAL CORNACCHIA DAT	3/4 inch	83.0	2.3	2.3	98		-			
3/8 inch 64.0 1.8 6.3 94 1 NO.4 198.0 5.5 11.8 88 1 NO.8 234.0 6.5 18.3 82 1 NO.18 252.0 7.0 25.3 75 1 NO.30 307.0 8.5 33.8 66 MATERIAL SPECIFICATION Class IIA NO.100 964.0 26.8 79.3 21 0 -35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 0 -35 *TONS / Cu.Yd. TESTED (This Report) 0.0 LBW. 346.0 9.6 *TONS / Cu.Yd. TESTED (This Report) 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED IT IS ACCEPTED THIS MATERIAL MEETS SPECIFICATIONS Project Engineer Notified: TESTED BY:	1/2 inch	78.0	2.2	4.5	96					
NO.4 198.0 5.5 11.8 88 NO.8 234.0 6.5 18.3 82 NO.16 252.0 7.0 25.3 75 NO.30 307.0 8.5 33.8 66 NO.100 964.0 26.8 79.3 21 035 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 *PREVIOUS CUMULATIVE TOTAL 0.0 LBW. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 **Dark Shading Indicates Failing Result ** * (Quantifies Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED Project Engineer Notified: TESTED BY: MICHAEL CORNACCHIA DATE:05/15/	3/8 inch	64.0	1.8	6.3	94					
NO.8 234.0 6.5 18.3 82 NO.16 252.0 7.0 25.3 75 NO.30 307.0 8.5 33.8 66 NO.50 671.0 18.7 52.5 48 MATERIAL SPECIFICATION Class IIA NO.100 964.0 26.8 79.3 21 0 - 35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 *PREVIOUS CUMULATIVE TOTAL 0.0 LBW. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 THIS MATERIAL MEETS SPECIFICATIONS DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED	NO. 4	198.0	5.5	11.8	88					
NO. 16 252.0 7.0 25.3 75 NO. 30 307.0 8.5 33.8 66 NO. 50 671.0 18.7 52.5 48 MATERIAL SPECIFICATION Class IIA NO. 100 964.0 26.8 79.3 21 0 - 35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 48 *NEW CUMULATIVE TOTAL 0.0 LBW. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 0.0 TOTAL 3596.0 100.0 ** Dark Shading indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 * (Quantities Based On Contractor's Estimate) 0.0 DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED IT IS ACCEPTED	NÖ. 8	234.0	6.5	18.3	82					
NO. 30 307.0 8.5 33.8 66 NO. 50 671.0 18.7 52.5 48 MATERIAL SPECIFICATION Class IIA NO. 100 964.0 26.8 79.3 21 0 - 35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 4 48 *PREVIOUS CUMULATIVE TOTAL 0.0 LB.W. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 THIS MATERIAL MEETS SPECIFICATIONS DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED	NO. 16	252.0	7.0	25.3	75					
NO. 50 671.0 18.7 52.5 48 MATERIAL SPECIFICATION Class IIA NO. 100 964.0 26.8 79.3 21 0 - 35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 *PREVIOUS CUMULATIVE TOTAL 0.0 LB.W. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 THIS MATERIAL MEETS SPECIFICATIONS DOES NOT MEET CLASS II IT IS ACCEPTED IT IS ACCEPTED	NO. 30	307.0	8.5	33.8	66					
NO. 100 964.0 26.8 79.3 21 0 - 35 *TONS / Cu.Yd. TESTED (This Report) 0.0 PAN 399.0 11.1 *PREVIOUS CUMULATIVE TOTAL 0.0 LB.W. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 * (Quantities Desced On Contractor's Estimate) DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED Project Engineer Notified: TESTED BY: MICHAEL CORNACCHIA DATE:05/15/	NO. 50	671.0	18.7	52.5	4.8		MATERIAL SPECIFICATION		Cla	ss IIA
PAN 399.0 11.1 *PREVIOUS CUMULATIVE TOTAL 0.0 LB.W. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 * (Quantities Based On Contractor's Estimate) DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED	NO. 100	964.0	26.8	79.3	21	0 - 35	*TONS / Cu.Yd. TESTED (This Report)			0.0
LB.W. 346.0 9.6 *NEW CUMULATIVE TOTAL 0.0 TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 * (Quantities Based On Contractor's Estimate) DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED	PAN	399.0	11.1				*PREVIOUS CUMULATIVE TOTAL			0.0
TOTAL 3596.0 100.0 ** Dark Shading Indicates Failing Result ** * (Quantities Based On Contractor's Estimate) REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 THIS MATERIAL MEETS SPECIFICATIONS DOES NOT MEET CLASS II IT IS ACCEPTED Project Engineer Notified: TESTED BY: MICHAEL CORNACCHIA DATE: 05/15/	L.B.W.	346.0	9.6			8	*NEW CUMULATIVE TOTAL			0.0
REMARKS: MATERIAL SAMPLED FROM STA. 315+66 TO 317+33 DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED TESTED BY: MICHAEL CORNACCHIA DATE: 05/15/ Project Engineer Notified:	TOTAL	3596.0	100.0	** Dark Shad	ling Indicates Failing F	Result **	* (Quantities Based On C	contractor's Estima	te)	
DOES NOT MEET CLASS II THIS MATERIAL MEETS SPECIFICATIONS IT IS ACCEPTED TESTED BY: MICHAEL CORNACCHIA DATE: 05/15/ Project Engineer Notified:		MATE	RIAL SAMPLED	FROM STA. 3	15+66 TO 317+	+33			-	
TESTED BY: MICHAEL CORNACCHIA DATE: 05/15/	REMARKS:	DORS	NOT MEET OF	NCC TT			-			
TESTED BY: MICHAEL CORNACCHIA DATE: 05/15/	REMARKS:		NOT MEET CE	H22 II			THIS MATERIAL MEETS SPEC	CIFICATIONS		
Project Engineer Notified:	REMARKS:				÷ 1		IT IS ACC	CEPTED		
Project Engineer Notified:	REMARKS:		the second se							
Project Engineer Notified:	REMARKS:									
Project Engineer Notified;	REMARKS:									
MAN PARTIE	REMARKS:						TESTED BY: MICHAEL CORNA	ACCHIA	DATE:	<u>05/15/</u> 05
Contractor / Producer Notified: SIGNATURE: // upsel L Connacchee	Project Eng	ineer Notified;					TESTED BY: MICHAEL CORNE	ACCHIA	DATE:	<u>05/15/</u> 05

Figure 97. Aggregate inspection report on I-96 WB existing subbase

Michig	an Depar 1845		ortation	REPORT SOIL AN	OF TEST		Control Section Identification 82122 Job No. 52803A Laboratory No. 05S-152 Date August 5, 2005	
Report o Date Sar Source o Sampleo Submitte Intended	of Samp mpled of Mate d From ed By d Use	ole of rial	Soil April 18 Metro I-96 (Sta. 314+25 A. Punjabi,	3, 2005 Demo) WB 5, center of r Metro Soils	Local middle lane Engineer		Date Received April 26, 2005	
					TEST	RESULT	5	
	ASTN Unifi Class	1 D 2487 ed Soils sification	Size	opening mm	Cumulative Percent Passing	Percent Retained	Soil Constants	
S I E	G	oarse ravel	3 inch 2-1/2 inch 2 inch 1-1/2 inch 1 inch 3/4 inch	75.0 63.0 50.0 37.5 25.0 19.0			Liquid Limit Plasticity Index Specific Gravity Shrinkage Limit Shrinkage Ratio	3 2 2.1
E .	G	ine ravel	1/2 inch 3/8 inch No. 4	12.70 9.52 4.76	100 99	1	Organic Content by Loss on Ignition, percent by weight	
N A L Y S I	Me	and edium Sand	No. 10 No. 16 No. 20 No. 30 No. 40 No. 50	2.00 1.180 0.850 0.600 0.425 0.300	97 94 93 91 89	6	Natural Moisture, percent by weight (MTM 407) Compaction and Density of Soils (AASHTO T-99 Method A) Maximum Density, dry, lb per cu ft Optimum Moisture, percent by weight	19
S	S S	-ine Sand	No. 60 No. 100 No. 140 No. 200	0.250 0.150 0.106 0.075	83 78	13	Compaction and Density of Soils (MDOT)	
Hydro- meter	Silt- Clay	Silt Clay Colloids		0.050 0.005 0.002 0.001	76 50 38	40 38	Moisture Content, percent by weight	
REMAR	KS:	Except Tested Sample CL - Le	where noted for Informati tested meet an Clay with	, laboratory on. is specificat Sand	testing is po	erformed in nents for E	accordance with current AASHTO procedur mbankment Construction, Top 3'.	es.
cc:	File				U	Korra Geo	echnical Contracts Engineer	
	Solls M. Gra M. Ea T. Hyr	i esting azioli cker nes						

106



REPORT OF TEST

SOIL ANALYSIS

	FILE 300	
Control Section		
Identification	82122	
Job No.	52803A	
Laboratory No.	05S-153	
Date	August 5, 2005	

1845

Report of Sample of	Soil		
Date Sampled	April 18, 2005	Date Received	April 26, 2005
Source of Material	Metro I-96 (Demo) WB Local		
Sampled From	Sta. 317+00, center of right (outside) lane		
Submitted By	A. Punjabi, Metro Soils Engineer		
Intended Use		Specification	2003 Standard

					TEST	RESULT	S	
	ASTN	D 2487	Sie	NA	Cumulative)[
	Unifi	ed Soils		Opening	Percent	Percent	Soil Constants	
	Class	ification	Size	mm	Passing	Retained		
			3 inch	75.0	ŭ			
			2-1/2 inch	63.0			Liquid Limit	40
	C	barse	2 inch	50.0			Plasticity Index	22
s	G	ravel	1-1/2 inch	37.5			Specific Gravity	2.76
1			1 inch	25.0			Shrinkage Limit	
E			3/4 inch	19.0	100		Shrinkage Ratio	
v			1/2 inch	12.70			1	
E	1	Fine	3/8 inch	9.52	100		Organic Content by Loss on Ignition,	1
	G	ravel	No. 4	4.76	99	1.	percent by weight	
A	C	oarse	No. 8	2.36	97			
N	5	Sand	No. 10	2.00	97	2	Natural Moisture, percent by weight (MTM 407)	20.0
А			No. 16	1.180	96			
L	Me	edium	No. 20	0.850			Compaction and Density of Soils	
Y	5	Sand	No. 30	0.600	94		(AASHTO T-99 Method A)	
S			No. 40	0.425	92	5	Maximum Density, dry, lb per cu ft	
I			No. 50	0.300	90		Optimum Moisture, percent by weight	
S	'	Fine	No. 60	0.250				
		Sand	No. 100	0.150	83		Compaction and Density of Soils	
			No. 140	0.106			(MDOT)	
			No. 200	0.075	77	15	Cone Density, Ib per cu ft	
	1			0.050	75		Moisture Content, percent by weight	
		Silt		0.005	50			
Hydro-	Silt-			0.002	37	40	Loss by Washing, percent	
meter	Clay	Clay		0.001		37	4	
	1	Colloids	I	1				-
REMAR	KS:	Except	where noted	l, laboratory	testing is p	erformed ir	accordance with current AASHTO procedur	res.
		Tested	for Informat	ion.				
		Sample	tested mee	ts specifica	tion requirer	nents for E	mbankment Construction, Top 3'.	
		CL - Le	an Clay with	Sand				
						10	· OTA	
						Xou	is a. laylor	

Geotechnical Contracts Engineer

cc: File

- Soils Testing M. Grazioli
- M. Eacker
- T. Hynes
- . Hynob

Figure 99. Subgrade soil information for the I-96 WB project, page 2

Michig	Jan Depa 1845		iransportation	REPORT	OF TEST		Control Section Identification 8 Job No. 5 Laboratory No. 0 Date	2123 2803A 5S-156 August 5, 2005	
Report o Date Sa Source o	of Sam mpled of Mate	ole of erial	Lime Stabil April 2 Metro I-96	ized Subgra 8, 2005 (Demo) WB	de Soil		Date Received	May 2, 2005	
Sampleo Submitte	d From ed By		Subgrade S A. Punjabi,	Sta. 317+00 Metro Soils	, 42 feet Lt. Engineer	of Const. C	centerline		
					TEST	PESIII T		003 Standard	
	ASTA	1 D 2487	Si	eve	Cumulative		.		
	Unifi Class	ed Soils sification	Size	Opening mm	Percent Passing	Percent Retained		Soil Constants	
s	G	oarse ravel	2-1/2 inch 2 inch 1-1/2 inch	75.0 63.0 50.0 37.5	100		Liquid Limit Plasticity Index Specific Gravity		38 10 2.74
E V	I E V E Fine Gravel	3/4 inch 1/2 inch	25.0 19.0 12.70	97 95	5	Shrinkage Limit Shrinkage Ratio			
E	G	ine ravel parse	3/8 inch No. 4 No. 8	9.52 4.76	94 91 88	4	Organic Content by Loss percent by weight	on Ignition,	
N A L	A Co N S A L Me	and	No. 10 No. 16 No. 20	2.00 1.180 0.850	87 83	4	Natural Moisture, percen Compaction and Density	t by weight (MTM 407) _	22.9
Y S I	5	and	No. 30 No. 40 No. 50	0.600 0.425 0.300	77 73 69	14	(AASHTO T-99 Maximum Dens Optimum Moist	Method A) sity, dry, lb per cu ft ture, percent by weight	
5	s	and	No. 60 No. 100 No. 140	0.250 0.150 0.106	58		Compaction and Density (MDOT)	of Solls	
Hydro-	Silt	Silt	NO. 200	0.075	47 26	23	Cone Density, I Moisture Conter	b per cu ft nt, percent by weight	
meter	Clay	Clay Colloids		0.002	16	34 16	Loss by Washing, percer	nt	
REMARI	KS:	Except Tested Sample ML - Sa	where noted for Informati tested mee andy Silt	l, laboratory on. ts specificat	testing is pe ion requiren	erformed in nents for Ei	accordance with curr mbankment Construc	rent AASHTO procedu tion, Top 3'.	res.
CC:	File				C	<i>Loui</i> Geot	echnical Contracts Ef	aylor ngineer	
	Soils M. Gra M. Ea T. Hyr	Testing azioli cker nes							

MODOT	REPORT OF TES
Michigan Department of Transportation	SOIL ANALYSIS

ORT OF TEST

FILE 300

Control Section		
Identification	82123	
Job No.	52803A	
Laboratory No.	05S-182	
Date	August 5, 2005	

1845

Report of Sample of	Lime Stabilized Subgrade Soil			
Date Sampled	May 9, 2005	Date Received	May 18, 2005	
Source of Material	Metro I-96 (Demo) WB Local			
Sampled From	Subgrade Sta. 314+25, 18 feet Lt.of Cons	st. Centerline		
Submitted By	A. Punjabi, Metro Soils Engineer			
Intended Use		Specification	2003 Standard	

TEST RESULTS

	ASTM	D 2487	Sie	ve	Cumulative			_
	Unifie	ed Soils		Opening	Percent	Percent	Soil Constants	
-	Class	ification	Size	mm	Passing	Retained		
			3 inch	75.0				
			2-1/2 inch	63.0			Liquid Limit 38	
	Co	barse	2 inch	50.0			Plasticity Index 16	
S	G	ravel	1-1/2 inch	37.5			Specific Gravity 2.74	_
1			1 inch	25.0			Shrinkage Limit	
E			3/4 inch	19.0	100		Shrinkage Ratio	
v			1/2 inch	12.70				
E	F	ine	3/8 inch	9.52	98		Organic Content by Loss on Ignition.	
	G	ravel	No. 4	4.76	93	7	percent by weight	
А	Co	barse	No. 8	2.36	88			
N	S	and	No. 10	2.00	88	5	Natural Moisture, percent by weight (MTM 407) 20.0	1
А			No. 16	1.180	84			
L	Me	dium	No. 20	0.850			Compaction and Density of Soils	
Y	s	and	No. 30	0.600	77		(AASHTO T-99 Method A)	
S			No. 40	0.425	73	15	Maximum Density, dry, lb per cu ft	
I			No. 50	0.300	67		Optimum Moisture, percent by weight	
S	F	ine	No. 60	0.250				
	s	and	No. 100	0.150	57		Compaction and Density of Soils	
			No. 140	0.106			(MDOT)	
1			No. 200	0.075	49	24	Cone Density, Ib per cu ft	
				0.050	46		Moisture Content, percent by weight	
		Silt		0.005	24			
Hydro-	Silt-			0.002	15	34	Loss by Washing, percent	
meter	Clay	Clay		0.001		15		
		Colloids						

REMARKS:

Except where noted, laboratory testing is performed in accordance with current AASHTO procedures. Tested for Information.

Sample tested meets specification requirements for Embankment Construction, Top 3'. SC - Clayey Sand

Corris D. Laylor Geotechnical Contracts Engineer

cc: File

Soils Testing M. Grazioli

M. Eacker

T. Hynes

Figure 101. Stabilized subgrade soil information for the I-96 WB project, page 2

EMIDOT Inligan Department of Transportation	REPORT OF TEST	Control Section Identification Job No.	FILE 300 82123 52803A 055-196
		Date	August 5, 2005

Report of Sample of	Granular material - Reclaimed Sand Subbase			
Date Sampled	May 12, 2005	Date Received	May 26, 2005	
Source of Material	I-96 (Demo) WB			
Sampled From	Sta. 314+00 to Sta. 315+66			
Submitted By	M. Cornacchia - Engineering Technician		· · · · · · · · · · · · · · · · · · ·	
Intended Use	MDOT Class IIA, Subbase	Specification	2003 Standard	

TEST RESULTS

	Percent Passing														Loss		
	Sieve Sizes															Ву	
								No.	No.	Wash.							
3"	2-1/2"	2"	1-1/2"	1"	3/4"	1/2"	3/8"	4	8	10	16	30	40	50	100	200	%
				100	96	95	94	89	84	82	78	70	62	52	25	11	* 9.7

REMARKS: *Sample tested does not meet specification requirements for Granular Material Class II. Sample tested meets specification requirements for Granular Material Class IIA and III. SP-SM - Poorly Graded Sand with Silt

Couris D. Laylor Geotechnical Contracts Engineer

cc: File Soils Testing M. Grazioli M. Eacker T. Hynes

Figure 102. Reclaimed (existing) subbase material information for I-96 WB, page 1

6 m _		_	_	_					ſ	Contro	ol Sect	lion			TILL O		
72N	ЛТ	М	M	REPO	RT OF	TES	г			Identif	ficatio	n	82123	3			
	VIL	Л	ノユ							Job N	o.		52803	3A			
Michigar	n Departmer	t of Trai	nsportation	SOIL	ANAL	YSIS				Laboratory No. 05S-197							
									l	Date			A	ugust	5,200)5	
	1846																
eport of	Sample	of	Granula	ar materia	I - Rec	laime	d San	d Subl	base								
ate Sam	pled			May 12, 2	005					Date	Rece	ived	Ν	May 26	6, 200	5	
ource of	Material		1-96 (De	emo) WB	10 24	7.00											
ubmitted	d Bv		M. Corr	acchia - I	Engine	r +33	Tech	nician									
tended	Use		MDOT	Class IIA,	Subb	ase	Teen	liciali		Spe	ecifica	tion	200)3 Sta	ndard		
						т	EST	RESI	JLTS	5							
						Pere S	cent P	assin Sizes	g								Loss By
								No.	No.	No.	No.	No.	No.	No.	No.	No.	Wash
3"	2-1/2"	2"	1-1/2"	1"	3/4"	1/2"	3/8"	4	8	10	16	30	40	50	100	200	%
	1																*
				100	99	90	96	90	84	83	78	69	60	51	25	11	10.3
REM	MARKS'	*Sam		100	99 01 me	et spe	96	90	84	83	for Gr	69	60	51	25	11	10.3
REN	MARKS:	*Sam Sam SP-S	nple test ple teste SM - Poo	ed does n d meets s rly Grade	ot me specifi d San	et spe cation d with	96 ecificat requi Silt	ion rec remen	quirents for	B3 Granu Granu Geot	for Gr ilar Ma	anular aterial	Mate Class	\int_{a}^{51}	ass II nd III.	11 1 2	-
REN	File Soils Te M. Graz M. Eack T. Hyne	*Sam Sam SP-S setting ioli ioli ier s	nple testi ple teste SM - Poo	ed does n d meets s rly Grade	ot me specifie d San	et spe cation d with	ecificat requi Silt	ion req	quiren ts for	83 Granu Granu Geod	for Gr allar Ma	69 anula aterial	for Mater Class	$\int_{a}^{51} E = \int_{a}^{51} E = \int_{a$	ass II nd III.	11	-
REN	File Soils Te M. Graz M. Eack T. Hyne	*Sam Sam SP-S seting ioli ioli eer s	nple testa ple teste IM - Poo	ed does n d meets s rly Grader	ot me specifi d San	et spe cation d with	ecificat requir Silt	90 ion rec remen	quiren ts for	B3 Granu Granu Geod	for Gr alar Ma	69 anula aterial	for Mate	ts Eng	ass II nd III.	11 1	-
REM	File Soils Te M. Graz M. Eack T. Hyne	*Sarr Sam SP-S solidi	nple test ple teste SM - Poo	ed does n d meets s rly Grade	ot me specifi d San	et spe cation d with	ecificat requir Silt	90 ion rec remen	quiren ts for	B3 Granu Geor	for Gr ilar Ma	69 anula aterial	60 r Mate Class	ts Eng	ass II nd III.	11	-
REN	File Soils Te M. Graz M. Eack T. Hyne	*Sam SP-S solution ioli eer s	nple testi ple teste SM - Poo	ed does n d meets s rly Grader	ot me specifi d San	et spe cation d with	ecificat requi Silt	ion rec	quiren ts for	B3 Granu Geod	for Gr ilar Ma	69 anula aterial	60 r Mate Class	ts Erig	ass II nd III.		-
REN	File Soils Te M. Graz M. Eack T. Hyne	*Sam SP-S solution solution	nple testi ple teste SM - Poo	ed does n d meets s rly Grader	ot me specifi d San	et spe cation d with	ecificat requi Silt	ion rec remen	quiren ts for	B3 Granu Geot	for Gr ilar Ma	69 anula aterial	60 r Mate Class	ts Eng	ass II nd III.	11 2	-
REN	File Soils Te M. Graz M. Eack T. Hyne	*Sam Sam SP-S	nple test ple teste SM - Poo	ed does n d meets s rly Grader	ot me specifi d San	et spe cation d with	ecificat requi Silt	90 ion rec remen	quirents for	B3 Granu Geol	for Gr Ilar Ma	69 anulai aterial	60 r Mate Class	$\int \frac{51}{100}$	ass II nd III.		-

MDOT	REPORT OF TEST
Michigan Department of Transportation	SOIL ANALYSIS

	FILE 300	
Control Section		
Identification	82123	
Job No.	52803A	
Laboratory No.	05S-198	
Date	August 5, 2005	

1846

_
_

TEST RESULTS

	Percent Passing														Loss		
	Sieve Sizes														By		
								No.	No.	Wash.							
3"	2-1/2"	2"	1-1/2"	1"	3/4"	1/2"	3/8**	4	8	10	16	30	40	50	100	200	%
			100	97	94	89	86	79	73	71	67	58	50	41	18	10	* 8.9

REMARKS: *Sample tested does not meet specification requirements for Granular Material Class II. Sample tested meets specification requirements for Granular Material Class IIA and III. SP-SM - Poorly Graded Sand with Silt and Gravel

Louis D. Laylor Geotechnical Contracts Engineer

cc: File Soils Testing M. Grazioli M. Eacker T. Hynes

Figure 104. Reclaimed (existing) subbase material information for I-96 WB, page 3

Appendix E: Field Evaluation Reports

Field Evaluation ReportSheetMichigan Department of TransportationofConstruction Field Services DivisionPavement Management Section					
Research Proj.:	Date: 4/27/22 Weather: 40°F, partially cloudy				
Proj. Manager:	Control Sec./Job No.: <u>Attendance:</u>				
Item(s) Surveyed: Perp Pavement Project	al Pavement Demonstration Project & Standard J. Schenkel F. Kaseer				
Location: M-84 from Pi	e Rd to Delta Rd, Bay and Saginaw Counties E. Akerly A. Hargrove				
Contractor(s):					
Objective: Yearly visu	review				
 3. Northmost 1 Began surveying - After reaching ti Finished surveyi: Note that in prethowever, like lamilled/resurface SB Direction (perpetua For Section (1), two mainline lamAlso, 60' of lomobserved. For Section (2), two mainline lamAlso, 101' of lompotholes (not reported totaline) For Section (3), two mainline lamAlso, 12' of lomorepaired) observed NB Direction (standard - For Section (1), two mainline lamAlso, 101' of lomorepaired) 	<pre>National Ru naround to POE (near Delta Rd) the north end (near Delta Rd), traveling in the SE direction. POB (at Pierce Rd), started traveling in the NB direction. NB at the POE, (near Delta Rd). us years, counts attempted to excluded milled/resurfaced area year, this year's review may include these areas because the reas are too difficult to discern now. avement) observed distress survey: 7' of sealed, and 3399' of unsealed transverse cracking in th (4336' total). Total transverse cracking is ~<u>5,212</u> ft/ln-mi. udinal cracking (60' unsealed) observed. Finally, 0 potholes 14' of sealed, and 5288' of unsealed transverse cracking in t (7402' total). Total transverse cracking is ~<u>4,908</u> ft/ln-mi. tudinal cracking (79' sealed, 14' unsealed) observed. Also, red) observed. Finally, 8 new mill/resurface repairs were 45-ft across both lanes. 9' of sealed, and 540' of unsealed transverse cracking in the (959' total). Total transverse cracking is ~<u>2,472</u> ft/ln-mi. udinal cracking (12' unsealed) observed. Finally, 1 pothole (vement) observed distress survey: 92' of sealed, and 765' of unsealed transverse cracking in th (1957' total). Total transverse cracking is ~<u>2,387</u> ft/ln-mi.</pre>	s. e he 2 not			
pothole (not rep. - For Section (2), two mainline lan- Also, 90' of lon-	ed) observed. 65' of sealed, and 1274' of unsealed transverse cracking in t (3539' total). Total transverse cracking is ~2,369 ft/ln-mi. udinal cracking (90' unsealed) observed. Finally, 1 pothole	he			

Figure 105. Field evaluation report of M-84 in 2022, page 1

Field Evaluation Report

Sheet <u>2</u> of 2

Michigan Department of Transportation Construction Field Services Division Pavement Management Section

- For Section (3), 797' of sealed, and 559' of unsealed transverse cracking in the two mainline lanes (1356' total). Total transverse cracking is ~3,477 ft/ln-mi. Also, 101' of longitudinal cracking (101' unsealed) observed. Finally, 2 pothole (not repaired) observed.
- The SB direction has more cracking than the NB section. The previously noted tears in SB are starting to grow in length and there seem to be new transverse tears. For NB, cracks are mostly full width with some new cracking observed. NB cracks may be widening (separating), while the SB cracks are mostly still tight. Additionally, some of the NB transverse cracks are faulting. Longitudinal cracking is remained about the same as last year for both directions (slight reduction from 556 to 453).

Conclusions:

Transverse cracking has increased in both directions. The SB perpetual pavement has more cracking than the NB standard pavement (4,654 ft/ln-mi vs 2,534 ft/ln-mi), but the cracks in SB are tighter than those in NB (width of crack). Overall, the ride on both bounds are fair with good longitudinal joint density. Latest average IRI for NB and SB are, 109 and 98, respectively (per 2018 data).

Note that coring and FWD occurred in April and May of 2020. This was to help determine the cracking propagation (top or bottom) to verify that the SB direction perpetual pavement is performing as designed (preventing bottom-up cracking). Additionally, cores verify depth of the asphalt pavement per direction. This information was summarized and included in the February 2021 Demo Evaluation report.

Future Work:

Per the February 2021 Pavement Demonstration Program Project Evaluation technical report, it is recommended that monitoring of this demonstration project end with final report because it now has enough condition data and evidence that it is ready for project close out. Moreover, while cracking will likely increase, the relative annual increase is decreasing. Therefore, additional annual field reviews are unlikely to add benefit considering that cracking is unlikely to significantly change and/or alter conclusions. In the interim, monitoring of this project will continue until its final report is officially approved by MDOT.

If monitoring continues, due to the number of cracks, field collection will continue to use the sampling procedure of the same 3 sections.

Notes taken by: Justin Schenkel

Figure 106. Field evaluation report of M-84 in 2022, page 2

Field Evaluation Report

Michigan Department of Transportation Construction Field Services Division Pavement Management Section Sheet <u>1</u> of <u>2</u>

Proj. Manager:	Control Sec./Job	No.:	Attendance:
Item(s) Surveyed: Perpetu	J. Schenkel		
Location: I-96 WB, Schaef	er Rd to M-39		F. Kaseer E. Akerly
Contractor(s):			
Objective: Yearly visual	review		
Observations: General Notes: - Surveyed express la - Both sections were recommended that fu local section revie	nes first followed b difficult to survey ture review take pla w or use a camera to	by the local lanes. due to ramps and sh ace in the express s film the review.	oulder debris. It is ection right shoulder fo
 29 total potholes, cracking, & 72' of o Leftmost lane transverse cr <u>Center lane</u> - transverse cr <u>Rightmost lan</u> transverse cr Intermittent pothol All of the longitud General oxidation o 	58 repairs/patches (transverse cracking - 9 potholes, 22 re acking 13 potholes, 30 rep acking e -7 potholes, 6 rep acking es appear to be deve inal joint separatic f the HMA surface.	~28,100 sq-ft), 123 observed: epair/patch, 106' lo pair/patch, 17' long pair/patch, 0' longi eloping from surface on has been repaired	' of longitudinal ngitudinal crack, 55' itudinal crack, 10' tudinal crack, 7' raveling. with HMA patches.
Express Lanes: - 35 total potholes, cracking, & 240' of o Leftmost lane transverse cr o Center lane - transverse cr o Rightmost lan transverse cr - Intermittent pothol - All of the longitud - General oxidation o	58 repairs/patches (transverse cracking - 17 potholes, 32 r acking 4 potholes, 17 repa acking <u>e</u> - 14 potholes, 9 r acking es appear to be deve inal joint separatio f the HMA surface.	<pre>(~39,327 sq-ft), 645 g observed: cepair/patch, 463' l air/patch, 61' longi cepair/patch, 121' l eloping from surface on has been repaired</pre>	' of longitudinal ongitudinal crack, 126' tudinal crack, 55' ongitudinal crack, 59' raveling. with HMA patches.

Figure 107. Field evaluation report of I-96 in 2022, page 1

Field Evaluation Report

Michigan Department of Transportation Construction Field Services Division Pavement Management Section Sheet <u>2</u> of <u>2</u>

Conclusions:

Since the last review, the local lanes now have the same longitudinal and spot location repairs. Overall, the local lanes are currently performing better than the express lanes due to the lower amount of observed cracking (longitudinal & transverse totals of 195 ft vs 885 ft) and total surface area of patching (7.6% vs 10.6%). Still, for both sections, total cracking is low, and most repairs were to mitigate the longitudinal joint separation where approximately 3200 ft and 6000 ft between lanes were patched out of the total 10,338 ft (so ~31% and 58%). Otherwise, both sections are in good condition.

Future Work:

Continue with annual evaluations and/or evaluate perpetual HMA pavements for use as standard MDOT design type.

Notes taken by: Justin Schenkel

Figure 108. Field evaluation report of I-96 in 2022, page 2

Appendix F: Field Evaluation Figures



Figure 109. Field evaluation of M-84 on 07-14-2005



Figure 110. Field evaluation of M-84 on 01-28-2010



Figure 111. Field evaluation of M-84 on 11-22-2010



Figure 112. Field evaluation of M-84 on 12-08-2011



Figure 113. Field evaluation of M-84 on 12-18-2012



Figure 114. Field evaluation of M-84 on 12-04-2013



Figure 115. Field evaluation of M-84 on 12-23-2014



Figure 116. Field evaluation of M-84 on 12-16-2015



Figure 117. Field evaluation of M-84 on 12-21-2016



Figure 118. Field evaluation of M-84 on 04-24-2018



Figure 119. Field evaluation of M-84 on 04-01-2019



Figure 120. Field evaluation of M-84 on 04-22-2020



Figure 121. Field evaluation of M-84 on 05-03-2021



Figure 122. Field evaluation of M-84 on 01-23-2022



Figure 123. Field evaluation of I-96 on 10-07-2005



Figure 124. Field evaluation of I-96 on 11-09-2007



Figure 125. Field evaluation of I-96 on 02-03-2010



Figure 126. Field evaluation of I-96 on 11-23-2010



Figure 127. Field evaluation of I-96 on 12-20-2013



Figure 128. Field evaluation of I-96 on 12-11-2014



Figure 129. Field evaluation of I-96 on 11-21-2016





Figure 130. Field evaluation of I-96 on 03-25-2019



Figure 131. Field evaluation of I-96 on 05-04-2020



Figure 132. Field evaluation of I-96 on 04-21-2021