


PLAN VIEW - TYPE A DRILLED SHAFT



PLAN VIEW - TYPE B DRILLED SHAFT IN BARRIER WALL

- * CONTRACTOR TO VERIFY D04 BARS DO NOT CONFLICT WITH ANCHOR RODS.
- ** CONTRACTOR TO DETERMINE DIMENSIONS FOR D04 AND K04 BARS BASED ON LIMITS OF REMOVAL, TYPE OF BARRIER, AND CLEAR COVER REQUIREMENTS SPECIFIED HEREIN.

Rev.

NOT TO SCALE File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn

MDOT
Michigan Department of Transportation

PREPARED BY
ANCILLARY STRUCTURES

DRAWN BY: HNTB
CHECKED BY: MLO

ENGINEER OF DELIVERY

ENGINEER OF DEVELOPMENT

(SPECIAL DETAIL)
FHWA APPROVAL DATE


MICHIGAN DEPARTMENT OF TRANSPORTATION

**DMS SIGN
SUPPORT FOUNDATION**

08/08/23
PLAN DATE

ITS-032-A

SHEET
1 of 6



ELEVATION VIEW - TYPE A DRILLED SHAFT

* SEE CONTRACT PLANS FOR DEPTH OF DRILLED SHAFT.

Rev.

NOT TO SCALE

File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn


MICHIGAN DEPARTMENT OF TRANSPORTATION

(SPECIAL DETAIL)
FHWA APPROVAL DATE

08/08/23
PLAN DATE

ITS-032-A

SHEET
2 of 6



ELEVATION VIEW - TYPE B DRILLED SHAFT IN BARRIER WALL

* SEE CONTRACT PLANS FOR DEPTH OF DRILLED SHAFT.

** CONTRACTOR TO DETERMINE DIMENSIONS FOR D04 AND K04 BARS BASED ON LIMITS OF REMOVAL, TYPE OF BARRIER, AND CLEAR COVER REQUIREMENTS SPECIFIED HEREIN.

Rev.

NOT TO SCALE

File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn

MICHIGAN DEPARTMENT OF TRANSPORTATION

(SPECIAL DETAIL)
FHWA APPROVAL DATE


08/08/23
PLAN DATE

ITS-032-A


SHEET
3 of 6

NOTES:

1. THE FINISHED GRADE FOR ROADSIDE SIGNS INSTALLED ON SLOPES IS THE UPSLOPE SIDE OF THE DRILLED SHAFT.
2. WELD V06 ANCHOR ROD CAGE BAR REINFORCEMENT IN ACCORDANCE WITH AWS D1.4 USING E8018 OR E9018 ELECTRODES. SEE SHEET 6 OF 6 FOR WELD DETAILS.
3. SUBSURFACE AND GROUNDWATER INFORMATION WILL BE OBTAINED FROM THE SOIL BORING LOG INFORMATION.
4. V06 ANCHOR ROD CAGE BAR REINFORCEMENT SHALL MEET THE REQUIREMENTS OF ASTM A706 IF WELDED TO THE ANCHOR RODS.
5. TOP AND BOTTOM ANCHOR ROD TEMPLATES MAY BE FABRICATED FROM MULTIPLE PARTS USING CJP WELDS LOCATED A MINIMUM OF 2" CLEAR OF ANCHOR ROD HOLES.
6. ANCHOR RODS SHALL BE IN ACCORDANCE WITH SUBSECTION 908.14 OF THE MDOT STANDARD SPECIFICATIONS FOR CONSTRUCTION.



TOP ANCHOR ROD TEMPLATE DETAIL



BOTTOM ANCHOR ROD TEMPLATE DETAIL

Rev.

NOT TO SCALE

File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn


MICHIGAN DEPARTMENT OF TRANSPORTATION

(SPECIAL DETAIL)
FHWA APPROVAL DATE

08/08/23
PLAN DATE

ITS-032-A

SHEET
4 of 6



ANCHOR ROD DETAIL

FOUNDATION CHART					
SOIL TYPE	SOIL CONDITION		DIAMETER (in)	DEPTH "D" (ft)	CONCRETE (cyd)
	*Su	**N60			
LOW SAND	-	5 < N60 < 10	48	26	12.1
MED SAND	-	10 < N60 < 20		22	10.2
HIGH SAND	-	N60 > 20		20	9.3
LOW CLAY	400 < Su < 1000	-		37	17.2
MED CLAY	1000 < Su < 2000	-		21	9.8
HIGH CLAY	Su > 2000	-		17	7.9

* Su = Undrained shear strength of cohesive soils. (lbs/ft²)

** N60 = SPT blow count corrected for hammer efficiency. (blows/ft)
(ASTM testing procedure D1586)

MISCELLANEOUS QUANTITIES

(FOR INFORMATION ONLY)

- * STEEL WEIGHT = 16,398 Lbs
- CONDUIT, 1 INCH = 8.5 Ft
- CONDUIT, 3 INCH = 10.5 Ft
- CONDUIT, 1 1/2 INCH = 10.0 Ft
- ** SUBSTRUCTURE CONCRETE = 0.465 CY/Ft
- STEEL REINFORCEMENT = 70 Lb/Ft
- SAFETY GATE = 1 Ea.

* STEEL WEIGHT INCLUDES COLUMN, CHORDS, DIAGONALS, VERTICALS, GUSSET PLATES, BASE PLATES, HORIZONTAL PLATFORM SUPPORTS, VERTICAL PLATFORM SUPPORTS, STIFFENER PLATES, U BOLTS, ANCHOR BOLTS, BOLTS FOR ALL OTHER CONNECTIONS, LADDER RUNGS, LADDER BARS, AND KICK PLATE.
COLUMN HEIGHT IS BASED ON A 32 FT DIMENSION FROM THE TOP OF THE BASE PLATE TO THE CENTER OF THE BOTTOM CHORD.

** STEEL REINFORCEMENT WEIGHT IS IN TERMS OF LBS/FT OF DRILLED SHAFT LENGTH. THIS DOES NOT INCLUDE THE REINFORCING BARS FOR THE MEDIAN BARRIER.

Rev.

NOT TO SCALE

File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn


MICHIGAN DEPARTMENT OF TRANSPORTATION

(SPECIAL DETAIL)
FHWA APPROVAL DATE

08/08/23
PLAN DATE


ITS-032-A

SHEET
5 of 6




A BAR


BAR LEGEND




D041509



K042210



V051400



V060811

REINFORCEMENT DETAILS

Rev.

NOT TO SCALE File: External Partnerships/ITS Program Office/ITS Standard Details/DMS Structure/ITS-032-A DMS Sign Support Foundation.dgn